

A COURSE IN

Combinatorics

SECOND EDITION

J. H. van Lint & R. M. Wilson



CAMBRIDGE

CAMBRIDGE

www.cambridge.org/9780521803403

This page intentionally left blank

A course in combinatorics

This is the second edition of a popular book on combinatorics, a subject dealing with ways of arranging and distributing objects, and which involves ideas from geometry, algebra and analysis. The breadth of the theory is matched by that of its applications, which include topics as diverse as codes, circuit design and algorithm complexity. It has thus become essential for workers in many scientific fields to have some familiarity with the subject. The authors have tried to be as comprehensive as possible, dealing in a unified manner with, for example, graph theory, extremal problems, designs, colorings and codes. The depth and breadth of the coverage make the book a unique guide to the whole of the subject. The book is ideal for courses on combinatorial mathematics at the advanced undergraduate or beginning graduate level. Working mathematicians and scientists will also find it a valuable introduction and reference.

J.H. VAN LINT is Emeritus Professor of Mathematics at the Technical University of Eindhoven.

R.M. WILSON is Professor of Mathematics at the California Institute of Technology.

A Course in
Combinatorics
SECOND EDITION

J. H. van Lint

Technical University of Eindhoven

and

R. M. Wilson

California Institute of Technology



CAMBRIDGE UNIVERSITY PRESS
Cambridge, New York, Melbourne, Madrid, Cape Town, Singapore,
São Paulo, Delhi, Dubai, Tokyo

Cambridge University Press
The Edinburgh Building, Cambridge CB2 8RU, UK

Published in the United States of America by Cambridge University Press, New York

www.cambridge.org

Information on this title: www.cambridge.org/9780521803403

© Cambridge University Press 1992, 2001

This publication is in copyright. Subject to statutory exception and to the provision of relevant collective licensing agreements, no reproduction of any part may take place without the written permission of Cambridge University Press.

First published in print format 2001

ISBN-13 978-0-511-67289-7 eBook (EBL)

ISBN-13 978-0-521-80340-3 Hardback

ISBN-13 978-0-521-00601-9 Paperback

Cambridge University Press has no responsibility for the persistence or accuracy of urls for external or third-party internet websites referred to in this publication, and does not guarantee that any content on such websites is, or will remain, accurate or appropriate.

CONTENTS

Preface to the first edition	xi
Preface to the second edition	xiii
1. Graphs	1
<i>Terminology of graphs and digraphs, Eulerian circuits, Hamiltonian circuits</i>	
2. Trees	12
<i>Cayley's theorem, spanning trees and the greedy algorithm, search trees, strong connectivity</i>	
3. Colorings of graphs and Ramsey's theorem	24
<i>Brooks' theorem, Ramsey's theorem and Ramsey numbers, the Lóvasz sieve, the Erdős-Szekeres theorem</i>	
4. Turán's theorem and extremal graphs	37
<i>Turán's theorem and extremal graph theory</i>	
5. Systems of distinct representatives	43
<i>Bipartite graphs, P. Hall's condition, SDRs, König's theorem, Birkhoff's theorem</i>	
6. Dilworth's theorem and extremal set theory	53
<i>Partially ordered sets, Dilworth's theorem, Sperner's theorem, symmetric chains, the Erdős-Ko-Rado theorem</i>	
7. Flows in networks	61
<i>The Ford-Fulkerson theorem, the integrality theorem, a generalization of Birkhoff's theorem, circulations</i>	
8. De Bruijn sequences	71
<i>The number of De Bruijn sequences</i>	

9. Two $(0, 1, \star)$ problems: addressing for graphs and a hash-coding scheme	77
<i>Quadratic forms, Winkler's theorem, associative block designs</i>	
10. The principle of inclusion and exclusion; inversion formulae	89
<i>Inclusion–exclusion, derangements, Euler indica- tor, Möbius function, Möbius inversion, Burnside's lemma, problème des ménages</i>	
11. Permanents	98
<i>Bounds on permanents, Schrijver's proof of the Minc conjecture, Fekete's lemma, permanents of doubly stochastic matrices</i>	
12. The Van der Waerden conjecture	110
<i>The early results of Marcus and Newman, London's theorem, Egoritsjev's proof</i>	
13. Elementary counting; Stirling numbers	119
<i>Stirling numbers of the first and second kind, Bell numbers, generating functions</i>	
14. Recursions and generating functions	129
<i>Elementary recurrences, Catalan numbers, counting of trees, Joyal theory, Lagrange inversion</i>	
15. Partitions	152
<i>The function $p_k(n)$, the partition function, Ferrers diagrams, Euler's identity, asymptotics, the Jacobi triple product identity, Young tableaux and the hook formula</i>	
16. $(0, 1)$-Matrices	169
<i>Matrices with given line sums, counting $(0, 1)$- matrices</i>	
17. Latin squares	182
<i>Orthogonal arrays, conjugates and isomorphism, partial and incomplete Latin squares, counting Latin squares, the Evans conjecture, the Dinitz conjecture</i>	
18. Hadamard matrices, Reed–Muller codes	199
<i>Hadamard matrices and conference matrices, re- cursive constructions, Paley matrices, Williamson's method, excess of a Hadamard matrix, first order Reed–Muller codes</i>	

19. Designs	215
<i>The Erdős–De Bruijn theorem, Steiner systems, balanced incomplete block designs, Hadamard designs, counting, (higher) incidence matrices, the Wilson–Petrenjuk theorem, symmetric designs, projective planes, derived and residual designs, the Bruck–Ryser–Chowla theorem, constructions of Steiner triple systems, write-once memories</i>	
20. Codes and designs	244
<i>Terminology of coding theory, the Hamming bound, the Singleton bound, weight enumerators and MacWilliams’ theorem, the Assmus–Mattson theorem, symmetry codes, the Golay codes, codes from projective planes</i>	
21. Strongly regular graphs and partial geometries	261
<i>The Bose–Mesner algebra, eigenvalues, the integrality condition, quasisymmetric designs, the Krein condition, the absolute bound, uniqueness theorems, partial geometries, examples, directed strongly regular graphs, neighborhood regular graphs</i>	
22. Orthogonal Latin squares	283
<i>Pairwise orthogonal Latin squares and nets, Euler’s conjecture, the Bose–Parker–Shrikhande theorem, asymptotic existence, orthogonal arrays and transversal designs, difference methods, orthogonal subsquares</i>	
23. Projective and combinatorial geometries	303
<i>Projective and affine geometries, duality, Pasch’s axiom, Desargues’ theorem, combinatorial geometries, geometric lattices, Greene’s theorem</i>	
24. Gaussian numbers and q-analogues	325
<i>Chains in the lattice of subspaces, q-analogue of Sperner’s theorem, interpretation of the coefficients of the Gaussian polynomials, spreads</i>	
25. Lattices and Möbius inversion	333
<i>The incidence algebra of a poset, the Möbius function, chromatic polynomial of a graph, Weisner’s theorem, complementing permutations of geometric lattices, connected labeled graphs, MDS codes</i>	
26. Combinatorial designs and projective geometries	351
<i>Arcs and subplanes in projective planes, blocking sets, quadratic and Hermitian forms, unitals, generalized quadrangles, Möbius planes</i>	

27. Difference sets and automorphisms	369
<i>Block's lemma, automorphisms of symmetric designs, Paley–Todd and Stanton–Sprott difference sets, Singer's theorem</i>	
28. Difference sets and the group ring	383
<i>The Multiplier Theorem and extensions, homomorphisms and further necessary conditions</i>	
29. Codes and symmetric designs	396
<i>The sequence of codes of a symmetric design, Wilbrink's theorem</i>	
30. Association schemes	405
<i>Examples, the eigenmatrices and orthogonality relations, formal duality, the distribution vector of a subset, Delsarte's inequalities, polynomial schemes, perfect codes and tight designs</i>	
31. (More) algebraic techniques in graph theory	432
<i>Tournaments and the Graham–Pollak theorem, the spectrum of a graph, Hoffman's theorem, Shannon capacity, applications of interlacing and Perron–Frobenius</i>	
32. Graph connectivity	451
<i>Vertex connectivity, Menger's theorem, Tutte connectivity</i>	
33. Planarity and coloring	459
<i>The chromatic polynomial, Kuratowski's theorem, Euler's formula, the Five Color Theorem, list-colorings</i>	
34. Whitney Duality	472
<i>Whitney duality, circuits and cutsets, MacLane's theorem</i>	
35. Embeddings of graphs on surfaces	491
<i>Embeddings on arbitrary surfaces, the Ringel–Youngs theorem, the Heawood conjecture, the Edmonds embedding technique</i>	
36. Electrical networks and squared squares	507
<i>The matrix-tree theorem, De Bruijn sequences, the network of a squared rectangle, Kirchhoff's theorem</i>	
37. Pólya theory of counting	522
<i>The cycle index of a permutation group, counting orbits, weights, necklaces, the symmetric group, Stirling numbers</i>	

38. Baranyai's theorem	536
<i>One-factorizations of complete graphs and complete designs</i>	
Appendix 1. Hints and comments on problems	542
<i>Hints, suggestions, and comments on the problems in each chapter</i>	
Appendix 2. Formal power series	578
<i>Formal power series ring, formal derivatives, inverse functions, residues, the Lagrange–Bürmann formula</i>	
Name Index	584
Subject Index	590

Preface to the first edition

One of the most popular upper level mathematics courses taught at Caltech for very many years was H. J. Ryser's course *Combinatorial Analysis*, Math 121. One of Ryser's main goals was to show elegance and simplicity. Furthermore, in this course that he taught so well, he sought to demonstrate coherence of the subject of combinatorics. We dedicate this book to the memory of Herb Ryser, our friend whom we admired and from whom we learned much.

Work on the present book was started during the academic year 1988–89 when the two authors taught the course Math 121 together. Our aim was not only to continue in the style of Ryser by showing many links between areas of combinatorics that seem unrelated, but also to try to more-or-less survey the subject. We had in mind that after a course like this, students who subsequently attend a conference on “Combinatorics” would hear no talks where they are completely lost because of unfamiliarity with the topic. Well, at least they should have heard many of the words before. We strongly believe that a student studying combinatorics should see as many of its branches as possible.

Of course, none of the chapters could possibly give a complete treatment of the subject indicated in their titles. Instead, we cover some highlights—but we insist on doing something substantial or nontrivial with each topic. It is our opinion that a good way to learn combinatorics is to see subjects repeated at intervals. For this reason, several areas are covered in more than one part of the book. For example, partially ordered sets and codes appear several times. Enumeration problems and graph theory occur throughout

the book. A few topics are treated in more detail (because we like them) and some material, like our proof of the Van der Waerden permanent conjecture, appears here in a text book for the first time.

A course in modern algebra is sufficient background for this book, but is not absolutely necessary; a great deal can be understood with only a certain level of maturity. Indeed, combinatorics is well known for being “accessible”. But readers should find this book challenging and will be expected to fill in details (that we hope are instructive and not too difficult). We mention in passing that we believe there is no substitute for a human teacher when trying to learn a subject. An acquaintance with calculus, groups, finite fields, elementary number theory, and especially linear algebra will be necessary for some topics. Both undergraduates and graduate students take the course at Caltech. The material in every chapter has been presented in class, but we have never managed to do all the chapters in one year.

The notes at the end of chapters often include biographical remarks on mathematicians. We have chosen to refrain from any mention of living mathematicians unless they have retired (with the exception of P. Erdős).

Exercises vary in difficulty. For some it may be necessary to consult the hints in Appendix 1. We include a short discussion of formal power series in Appendix 2.

This manuscript was typeset by the authors in $\mathcal{A}\mathcal{M}\mathcal{S}$ - $\mathcal{T}\mathcal{E}\mathcal{X}$.

J. H. v. L., R. M. W.

Eindhoven and Pasadena, 1992

Preface to the 2nd edition

The favorable reception of our book and its use for a variety of courses on combinatorial mathematics at numerous colleges and universities has encouraged us to prepare this second edition. We have added new material and have updated references for this version. A number of typographical and other errors have been corrected. We had to change “this century” to “the last century” in several places.

The new material has, for the most part, been inserted into the chapters with the same titles as in the first edition. An exception is that the material of the later chapters on graph theory has been reorganized into four chapters rather than two. The added material includes, for example, discussion of the Lovász sieve, associative block designs, and list colorings of graphs.

Many new problems have been added, and we hope that this last change, in particular, will increase the value of the book as a text. We have decided not to attempt to indicate in the book the level of difficulty of the various problems, but remark again that this can vary greatly. The difficulty will often depend on the experience and background of the reader, and an instructor will need to decide which exercises are appropriate for his or her students. We like the idea of stating problems at the point in the text where they are most relevant, but have also added some problems at the end of the chapters. It is not true that the problems appearing later are necessarily more difficult than those at the beginning of a chapter. A number of the hints and comments in Appendix 1 have been improved.

Preparation of the second edition was done during a six-month visit to the California Institute of Technology by the first author as Moore Distinguished Scholar. He gratefully acknowledges the support of the Moore Foundation.

1

Graphs

A *graph* G consists of a set V (or $V(G)$) of *vertices*, a set E (or $E(G)$) of *edges*, and a mapping associating to each edge $e \in E(G)$ an unordered pair x, y of vertices called the *endpoints* (or simply the *ends*) of e . We say an edge is *incident* with its ends, and that it *joins* its ends. We allow $x = y$, in which case the edge is called a *loop*. A vertex is *isolated* when it is incident with no edges.

It is common to represent a graph by a *drawing* where we represent each vertex by a point in the plane, and represent edges by line segments or arcs joining some of the pairs of points. One can think e.g. of a network of roads between cities. A graph is called *planar* if it can be drawn in the plane such that no two edges (that is, the line segments or arcs representing the edges) cross. The topic of planarity will be dealt with in Chapter 33; we wish to deal with graphs more purely combinatorially for the present.

edge	ends
a	x, z
b	y, w
c	x, z
d	z, w
e	z, w
f	x, y
g	z, w

Figure 1.1


Thus a graph is described by a table such as the one in Fig. 1.1 that lists the ends of each edge. Here the graph we are describing

has vertex set $V = \{x, y, z, w\}$ and edge set $E = \{a, b, c, d, e, f, g\}$; a drawing of this graph may be found as Fig. 1.2(iv).

A graph is *simple* when it has no loops and no two distinct edges have exactly the same pair of ends. Two nonloops are *parallel* when they have the same ends; graphs that contain them are called *multigraphs* by some authors, or are said to have ‘multiple edges’.

If an *ordered* pair of vertices is associated to each edge, we have a *directed graph* or *digraph*. In a drawing of a digraph, we use an arrowhead to point from the first vertex (the *tail*) towards the second vertex (the *head*) incident with an edge. For a *simple* digraph, we disallow loops and require that no two distinct edges have the same ordered pair of ends.

When dealing with simple graphs, it is often convenient to identify the edges with the unordered pairs of vertices they join; thus an edge joining x and y can be called $\{x, y\}$. Similarly, the edges of a simple digraph can be identified with ordered pairs (x, y) of distinct vertices.



(i) graph (ii) graph with loop (iii) digraph (iv) multiple edges

Figure 1.2

There are several ways to draw the same graph. For example, the two graphs of Fig. 1.3 are essentially the same.

We make this more precise, but to avoid unnecessarily technical definitions at this point, let us assume that all graphs are undirected and simple for the next two definitions.

We say two graphs are *isomorphic* if there is a one-to-one correspondence between the vertex sets such that if two vertices are joined by an edge in one graph, then the corresponding vertices are joined by an edge in the other graph. To show that the two graphs in Fig. 1.3 are the same, find a suitable numbering of the vertices

in both graphs (using 1, 2, 3, 4, 5, 6) and observe that the edge sets are the same sets of unordered pairs.




Figure 1.3

A permutation σ of the vertex set of a graph G with the property that $\{a, b\}$ is an edge if and only if $\{\sigma(a), \sigma(b)\}$ is an edge, is called an *automorphism* of G .

Problem 1A. (i) Show that the drawings in Fig. 1.4 represent the same graph (or isomorphic graphs).

(ii) Find the group of automorphisms of the graph in Fig. 1.4. Remark: There is no quick or easy way to do this unless you are lucky; you will have to experiment and try things.




Figure 1.4

The *complete* graph K_n on n vertices is the simple graph that has all $\binom{n}{2}$ possible edges.

Two vertices a and b of a graph G are called *adjacent* if they are distinct and joined by an edge. We will use $\Gamma(x)$ to denote the set of all vertices adjacent to a given vertex x ; these vertices are also called the *neighbors* of x .

The number of edges incident with a vertex x is called the *degree* or the *valency* of x . Loops are considered to contribute 2 to the valency, as the pictures we draw suggest. If all the vertices of a graph have the same degree, then the graph is called *regular*.

One of the important tools in combinatorics is the method of *counting* certain objects in two different ways. It is a well known fact that if one makes no mistakes, then the two answers are the same. We give a first elementary example. A graph is *finite* when both $E(G)$ and $V(G)$ are finite sets. We will be primarily concerned with finite graphs, so much so that it is possible we have occasionally forgotten to specify this condition as a hypothesis in some assertions.

Theorem 1.1. *A finite graph G has an even number of vertices with odd valency.*

PROOF: Consider a table listing the ends of the edges, as in Fig. 1.1. The number of entries in the right column of the table is twice the number of edges. On the other hand, the degree of a vertex x is, by definition, the number of times it occurs in the table. So the number of entries in the right column is

$$(1.1) \quad \sum_{x \in V(G)} \deg(x) = 2|E(G)|.$$

The assertion follows immediately. □

The equation (1.1) is simple but important. It might be called the ‘first theorem of graph theory’, and our Theorem 1.1 is its first corollary.

A *subgraph* of a graph G is a graph H such that $V(H) \subseteq V(G)$, $E(H) \subseteq E(G)$, and the ends of an edge $e \in E(H)$ are the same as its ends in G . H is a *spanning* subgraph when $V(H) = V(G)$. The subgraph of G *induced* by a subset S of vertices of G is the subgraph whose vertex set is S and whose edges are *all* the edges of G with both ends in S .

A *walk* in a graph G consists of an alternating sequence

$$x_0, e_1, x_1, e_2, x_2, \dots, x_{k-1}, e_k, x_k$$

of vertices x_i , not necessarily distinct, and edges e_i so that the ends of e_i are exactly x_{i-1} and x_i , $i = 1, 2, \dots, k$. Such a walk has *length* k . If the graph is simple, a walk is determined by its sequence of vertices, any two successive elements of which are adjacent.

If the edge terms e_1, \dots, e_k are distinct, then the walk is called a *path* from x_0 to x_k . If $x_0 = x_k$, then a walk (or path) is called *closed*. A *simple path* is one in which the vertex terms x_0, x_1, \dots, x_k are also distinct, although we say we have a *simple closed path* when $k \geq 1$ and all vertex terms are distinct except $x_0 = x_k$.

If a path from x to y exists for every pair of vertices x, y of G , then G is called *connected*. Otherwise G consists of a number of connected *components* (maximal connected subgraphs). It will be convenient to agree that the null graph with no vertices and no edges is not connected.

Problem 1B. Suppose G is a simple graph on 10 vertices that is not connected. Prove that G has at most 36 edges. Can equality occur?

The length of the shortest walk from a to b , if such walks exist, is called the *distance* $d(a, b)$ between these vertices. Such a shortest walk is necessarily a simple path.

Example 1.1. A well known graph has the mathematicians of the world as vertices. Two vertices are adjacent if and only if they have published a joint paper. The distance in this graph from some mathematician to the vertex P. Erdős is known as his or her Erdős-number.




Figure 1.5

A *polygon* is the ‘graph of’ a simple closed path, but more precisely it can be defined as a finite connected graph that is regular of degree 2. There is, up to isomorphism, exactly one polygon P_n

with n vertices (often called the n -gon) for each positive integer n . The sequence of polygons is shown in Fig. 1.5.

A connected graph that contains no simple closed paths, i.e. that has no polygons as subgraphs, is called a *tree*.

Problem 1C. Show that a connected graph on n vertices is a tree if and only if it has $n - 1$ edges.

Problem 1D. The *complete bipartite graph* $K_{n,m}$ has $n + m$ vertices a_1, \dots, a_n and b_1, \dots, b_m , and as edges all mn pairs $\{a_i, b_j\}$. Show that $K_{3,3}$ is not planar.

No introduction to graph theory can omit the problem of the bridges of Königsberg (formerly a city in Prussia). The river Pregel flowed through this city and split into two parts. In the river was the island Kneiphof. There were seven bridges connecting different parts of the city as shown in the diagram of Fig. 1.6.




Figure 1.6

In a paper written in 1736 by L. Euler (considered the first paper on graph theory) the author claims that the following question was considered difficult: Is it possible to make a walk through the city, returning to the starting point and crossing each bridge exactly once? This paper has led to the following definition. A closed path through a graph using every edge once is called an *Eulerian circuit* and a graph that has such a path is called an *Eulerian graph*.

Theorem 1.2. A finite graph G with no isolated vertices (but possibly with multiple edges) is Eulerian if and only if it is connected and every vertex has even degree.

PROOF: That G must be connected is obvious. Since the path enters a vertex through some edge and leaves by another edge, it is clear that all degrees must be even. To show that the conditions are sufficient, we start in a vertex x and begin making a path. We keep going, never using the same edge twice, until we cannot go further. Since every vertex has even degree, this can only happen when we return to x and all edges from x have been used. If there are unused edges, then we consider the subgraph formed by these edges. We use the same procedure on a component of this subgraph, producing a second closed path. If we start this second path in a point occurring in the first path, then the two paths can be combined to a longer closed path from x to x . Therefore the longest of these paths uses all the edges. \square

The problem of the bridges of Königsberg is described by the graph in Fig. 1.6. No vertex has even degree, so there is no Eulerian circuit.

One can consider a similar problem for digraphs. The necessary and sufficient condition for a directed Eulerian circuit is that the graph is connected and that each vertex has the same ‘in-degree’ as ‘out-degree’.

Example 1.2. A puzzle with the name *Instant Insanity* concerns four cubes with faces colored red, blue, green, and yellow, in such a way that each cube has at least one face of each color. The problem is to make a stack of these cubes so that all four colors appear on each of the four sides of the stack. In Fig. 1.7 we describe four possible cubes in flattened form.




Figure 1.7

It is not a very good idea to try all possibilities. A systematic approach is as follows. The essential information about the cubes is given by the four graphs in Fig. 1.8.




Figure 1.8

An edge indicates that the two adjacent colors occur on opposite faces of the cube. We obtain a graph G by superposition of the four graphs and number the edges according to their origin. It is not difficult to see that we need to find in G two subgraphs that are regular of degree 2, with edges numbered 1, 2, 3, 4 and such that they have no edge in common. One of the subgraphs tells us which pairs of colors to align on the left side and right side of the stack. The other graph describes the colors on front and back. Of course it is easy to rotate the cubes in such a way that the colors are where we wish them to be. The point of the example is that it takes only a minute to find two subgraphs as described above. In this example the solution is unique.

We mention a concept that seems similar to Eulerian circuits but that is in reality quite different. A *Hamiltonian circuit* in a graph G is a simple closed path that passes through each *vertex* exactly once (rather than each *edge*). So a graph admits a Hamiltonian circuit if and only if it has a polygon as a spanning subgraph. In the mid-19th century, Sir William Rowan Hamilton tried to popularize the exercise of finding such a closed path in the graph of the dodecahedron (Fig. 1.9).




Figure 1.9

The graph in Fig. 1.4 is called the Petersen graph (cf. Chapter 21) and one of the reasons it is famous is that it is *not* ‘Hamiltonian’; it contains n -gons only for $n = 5, 6, 8, 9$, and not when $n = 7$ or $n = 10$.

By Theorem 1.2, it is easy to decide whether a graph admits an Eulerian circuit. A computer can easily be programmed to check whether the degrees of a graph are even and whether the graph is connected, and even to produce an Eulerian circuit when one exists. In contrast to this, the problem of deciding whether an arbitrary graph admits a Hamiltonian circuit is likely ‘intractable’. To be more precise, it has been proved to be *NP-complete*—see Garey and Johnson (1979).

Problem 1E. Let A_1, \dots, A_n be n distinct subsets of the n -set $N := \{1, \dots, n\}$. Show that there is an element $x \in N$ such that the sets $A_i \setminus \{x\}$, $1 \leq i \leq n$, are all distinct. To do this, form a graph G on the vertices A_i with an edge with ‘color’ x between A_i and A_j if and only if the symmetric difference of the sets A_i and A_j is $\{x\}$. Consider the colors occurring on the edges of a polygon. Show that one can delete edges from G in such a way that *no* polygons are left and the number of different colors remains the same. Then use 1C. (This idea is due to J. A. Bondy (1972).)

Problem 1F. The *girth* of a graph is the length of the smallest polygon in the graph. Let G be a graph with girth 5 for which all vertices have degree $\geq d$. Show that G has at least $d^2 + 1$ vertices. Can equality hold?

Problem 1G. Show that a finite simple graph with more than one vertex has at least two vertices with the same degree.

Problem 1H. A graph on the vertex set $\{1, 2, \dots, n\}$ is often described by a matrix A of size n , where a_{ij} and a_{ji} are equal to the number of edges with ends i and j . What is the combinatorial interpretation of the entries of the matrix A^2 ?

Problem 1I. Let $Q := \{1, 2, \dots, q\}$. Let G be a graph with the elements of Q^n as vertices and an edge between (a_1, a_2, \dots, a_n) and (b_1, b_2, \dots, b_n) if and only if $a_i \neq b_i$ for exactly one value of i . Show that G is Hamiltonian.

Problem 1J. Let G be a simple graph on n vertices ($n > 3$) with no vertex of degree $n - 1$. Suppose that for any two vertices of G , there is a *unique* vertex joined to both of them.

(i) If x and y are not adjacent, prove that they have the same degree.

(ii) Now show that G is a regular graph.

Notes.

Paul Erdős (1913–1996) (cf. Example 1.1) was probably the most prolific mathematician of the 20th century with well over 1400 papers having been published. His contributions to combinatorics, number theory, set theory, etc., include many important results. He collaborated with many mathematicians all over the world, all of them proud to have Erdős-number 1, among them the authors of this book; see J. W. Grossman (1997).

Leonhard Euler (1707–1783) was a Swiss mathematician who spent most of his life in St. Petersburg. He was probably the most productive mathematician of all times. Even after becoming blind in 1766, his work continued at the same pace. The celebration in 1986 of the 250th birthday of graph theory was based on Euler's paper on the Königsberg bridge problem. Königsberg is now the city of Kaliningrad in Russia.

For an elementary introduction to graph theory, we recommend R. J. Wilson (1979), and J. J. Watkins and R. J. Wilson (1990).

Sir William Rowan Hamilton (1805–1865) was an Irish mathematician. He was considered a genius. He knew 13 languages at the age of 12 and was appointed professor of astronomy at Trinity College Dublin at the age of 22 (before completing his degree). His most important work was in mathematical physics.

References.

M. Garey and D. S. Johnson (1979), *Computers and Intractability; A Guide to the Theory of NP-completeness*, W. H. Freeman and Co.

J. W. Grossman (1997), Paul Erdős: The Master of Collaboration, pp. 467–475 in *The Mathematics of Paul Erdős*, R. L. Graham and J. Nešetřil (eds.), Springer-Verlag.

J. J. Watkins and R. J. Wilson (1990), *Graphs (An Introductory Approach)*, J. Wiley & Sons.

R. J. Wilson (1979), *Introduction to Graph Theory*, Longman.

2


Trees

We come to the first not so easy theorem. It is due to A. Cayley (1889). We shall give three different proofs here. Two more proofs will occur in later chapters; see Example 14.14 and Example 38.2. The first two proofs illustrate a method that is used very often in combinatorics. In order to count certain objects that seem hard to count, one finds a one-to-one mapping onto a set of other objects whose number is easier to determine.

Theorem 2.1. *There are n^{n-2} different labeled trees on n vertices.*

The term *labeled* emphasizes that we are not identifying isomorphic graphs. We have fixed the set of vertices, and two trees are counted as the same if and only if exactly the same pairs of vertices are adjacent. A *spanning tree* of a connected graph G is a spanning subgraph of G that is a tree. The theorem could have been stated: the complete graph K_n has n^{n-2} spanning trees.

Example 2.1. Here are the 16 labeled trees on four vertices:



Example 2.2. There are three nonisomorphic trees on five vertices:



The number of spanning trees in K_5 isomorphic to a specific tree T on five vertices is $5!$ divided by the order of the automorphism group of T (why?). Thus there are $5!/4! = 5$ trees in K_5 isomorphic to the first tree above, and $5!/2 = 60$ trees isomorphic to either of the other two trees, for a total of 125 spanning trees.

Problem 2A. Find the six nonisomorphic trees on 6 vertices, and for each compute the number of distinct spanning trees in K_6 isomorphic to it.

Before starting the proofs, we make the following observations. (Probably the reader has already noticed these things in solving Problem 1C.) Firstly, every tree with $n \geq 2$ vertices has at least two monovalent vertices (vertices of degree 1). This is immediate, for example, from Problem 1C and equation (1.1): the sum of the degrees d_1, d_2, \dots, d_n , all of which are at least 1, is $2n - 2$. Secondly, if a monovalent vertex and its incident edge are deleted from a tree, the resulting graph is still a tree. Finally, given a tree T , if we introduce a new vertex x and a new edge joining x to *any* vertex of T , the new graph is again a tree.




Figure 2.1

PROOF 1: The first proof we present, due to H. Prüfer (1918), uses an algorithm that associates to any tree T a ‘name’ $\mathcal{P}(T)$ (called the *Prüfer code*) that characterizes the tree.

For the vertices of K_n , we take the ordered set $V = \{1, 2, 3, \dots, n\}$. Given a spanning tree T in K_n , we let $T_1 = T$ and generate a sequence of trees T_1, T_2, \dots, T_{n-1} and two sequences of vertices as follows: Given the tree T_i with $n - i + 1$ vertices, $i = 1, 2, \dots, n - 1$, let x_i be the least monovalent vertex of T_i and delete x_i and its incident edge $\{x_i, y_i\}$ from T_i to obtain a tree T_{i+1} on $n - i$ vertices. The *name* of T is to be

$$\mathcal{P}(T) = (y_1, y_2, \dots, y_{n-2}).$$

We claim that the mapping \mathcal{P} , from the set of all spanning trees in K_n to the set V^{n-2} of all possible names, is one-to-one and onto (bijective). This will prove that the number of spanning trees in K_n is n^{n-2} .

For the tree in Fig. 2.1, where $n = 10$, we have $(x_1, y_1) = (3, 2)$, $(x_2, y_2) = (4, 2)$, $(x_3, y_3) = (2, 1), \dots, (x_9, y_9) = (9, 10)$; these edges are the columns of the matrix below.

$$\begin{bmatrix} 3 & 4 & 2 & 5 & 6 & 7 & 1 & 8 & 9 \\ 2 & 2 & 1 & 1 & 7 & 1 & 10 & 10 & 10 \end{bmatrix}$$

So $\mathcal{P}(T) = (2, 2, 1, 1, 7, 1, 10, 10)$. Don't include $y_9 = 10$.

To understand why \mathcal{P} is bijective, we first note some simple facts about the x_i 's and y_i 's. First, $y_{n-1} = n$, always. This is because every tree (with at least two vertices) has at least two monovalent vertices, so the vertex n will never be the least monovalent vertex. Second, $x_k, x_{k+1}, \dots, x_{n-1}$ and n are the vertices of the tree T_k . Third, $\{x_i, y_i\}$, $k \leq i \leq n - 1$, are exactly the edges of T_k , in some order.

The number of times a vertex v occurs among y_1, y_2, \dots, y_{n-2} is $\deg_T(v) - 1$. This is because v occurs $\deg_T(v)$ times among the edges $\{x_i, y_i\}$, $1 \leq i \leq n - 1$, and exactly once in $x_1, x_2, \dots, x_{n-1}, y_{n-1}$. Similarly, the number of times a vertex v of T_k occurs among $y_k, y_{k+1}, \dots, y_{n-2}$ is its degree in the tree T_k less 1. In particular, *the monovalent vertices of T_k are those elements of V not in*

$$\{x_1, x_2, \dots, x_{k-1}\} \cup \{y_k, y_{k+1}, \dots, y_{n-1}\},$$

and this means that x_k , the least monovalent vertex of T_k , is the least element of $\{1, 2, \dots, n\}$ not in the above set. In particular,

x_1 is the least element of V not in the name $\mathcal{P}(T)$, and we can uniquely determine x_k from $\mathcal{P}(T)$ and x_1, \dots, x_{k-1} . \square

Problem 2B. How many trees T are there on the set of vertices $\{1, 2, 3, 4, 5, 6, 7\}$ in which the vertices 2 and 3 have degree 3, vertex 5 has degree 2, and hence all others have degree 1? Do not just draw pictures but consider the possible Prüfer codes of these trees.

PROOF 2: We give another proof, again by a reversible algorithm. Consider any mapping f from $\{2, 3, \dots, n - 1\}$ to $\{1, 2, \dots, n\}$. There are n^{n-2} such mappings f . Construct a digraph D on the vertices 1 to n by defining $(i, f(i)), i = 2, \dots, n - 1$, to be the edges. Fig. 2.2 shows an example with $n = 21$.

D consists of two trees ‘rooted’ at 1 and n and a number (say k) of circuits (directed polygons) to which trees are attached. (Directed trees with all the edges pointing in the direction of one vertex, called the root, are called *arborescences*.) These circuits are placed as in Fig. 2.2 where the rightmost vertex in the i -th component, denoted by r_i , is its minimal element (and l_i is the vertex on the left). The circuits are ordered by the condition $r_1 < r_2 < \dots < r_k$. To D we adjoin the tree obtained by adding the edges $\{1, l_1\}, \{r_1, l_2\}, \dots, \{r_{k-1}, l_k\}, \{r_k, n\}$ and deleting the edges $\{r_i, l_i\}$ as in Fig. 2.3.




Figure 2.2

If the tree of Fig. 2.3 is given, consider the path from 1 to n ($=21$). Let $r_0 := 1$. Define r_1 to be the minimal number on this path (excluding $r_0 = 1$) and in general r_i as the minimal number on the path from r_{i-1} to n . It is easily seen that we recover the function f in this way. \square




Figure 2.3

Generalizations of this proof may be found in Egecioglu and Remmel (1986).

Problem 2C. Let G be a directed graph with vertices x_1, \dots, x_n for which a (directed) Eulerian circuit exists. A *spanning arborescence* with root x_i is a spanning tree T of G , with root x_i , such that for all $j \neq i$ there is a directed path from x_j to x_i in T . Show that the number of spanning arborescences of G with root x_i does not depend on i . (This is difficult; see the hints.)

PROOF 3: We now give a proof by counting since it is useful to have seen this method. We remind the reader of the definition of a *multinomial coefficient*. Let r_1, r_2, \dots, r_k be nonnegative integers with sum n . Then $\binom{n}{r_1, \dots, r_k}$ is defined by

$$(2.1) \quad (x_1 + x_2 + \dots + x_k)^n = \sum \binom{n}{r_1, \dots, r_k} x_1^{r_1} x_2^{r_2} \dots x_k^{r_k},$$

where the sum is over all k -tuples (r_1, \dots, r_k) with sum n .

Since $(x_1 + \dots + x_k)^n = (x_1 + \dots + x_k)^{n-1} (x_1 + \dots + x_k)$, we have

$$(2.2) \quad \binom{n}{r_1, \dots, r_k} = \sum_{i=1}^k \binom{n-1}{r_1, \dots, r_i-1, \dots, r_k}.$$

We denote the number of labeled trees with n vertices for which the degrees are d_1, d_2, \dots, d_n by $t(n; d_1, d_2, \dots, d_n)$. Clearly this number is 0 if one of the d_i is 0. The value of $t(n; d_1, d_2, \dots, d_n)$ depends only on the multiset of numbers d_i and not on their order. We may assume without loss of generality that $d_1 \geq d_2 \geq \dots \geq d_n$, so $d_n = 1$. Take the vertex v_n corresponding to d_n . It is joined to some vertex v_i of degree $d_i \geq 2$, and any of the remaining vertices

is a candidate. Therefore

$$(2.3) \quad t(n; d_1, \dots, d_n) = \sum_{i=1}^{n-1} t(n-1; d_1, \dots, d_i-1, \dots, d_{n-1}).$$

It is trivial to check by hand that

$$(2.4) \quad t(n; d_1, \dots, d_n) = \binom{n-2}{d_1-1, \dots, d_n-1}$$

for $n = 3$. Since the numbers on the left-hand side, respectively right-hand side, of (2.4) satisfy the same recurrence relation ((2.3), respectively (2.2)) it follows by induction that (2.4) is true for all n . In (2.1), we replace n by $n-2$, k by n , r_i by d_i-1 and x_i by 1. We find

$$n^{n-2} = \sum t(n; d_1, d_2, \dots, d_n).$$

□

Compare (2.4) with Problem 2B.

A spanning tree is easily constructed by starting at any vertex, taking the edges to vertices at distance 1, then one edge to each vertex at distance 2, etc. Several other constructions are possible (e.g. by starting with G and deleting suitable edges).

A graph with no polygons as subgraphs is called a *forest*. Each component C_1, C_2, \dots, C_k of a forest G is a tree, so if a forest with n vertices has k components, it has

$$(|V(C_1)| - 1) + (|V(C_2)| - 1) + \dots + (|V(C_k)| - 1) = n - k$$

edges.

A *weighted graph* is a graph G together with a function associating a real number $c(e)$ (usually nonnegative) to each edge e , called its *length* or *cost* according to context. Let us use the term ‘cost’ here. Given a weighted connected graph G , define the *cost* of a spanning tree T of G as

$$c(T) := \sum_{e \in E(T)} c(e).$$

The graph may represent a network of cities where $c(\{x, y\})$ is the cost of erecting a telephone line joining cities x and y , and so it is clear that finding a *cheapest* spanning tree in G is a problem of practical importance.

The following method is often called the *greedy algorithm*. In fact, it is only one of a number of algorithms which can be called greedy algorithms, where one does not plan ahead but takes what seems to be the best alternative at each moment and does not look back. It is surprising that such a simple procedure actually produces a cheapest spanning tree, but this is proved in Theorem 2.2 below. Let us say that a set S of edges of a graph G is *independent* when the spanning subgraph with edge set S (denoted $G:S$) is a forest.

Greedy algorithm. Let G be a connected weighted graph with n vertices. At each point, we will have a set $\{e_1, e_2, \dots, e_i\}$ of i independent edges ($i = 0$ to start), so that $G:\{e_1, e_2, \dots, e_i\}$ has $n-i$ components. If $i < n-1$, let e_{i+1} be an edge with ends in different components of $G:\{e_1, e_2, \dots, e_i\}$ and whose cost is minimum with respect to this property. Stop when we have chosen $n-1$ edges.

Theorem 2.2. *With e_1, \dots, e_{n-1} chosen as above, the spanning tree $T_0 := G:\{e_1, \dots, e_{n-1}\}$ has the property that $c(T_0) \leq c(T)$ for any spanning tree T .*

PROOF: Let $\{a_1, a_2, \dots, a_{n-1}\}$ be the edge set of a tree T , numbered so that $c(a_1) \leq c(a_2) \leq \dots \leq c(a_{n-1})$. We claim something much stronger than $c(T_0) \leq c(T)$; namely, we claim that $c(e_i) \leq c(a_i)$ for each $i = 1, 2, \dots, n-1$. If this is false, then

$$c(e_k) > c(a_k) \geq c(a_{k-1}) \geq \dots \geq c(a_1)$$

for some k . Since none of a_1, a_2, \dots, a_k was chosen at the point when e_k was chosen, each of these k edges has both ends in the same component of $G:\{e_1, e_2, \dots, e_{k-1}\}$. Then the number of components of $G:\{a_1, a_2, \dots, a_k\}$ is at least the number $n-k+1$ of components of $G:\{e_1, e_2, \dots, e_{k-1}\}$ and this contradicts the fact that $\{a_1, a_2, \dots, a_k\}$ is independent. \square

Problem 2D. Here is a variation on the above greedy algorithm. Let x_1 be any vertex of a weighted connected graph G with n

vertices and let T_1 be the subgraph with the one vertex x_1 and no edges. After a tree (subgraph) T_k , $k < n$, has been defined, let e_k be a cheapest edge among all edges with one end in $V(T_k)$ and the other end *not* in $V(T_k)$, and let T_{k+1} be the tree obtained by adding that edge and its other end to T_k . Prove that T_n is a cheapest spanning tree in G .

In many practical situations, it is necessary to search through a tree starting from a particular vertex. (A tree with a distinguished vertex—the *root*—is called a *rooted tree*.) There are two well known methods known as *depth-first search* and *breadth-first search*. We explain the terminology by the example of Fig. 2.4.




Figure 2.4

In a depth-first search starting at a , one essentially considers the tree as a fence and walks around it, keeping the fence on the left, i.e. along the walk $abdidi jdbefk \dots lhca$. If one decides to number the vertices in accordance with the search, one finds the numbering $a = 1$, $b = 2$, $d = 3$, $i = 4$, \dots , $l = 12$. In this description, we rely on a planar drawing of the tree; but see below.

In a breadth-first search, one proceeds as in the construction of a spanning tree mentioned above. The vertices are then numbered in the order of Fig. 2.4, i.e. alphabetically.

These ideas apply, more generally, to searching through the vertices of a connected graph.

Given a finite connected graph G , we can obtain a numbering of the vertices of G and a spanning tree T of G , called a ‘depth-first search tree’ for G , in the following manner. Pick a vertex v_0 and start with the tree T_0 with vertex v_0 and no edges. Proceed inductively: once vertices $v_0, v_1, v_2, \dots, v_k$ and a tree T_k with exactly those vertices and some of the edges of G have been chosen, let ℓ

be the largest index $\leq k$ so that v_ℓ is adjacent to some vertex not in T_k . Such a vertex will exist if T_k is not yet a spanning tree; otherwise stop and let $T = T_k$. Call that new vertex v_{k+1} and add it and the edge $\{v_\ell, v_{k+1}\}$ to T_k to obtain a tree T_{k+1} . We consider T as a rooted tree with root v_0 .

We give two properties of depth-first search trees and use them to give a simple constructive proof of a theorem on orientations of graphs.

Given a vertex x of a rooted tree with root v_0 , the *ancestors* of x are the vertices traversed by the (unique) path from x to the root v_0 . The first vertex other than x on that path is the *parent* of x . If x is an ancestor of y , we also say that y is a *descendant* of x . We will count x as a descendent and ancestor of itself.

Proposition 2.3. If vertices x and y are adjacent in G , then one of them is a descendant of the other in any depth-first search tree T of G .

PROOF: Suppose x is numbered with a smaller index than y in the depth-first search, say $x = v_k$.

At the stage when $v_0, v_1, v_2, \dots, v_k$ have been chosen, the largest index ℓ so that v_ℓ is adjacent to an as-yet-unnumbered vertex is clearly $\ell = k$. So v_{k+1} is joined to v_k (and not to some v_i with $i < k$) in T . If $v_{k+1} = y$, we are done; y is a descendant of v_k . Otherwise, since v_k is still adjacent to an as-yet-unnumbered vertex, namely y , the choice of ℓ will be $\ell = k$ or $\ell = k + 1$, and v_{k+2} is adjacent to either v_k or v_{k+1} in T . If $v_{k+2} = y$, we are done; y is a descendant of v_k .

Inductively, *as long as y remains unnumbered*, $v_k, v_{k+1}, \dots, v_{k+j}$ will be descendants of v_k and the next choice of ℓ will be as one of $k, k + 1, \dots, k + j$. Then the vertex v_{k+j+1} numbered next will be adjacent to one of $v_k, v_{k+1}, \dots, v_{k+j}$ and hence will be a descendant of v_k . Since the graph is finite, eventually this newly numbered vertex must be y . \square

An *isthmus* of a connected graph G is an edge whose deletion results in a disconnected graph. (Some authors call this a *bridge*.)

Proposition 2.4. Let $\{x, y\}$ be an edge of T which is not an isthmus in G ; say x is the parent of y . Then there is an edge in G

but not in T joining some descendant a of y and some ancestor b of x .

PROOF: Let D be the set of descendants of y . So $y \in D$ and $x \notin D$. Since G with $\{x, y\}$ deleted is still connected, there is some edge $\{a, b\} \neq \{x, y\}$ with one end $a \in D$ and the other end $b \notin D$. This edge $\{a, b\}$ is certainly not in T and by Proposition 2.3, b is an ancestor of a (since it cannot be a descendant of a because then it would be a descendant of y too and hence would be in D). The (unique) path in T from a to v_0 passes through y (an ancestor of a) and then x (the parent of y); but b must be on this path (since it is an ancestor of a), so b must be an ancestor of x too. \square

Any directed graph obtained from an undirected graph G by assigning a direction to each edge of G is called an *orientation* of G . A walk in a digraph D may be called *strong* when each edge is traversed by the walk according to its direction, i.e. from its tail to its head, and the digraph D is *strongly connected* when for any two vertices x, y , there is a strong walk from x to y .

Theorem 2.5. Let G be a finite connected graph without isthmuses. Then G admits a strong orientation, i.e. an orientation that is a strongly connected digraph.

PROOF: We will construct a digraph D from G by choosing a direction for each edge. Find a depth-first search tree T and numbering v_0, v_1, \dots of the vertices of G . Let $\{v_i, v_j\}$ be an edge of G with $i < j$. If $\{v_i, v_j\}$ is in T , direct it from v_i to v_j , i.e. (v_i, v_j) is an edge of D . If $\{v_i, v_j\}$ is in not T , direct it from v_j to v_i , i.e. (v_j, v_i) is an edge of D .

It remains to show that D is strongly connected. There is a strong walk from v_0 to any vertex x of G (using only edges of the tree T), so it will suffice to show that we can find a strong walk from any vertex x to v_0 .

Given a vertex x_k , $k > 0$, Proposition 2.4 says that some edge $\{a, b\}$ in G but not in T joins some descendant a of y to some ancestor $b = v_i$ of v_k . We get a strong walk in D from v_k to v_i by appending the directed edge (a, v_i) to a strong walk in T from v_k to its descendant a . Of course, $i < k$ since v_i is an ancestor of v_k . If $i = 0$ we are done. Otherwise, we repeat the argument to find

a strong walk from v_i to some v_j with $j < i$ and concatenate the walks to get a strong walk from v_k to v_j . Continue in this manner until you reach v_0 . \square

Problem 2E. A *graceful labeling* of a tree T on n vertices is a mapping $f : V(T) \rightarrow \{1, 2, \dots, n\}$ so that the numbers $|f(x) - f(y)|$ computed across edges $\{x, y\}$ are all different. Show that the path-graphs (trees with exactly two monovalent vertices) admit graceful labelings. (It is conjectured that all trees admit graceful labelings.)

Problem 2F. Suppose a tree G has exactly one vertex of degree i for $2 \leq i \leq m$ and all other vertices have degree 1. How many vertices does G have?

Problem 2G. Let G be a graph with exactly one vertex of degree i for $2 \leq i \leq m$ and k other vertices, all of degree 1. Prove that $k \geq \lfloor \frac{m+3}{2} \rfloor$. Give a construction for such a graph.

Problem 2H. Consider labeled trivalent rooted trees T with $2n$ vertices, counting the root labeled $2n$; see Figure 14.3. The labels are chosen in such a way that the procedure leading to $\mathcal{P}(T)$ has $1, 2, 3, \dots, 2n - 1$ as first row. How many possible codes $\mathcal{P}(T)$ are there?

Notes.

A. Cayley (1821–1895), professor at Cambridge from 1863 until his death, was one of the great mathematicians of the 19th century. His work includes important contributions to the theory of elliptic functions, analytic geometry and algebra, e.g. the theory of invariants. His paper on trees appeared in 1889 but it did not contain what we would consider a proof. Of the many proofs (five of which are treated in this book) the one by Prüfer is the best known.

H. Prüfer (1896–1934) was one of I. Schur's many pupils. He was professor at Münster.

References.

A. Cayley (1889), A theorem on trees, *Quart. J. Pure and App. Math.* **23**, 376–378.

- Ö. Egecioğlu and J. B. Remmel (1986), Bijections for Cayley trees, spanning trees, and their q -analogues, *J. Combinatorial Theory (A)* **42**, 15–30.
- H. Prüfer (1918), Neuer Beweis eines Satzes über Permutationen, *Archiv der Math. und Phys.* (3) **27**, 142–144.

3

Colorings of graphs and Ramsey's theorem

We shall first look at a few so-called coloring problems for graphs.

A *proper coloring* of a graph G is a function from the vertices to a set C of 'colors' (e.g. $C = \{1, 2, 3, 4\}$) such that the ends of every edge have distinct colors. (So a graph with a loop will admit no proper colorings.) If $|C| = k$, we say that G is *k-colored*.

The *chromatic number* $\chi(G)$ of a graph G is the minimal number of colors for which a proper coloring exists.

If $\chi(G) = 2$ (or $\chi(G) = 1$, which is the case when and only when G has no edges), then G is called *bipartite*. A graph with no odd polygons (equivalently, no closed paths of odd length) is bipartite as the reader should verify.

The famous 'Four Color Theorem' (K. Appel and W. Haken, 1977) states that if G is planar, then $\chi(G) \leq 4$.

Clearly $\chi(K_n) = n$. If k is odd then $\chi(P_k) = 3$. In the following theorem, we show that, with the exception of these examples, the chromatic number is at most equal to the maximum degree (R. L. Brooks, 1941).

Theorem 3.1. *Let $d \geq 3$ and let G be a graph in which all vertices have degree $\leq d$ and such that K_{d+1} is not a subgraph of G . Then $\chi(G) \leq d$.*

PROOF 1: As is the case in many theorems in combinatorial analysis, one can prove the theorem by assuming that it is not true, then considering a *minimal* counterexample (in this case a graph with the minimal number of vertices) and arriving at a contradiction. We shall use the technique of recoloring: it is possible to change

the colors of certain vertices to go from one proper coloring to another. For example, let S be a subset of the set C of colors. On any connected component of the subgraph induced by the vertices with colors from S , we arbitrarily permute the colors (without changing those of the vertices with colors in $C \setminus S$). Clearly we again have a proper coloring.

So let G be a counterexample with the minimum number of vertices. Let $x \in G$ and let $\Gamma(x) = \{x_1, \dots, x_l\}$, $l \leq d$. Since G is a minimal counterexample, the graph H , obtained by deleting x and the edges incident with x , has a d -coloring, say with colors $1, 2, \dots, d$. If one of these colors is not used in the coloring of $\Gamma(x)$, then we can assign this color to x and obtain a d -coloring of G . It follows that $l = d$ and every d -coloring of H must use all the colors on the set $\Gamma(x)$. Let us assume that x_i has color i for $i = 1, 2, \dots, d$.

Now consider x_i and x_j and the induced subgraph H_{ij} of H with colors i and j . If x_i and x_j were in different connected components of H_{ij} , then we could interchange the colors in one of these components, after which x_i and x_j would have the same color, which is impossible. So x_i and x_j are in the same component (say C_{ij}) of H_{ij} . We shall now show that this component is (the graph of) a *simple path* (with alternating colors i and j) from x_i to x_j . If two neighbors of x_i in H had color j , then the neighbors of x_i in H would have at most $d - 2$ different colors. Then we could recolor x_i and that is impossible. Suppose y is the first vertex on a path from x_i to x_j in C_{ij} that has degree ≥ 3 . The neighbors of y in H have at most $d - 2$ colors, so we can recolor y to some color $\notin \{i, j\}$ and then x_i and x_j are no longer connected in H_{ij} , which we know to be impossible. So such a y does not exist, proving that C_{ij} is a path.

Suppose that z is a vertex $\neq x_i$ on C_{ij} and on C_{ik} . Then z has two neighbors with color j and two with color k . Again the neighbors of z in H have at most $d - 2$ colors and z can be recolored to some color $\notin \{i, j, k\}$, again a contradiction. Hence $C_{ij} \cap C_{ik} = \{x_i\}$.

Our assumption that $K_{d+1} \not\subseteq G$ shows that there are two vertices in $\Gamma(x)$, say x_1 and x_2 , that are not connected by an edge. We have the situation of Fig. 3.1. The vertex a is the neighbor of x_1 with color 2 on C_{12} .

We recolor H by interchanging the colors 1 and 3 on the subgraph C_{13} . For the new coloring, we have new paths that we call C'_{ij} . Clearly $a \in C'_{23}$ (since x_1 now has color 3). However, on C_{12} no point except x_1 has changed color, so $a \in C'_{12}$. Hence $C'_{12} \cap C'_{23} \neq \{x_2\}$, contradicting what we proved above. The contradiction shows that our assumption that a minimal counterexample exists is false. \square




Figure 3.1

In preparation for a second proof of Brook's Theorem, the reader should do the following problem without applying the theorem.

Problem 3A. Fix an integer $d \geq 3$. Let H be a simple graph with all degrees $\leq d$ which cannot be d -colored and which is minimal (with the fewest vertices) subject to these properties. (We claim H is complete on $d+1$ vertices, but we don't know that yet.) (i) Show that H is nonseparable (this means that every graph obtained from H by deleting a vertex is connected). (ii) Then show that if the vertex set $V(H)$ is partitioned into sets X and Y with $|Y| \geq 3$, then there are at least three vertices $a, b, c \in Y$ each of which is adjacent to at least one vertex in X .

PROOF 2: Let d and H be as in Problem 3A. If H is not complete, there are vertices x_1, x_{n-1}, x_n so that x_1 is adjacent to x_{n-1} and x_n but so that these last two vertices are not adjacent. We want to number the other $n - 3$ vertices so that the sequence

$$x_1, x_2, \dots, x_{n-1}, x_n$$

has the property that each x_k , $k \geq 2$, is adjacent to at least one of the vertices x_i preceding it, i.e. with $i < k$. This is simple: when x_1, x_2, \dots, x_k have been chosen, $k < n - 2$, choose x_{k+1} to be any

vertex other than x_{n-1} or x_n adjacent to one of x_1, x_2, \dots, x_k ; since there are at least three such vertices, this is always possible.

Once this is done, we d -color the vertices starting at the end of the sequence. Assign x_{n-1} and x_n the same color. When the last k vertices $x_{k+1}, \dots, x_{n-1}, x_n$ have been colored, $k \geq 2$, there is a color available for x_k since x_k is adjacent to at most $d - 1$ of the already-colored vertices. Finally, there is a color available for x_1 since two of the vertices adjacent to x_1 have been given the same color. \square

We now consider a coloring problem of a completely different nature. It serves as an introduction to a very important theorem of combinatorics, namely Ramsey's theorem. Before reading on, the reader should try the following problem.

Problem 3B. Let the edges of K_7 be colored with the colors red and blue. Show that there are at least four subgraphs K_3 with all three edges the same color (*monochromatic triangles*). Also show that equality can occur.

The example that is always used to introduce this subject is K_6 with its edges colored red or blue. We shall show that there is at least one monochromatic triangle. A proof is as follows. Let a be any vertex. Because a has degree 5, it is incident with at least three edges of the same color, say red edges to the vertices b, c, d . If one of the edges between these three vertices is red, then we have a red triangle; if not, then they form a blue triangle.

The idea of the proof is the same as for the more difficult situation of Ramsey's theorem. However, it does not show as much as the following counting argument.

Theorem 3.2. *If the edges of K_n are colored red or blue, and r_i , $i = 1, 2, \dots, n$, denotes the number of red edges with vertex i as an endpoint, and if Δ denotes the number of monochromatic triangles, then*

$$(3.1) \quad \Delta = \binom{n}{3} - \frac{1}{2} \sum_{i=1}^n r_i(n-1-r_i).$$

PROOF: Every triangle in K_n that is not monochromatic has exactly two vertices where a red and a blue edge meet. On the i -th

vertex, two such edges can be chosen in $r_i(n-1-r_i)$ ways. So the sum in (3.1) counts the bichromatic triangles twice. \square

Corollary.

$$(3.2) \quad \Delta \geq \binom{n}{3} - \lfloor \frac{n}{2} \lfloor (\frac{n-1}{2})^2 \rfloor \rfloor.$$

PROOF: From (3.1) we see that Δ is minimized if $r_i = (n-1-r_i)$ for all i when n is odd, or if $r_i = \frac{n}{2}$ or $r_i = \frac{n}{2} - 1$ for all i in the case that n is even. Since Δ is an integer, the first situation cannot always arise. It is easy to show that (3.2) cannot be improved. \square

Note that this argument shows that a red-blue coloring of K_6 must always have at least two monochromatic triangles.

We now treat Ramsey's theorem (Ramsey, 1930).

Theorem 3.3. *Let $r \geq 1$ and $q_i \geq r$, $i = 1, 2, \dots, s$ be given. There exists a minimal positive integer $N(q_1, q_2, \dots, q_s; r)$ with the following property. Let S be a set with n elements. Suppose that all $\binom{n}{r}$ r -subsets of S are divided into s mutually exclusive families T_1, \dots, T_s ('colors'). Then if $n \geq N(q_1, q_2, \dots, q_s; r)$ there is an i , $1 \leq i \leq s$, and some q_i -subset of S for which every r -subset is in T_i .*

(The reader should compare this with our introductory example and show that $N(3, 3; 2) = 6$.)

PROOF: We give the proof only for $s = 2$. The general case only involves a little more bookkeeping.

(a) Trivially, the theorem is true for $r = 1$ and $N(p, q; 1) = p + q - 1$.

(b) For any r and $p \geq r$ it is also obvious that $N(p, r; r) = p$ and similarly $N(r, q; r) = q$ for $q \geq r$.

(c) We proceed by induction on r . So assume the theorem is true for $r - 1$. We now use induction on $p + q$, using (b). So we can define $p_1 = N(p - 1, q; r)$, $q_1 = N(p, q - 1; r)$. Let S be a set with n elements, where $n \geq 1 + N(p_1, q_1; r - 1)$. Let the r -subsets of S be colored with two colors, say red and blue. As in the proof for K_6 , we pick an arbitrary element a of S . We now define a coloring of the $(r - 1)$ -subsets of $S' := S \setminus \{a\}$ by giving $X \subseteq S'$ the same

color as $X \cup \{a\}$. By induction S' either contains a subset A of size p_1 such that all its $(r-1)$ -subsets are red or a subset B of size q_1 such that all its $(r-1)$ -subsets are colored blue. Without loss of generality the first situation occurs. Since A has $N(p-1, q; r)$ elements, there are two possibilities. The first is that A has a subset of q elements with all its r -subsets blue, in which case we are done. The other possibility is that A has a subset A' of $p-1$ elements with all its r -subsets red. The set $A' \cup \{a\}$ also has this property because $A' \subseteq A$. This proves the theorem and furthermore we have shown

$$(3.3) \quad N(p, q; r) \leq N(N(p-1, q; r), N(p, q-1; r); r-1) + 1.$$

□

A special case of (3.3) occurs when we go back to the coloring of edges ($r=2$) of a graph with two colors. Using (a) from the proof, we find

$$(3.4) \quad N(p, q; 2) \leq N(p-1, q; 2) + N(p, q-1; 2).$$

Problem 3C. Show that equality cannot hold in (3.4) if both terms on the right-hand side are even.

Theorem 3.4.

$$N(p, q; 2) \leq \binom{p+q-2}{p-1}.$$

PROOF: Since $N(p, 2; 2) = p$, the result follows from (3.4) because binomial coefficients satisfy the same relation with equality. □

Let us look at what we now know about $N(p, q; 2)$. By Problem 3C, we have $N(3, 4; 2) \leq 9$. To show that equality holds, we have to color K_8 such that there is no red triangle and no blue K_4 . We do this as follows: number the vertices with the elements of \mathbb{Z}_8 . Let the edge $\{i, j\}$ be red if and only if $i-j \equiv \pm 3$ or $i-j \equiv 4 \pmod{8}$. One easily checks that this coloring does the job.

Problem 3D. Use the same method to show that $N(4, 4; 2) = 18$ and that $N(3, 5; 2) = 14$.

With a lot more work it has been shown that

$$N(3, 6; 2) = 18, \quad N(3, 7; 2) = 23, \quad N(3, 8; 2) = 28, \quad N(3, 9; 2) = 36,$$

$$N(4, 5; 2) = 25.$$

No other values of $N(p, q; 2)$ are known.

One of the interesting problems in this area that has seen virtually no progress for 30 years is the asymptotic behavior of $N(p, p; 2)$. We know by Theorem 3.4 that

$$(3.5) \quad N(p, p; 2) \leq \binom{2p-2}{p-1} \leq 2^{2p-2}.$$

We now show that $N(p, p; 2)$ grows exponentially, using a method that is used quite often in combinatorics. It is often referred to as ‘probabilistic’ since it estimates the probability that a random coloring has a monochromatic K_p . Consider a K_n . There are $2^{\binom{n}{2}}$ different ways of coloring the edges red or blue. Now fix a subgraph K_p . There are $2^{\binom{n}{2} - \binom{p}{2} + 1}$ colorings for which that K_p is monochromatic. The number of colorings for which some K_p is monochromatic is at most $\binom{n}{p}$ times as large (because we may count some colorings more than once). If this number is less than the total number of colorings, then there exist colorings with no monochromatic K_p . Using the fact that $\binom{n}{p} < n^p/p!$, we find that such a coloring certainly exists if $n < 2^{p/2}$ (unless $p = 2$). This proves the following theorem.

Theorem 3.5. $N(p, p; 2) \geq 2^{p/2}$.

From (3.5) and Theorem 3.5, we know that

$$\sqrt{2} \leq \sqrt[p]{N(p, p; 2)} \leq 4 \quad (p \geq 2).$$

It would be very nice if one could show that this p -th root has a limit for $p \rightarrow \infty$.

To give a considerable improvement of Theorem 3.5, we discuss a probabilistic method that is useful in many parts of combinatorics. We consider *events* A_1, A_2, \dots, A_n in a probability space. Denote by $Pr[A_i]$ the probability of the event A_i and, as usual, let $\overline{A_i}$ denote the complement of A_i , i.e. non-occurrence of A_i . We are interested in applications where the A_i denote situations we *do not* wish to occur and where we would like to assert that there is a

positive probability that *none* of the events A_i occurs. In some easy counting situations one can use

$$\sum_{i=1}^n Pr[A_i] < 1 \Rightarrow \cap \overline{A_i} \neq \emptyset.$$

Cf. Problem 5E. However, in general, dependence among the undesirable events leads to multiple counting which results in a sum that is much larger than 1. Of course, if the events A_i are independent, then it suffices that each has probability less than one to guarantee that non-occurrence of all of them has positive probability. The *Lovász Sieve* handles situations where there is indeed some dependence but simultaneously there are many obviously independent combinations of events.

We define what we shall call a *dependency graph* for the events A_1, \dots, A_n . This is a graph G on the set of indices $\{1, 2, \dots, n\}$ with the property that for *every* i the event A_i is independent of *every subset* of $\{A_j : \{i, j\} \notin E(G)\}$. Note that we require a lot more than that A_i is independent of each of the A_j in this subset.

Theorem 3.6. *Let G be some dependency graph for the events A_1, \dots, A_n . Suppose that $Pr[A_i] \leq p$, $i = 1, \dots, n$ and that every vertex in G has degree $\leq d$. If $4dp < 1$, then $\cap \overline{A_i} \neq \emptyset$.*

PROOF: We first show that for every subset $\{i_1, i_2, \dots, i_m\}$ of the index set,

$$(3.6) \quad Pr[A_{i_1} | \overline{A_{i_2}} \dots \overline{A_{i_m}}] \leq \frac{1}{2d}.$$

The case $m = 1$ is trivial and for $m = 2$ we have

$$Pr[A_1 | \overline{A_2}] \leq \frac{p_1}{1 - p_2} \leq \frac{1}{4d - 1} < \frac{1}{2d},$$

where for convenience of notation we have taken $i_j = j$ and $p_i := Pr[A_i]$. We proceed by induction.

Suppose that in G , 1 is adjacent to 2, 3, \dots , q and not adjacent to $q + 1, \dots, m$. We have

$$Pr[A_1 | \overline{A_2} \dots \overline{A_m}] = \frac{Pr[A_1 \overline{A_2} \dots \overline{A_q} | \overline{A_{q+1}} \dots \overline{A_m}]}{Pr[\overline{A_2} \dots \overline{A_q} | \overline{A_{q+1}} \dots \overline{A_m}]}.$$

The numerator is (by definition of G) at most

$$Pr[A_1 | \overline{A_{q+1}} \dots \overline{A_m}] = Pr[A_1] \leq \frac{1}{4d}.$$

Using the induction hypothesis, we find that the denominator is at least

$$1 - \sum_{i=2}^q Pr[A_1 | \overline{A_{q+1}} \dots \overline{A_m}] \geq 1 - \frac{q-1}{2d} \geq \frac{1}{2}.$$

This proves (3.6). We now have

$$Pr[\overline{A_1} \dots \overline{A_n}] = \prod_{i=1}^n Pr[\overline{A_i} | \overline{A_1} \dots \overline{A_{i-1}}] \geq (1 - \frac{1}{2d})^n > 0,$$

where we have used (3.6) for each term in the product. \square

We apply this method to obtain a lower bound for $N(p, p; 2)$.

Theorem 3.7. $N(p, p; 2) \geq c \cdot p \cdot 2^{p/2}$, where c is a constant.

PROOF: Consider K_n and color the edges randomly with two colors. For each set S of k vertices let A_S be the event that the subgraph on S is colored monochromatically. We wish to assert that among the random colorings, there is at least one in which no monochromatic subgraph on k vertices occurs. We define a dependency graph by making S and T adjacent if and only if $|S \cap T| \geq 2$, i.e. the subgraphs on S and T have an edge in common. The degree d of G is clearly at most $\binom{k}{2} \binom{n}{k-2}$. The events A_S all have probability $2^{1-\binom{k}{2}}$. From Theorem 3.6, Stirling's formula and a little manipulation, we find the result (and if we wish an estimate for c). \square

We have given some examples of an area of combinatorics known as Ramsey theory. We just mention one more example, namely a theorem due to B. L. van der Waerden (1927). It states that there exists a number $N(r)$ such that if $N \geq N(r)$ and the integers from 1 to N are colored red or blue, then there is a monochromatic arithmetic progression of length r in the set. For a short (but not easy) proof see Graham and Rothschild (1974). A general reference

for this area is the book *Ramsey Theory* by R. L. Graham, B. L. Rothschild and J. L. Spencer (1980).

An interesting application of Ramsey's theorem is the following theorem due to Erdős and Szekeres (1935).

Theorem 3.8. *For a given n , there is an integer $N(n)$ such that any collection of $N \geq N(n)$ points in the plane, no three on a line, has a subset of n points forming a convex n -gon.*

PROOF: (i) First we observe that if we have n points, no three on a line, then they form a convex n -gon if and only if every quadrilateral formed by taking four of the points is convex.

(ii) We now claim that $N(n) = N(n, n; 3)$ will do the job. Let S be a set of $N(n)$ points. Number the points and then color triangles red, respectively blue, if the path from the smallest number via the middle one to the largest number is clockwise, respectively counterclockwise. There is an n -subset with all its triangles the same color, say red. We shall show that this set cannot contain the configuration of Fig. 3.2.




Figure 3.2

Without loss of generality $a < b < c$. From triangle adc , we see that $a < d < c$. Then from triangle abd it follows that $a < b < d$. But then triangle bcd is blue, a contradiction. So all quadrilaterals formed from the n -subset are convex and by (i), we are done. \square

Problem 3E. A *tournament* on n vertices is an orientation of K_n . A *transitive tournament* is a tournament for which the vertices can be numbered in such a way that (i, j) is an edge if and only if $i < j$.

(a) Show that if $k \leq \log_2 n$, every tournament on n vertices has a transitive subtournament on k vertices.

(b) Show that if $k > 1 + 2 \log_2 n$, there exists a tournament on n vertices with no transitive subtournament on k vertices.

Problem 3F. Prove that for all $r \in \mathbb{N}$ there is a minimal number $N(r)$ with the following property. If $n \geq N(r)$ and the integers in $\{1, 2, \dots, n\}$ are colored with r colors, then there are three elements x, y, z (not necessarily distinct) with the same color and $x + y = z$. (A result due to I. Schur.) Determine $N(2)$. Show by an elementary argument that $N(3) > 13$.

Problem 3G. Let m be given. Show that if n is large enough, every $n \times n$ $(0, 1)$ -matrix has a principal submatrix of size m , in which all the elements below the diagonal are the same, and all the elements above the diagonal are the same.

Problem 3H. Show that if the edges of K_{17} are colored with three colors, there must be a monochromatic triangle.

Problem 3I. Let $\{1, \alpha, \alpha^2, \dots, \alpha^{14}\}$ be the multiplicative group of \mathbb{F}_{16} . Number the vertices of K_{16} with the elements of \mathbb{F}_{16} . We will color the edges of K_{16} with three colors. Edge $\{i, j\}$ is to be colored with a color that depends only on ν , where $i - j = \alpha^\nu$. Do this in such a way that there is *no* monochromatic triangle. (In the notation of Theorem 3.3, this problem and the previous one show that $N(3, 3, 3; 2) = 17$.)

Problem 3J. The edges of K_n are colored red and blue in such a way that a red edge is in at most one red triangle. Show that there is a subgraph K_k with $k \geq \lfloor \sqrt{2n} \rfloor$ that contains *no* red triangle.

Problem 3K. Let G satisfy the conditions of Theorem 3.1. Show that by removing at most n/d edges we can find a subgraph G' with chromatic number $\leq d - 1$.

Notes.

The four color conjecture was considered one of the most famous open problems in combinatorics until 1976. Its solution by Appel and Haken has caused much debate because the proof depends on an extensive computer analysis of many cases. The validity of the argument depends on one's trust in computers and programs. (See Chapter 34 for two proofs of the Five Color Theorem.)

The theorem by Brooks, Theorem 3.1, which he discovered while an undergraduate at Cambridge, is a typical example of the inge-

nious arguments that are quite often necessary in that part of graph theory where algebraic methods do not apply.

F. P. Ramsey (1902–1928) died too young to produce the results that he probably would have. He was interested in decision procedures for logical systems and, strangely enough, this led to the theorem that in turn led to so-called Ramsey theory.

Theorem 3.5 is due to P. Erdős (1947). For more on probabilistic methods, see Erdős and Spencer (1974).

Values of and estimates for the numbers $N(p, q; 2)$ can be found in Radziszowski (1999). The value of $N(3, 9; 2)$ is from Grinstead and Roberts (1982).

The proof of Theorem 3.6 is not the original proof by Erdős and Szekeres that one usually finds in books. This proof was produced by a student in Haifa (M. Tarsy) during an examination! He had missed the class in which the proof had been presented. See Lewin (1976). A proof in a similar vein was given by Johnson (1986).

References.

- K. Appel and W. Haken (1977), Every planar map is four-colorable, *Illinois J. Math.* **21**, 429–567.
- R. L. Brooks (1941), On colouring the nodes of a network, *Cambridge Philos. Soc.* **37**, 194–197.
- P. Erdős (1947), Some remarks on the theory of graphs, *Bull. Amer. Math. Soc.* **53**, 292–294.
- P. Erdős and J. L. Spencer (1974), *Probabilistic Methods in Combinatorics*, Academic Press.
- P. Erdős and G. Szekeres (1935), A combinatorial problem in geometry, *Compositio Math.* **2**, 463–470.
- R. L. Graham and B. L. Rothschild (1974), A short proof of van der Waerden's theorem on arithmetic progressions, *Proc. Amer. Math. Soc.* **42**, 385–386.
- R. L. Graham, B. L. Rothschild, and J. L. Spencer (1980), *Ramsey Theory*, Wiley.
- C. M. Grinstead and S. M. Roberts (1982), On the Ramsey numbers $R(3, 8)$ and $R(3, 9)$, *J. Combinatorial Theory (B)* **33**, 27–51.
- S. Johnson (1986), A new proof of the Erdős–Szekeres convex k -gon result, *J. Combinatorial Theory (A)* **42**, 318–319.

- M. Lewin (1976), A new proof of a theorem of Erdős and Szekeres, *The Math. Gazette* **60**, 136–138, 298.
- S. P. Radziszowski (1999), Small Ramsey Numbers, *The Electronic Journal of Combinatorics* **1** DS 1.
- F. P. Ramsey (1930), On a problem of formal logic, *Proc. London Math. Soc.* (2) **30**, 264–286.
- B. L. van der Waerden (1927), Beweis einer Baudetschen Vermutung, *Nieuw Archief voor Wiskunde* **15**, 212–216.

4

Turán's theorem and extremal graphs

As an introduction, we first ask the question how many edges a simple graph must have to guarantee that the graph contains a *triangle*. Since $K_{m,m}$ and $K_{m,m+1}$ do not contain triangles, we see that if the graph has n vertices, then $\lfloor n^2/4 \rfloor$ edges are not enough. We claim that if there are more edges, then the graph contains a triangle (W. Mantel, 1907). The following proof is surprising. Let G have n vertices, numbered from 1 to n , and no triangles. We give vertex i a weight $z_i \geq 0$ such that $\sum z_i = 1$ and we wish to maximize $S := \sum z_i z_j$, where the sum is taken over all edges $\{i, j\}$. Suppose that vertex k and vertex l are not joined. Let the neighbors of k have total weight x , and those of l total weight y , where $x \geq y$. Since $(z_k + \epsilon)x + (z_l - \epsilon)y \geq z_k x + z_l y$, we do not decrease the value of S if we shift some of the weight of vertex l to the vertex k . It follows that S is maximal if all of the weight is concentrated on some complete subgraph of G , i.e. on *one* edge! Therefore $S \leq \frac{1}{4}$. On the other hand, taking all z_i equal to n^{-1} would yield a value of $n^{-2}|E|$ for S . Therefore $|E| \leq \frac{1}{4}n^2$.

Note that Ramsey's theorem states that if a graph on n vertices has $n \geq N(p, q; 2)$, then the graph either has a complete subgraph on p vertices or a set of q vertices with no edges between them (called an *independent* set). We now ask the question whether some condition on the number of edges guarantees a K_p as a subgraph. We saw above what the answer is for $p = 3$. We also already have an idea of how to avoid a K_p . Divide the vertices into $p - 1$ subsets S_1, \dots, S_{p-1} of almost equal size, i.e. r subsets of size $t + 1$ and $p - 1 - r$ subsets of size t , where $n = t(p - 1) + r$, $1 \leq r \leq p - 1$. Within each S_i there are no edges but every vertex in S_i is joined to

every vertex in S_j if $i \neq j$. (This is a *complete multipartite graph*.) The number of edges is

$$M(n, p) := \frac{p-2}{2(p-1)}n^2 - \frac{r(p-1-r)}{2(p-1)}.$$

Theorem 4.1. (Turán, 1941) *If a simple graph on n vertices has more than $M(n, p)$ edges, then it contains a K_p as a subgraph.*

PROOF: The proof is by induction on t . If $t = 0$, the theorem is obvious. Consider a graph G with n vertices, no K_p , and the maximum number of edges subject to those properties. Clearly G contains a K_{p-1} (otherwise adding an edge would not produce a K_p), say H . Each of the remaining vertices is joined to at most $p-2$ vertices of H . The remaining $n-p+1$ vertices do not contain a K_p as subgraph. Since $n-p+1 = (t-1)(p-1) + r$, we can apply the induction hypothesis to this set of points. So the number of edges of G is at most

$$M(n-p+1, p) + (n-p+1)(p-2) + \binom{p-1}{2}$$

and this number is equal to $M(n, p)$. □

Remark. The argument that was used for Mantel's theorem would show that if there is no K_p , then $|E| \leq \frac{p-2}{2(p-1)}n^2$.

Problem 4A. Let G be a simple graph with 10 vertices and 26 edges. Show that G has at least 5 triangles. Can equality occur?

Turán's paper on graph theory that contains Theorem 4.1 is considered the starting point of what is now known as extremal graph theory—see Bollobás (1978). A simple instance of an extremal problem will ask for the maximum number of edges a graph with a certain property may have. The graphs whose number of edges is maximum are called the *extremal graphs* with respect to the property.

The extremal graphs for Turán's problem are *only* the complete multipartite graphs described above. This follows from an analysis of the proof of Theorem 4.1; we ask the reader to do this at least in the case $p = 3$ in the problem below.

Problem 4B. Show that a simple graph on n vertices with $\lfloor n^2/4 \rfloor$ edges and no triangles is a complete bipartite graph $K_{k,k}$ if $n = 2k$, or $K_{k,k+1}$ if $n = 2k + 1$.

Problem 4C. If a simple graph on n vertices has e edges, then it has at least $\frac{e}{3n}(4e - n^2)$ triangles.

The *girth* of a graph G is the size of a smallest polygon P_n in G . (A forest has infinite girth.) By definition, a graph is simple if and only if it has girth ≥ 3 . By Mantel's theorem, a graph with more than $n^2/4$ edges has girth ≤ 3 .

Theorem 4.2. *If a graph G on n vertices has more than $\frac{1}{2}n\sqrt{n-1}$ edges, then G has girth ≤ 4 . That is, G is not simple or contains a P_3 or a P_4 (a triangle or a quadrilateral).*

PROOF: Suppose G has girth ≥ 5 . Let y_1, y_2, \dots, y_d be the vertices adjacent to a vertex x , where $d := \deg(x)$. No two of these are adjacent since G has no triangles. Moreover, no vertex (other than x) can be adjacent to more than one of y_1, \dots, y_d since there are no quadrilaterals in G . Thus $(\deg(y_1) - 1) + \dots + (\deg(y_d) - 1) + (d + 1)$ cannot exceed the total number n of vertices. That is,

$$\sum_{y \text{ adjacent to } x} \deg(y) \leq n - 1.$$

Then

$$\begin{aligned} n(n-1) &\geq \sum_x \sum_{y \text{ adjacent to } x} \deg(y) = \sum_y \deg(y)^2 \\ &\geq \frac{1}{n} \left(\sum_y \deg(y) \right)^2 = \frac{1}{n} (2|E(G)|)^2. \end{aligned}$$

□

The number $\frac{1}{2}n\sqrt{n-1}$ in Theorem 4.2 is only a bound—it is not the exact answer for all n . Determination of the extremal graphs for this problem (maximum number of edges subject to girth ≥ 5) for all values of n is impossibly difficult; a determination of the graphs for which equality holds has, however, been almost possible.

Perhaps surprisingly, there are at most four graphs with $n > 2$ vertices, girth ≥ 5 , and $\frac{1}{2}n\sqrt{n-1}$ edges: The pentagon ($n = 5$), the Petersen graph ($n = 10$), one with $n = 50$, and possibly one with $n = 3250$. See the notes and Chapter 21.

Problem 4D. Suppose G is regular of degree r and has girth g or greater. Find a lower bound for $|V(G)|$. (Consider the cases g even and odd separately.)

It is not so interesting to ask how many edges are required to force a Hamiltonian circuit. But we can ask what bound on the minimum degree will do the job.

Theorem 4.3. *If a simple graph G on n vertices has all vertices of degree at least $n/2$, then it contains a P_n as a subgraph, i.e. it has a Hamiltonian circuit.*

PROOF: Suppose the theorem is not true and let G be a graph satisfying the hypothesis for some n but having no Hamiltonian circuits. We may take G to be such a counterexample with the maximum number of edges; then the addition of any edge to G (i.e. joining two nonadjacent vertices by an edge) creates a Hamiltonian circuit.

Let y and z be nonadjacent vertices. Since adding $\{y, z\}$ creates a Hamiltonian circuit, there exists a simple path from y to z with vertex terms, $y = x_1, x_2, \dots, x_n = z$, say. The sets

$$\{i : y \text{ is adjacent to } x_{i+1}\}$$

and

$$\{i : z \text{ is adjacent to } x_i\}$$

each have cardinality $\geq n/2$ and are contained in $\{1, 2, 3, \dots, n-1\}$, so they must meet; let i_0 belong to both. Then

$$y = x_1, x_2, \dots, x_{i_0}, z = x_n, x_{n-1}, \dots, x_{i_0+1}, x_1 = y$$

is the vertex sequence of a simple closed path of length n in G , contradicting our choice of G as a counterexample. \square

Theorem 4.3 is due to G. A. Dirac and is best possible at least in the sense that it does not remain true if we replace $n/2$ by

$(n - 1)/2$. For example, the complete bipartite graphs $K_{k,k+1}$ have no Hamiltonian circuits. But it does admit improvements and generalizations—see e.g. Lovász (1979), Problem 10.21.

Problem 4E. A $3 \times 3 \times 3$ cube of cheese is divided into 27 $1 \times 1 \times 1$ small cubes. A mouse eats one small cube each day and an *adjacent* small cube (sharing a face) the next day. Can the mouse eat the *center* small cube on the last day?

Problem 4F. Let G be a simple graph with n vertices. Prove: If each vertex of G has degree $\geq (n + 1)/2$, then for any edge e , there exists a Hamiltonian circuit of G that passes through e .

Problem 4G. Prove the remark following Theorem 4.1.

Problem 4H. Show that a graph on n vertices that does not contain a circuit on four vertices has at most $\frac{n}{4}(1 + \sqrt{4n - 3})$ edges.

Notes.

P. Turán (1910–1976), one of the famous Hungarian mathematicians of the 20th century, is best known for his work in analytic number theory and real and complex analysis.

For every $r \geq 2$ and $g \geq 2$, there exists a graph that is regular of degree r and has girth $\geq g$. See Lovász (1979), Problem 10.12.

Analysis of the proof of Theorem 4.2 shows that a graph with $n > 2$ vertices, girth ≥ 5 , and $\frac{1}{2}n\sqrt{n - 1}$ edges is regular of degree $k := \sqrt{n - 1}$ and also that any two vertices are joined by a (unique) path of length 2 if they are not adjacent. With the notation of Chapter 21, such a graph is an $srg(n, k, 0, 1)$ and the methods of that chapter show that $k = 2, 3, 7$, or 57. This was first shown in Hoffman and Singleton (1960) where in addition an example with $k = 7$ and $n = 50$ was described (that is now known as the *Hoffman-Singleton graph*). It is not known at this time whether there exists an $srg(3250, 57, 0, 1)$.

References.

- B. Bollobás (1978), *Extremal Graph Theory*, Academic Press.
 A. J. Hoffman and R. R. Singleton (1960), On Moore graphs with diameters two and three, *IBM J. Res. Develop.* **4**, 497–504.

- L. Lovász (1979), *Combinatorial Problems and Exercises*, North Holland.
- W. Mantel (1907), Problem 28, *Wiskundige Opgaven* **10**, 60–61.
- P. Turán (1941), An extremal problem in graph theory (in Hungarian), *Mat. Fiz. Lapok* **48**, 435–452.

5

Systems of distinct representatives

We first give two different formulations of a theorem known as P. Hall's *marriage theorem*. We give a constructive proof and an enumerative one. If A is a subset of the vertices of a graph, then denote by $\Gamma(A)$ the set $\bigcup_{a \in A} \Gamma(a)$. Consider a bipartite graph G with vertex set $X \cup Y$ (every edge has one endpoint in X and one in Y). A *matching* in G is a subset E_1 of the edge set such that no vertex is incident with more than one edge in E_1 . A *complete matching* from X to Y is a matching such that every vertex in X is incident with an edge in E_1 . If the vertices of X and Y are thought of as boys and girls, respectively, or vice versa, and an edge is present when the persons corresponding to its ends have amicable feelings towards one another, then a complete matching represents a possible assignment of marriage partners to the persons in X .

Theorem 5.1. *A necessary and sufficient condition for there to be a complete matching from X to Y in G is that $|\Gamma(A)| \geq |A|$ for every $A \subseteq X$.*

PROOF: (i) It is obvious that the condition is necessary.

(ii) Assume that $|\Gamma(A)| \geq |A|$ for every $A \subseteq X$. Let $|X| = n$, $m < n$, and suppose we have a matching M with m edges. We shall show that a larger matching exists. (We mean larger in *cardinality*; we may not be able to find a complete matching containing these particular m edges.)

Call the edges of M red and all other edges blue. Let $x_0 \in X$ be a vertex not incident with an edge of the matching. We claim that there exists a simple path (of odd length) starting with x_0 and a blue edge, using red and blue edges alternately, and terminating

with a blue edge and a vertex y not incident with an edge of the matching. If we find such a path p , we are done because we obtain a matching with $m + 1$ edges by deleting the red edges of p from M and replacing them with the blue edges of p . In other words, we switch the colors on the edges of p .

Since $|\Gamma(\{x_0\})| \geq 1$, there is a vertex y_1 adjacent to x_0 (obviously by a blue edge since x_0 is not incident with any red edges). If y_1 is also not incident with any red edges, we have the required path (of length one); if y_1 is incident with a red edge, let x_1 be the other end of that red edge. Recursively, define x_0, x_1, \dots and y_1, y_2, \dots as follows. If x_0, x_1, \dots, x_k and y_1, \dots, y_k have been defined, then since $|\Gamma(\{x_0, x_1, \dots, x_k\})| \geq k + 1$, there exists a vertex y_{k+1} , distinct from y_1, \dots, y_k , that is adjacent to at least one vertex in $\{x_0, x_1, \dots, x_k\}$. If y_{k+1} is not incident with a red edge, stop; otherwise, let x_{k+1} be the other end of that red edge.

When the procedure terminates, we construct the path p by starting with y_{k+1} and the blue edge joining it to, say, x_{i_1} , $i_1 < k + 1$. Then add the red edge $\{x_{i_1}, y_{i_1}\}$. By construction, y_{i_1} is joined by an edge (necessarily blue) to some x_{i_2} , $i_2 < i_1$. Then add the red edge $\{x_{i_2}, y_{i_2}\}$. Continue in this way until x_0 is reached. \square

Problem 5A. A *perfect* matching in a graph G (not necessarily bipartite) is a matching so that each vertex of G is incident with one edge of the matching. (i) Show that a finite *regular* bipartite graph (regular of degree $d > 0$) has a perfect matching. (ii) Find a trivalent (regular of degree 3) simple graph which does not have a perfect matching. (iii) Suppose G is bipartite with vertices $X \cup Y$ (every edge having one end in X and one in Y). Further assume that every vertex in X has the same degree $s > 0$ and every vertex in Y has the same degree t . (This condition is called *semiregularity*.) Prove: If $|X| \leq |Y|$ (equivalently, if $s \geq t$), then there is a complete matching M of X into Y .

Example 5.1. A parlor trick involving a standard deck of 52 cards is as follows. You are dealt five cards at random. You keep one and put the other four (in a specific order) into an envelope which is taken to your partner in another room. Your partner looks at these and announces the name of the fifth card, that you had retained.

Using the values of suits and ranks, it is possible to think of clever

or relatively simple ways to determine which card to keep and which to pass, and for the partner to determine the retained card; see the notes. Ignoring complexity of solution, however, the relevant general mathematical problem, stated for a deck of N cards, is does there exist an injective mapping f from the set X of the $\binom{N}{5}$ 5-element subsets of the N cards into the set Y of $N(N-1)(N-2)(N-3)$ ordered 4-tuples of distinct cards, subject to the condition that if $f(S) = (c_1, c_2, c_3, c_4)$, then $\{c_1, c_2, c_3, c_4\} \subseteq S$.

In terms of matchings, we consider the bipartite graph G whose vertices are $X \cup Y$ as defined above, and where there is an edge joining $S \in X$ to $\{c_1, c_2, c_3, c_4\} \in Y$ exactly when $\{c_1, c_2, c_3, c_4\} \subseteq S$. We require a complete matching M of X into Y . The reader may check that G is semiregular and that $|X| \leq |Y|$ if and only if $N \leq 124$. So by Problem 5A(iii), for $N \leq 124$, there exists such a matching.

We now reformulate Theorem 5.1 in terms of sets and not only prove the theorem but also give a lower bound for the number of matchings. We consider subsets A_0, A_1, \dots, A_{n-1} of a finite set S . We shall say that this collection has property H (Hall's condition) if (for all k) the union of any k -tuple of subsets A_i has at least k elements. If the union of some k -tuple of subsets contains exactly k elements ($0 < k < n$), then we call this k -tuple a *critical block*.

We define a *system of distinct representatives* (SDR) of the sets A_0, \dots, A_{n-1} to be a sequence of n *distinct* elements a_0, \dots, a_{n-1} with $a_i \in A_i$, $0 \leq i \leq n-1$.

Let $m_0 \leq m_1 \leq \dots \leq m_{n-1}$. We define

$$F_n(m_0, m_1, \dots, m_{n-1}) := \prod_{i=0}^{n-1} (m_i - i)_*,$$

where $(a)_* := \max\{1, a\}$.

From now on, we assume that the sequence $m_i := |A_i|$ is nondecreasing.

For the proof of the main theorem, we need a lemma.

Lemma 5.2. For $n \geq 1$, let $f_n : \mathbb{Z}^n \rightarrow \mathbb{N}$ be defined by

$$f_n(a_0, a_1, \dots, a_{n-1}) := F_n(m_0, m_1, \dots, m_{n-1})$$

if (m_0, \dots, m_{n-1}) is a nondecreasing rearrangement of the n -tuple (a_0, \dots, a_{n-1}) . Then f_n is nondecreasing with respect to each of the variables a_i .

PROOF: Let

$$m_0 \leq \dots \leq m_{k-1} \leq a_i = m_k \leq m_{k+1} \leq \dots \\ \leq m_l \leq m_{l+1} \leq \dots \leq m_{n-1}$$

be a nondecreasing rearrangement of (a_0, \dots, a_{n-1}) . If $a'_i \geq a_i$ and

$$m_0 \leq \dots \leq m_{k-1} \leq m_{k+1} \leq \dots \leq m_l \leq a'_i \leq m_{l+1} \leq \dots \leq m_{n-1}$$

is a nondecreasing rearrangement of $(a_0, \dots, a_{i-1}, a'_i, a_{i+1}, \dots, a_{n-1})$ then

$$\frac{f_n(a_0, \dots, a_{i-1}, a'_i, a_{i+1}, \dots, a_{n-1})}{f_n(a_0, \dots, a_{n-1})} = \\ = \frac{(m_{k+1} - k)_*}{(a_i - k)_*} \cdot \frac{(a'_i - l)_*}{(m_l - l)_*} \prod_{j=k+1}^{l-1} \frac{(m_{j+1} - j)_*}{(m_j - j)_*}$$

and this is ≥ 1 since $a_i \leq m_{k+1}$, $a'_i \geq m_l$, and $m_{j+1} \geq m_j$ for $j = k+1, \dots, l-1$. \square

We now come to the second form of Hall's theorem. We denote by $N(A_0, \dots, A_{n-1})$ the number of SDRs of (A_0, \dots, A_{n-1}) .

Theorem 5.3. *Let (A_0, \dots, A_{n-1}) be a sequence of subsets of a set S . Let $m_i := |A_i|$ ($i = 0, \dots, n-1$) and let $m_0 \leq m_1 \leq \dots \leq m_{n-1}$. If the sequence has property H , then*

$$N(A_0, \dots, A_{n-1}) \geq F_n(m_0, \dots, m_{n-1}).$$

PROOF: The proof is by induction. Clearly the theorem is true for $n = 1$. We distinguish two cases.

Case 1. There is no critical block. In this case, we choose any element a of A_0 as its representative and then remove a from all the other sets. This yields sets, that we call $A_1(a), \dots, A_{n-1}(a)$, and

for these sets property H still holds. By the induction hypothesis and by the lemma, we find

$$\begin{aligned}
 N(A_0, \dots, A_{n-1}) &\geq \sum_{a \in A_0} f_{n-1}(|A_1(a)|, \dots, |A_{n-1}(a)|) \\
 &\geq \sum_{a \in A_0} f_{n-1}(m_1 - 1, \dots, m_{n-1} - 1) \\
 &= m_0 f_{n-1}(m_1 - 1, \dots, m_{n-1} - 1) \\
 &= F_n(m_0, m_1, \dots, m_{n-1}).
 \end{aligned}$$

Case 2. There is a critical block $(A_{\nu_0}, \dots, A_{\nu_{k-1}})$ with $\nu_0 < \dots < \nu_{k-1}$ and $0 < k < n$. In this case, we delete all elements of $A_{\nu_0} \cup \dots \cup A_{\nu_{k-1}}$ from all the other sets A_i which produces $A'_{\mu_0}, \dots, A'_{\mu_{l-1}}$, where $\{\nu_0, \dots, \nu_{k-1}, \mu_0, \dots, \mu_{l-1}\} = \{0, 1, \dots, n-1\}$, $k+l=n$.

Now both $(A_{\nu_0}, \dots, A_{\nu_{k-1}})$ and $(A'_{\mu_0}, \dots, A'_{\mu_{l-1}})$ satisfy property H and SDRs of the two sequences are always disjoint. Hence by the induction hypothesis and the lemma, we have

$$\begin{aligned}
 (5.1) \quad N(A_0, \dots, A_{n-1}) &= N(A_{\nu_0}, \dots, A_{\nu_{k-1}}) N(A'_{\mu_0}, \dots, A'_{\mu_{l-1}}) \\
 &\geq f_k(m_{\nu_0}, \dots, m_{\nu_{k-1}}) f_l(|A'_{\mu_0}|, \dots, |A'_{\mu_{l-1}}|) \\
 &\geq f_k(m_{\nu_0}, \dots, m_{\nu_{k-1}}) f_l(m_{\mu_0} - k, \dots, m_{\mu_{l-1}} - k) \\
 &\geq f_k(m_0, \dots, m_{k-1}) f_l(m_{\mu_0} - k, \dots, m_{\mu_{l-1}} - k).
 \end{aligned}$$

Now we remark that

$$m_{\nu_{k-1}} \leq |A_{\nu_0} \cup \dots \cup A_{\nu_{k-1}}| = k,$$

and therefore we have

$$(m_r - r)_* = 1 \quad \text{if } k \leq r \leq \nu_{k-1},$$

and

$$(m_{\mu_i} - k - i)_* = 1 \quad \text{if } \mu_i \leq \nu_{k-1}.$$

This implies that

$$\begin{aligned}
 f_k(m_0, \dots, m_{k-1}) &= \prod_{0 \leq i \leq \nu_{k-1}} (m_i - i)_*, \\
 f_l(m_{\mu_0} - k, \dots, m_{\mu_{l-1}} - k) &= \prod_{\nu_{k-1} < j < n} (m_j - j)_*,
 \end{aligned}$$

i.e. the product (5.1) is equal to $F_n(m_0, \dots, m_{n-1})$, which proves the theorem. \square

Problem 5B. Show that Theorem 5.3 gives the best lower bound for the number of SDRs of the sets A_i that only involves the numbers $|A_i|$.

We now come to a theorem known as König's theorem. It is equivalent (whatever that means) to Hall's theorem. In the theorem, A is a $(0,1)$ -matrix with entries a_{ij} . By a *line*, we mean a row or a column of A .

Theorem 5.4. *The minimum number of lines of A that contain all the 1's of A is equal to the maximum number of 1's in A , no two on a line.*

PROOF: Let m be the minimum number of lines of A containing all the 1's of A and let M be the maximum number of 1's, no two on a line. Clearly $m \geq M$. Let the minimum covering by lines consist of r rows and s columns ($r + s = m$). Without loss of generality, these are the first r rows and the first s columns. We now define sets A_i , $1 \leq i \leq r$, by $A_i := \{j > s : a_{ij} = 1\}$. If some k -tuple of the A_i 's contained less than k elements, then we could replace the corresponding k rows by $k - 1$ columns, still covering all the 1's. Since this is impossible, we see that the A_i 's satisfy property H . So the A_i 's have an SDR. This means that there are r 1's, no two on a line, in the first r rows and not in the first s columns. By the same argument there are s 1's, no two on a line, in the first s columns and not in the first r rows. This shows that $M \geq r + s = m$ and we are done. \square

The following theorem of G. Birkhoff is an application of Hall's theorem.

Theorem 5.5. *Let $A = (a_{ij})$ be an $n \times n$ matrix with nonnegative integers as entries, such that every row and column of A has sum l . Then A is the sum of l permutation matrices.*

PROOF: Define A_i , $1 \leq i \leq n$, by $A_i := \{j : a_{ij} > 0\}$. For any k -tuple of the A_i 's, the sum of the corresponding rows of A is kl . Since every column of A has sum l , the nonzero entries in the

chosen k rows must be in at least k columns. Hence the A_i 's satisfy property H . An SDR of the A_i 's corresponds to a permutation matrix $P = (p_{ij})$ such that $a_{ij} > 0$ if $p_{ij} = 1$. The theorem now follows by induction on l . \square

Problem 5C. In the hypothesis of Theorem 5.5, we replace 'integers' by 'reals'. Show that in this case, A is a nonnegative linear combination of permutation matrices. (Equivalently, every doubly stochastic matrix—see Chapter 11—is a *convex* combination of permutation matrices.)

Problem 5D. Let S be the set $\{1, 2, \dots, mn\}$. We partition S into m sets A_1, \dots, A_m of size n . Let a second partitioning into m sets of size n be B_1, \dots, B_m . Show that the sets A_i can be renumbered in such a way that $A_i \cap B_i \neq \emptyset$.

Problem 5E. Let $A_i = \{i-1, i, i+1\} \cap \{1, 2, \dots, n\}$, $i = 1, 2, \dots, n$. Let S_n denote the number of SDR's of the collection $\{A_1, \dots, A_n\}$. Determine S_n and $\lim_{n \rightarrow \infty} S_n^{1/n}$.

Let G be a bipartite graph, finite or infinite; say the vertex set is partitioned into sets X, Y of vertices so that every edge of G has one end in X and one end in Y . We say that a matching M in G *covers* a subset S of the vertices when every vertex in S is incident with one of the edges in M .

Theorem 5.6. *If there exists a matching M_1 that covers a subset X_0 of X and there exists a matching M_2 that covers a subset Y_0 of Y , then there exists a matching M_3 that covers $X_0 \cup Y_0$.*

PROOF: Think of the edges of M_1 as 'red edges' and the edges of M_2 as 'blue edges'. If an edge belongs to both M_1 and M_2 , it is 'purple'.

A connected graph all of whose vertices have degree at most two is easily seen to be one of: a finite path-graph (allowing the trivial case of length 0, when the component has one vertex and no edges), a finite polygon, an infinite 'one-sided' path-graph (with one monovalent vertex), or an infinite 'two-sided' path-graph. The graph H whose vertices are those of G and whose edges $M_1 \cup M_2$ has the property that every vertex has degree at most two, so its connected components are of the types enumerated above. The

edges of any of these components, other than the graphs consisting of a purple edge and its two ends, are alternately colored red and blue; in particular, all polygons have even length. Every vertex of $X_0 \cup Y_0$ is in one of these nontrivial components.

For the matching M_3 , we will take all purple edges, and either all red edges or all blue edges from every other component of H . From the cycles and infinite two-sided paths, it doesn't matter; take all red or all blue edges, and they will cover all vertices of the component. From the paths of odd length and infinite one-sided paths, take all red or blue edges depending on whether the first edge is red or blue (for a path of odd length, the first and last edge have the same color, so it doesn't matter what side you start on). Again, the selected edges will cover all vertices of the component.

We have to think just a tiny bit harder for a component that is a finite path P of even length, with vertices v_0, v_1, \dots, v_k , say. There is an odd number of vertices and they alternate between X and Y , so v_0 and v_k are both in X or both in Y . If they are both in X , take all red edges of P (those of M_1) and put them in M_3 ; if they are both in Y , take all blue edges of P and put them in M_3 . Only one end of the path is not covered by the chosen edges.

Consider the case that both $v_0, v_k \in X$ (the case when they are in Y is completely analogous). If the first edge of P is red, then the last is blue and it follows that $v_k \notin X_0$ since no edge of M_1 covers v_k . Thus the red edges of P still cover all vertices of X_0 and Y_0 that were in P . Similarly, if the first edge of P is blue, then $v_0 \notin X_0$ and the red edges of P still cover all vertices of X_0 and Y_0 that were in P . \square

For the case $X_0 = X$, $Y_0 = Y$, and when the graph G is complete bipartite, matchings that cover X_0 or Y_0 correspond to, or can be interpreted as, injective mappings $X \rightarrow Y$ or $Y \rightarrow X$, respectively. Theorem 5.6 says:

Corollary. *If X and Y are sets and there exist injective mappings $f : X \rightarrow Y$ and $g : Y \rightarrow X$, then there exists a bijective mapping from X to Y , or from Y to X , i.e. there is a one-to-one correspondence between the two sets.*

In terms of 'cardinality' of sets, this says that if $|X| \leq |Y|$ and

$|Y| \leq |X|$, then $|X| = |Y|$. This is the Schröder-Bernstein Theorem; see Section 22 of P. R. Halmos (1974). It is trivial for finite sets, of course.

Problem 5F. Let A_1, A_2, \dots, A_n be finite sets. Show that if

$$\sum_{1 \leq i < j \leq n} \frac{|A_i \cap A_j|}{|A_i| \cdot |A_j|} < 1,$$

then the sets A_1, A_2, \dots, A_n have a system of distinct representatives.

Problem 5G. (i) From Problem 5A we know that a bipartite graph on $2n$ vertices that is regular of degree 3 has a perfect matching. How many different perfect matchings are there if $n = 4$? (ii) The same question for a bipartite graph on 10 vertices that is regular of degree 4.

Notes.

Philip Hall published his result in 1935 (with a rather difficult proof). The proof that we gave is a generalization of ideas of Halmos and Vaughan, Rado, and M. Hall. The proof is due to Ostrand (1970) and Hautus and Van Lint (1972). See Van Lint (1974). The problem of complete matchings is often referred to as the *marriage problem*.

D. König (1884–1944) was professor at Budapest. He wrote the first comprehensive treatise on graph theory (*Theorie der endlichen und unendlichen Graphen*, 1936). König (1916) contains the first proof of (one of the theorems called) König's theorem.

Just before Theorem 5.4, we referred to the 'equivalence' of these theorems. This expression is often used when each of two theorems is more or less an immediate consequence of the other.

The theorem by Birkhoff (1946), i.e. Theorem 5.5, is extremely useful and will be applied a number of times in later chapters.

For the card problem mentioned in Example 5.1, here is one solution. In a set of five cards, some suit must be represented at least twice. The first card you pass to your partner should be the 'larger' of two cards of the same suit, and you will retain the 'smaller', where we think of the ranks 2, 3, ..., 10, J, Q, K, A as arranged clockwise on a circle (modulo 13), and by 'smaller' we mean

the card from which we must travel the least distance clockwise to get to the other. For example, if $S = \{3\spadesuit, Q\diamond, 6\clubsuit, 3\diamond, 7\spadesuit\}$, you pass either the $7\spadesuit$ or $3\diamond$ to your partner. This already tells your partner the suit of the retained card and limits that card to six possibilities in that suit. To determine how far to count back (counterclockwise) from the rank of the first card, you and your partner use the *order* of the remaining three cards (the 52 cards are ordered lexicographically), and agree on some correspondence between the six permutations of three objects and the integers from 1 to 6.

References.

- G. Birkhoff (1946), Tres observaciones sobre el algebra lineal, *Univ. Nac. Tucumán, Rev. Ser. A*, **5**, 147–151.
- P. Hall (1935), On representatives of subsets, *J. London Math. Soc.* **10**, 26–30.
- P. R. Halmos (1974), *Naive Set Theory*, Springer-Verlag.
- D. König (1916), Über Graphen und ihre Anwendung auf Determinantentheorie und Mengenlehre, *Math. Annalen* **77**, 453–465.
- J. H. van Lint (1974), *Combinatorial Theory Seminar Eindhoven University of Technology*, Lecture Notes in Mathematics **382**, Springer-Verlag.
- P. Ostrand (1970), Systems of distinct representatives, *J. of Math. Analysis and Applic.* **32**, 1–4.

6

Dilworth's theorem and extremal set theory

A *partially ordered set* (also *poset*) is a set S with a binary relation \leq (sometimes \subseteq is used) such that:

- (i) $a \leq a$ for all $a \in S$ (reflexivity),
- (ii) if $a \leq b$ and $b \leq c$ then $a \leq c$ (transitivity),
- (iii) if $a \leq b$ and $b \leq a$ then $a = b$ (antisymmetry).

If for any a and b in S , either $a \leq b$ or $b \leq a$, then the partial order is called a *total order*, or a *linear order*. If $a \leq b$ and $a \neq b$, then we also write $a < b$. Examples of posets include the integers with the usual order or the subsets of a set, ordered by inclusion. If a subset of S is totally ordered, it is called a *chain*. An *antichain* is a set of elements that are pairwise incomparable.

The following theorem is due to R. Dilworth (1950). This proof is due to H. Tverberg (1967).

Theorem 6.1. *Let P be a partially ordered finite set. The minimum number m of disjoint chains which together contain all elements of P is equal to the maximum number M of elements in an antichain of P .*

PROOF: (i) It is trivial that $m \geq M$.

(ii) We use induction on $|P|$. If $|P| = 0$, there is nothing to prove. Let C be a maximal chain in P . If every antichain in $P \setminus C$ contains at most $M - 1$ elements, we are done. So assume that $\{a_1, \dots, a_M\}$ is an antichain in $P \setminus C$. Now define $S^- := \{x \in P : \exists_i [x \leq a_i]\}$, and define S^+ analogously. Since C is a maximal chain, the largest element in C is not in S^- and hence by the induction hypothesis, the theorem holds for S^- . Hence S^- is the union of M disjoint chains S_1^-, \dots, S_M^- , where $a_i \in S_i^-$. Suppose $x \in S_i^-$ and

$x > a_i$. Since there is a j with $x \leq a_j$, we would have $a_i < a_j$, a contradiction. This shows that a_i is the maximal element of the chain S_i^- , $i = 1, \dots, m$. We do the same for S^+ . By combining the chains the theorem follows. \square

A ‘dual’ to Dilworth’s theorem was given by Mirsky (1971).

Theorem 6.2. *Let P be a partially ordered set. If P possesses no chain of $m + 1$ elements, then P is the union of m antichains.*

PROOF: For $m = 1$ the theorem is trivial. Let $m \geq 2$ and assume that the theorem is true for $m - 1$. Let P be a partially ordered set that has no chain of $m + 1$ elements. Let M be the set of maximal elements of P . M is an antichain. Suppose $x_1 < x_2 < \dots < x_m$ were a chain in $P \setminus M$. Then this would also be a maximal chain in P and hence we would have $x_m \in M$, a contradiction. Hence $P \setminus M$ has no chain of m elements. By the induction hypothesis, $P \setminus M$ is the union of $m - 1$ antichains. This proves the theorem. \square

The following famous theorem due to Sperner (1928) is of a similar nature. This proof is due to Lubell (1966).

Theorem 6.3. *If A_1, A_2, \dots, A_m are subsets of $N := \{1, 2, \dots, n\}$ such that A_i is not a subset of A_j if $i \neq j$, then $m \leq \binom{n}{\lfloor n/2 \rfloor}$.*

PROOF: Consider the poset of subsets of N . $\mathcal{A} := \{A_1, \dots, A_m\}$ is an antichain in this poset.

A maximal chain \mathcal{C} in this poset will consist of one subset of each cardinality $0, 1, \dots, n$, and is obtained by starting with the empty set, then any singleton set (n choices), then any 2-subset containing the singleton ($n - 1$ choices), then any 3-subset containing the 2-subset ($n - 2$ choices), etc. Thus there are $n!$ maximal chains. Similarly, there are exactly $k!(n - k)!$ maximal chains which contain a given k -subset A of N .

Now count the number of ordered pairs (A, \mathcal{C}) such that $A \in \mathcal{A}$, \mathcal{C} is a maximal chain, and $A \in \mathcal{C}$. Since each maximal chain \mathcal{C} contains at most one member of an antichain, this number is at most $n!$. If we let α_k denote the number of sets $A \in \mathcal{A}$ with $|A| = k$, then this number is $\sum_{k=0}^n \alpha_k k!(n - k)!$. Thus

$$\sum_{k=0}^n \alpha_k k!(n - k)! \leq n!, \quad \text{or equivalently,} \quad \sum_{k=0}^n \frac{\alpha_k}{\binom{n}{k}} \leq 1.$$

Since $\binom{n}{k}$ is maximal for $k = \lfloor n/2 \rfloor$ and $\sum \alpha_k = m$, the result follows. \square

Equality holds in Theorem 6.3 if we take all $\lfloor n/2 \rfloor$ -subsets of N as the antichain.

We now consider the poset B_n (with 2^n elements) of the subsets of the n -set N , ordered by inclusion. The set of i -subsets of N is denoted by \mathcal{A}_i . We define a *symmetric chain* in B_n to be a sequence $P_k, P_{k+1}, \dots, P_{n-k}$ of vertices such that $P_i \in \mathcal{A}_i$ and $P_i \subseteq P_{i+1}$ for $i = k, k+1, \dots, n-k-1$. We describe an algorithm due to De Bruijn, Van Ebbenhorst Tengbergen and Kruyswijk (1949), that splits B_n into (disjoint) symmetric chains.

Algorithm: Start with B_1 . Proceed by induction. If B_n has been split into symmetric chains, then for each such symmetric chain P_k, \dots, P_{n-k} define two symmetric chains in B_{n+1} , namely P_{k+1}, \dots, P_{n-k} and $P_k, P_k \cup \{n+1\}, P_{k+1} \cup \{n+1\}, \dots, P_{n-k} \cup \{n+1\}$.

It is easy to see that this algorithm does what we claim. Furthermore it provides a natural matching between k -subsets and $(n-k)$ -subsets in B_n (cf. Theorem 5.1). Also, see Problem 6D below.

Problem 6A. Let $a_1, a_2, \dots, a_{n^2+1}$ be a permutation of the integers $1, 2, \dots, n^2+1$. Show that Dilworth's theorem implies that the sequence has a subsequence of length $n+1$ that is monotone.

A nice direct proof of the assertion of Problem 6A is as follows. Suppose there is no increasing subsequence of $n+1$ terms. Define b_i to be the length of the longest increasing subsequence that starts with the term a_i . Then by the pigeonhole principle, there are at least $n+1$ terms in the b_i -sequence that have the same value. Since $i < j$ and $b_i = b_j$ imply that $a_i > a_j$, we have a decreasing subsequence of $n+1$ terms.

To show a connection between Chapters 5 and 6, we now prove that Theorem 5.1 immediately follows from Theorem 6.1. We consider the bipartite graph G of Theorem 5.1. Let $|X| = n$, $|Y| = n' \geq n$. We introduce a partial order by defining $x_i < y_j$ if and only if there is an edge from vertex x_i to vertex y_j . Suppose that the largest antichain contains s elements. Let this antichain be $\{x_1, \dots, x_h, y_1, \dots, y_k\}$, where $h+k = s$. Since $\Gamma(\{x_1, \dots, x_h\}) \subseteq$

$Y \setminus \{y_1, \dots, y_k\}$, we have $h \leq n' - k$. Hence $s \leq n'$. The partially ordered set is the union of s disjoint chains. This will consist of a matching of size a , the remaining $n - a$ elements of X , and the remaining $n' - a$ elements of Y . Therefore $n + n' - a = s \leq n'$, i.e. $a \geq n$, which means that we have a complete matching.

Theorem 6.3 is a (fairly easy) example of an area known as *extremal set theory* in which the problems are often quite difficult. We first give one more example as an easy exercise.

Problem 6B. Let the sets A_i , $1 \leq i \leq k$, be distinct subsets of $\{1, 2, \dots, n\}$. Suppose $A_i \cap A_j \neq \emptyset$ for all i and j . Show that $k \leq 2^{n-1}$ and give an example where equality holds.

We now give one more example of the method that we used to prove Sperner's theorem. We prove the so-called Erdős–Ko–Rado theorem (1961).

Theorem 6.4. Let $\mathcal{A} = \{A_1, \dots, A_m\}$ be a collection of m distinct k -subsets of $\{1, 2, \dots, n\}$, where $k \leq n/2$, with the property that any two of the subsets have a nonempty intersection. Then $m \leq \binom{n-1}{k-1}$.

PROOF: Place the integers 1 to n on a circle and consider the family $\mathcal{F} := \{F_1, \dots, F_n\}$ of all consecutive k -tuples on the circle, i.e. F_i denotes $\{i, i+1, \dots, i+k-1\}$ where the integers should be taken mod n . We observe that $|\mathcal{A} \cap \mathcal{F}| \leq k$ because if some F_i equals A_j , then at most one of the sets $\{l, l+1, \dots, l+k-1\}$, $\{l-k, \dots, l-1\}$ ($i < l < i+k$) is in \mathcal{A} . The same assertion holds for the collection \mathcal{F}^π obtained from \mathcal{F} by applying a permutation π to $\{1, \dots, n\}$. Therefore

$$\Sigma := \sum_{\pi \in \mathcal{S}_n} |\mathcal{A} \cap \mathcal{F}^\pi| \leq k \cdot n!.$$

We now count this sum by fixing $A_j \in \mathcal{A}$, $F_i \in \mathcal{F}$ and observing that there are $k!(n-k)!$ permutations π such that $F_i^\pi = A_j$. Hence $\Sigma = m \cdot n \cdot k!(n-k)!$. This proves the theorem. \square

By a slight modification of the proof, one can show that the theorem also holds if the sets in \mathcal{A} are assumed to have size at most k and they form an antichain. However we shall give a proof using Theorem 5.1.

Theorem 6.5. Let $\mathcal{A} = \{A_1, \dots, A_m\}$ be a collection of m subsets of $N := \{1, 2, \dots, n\}$ such that $A_i \not\subseteq A_j$ and $A_i \cap A_j \neq \emptyset$ if $i \neq j$ and $|A_i| \leq k \leq n/2$ for all i . Then $m \leq \binom{n-1}{k-1}$.

PROOF: (i) If all the subsets have size k , then we are done by Theorem 6.4.

(ii) Let A_1, \dots, A_s be the subsets with the smallest cardinality, say $l \leq \frac{n}{2} - 1$. Consider all the $(l+1)$ -subsets B_j of N that contain one or more of the sets A_i , $1 \leq i \leq s$. Clearly none of these is in \mathcal{A} . Each of the sets A_i , $1 \leq i \leq s$, is in exactly $n-l$ of the B_j 's and each B_j contains at most $l+1 \leq n-l$ of the A_i 's. So by Theorem 5.1, we can pick s distinct sets, say B_1, \dots, B_s , such that $A_i \subseteq B_i$. If we replace A_1, \dots, A_s by B_1, \dots, B_s , then the new collection \mathcal{A}' satisfies the conditions of the theorem and the subsets of smallest cardinality now all have size $> l$. By induction, we can reduce to case (i). \square

By replacing the counting argument of the proof of Theorem 6.4 by an argument in which the subsets are counted with weights, we can prove the following generalization due to B. Bollobás (1973).

Theorem 6.6. Let $\mathcal{A} = \{A_1, \dots, A_m\}$ be a collection of m distinct subsets of $\{1, 2, \dots, n\}$, where $|A_i| \leq n/2$ for $i = 1, \dots, m$, with the property that any two of the subsets have a nonempty intersection. Then

$$\sum_{i=1}^m \frac{1}{\binom{n-1}{|A_i|-1}} \leq 1.$$

PROOF: Let π be a permutation of $1, 2, \dots, n$ placed on a circle and let us say that $A_i \in \pi$ if the elements of A_i occur consecutively somewhere on that circle. By the same argument as in the proof of Theorem 6.4 we see that if $A_i \in \pi$, then $A_j \in \pi$ for at most $|A_i|$ values of j .

Now define

$$f(\pi, i) := \begin{cases} \frac{1}{|A_i|}, & \text{if } A_i \in \pi \\ 0, & \text{otherwise.} \end{cases}$$

By the argument above $\sum_{\pi \in S_n} \sum_{i=1}^m f(\pi, i) \leq n!$. Changing the order of summation we have to count, for a fixed A_i , the number of permutations π placed on a circle such that $A_i \in \pi$. This number

(by the same argument as in Theorem 6.4) is $n \cdot |A_i|!(n - |A_i|)!$. So we have

$$\sum_{i=1}^m \frac{1}{|A_i|} \cdot n \cdot |A_i|!(n - |A_i|)! \leq n!,$$

which yields the result. \square

Problem 6C. Let $\mathcal{A} = \{A_1, \dots, A_m\}$ be a collection of m distinct subsets of $N := \{1, 2, \dots, n\}$ such that if $i \neq j$ then $A_i \not\subseteq A_j$, $A_i \cap A_j \neq \emptyset$, $A_i \cup A_j \neq N$. Prove that

$$m \leq \binom{n-1}{\lfloor \frac{n}{2} \rfloor - 1}.$$

Problem 6D. Consider the decomposition of B_n into symmetric chains as described above. Show that Theorem 6.3 is an immediate consequence of this decomposition. Show that Theorem 6.5 reduces to Theorem 6.4 via this decomposition. How many of the chains have their smallest element in \mathcal{A}_i ?

Problem 6E. Here is an algorithm to construct a symmetric chain in the poset B_n which contains a given element S (a subset of $\{1, 2, \dots, n\}$). Consider the characteristic vector x of S ; for example, if $n = 7$ and $S = \{3, 4, 7\}$, then $x = 0011001$. Mark all consecutive pairs 10, temporarily delete these pairs and again mark all consecutive pairs 10, and repeat until only a string of the form $00 \cdots 01 \cdots 11$ remains. In our example, we obtain $00\dot{1}\dot{1}\dot{0}\dot{0}1$, where the i -th coordinates are marked for $i = 3, 4, 5, 6$; when these are deleted, the string 001 remains. The characteristic vectors of the subsets in the chain are obtained by fixing all marked coordinates and letting the remaining coordinates range over the strings $0 \cdots 000$, $0 \cdots 001$, $0 \cdots 011$, \dots , $1 \cdots 111$. In our example, these characteristic vectors are

$$\begin{aligned} &00\dot{1}\dot{1}\dot{0}\dot{0}0, \\ &00\dot{1}\dot{1}\dot{0}\dot{0}1, \\ &01\dot{1}\dot{1}\dot{0}\dot{0}1, \\ &11\dot{1}\dot{1}\dot{0}\dot{0}1, \end{aligned}$$

which correspond to the subsets

$$\{3, 4\}, \quad \{3, 4, 7\}, \quad \{2, 3, 4, 7\}, \quad \{1, 2, 3, 4, 7\}.$$

Show that this algorithm produces exactly the same symmetric chain containing S as is produced by the inductive algorithm of De Bruijn *et al.* described above.

Notes.

We shall return to partially ordered sets in Chapters 23 and 25.

E. Sperner (1905–1980) is best known for a lemma in combinatorial topology known as ‘Sperner’s lemma’, which occurred in his thesis (1928). It was used to give a proof of Brouwer’s fixed point theorem. (Another connection to combinatorics: his first professorship was in Königsberg!) He was one of the pioneers of the famous Oberwolfach research institute.

For a survey of extremal set theory, we refer to Frankl (1988).

The short proof of the Erdős–Ko–Rado theorem is due to Katona (1974). Theorem 6.5 is due to Kleitman and Spencer (1973) and Schönheim (1971). The proof of Theorem 6.6 is due to Greene, Katona and Kleitman (1976).

References.

- B. Bollobás (1973), Sperner systems consisting of pairs of complementary subsets, *J. Combinatorial Theory* (A) **15**, 363–366.
- N. G. de Bruijn, C. van Ebbenhorst Tengbergen and D. Kruyswijk (1949), On the set of divisors of a number, *Nieuw Archief v. Wisk.* (2) **23**, 191–193.
- R. P. Dilworth (1950), A decomposition theorem for partially ordered sets, *Annals of Math.* (2) **51**, 161–166.
- P. Erdős, Chao Ko, and R. Rado (1961), Extremal problems among subsets of a set, *Quart. J. Math. Oxford Ser.* (2) **12**, 313–318.
- P. Frankl (1988), Old and new problems on finite sets, Proc. Nineteenth S. E. Conf. on Combinatorics, Graph Th. and Computing, Baton Rouge, 1988.
- C. Greene, G. Katona, and D. J. Kleitman (1976), Extensions of the Erdős–Ko–Rado theorem, *Stud. Appl. Math.* **55**, 1–8.

- G. O. H. Katona (1974), Extremal problems for hypergraphs, in *Combinatorics* (edited by M. Hall, Jr. and J. H. van Lint), Reidel.
- D. J. Kleitman and J. Spencer (1973), Families of k -independent sets, *Discrete Math.* **6**, 255–262.
- D. Lubell (1966), A short proof of Sperner's lemma, *J. Combinatorial Theory* **1**, 299.
- L. Mirsky (1971), A dual of Dilworth's decomposition theorem, *Amer. Math. Monthly* **78**, 876–877.
- J. Schönheim (1971), A generalization of results of P. Erdős, G. Katona, and D. J. Kleitman concerning Sperner's theorem, *J. Combinatorial Theory (A)* **11**, 111–117.
- E. Sperner (1928), Ein Satz über Untermengen einer endlichen Menge, *Math. Zeitschrift* **27**, 544–548.
- H. Tverberg (1967), On Dilworth's decomposition theorem for partially ordered sets, *J. Combinatorial Theory* **3**, 305–306.

7

Flows in networks

By a *transportation network*, we will mean a finite directed graph D together with two distinguished vertices s and t called the *source* and the *sink*, respectively, and which is provided with a function c associating to each edge e a nonnegative real number $c(e)$ called its *capacity*. We may further assume that there are no loops, no multiple edges, and that no edges enter the source s or leave the sink t (although there would be no harm in admitting any of these types of edges other than our having to be more careful in a definition or two).




Figure 7.1

In Fig. 7.1 we give an example. We could think of a network of pipes through which some liquid could flow in the direction of the arrows. The capacity would indicate the maximal possible flow (per time unit) in that section of pipe.

A *flow* in a transportation network is a function f assigning a real number $f(e)$ to each edge e such that:

- $0 \leq f(e) \leq c(e)$ for all edges e (the flow is *feasible*);
- for each vertex x (not the source or the sink) the sum of the

values of f on incoming edges equals the sum of the values of f on outgoing edges (*conservation of flow*).

The sum of the values of a flow f on the edges leaving the source is called the *strength* of the flow (denoted by $|f|$). It seems obvious that the strength of the flow is also equal to the sum of the values of f on edges entering the sink; the reader might try to verify this formally before reading further.

One of our objectives will be to find a method for constructing a *maximum flow*, that is, a flow with maximum strength. Before we begin, it will be good to have a goal or an upper bound for the strength of a flow; for example, the sum of the capacities of all edges leaving the source is clearly such an upper bound. More generally, by a *cut separating s and t* (or simply a *cut*), we mean here a pair (X, Y) of subsets of the vertex set $V := V(D)$ which partition V and such that $s \in X$ and $t \in Y$. We define the *capacity* $c(X, Y)$ of the cut to be the sum of the capacities of the edges directed from X to Y (that is, edges $e = (x, y)$ with $x \in X$ and $y \in Y$). We claim that the capacity of any cut is an upper bound for the strength of any flow. More strongly, we claim that the conservation law implies (see below) that the strength of a flow f can be computed as

$$(7.1) \quad |f| = f(X, Y) - f(Y, X),$$

where $f(A, B)$ denotes the sum of the values of f on all edges directed from A to B ; then the feasibility of f immediately implies that $|f| \leq c(X, Y)$. Thus the minimum capacity of all cuts in a network (e.g. in Fig. 7.1 the minimum cut capacity is 20) is an upper bound for the strength of a flow in that network.

To establish (7.1), we introduce the function ϕ by defining for each pair (x, e) , where x is a vertex incident with the edge e , $\phi(x, e) := -1$ if the edge is incoming, and $\phi(x, e) := +1$ if the edge is outgoing; $\phi(x, e)$ is to be 0 if x is not incident with e . (We remark that ϕ is essentially the *incidence matrix* of the directed graph—see Chapter 36.) The conservation law is equivalent to $\sum_{e \in E} \phi(x, e)f(e) = 0$ for $x \neq s, t$. Notice that $\sum_{x \in X} \phi(x, e)$ is $+1$ if e is directed from X to Y , -1 if e is directed from Y to X , and

0 if e has both endpoints in X or both in Y . Then

$$\begin{aligned} |f| &= \sum_{e \in E} \phi(s, e) f(e) = \sum_{x \in X} \sum_{e \in E} \phi(x, e) f(e) \\ &= \sum_{e \in E} f(e) \sum_{x \in X} \phi(x, e) = f(X, Y) - f(Y, X). \end{aligned}$$

(In the first double sum above, the inner sum is 0 for all terms x other than s .)

A special instance of (7.1) is $|f| = f(V \setminus \{t\}, \{t\})$, the assertion which we invited the reader to reflect on earlier.

We now construct flows. Fix a flow f , possibly the 0-flow. We shall say that the sequence $x_0, x_1, \dots, x_{k-1}, x_k$ of distinct vertices is a *special path* from x_0 to x_k if for each i , $1 \leq i \leq k$, either

- (i) $e = (x_{i-1}, x_i)$ is an edge with $c(e) - f(e) > 0$, or
- (ii) $e = (x_i, x_{i-1})$ is an edge with $f(e) > 0$.

Edges e with $f(e) = c(e)$ are said to be *saturated* and conditions (i) and (ii) can be stated in words as requiring that ‘forward’ edges of the path are unsaturated while ‘backward’ edges are positive—all with respect to a given flow f . Suppose there exists such a special path from s to t . Define α_i as $c(e) - f(e)$ in the first case and as $f(e)$ in the second case (picking one of the edges to use if both cases hold) and let α be the minimum of these positive numbers α_i . On each edge of type (i) *increase* the flow value by α , and on each edge of type (ii) *decrease* the flow by α . It is easy to check that the two conditions for a flow (feasibility and conservation of flow) are still satisfied. Clearly the new flow has strength $|f| + \alpha$.

This idea for obtaining a stronger flow becomes an algorithm when we iterate it (starting with the 0-flow) and incorporate a systematic procedure for searching for special paths from s to t with respect to the current flow. We make brief remarks concerning termination in the notes to this chapter. But what happens when we can go no further?

Suppose that *no special path from source to sink exists* with respect to some flow f_0 . Let X_0 be the set of vertices x which can be reached from s by a special path, Y_0 the set of remaining vertices.

In this way we produce a cut. If $x \in X_0$, $y \in Y_0$ and $e = (x, y)$ is an edge, then e must be saturated or we could adjoin y to a special path from s to x to get a special path from s to y , contradicting the definitions of X_0 and Y_0 . If, on the other hand, $e = (y, x)$ is an edge, then, for a similar reason, $f(e)$ must be 0. In view of (7.1), we have then

$$|f_0| = f_0(X_0, Y_0) - f_0(Y_0, X_0) = c(X_0, Y_0).$$

Now it is clear that not only can no stronger flow be obtained by our method of special paths, but that no stronger flows exist at all because $|f| \leq c(X_0, Y_0)$ for any flow f .

If f_0 is chosen to be a maximum flow (which exists by continuity reasons in case one is unsure of the termination of the algorithm), then surely no special paths from s to t exist. Note that the constructed cut (X_0, Y_0) is a minimum cut (i.e. a cut of minimum capacity), since $c(X, Y) \geq |f_0|$ for any cut (X, Y) . Our observations have combined to prove the following famous theorem of Ford and Fulkerson (1956).

Theorem 7.1. *In a transportation network, the maximum value of $|f|$ over all flows f is equal to the minimum value of $c(X, Y)$ over all cuts (X, Y) .*

This theorem is usually referred to as the ‘maxflow-mincut’ theorem. The procedure for increasing the strength of a flow that we used above shows somewhat more.

Theorem 7.2. *If all the capacities in a transportation network are integers, then there is a maximum strength flow f for which all values $f(e)$ are integers.*

PROOF: Start with the 0-flow. The argument above provides a way to increase the strength until a maximum flow is reached. At each step α is an integer, so the next flow is integer valued too. \square

Problem 7A. Construct a maximum flow for the transportation network of Fig. 7.1.

Problem 7B. An *elementary flow* in a transportation network is a flow f which is obtained by assigning a constant positive value

α to the set of edges traversed by a simple (directed) path from s to t , and 0 to all other edges. Show that every flow is the sum of elementary flows and perhaps a flow of strength zero. (This means we can arrive at a maxflow by starting from the 0-flow and using only special paths with ‘forward’ edges.) Give an example of a network and a flow which is not maximum, but with respect to which there are no special paths using only ‘forward’ edges.

Problem 7C. Let (X_1, Y_1) and (X_2, Y_2) be minimum cuts (i.e. cuts of minimum capacity) in a transportation network. Show that $(X_1 \cup X_2, Y_1 \cap Y_2)$ is also a minimum cut. (This can be done either from first principles, or with an argument involving maximum flows.)

Problem 7D. Prove P. Hall’s marriage theorem, Theorem 5.1, from Theorems 7.1 and 7.2.

It should be clear that the topic of this chapter is of great practical importance. Routing schemes for all kinds of products depend on algorithms that produce optimal flows through transportation networks. We do not go into the algorithmic aspect of this area. Instead, we shall show a beautiful application of Theorem 7.2 to a problem related to Birkhoff’s theorem, Theorem 5.5. Before giving the theorem and its proof, we observe that several attempts were made to prove it by reducing it to Theorem 5.5 but with no success. The proof below is due to A. Schrijver. (If $b = v$ in Theorem 7.3, then we have the situation of Theorem 5.5.)

Theorem 7.3. *Let A be a $b \times v$ $(0, 1)$ -matrix with k ones per row and r ones per column (so $bk = vr$). Let α be a rational number, $0 < \alpha < 1$, such that $k' = \alpha k$ and $r' = \alpha r$ are integers. Then there is a $(0, 1)$ -matrix A' of size $b \times v$ with k' ones per row and r' ones per column such that entries a'_{ij} of A' are 1 only if the corresponding entries of A are 1, i.e. A' can be obtained from A by changing some ones into zeros.*

PROOF: We construct a transportation network with vertices s (the source), x_1, \dots, x_b (corresponding to the rows of A), y_1, \dots, y_v (corresponding to the columns of A), and t (the sink). Edges are (s, x_i) with capacity k , $1 \leq i \leq b$, (x_i, y_j) with capacity 1 if and only if $a_{ij} = 1$, and (y_j, t) with capacity r , $1 \leq j \leq v$. The definition

ensures that there is a maximum flow with all edges saturated. We now change the capacities of the edges from the source to k' and those of the edges to the sink to r' . Again, all the capacities are integers and clearly a maximum flow exists for which the flows $f((x_i, y_j))$ are equal to α . By Theorem 7.2 there is also a maximum flow f^* for which all the flows are integers, i.e. $f^*((x_i, y_j)) = 0$ or 1. From this flow, we immediately find the required matrix A' . \square

The theorem above can be generalized in several ways with essentially the same proof idea, but see below for a slightly different approach.

For some combinatorial applications, it is convenient to use the following theorem, which does not require the introduction of capacities or the concept of strength. It can be derived from Theorem 7.2—see Ford and Fulkerson (1956)—but we choose to give a direct proof.

A *circulation* on a digraph D is a mapping f from $E(D)$ to the reals satisfying conservation of flow at every vertex. We do not require nonnegativity. Circulations may be identified with vectors in the null space of the incidence matrix of the digraph.

Theorem 7.4. *Let f be a circulation on a finite digraph D . Then there exists an integral circulation g such that for every edge e , $g(e)$ is equal to one of $\lfloor f(e) \rfloor$ or $\lceil f(e) \rceil$.*

We may say that the values of g are those of f ‘rounded up or down’. Of course, if $f(e)$ is already an integer, then $g(e) = f(e)$.

PROOF: Given a circulation f , consider a circulation g that satisfies

$$(7.2) \quad \lfloor f(e) \rfloor \leq g(e) \leq \lceil f(e) \rceil$$

and for which the number of edges e with $g(e)$ an integer is as large as possible subject to (7.2).

Let H be the spanning subgraph of D with edge set consisting of those edges of D for which $g(e)$ is not an integer, i.e. for which strict inequality holds both times in (7.2). Conservation of flow implies that no vertex can have degree 1 in H , so if g is not integral, then H contains a polygon.

Let P be a polygon in H and traverse P with a simple closed path; let A be the set of edges of P that are forward edges of the

path in D , and B the set of edges of P that are backward edges in this path. For any constant c , we obtain a new circulation g' by

$$g'(e) := \begin{cases} g(e) + c & \text{if } e \in A, \\ g(e) - c & \text{if } e \in B, \\ g(e) & \text{if } e \notin E(P). \end{cases}$$

If c is small, (7.2) will still hold with g replaced by g' . Now choose

$$c := \min \left\{ \min_{e \in A} \left(\lceil f(e) \rceil - g(e) \right), \min_{e \in B} \left(g(e) - \lfloor f(e) \rfloor \right) \right\}.$$

Then g' still satisfies (7.2), yet $g'(e)$ is an integer for at least one more edge (any edge for the which term in the expression above achieves the minimum). This would contradict the choice of g , were g not integral. \square

Corollary. *Let f be an integral circulation on a finite digraph D and d any positive integer. Then f can be written as the sum $g_1 + g_2 + \cdots + g_d$ of integral circulations such that for each index j and each edge e ,*

$$(7.3) \quad \lfloor f(e)/d \rfloor \leq g_j(e) \leq \lceil f(e)/d \rceil.$$

PROOF: By induction on d . For $d = 1$, there is nothing to prove.

Given $d \geq 2$, apply Theorem 7.4 to f/d to find an integral circulation g_1 satisfying (7.3) for $j = 1$. Apply the induction hypothesis to find

$$f - g_1 = g_2 + g_3 + \cdots + g_d$$

where for each $j = 2, 3, \dots, d$, g_j is an integral circulation satisfying

$$\lfloor (f(e) - g_1(e))/(d-1) \rfloor \leq g_j(e) \leq \lceil (f(e) - g_1(e))/(d-1) \rceil.$$

An easy exercise is that if a is an integer and b is either $\lfloor a/d \rfloor$ or $\lceil a/d \rceil$, then

$$\lfloor \frac{a}{d} \rfloor \leq \lfloor \frac{a-b}{d-1} \rfloor \quad \text{and} \quad \lceil \frac{a-b}{d-1} \rceil \leq \lceil \frac{a}{d} \rceil,$$

so that the above inequalities imply (7.3) for $j = 2, 3, \dots, d$. \square

From an $m \times n$ matrix A of real numbers a_{ij} , not necessarily nonnegative or integers, we obtain a circulation on a digraph with $m + n + 2$ vertices and $mn + m + n + 1$ edges. The digraph is similar to the one used in the proof of Theorem 7.3. There are vertices x_1, \dots, x_m corresponding to the rows, vertices y_1, \dots, y_n corresponding to the columns, and two others called s and t . There is an edge from x_i to y_j with circulation value a_{ij} , an edge from s to x_i with circulation value equal to the i -th row-sum r_i , an edge from y_j to t with circulation value equal to the j -th column-sum k_j ($i = 1, \dots, m, j = 1, \dots, n$), and an edge from t to s with circulation value equal to the sum of all entries of M . If we multiply this circulation f by any scalar α , apply Theorem 7.4 to αf , and reinterpret the resulting integral circulation as a matrix, we obtain part (i) of the following theorem. Part (ii) follows from the corollary.

Theorem 7.5. (i) *Given a matrix A and a real number α , there is an integral matrix B so that the entries of B , the row-sums of B , the column-sums of B , and the sum of all entries of B , are the corresponding values for αA rounded up or down.* (ii) *If A is an integral matrix and d any positive integer, then*

$$A = B_1 + B_2 + \cdots + B_d$$

where each B_i is an integral matrix whose entries, row-sums, column-sums, and sum of all entries, are those of $(1/d)A$, rounded up or down.

Problem 7E. Show that the following results are quick consequences of Theorem 7.5: (i) Problem 5A(iii); (ii) Theorem 5.5; (iii) Theorem 7.3; (iv) A finite graph all of whose vertices have even degree has a *balanced orientation*, where the in-degree and out-degree of each vertex are equal; (v) If a bipartite graph has minimum degree \underline{d} and maximum degree \bar{d} , then its edges may be colored with \bar{d} colors so that the colors that appear at every vertex are distinct, and with \underline{d} colors so that all colors appear at each vertex.

Problem 7F. Show that the dimension of the vector space of all circulations on a connected digraph D is $|E(D)| - |V(D)| + 1$.

Notes.

The term *augmenting path* is often used instead of *special path*.

If the capacities of a transportation network are integers, the special path method for constructing maximum flows will terminate after finitely many iterations, since the strength increases by at least one each time. But Ford and Fulkerson (1962) give an example with irrational capacities where certain contrived choices of special paths lead to an infinite sequence of flows whose strengths converge—but only to one-fourth of the actual maximum flow strength! If one is careful to pick *shortest* special paths, however, then it can be shown that a maximum flow is reached after at most $O(n^3)$ iterations, where n is the number of vertices. See Edmonds and Karp (1972).

The problem of finding a maximum flow is an example of a linear programming problem and can be solved e.g. by the simplex algorithm. The network flow problem is special in that its matrix is totally unimodular, and this is one way of explaining why Theorem 7.2 holds. See the references below for more discussion of linear and integer programming. Graphical methods are usually faster than the simplex algorithm, and add insight.

Circulations on a digraph are called *1-cycles* in algebraic topology. An analogue of Theorem 7.4 holds for vectors f in the null space of any totally unimodular matrix.

Theorems 7.1, 7.2, 7.4, and the algorithm have many further combinatorial applications, since certain combinatorial problems can be phrased in terms of transportation networks. For example, finding a maximum matching in a bipartite graph is equivalent to finding a maximum (integer valued) flow in a certain associated network—see the references—and thus a good algorithm exists to find a maximum matching. We give further applications of these theorems in Chapter 16 to an existence problem on $(0,1)$ -matrices, and in Chapter 38 to a problem on partitions of sets.

References.

- J. Edmonds and R. M. Karp (1972), Theoretical improvements in algorithm efficiency for network flow problems, *J. Assn. for Computing Machinery* **19**, 248–264.

- L. R. Ford, Jr. and D. R. Fulkerson (1962), *Flows in Networks*, Princeton University Press.
- T. C. Hu (1969), *Integer Programming and Network Flows*, Addison-Wesley.
- V. Chvátal (1983), *Linear Programming*, W. H. Freeman.

8

De Bruijn sequences

The following problem has a practical origin: the so-called *rotating drum problem*. Consider a rotating drum as in Fig. 8.1.




Figure 8.1

Each of the segments is of one of two types, denoted by 0 and 1. We require that any four consecutive segments uniquely determine the position of the drum. This means that the 16 possible quadruples of consecutive 0's and 1's on the drum should be the binary representations of the integers 0 to 15. Can this be done and, if yes, in how many different ways? The first question is easy to answer. Both questions were treated by N. G. de Bruijn (1946) and for this reason the graphs described below and the corresponding circular sequences of 0's and 1's are often called *De Bruijn graphs* and *De Bruijn sequences*, respectively.

We consider a digraph (later to be called G_4) by taking all 3-tuples of 0's and 1's (i.e. 3-bit binary words) as vertices and joining the vertex $x_1x_2x_3$ by a directed edge (arc) to x_2x_30 and x_2x_31 . The arc $(x_1x_2x_3, x_2x_3x_4)$ is numbered e_j , where $x_1x_2x_3x_4$ is the binary representation of the integer j . The graph has a loop at 000 and at 111. As we saw before, the graph has an Eulerian circuit because every vertex has in-degree 2 and out-degree 2. Such a

closed path produces the required 16-bit sequence for the drum. Such a (circular) sequence is called a De Bruijn sequence. For example the path $000 \rightarrow 000 \rightarrow 001 \rightarrow 011 \rightarrow 111 \rightarrow 111 \rightarrow 110 \rightarrow 100 \rightarrow 001 \rightarrow 010 \rightarrow 101 \rightarrow 011 \rightarrow 110 \rightarrow 101 \rightarrow 010 \rightarrow 100 \rightarrow 000$ corresponds to 0000111100101101 (to be read circularly). We call such a path a *complete cycle*.

We define the graph G_n to be the directed graph on $(n-1)$ -tuples of 0's and 1's in a similar way as above. (So G_n has 2^n edges.)

The graph G_4 is given in Fig. 8.2. In this chapter, we shall call a digraph with in-degree 2 and out-degree 2 for every vertex, a '2-in 2-out graph'. For such a graph G we define the 'doubled' graph G^* as follows:

- (i) to each edge of G there corresponds a vertex of G^* ;
- (ii) if a and b are vertices of G^* , then there is an edge from a to b if and only if the edge of G corresponding to a has as terminal end (head) the initial end (tail) of the edge of G corresponding to b .

Clearly $G_n^* = G_{n+1}$.




Figure 8.2

Theorem 8.1. *Let G be a 2-in 2-out graph on m vertices with M complete cycles. Then G^* has $2^{m-1}M$ complete cycles.*

PROOF: The proof is by induction on m .

(a) If $m = 1$ then G has one vertex p and two loops from p to p . Then $G^* = G_2$ which has one complete cycle.

(b) We may assume that G is connected. If G has m vertices and there is a loop at *every* vertex, then, besides these loops, G is a circuit $p_1 \rightarrow p_2 \rightarrow \dots \rightarrow p_m \rightarrow p_1$. Let A_i be the loop $p_i \rightarrow p_i$ and B_i the arc $p_i \rightarrow p_{i+1}$. We shall always denote the corresponding vertices in G^* by lower case letters. The situation in G^* is as in Fig. 8.3.




Figure 8.3

Clearly a cycle in G^* has two ways of going from b_i to b_{i+1} . So G^* has 2^{m-1} complete cycles, whereas G has only one.

(c) We now assume that G has a vertex x that does not have a loop on it. The situation is as in Fig. 8.4, where P, Q, R, S are different edges of G (although some of the vertices a, b, c, d may coincide).

From G we form a new 2-in 2-out graph with one vertex less by deleting the vertex x . This can be done in two ways: G_1 is obtained by the identification $P = R, Q = S$, and G_2 is obtained by $P = S, Q = R$. By the induction hypothesis, the theorem applies to G_1 and to G_2 .




Figure 8.4

There are three different types of complete cycle in G^* , depending on whether the two paths leaving r and returning to p , respectively q , both go to p , both to q , or one to p and one to q . We treat one

case; the other two are similar and left to the reader. In Fig. 8.5 we show the situation where path 1 goes from r to p , path 2 from s to q , path 3 from s to p , and path 4 from r to q .




Figure 8.5

These yield the following four complete cycles in G^* :

- 1, pr , 4, qs , 3, ps , 2, qr
- 1, ps , 2, qr , 4, qs , 3, pr
- 1, ps , 3, pr , 4, qs , 2, qr
- 1, ps , 2, qs , 3, pr , 4, qr

In G_1^* and G_2^* the situation reduces to Fig. 8.6.




Figure 8.6

In each of G_1^* and G_2^* one complete cycle using the paths 1, 2, 3, 4 is possible. In the remaining two cases, we also find two complete cycles in G_1^* and G_2^* corresponding to four complete cycles in G^* . Therefore the number of complete cycles in G^* is twice the sum of the numbers for G_1^* and G_2^* . On the other hand, the number of complete cycles in G is clearly equal to the sum of the corresponding numbers for G_1 and G_2 . The theorem then follows from the induction hypothesis. \square

We are now able to answer the question how many complete cycles there are in a De Bruijn graph.

Theorem 8.2. G_n has exactly $2^{2^{n-1}-n}$ complete cycles.

PROOF: The theorem is true for $n = 1$. Since $G_n^* = G_{n+1}$, the result follows by induction from Theorem 8.1. \square

For a second proof, see Chapter 36.

Problem 8A. Let α be a primitive element in \mathbb{F}_{2^n} . For $1 \leq i \leq m := 2^n - 1$, let

$$\alpha^i = \sum_{j=0}^{n-1} c_{ij} \alpha^j.$$

Show that the sequence

$$0, c_{10}, c_{20}, \dots, c_{m0}$$

is a De Bruijn sequence.

Problem 8B. Find a circular ternary sequence (with symbols $0, 1, 2$) of length 27 so that each possible ternary ordered triple occurs as three (circularly) consecutive positions of the sequence. First sketch a certain directed graph on 9 vertices so that Eulerian circuits in the graph correspond to such sequences.

Problem 8C. We wish to construct a circular sequence a_0, \dots, a_7 (indices mod 8) in such a way that a sliding window a_i, a_{i+1}, a_{i+3} ($i = 0, 1, \dots, 7$) will contain every possible three-tuple once. Show (not just by trial and error) that this is impossible.

Problem 8D. Let $m := 2^n - 1$. An algorithm to construct a De Bruijn sequence a_0, a_1, \dots, a_m works as follows. Start with $a_0 = a_1 = \dots = a_{n-1} = 0$. For $k > n$, we define a_k to be the maximal value in $\{0, 1\}$ such that the sequence $(a_{k-n+1}, \dots, a_{k-1}, a_k)$ has not occurred in (a_0, \dots, a_{k-1}) as a (consecutive) subsequence. The resulting sequence is known as a *Ford sequence*. Prove that this algorithm indeed produces a De Bruijn sequence.

Notes.

Although the graphs of this chapter are commonly called De Bruijn graphs, Theorem 8.1 was proved in 1894 by C. Flye Sainte-Marie. This went unnoticed for a long time. We refer to De Bruijn (1975).

N. G. de Bruijn (1918–), one of the best-known Dutch mathematicians, worked in many different areas such as analysis, number theory, combinatorics, and also computing science and crystallography.

We mention a peculiarity concerning the spelling of some Dutch names. When omitting the initials of N. G. de Bruijn, one should capitalize the word ‘de’ and furthermore the name should be listed under B. Similarly Van der Waerden is correct when the initials are omitted and he should be listed under W.

For a proof of Theorem 8.1 using algebraic methods, we refer to Chapter 36.

References.

- N. G. de Bruijn (1946), A combinatorial problem, *Proc. Kon. Ned. Akad. v. Wetensch.* **49**, 758–764.
- N. G. de Bruijn (1975), Acknowledgement of priority to C. Flye Sainte-Marie on the counting of circular arrangements of 2^n zeros and ones that show each n -letter word exactly once, T. H. report 75-WSK-06, Eindhoven University of Technology.
- C. Flye Sainte-Marie (1894), Solution to question nr. 48, *Intermédiaire des Mathématiciens* **1**, 107–110.

9

Two $(0,1,*)$ problems: addressing for graphs and a hash-coding scheme

The following problem originated in communication theory. For a telephone network, a connection between terminals A and B is established before messages flow in either direction. For a network of computers it is desirable to be able to send a message from A to B without B knowing that a message is on its way. The idea is to let the message be preceded by some ‘address’ of B such that at each node of the network a decision can be made concerning the direction in which the message should proceed.

A natural thing to try is to give each vertex of a graph G a binary address, say in $\{0,1\}^k$, in such a way that the distance of two vertices in the graph is equal to the so-called *Hamming distance* of the addresses, i.e. the number of places where the addresses differ. This is equivalent to regarding G as an *induced subgraph* of the *hypercube* H_k , which has $V(H_k) := \{0,1\}^k$ and where k -tuples are adjacent when they differ in exactly one coordinate. The example $G = K_3$ already shows that this is impossible. We now introduce a new alphabet $\{0,1,*\}$ and form addresses by taking n -tuples from this alphabet. The distance between two addresses is defined to be the number of places where one has a 0 and the other a 1 (so stars do not contribute to the distance). For an addressing of a graph G , we require that the distance of any two vertices in G is equal to the distance of their addresses. It is trivial to show that this can be done if n is large enough. We denote by $N(G)$ the minimum value of n for which there exists an addressing of G with length n .

For a tree we can do without the stars as follows. We use induction. For a tree with two vertices, we have a trivial addressing with length 1. Suppose that we can address trees with k vertices. If x_0, x_1, \dots, x_k are the vertices of the tree T and x_0 is a monovalent vertex, then consider an addressing for the tree obtained by removing x_0 . Let \mathbf{x}_i be the address of x_i and suppose x_0 is joined to x_1 . We change all addresses to $(0, \mathbf{x}_i)$, $1 \leq i \leq k$, and give x_0 the address $(1, \mathbf{x}_1)$. Clearly this is now an addressing for T . So for a tree, we have $N(T) \leq |V(T)| - 1$.

As a second example, consider K_m . In the identity matrix of size $m - 1$, we replace the zeros above the diagonal by stars and add a row of zeros. Any two rows now have distance 1 and hence $N(K_m) \leq m - 1$.

As a third example, we consider the graph of Fig. 9.1.




Figure 9.1

A possible (though not optimal) addressing is

1	1	1	1	*	*
2	1	0	*	1	*
3	*	0	0	0	1
4	0	0	1	*	*
5	0	0	0	0	0

We now show a correspondence between addressings of a graph and *quadratic forms* (an idea of Graham and Pollak, 1971). Consider the graph G of Fig. 9.1 and the addressing given above. To the first column of the addressing, we associate the product $(x_1 + x_2)(x_4 + x_5)$. Here x_i is in the first, respectively second, factor if the address of i has a 1, respectively a 0, in the first column. If we do the same thing for each column and then add the terms, we obtain a quadratic form $\sum d_{ij}x_ix_j$, where d_{ij} is the distance of

the vertices i and j in G . Thus an addressing of G corresponds to writing the quadratic form $\sum d_{ij}x_i x_j$ as a sum of n products

$$(x_{i_1} + \cdots + x_{i_k})(x_{j_1} + \cdots + x_{j_l})$$

such that no x_i occurs in both of the factors. The number of variables is $|V(G)|$.

Theorem 9.1. *Let n_+ , respectively n_- , be the number of positive, respectively negative, eigenvalues of the distance matrix (d_{ij}) of the graph G . Then $N(G) \geq \max\{n_+, n_-\}$.*

PROOF: Each of the quadratic forms mentioned above can be represented as $\frac{1}{2}\mathbf{x}^\top A\mathbf{x}$, where $\mathbf{x} := (x_1, x_2, \dots, x_n)$ and A has entry $a_{ij} = 1$ if the term $x_i x_j$ occurs in the quadratic form and 0 otherwise. Such a matrix has rank 2 and trace 0. Therefore it has one positive and one negative eigenvalue. Since (d_{ij}) is the sum of the matrices corresponding to the quadratic forms, it can have at most n positive (respectively negative) eigenvalues. \square

Theorem 9.2. $N(K_m) = m - 1$.

PROOF: We have already seen that $N(K_m) \leq m - 1$. Since $J - I$, of size m , is the distance matrix of K_m and the eigenvalues of $J - I$ are $m - 1$, with multiplicity 1, and -1 , with multiplicity $m - 1$, the result follows from Theorem 9.1. \square

With slightly more work, we shall now show that the shortest addressing for a tree T has length $|V(T)| - 1$.

Theorem 9.3. *If T is a tree on n vertices, then $N(T) = n - 1$.*

PROOF: We first calculate the determinant of the distance matrix (d_{ij}) of T . We number the vertices p_1, \dots, p_n in such a way that p_n is an endpoint adjacent to p_{n-1} . In the distance matrix, we subtract row $n - 1$ from row n , and similarly for the columns. Then all the entries in the new last row and column are 1 except for the diagonal element which is equal to -2 . Now renumber the vertices p_1, \dots, p_{n-1} in such a way that the new vertex p_{n-1} is an endpoint

of $T \setminus \{p_n\}$ adjacent to p_{n-2} . Repeat the procedure for the rows and columns with numbers $n-1$ and $n-2$. After $n-1$ steps, we have the determinant

$$\begin{vmatrix} 0 & 1 & 1 & \dots & 1 \\ 1 & -2 & 0 & \dots & 0 \\ 1 & 0 & -2 & \dots & 0 \\ \vdots & \vdots & \vdots & \ddots & \vdots \\ 1 & 0 & 0 & \dots & -2 \end{vmatrix}.$$

From this we find the remarkable result that the determinant D_n of the distance matrix of a tree on n vertices satisfies

$$D_n = (-1)^{n-1}(n-1)2^{n-2},$$

i.e. it depends only on $|V(T)|$. If we number the vertices according to the procedure described above, then the $k \times k$ principal minor in the upper left-hand corner of the distance matrix is the distance matrix of a subtree on k vertices. Therefore the sequence $1, D_1, D_2, \dots, D_n$, where D_k is the determinant of the $k \times k$ minor, is equal to

$$1, 0, -1, 4, -12, \dots, (-1)^{n-1}(n-1)2^{n-2}.$$

If we consider the sign of 0 to be positive, then this sequence has only one occurrence of two consecutive terms of the same sign. By an elementary theorem on quadratic forms this implies that the corresponding quadratic form has index 1, and hence (d_{ij}) has one positive eigenvalue; see B. W. Jones (1950), Theorem 4. Now the result follows from Theorem 9.1. \square

The conjecture that in fact $N(G) \leq |V(G)| - 1$ for all (connected) graphs G was proved by P. Winkler in 1983. The proof is constructive. In order to describe the addressing, we need some preparation. Consider the graph of Fig. 9.2.




Figure 9.2

We pick a vertex x_0 , then construct a spanning tree T by a breadth-first search, and then number the vertices by a depth-first search. The result is shown on the right-hand side of Fig. 9.2, where edges of $E(G) \setminus E(T)$ are dashed.

Let $n := |V(G)| - 1$. We need several definitions.

For $i \leq n$, we define

$$P(i) := \{j : x_j \text{ is on a path from } x_0 \text{ to } x_i \text{ in } T\}.$$

For example, $P(6) = \{0, 3, 4, 6\}$. Let

$$i \Delta j := \max(P(i) \cap P(j)).$$

We describe the general situation in Fig. 9.3.




Figure 9.3

Note that in Fig. 9.3, we have $i < j$ if and only if $k < l$.

For $i \leq n$, we define

$$i' := \max(P(i) \setminus \{i\}).$$

For example, $7' = 3$ in Fig. 9.2. Define

$$i \sim j \Leftrightarrow P(i) \subseteq P(j) \text{ or } P(j) \subseteq P(i).$$

We denote distances in G , respectively T , by d_G , respectively d_T . The *discrepancy function* $c(i, j)$ is now defined by

$$c(i, j) := d_T(x_i, x_j) - d_G(x_i, x_j).$$

For example, in Fig. 9.2, $c(6, 9) = 4$.

Lemma 9.4.

- (i) $c(i, j) = c(j, i) \geq 0$;
- (ii) if $i \sim j$, then $c(i, j) = 0$;
- (iii) if $i \not\sim j$, then $c(i, j') \leq c(i, j) \leq c(i, j') + 2$.

PROOF: (i) is trivial; (ii) follows from the definition of T since

$$d_G(x_i, x_j) \geq |d_G(x_j, x_0) - d_G(x_i, x_0)| = d_T(x_i, x_j);$$

(iii) follows from the fact that $|d_G(x_i, x_j) - d_G(x_i, x_{j'})| \leq 1$ and that $d_T(x_i, x_j) = 1 + d_T(x_i, x_{j'})$. \square

Now we can define the addressing. For $0 \leq i \leq n$ the vertex x_i is given the address $\mathbf{a}_i \in \{0, 1, *\}^n$, where

$$\mathbf{a}_i = (a_i(1), a_i(2), \dots, a_i(n))$$

and

$$a_i(j) := \begin{cases} 1 & \text{if } j \in P(i), \\ * & \text{if } \begin{cases} c(i, j) - c(i, j') = 2, \text{ or} \\ c(i, j) - c(i, j') = 1, \ i < j, \ c(i, j) \text{ even, or} \\ c(i, j) - c(i, j') = 1, \ i > j, \ c(i, j) \text{ odd,} \end{cases} \\ 0 & \text{otherwise.} \end{cases}$$

Theorem 9.5. $d(\mathbf{a}_i, \mathbf{a}_k) = d_G(x_i, x_k)$.

PROOF: We may assume $i < k$.

(i) Suppose $i \sim k$. Then $d_G(x_i, x_k) = |P(k) \setminus P(i)|$. The values of j such that $j \in P(k) \setminus P(i)$ are exactly the positions where $a_k(j) = 1$, $a_i(j) \neq 1$. For these values of j we see that $c(i, j) = 0$, hence $a_i(j) = 0$ and we are done.

(ii) The hard case is when $i \not\sim k$. The key observation is the following. Let $n_1 \leq n_2 \leq \dots \leq n_l$ be a nondecreasing sequence of

integers such that $|n_{i+1} - n_i| \leq 2$ for all i . If m is an even integer between n_1 and n_l that does *not* occur in the sequence, then there is an i such that $n_i = m - 1$, $n_{i+1} = m + 1$. Now consider the sequence

$$c(i, k) \geq c(i, k') \geq c(i, k'') \geq \dots \geq c(i, i\Delta k) = 0.$$

By the definition of $a_i(j)$ and the observation above, $a_i(j) = *$ and $a_k(j) = 1$ exactly as many times as there are even integers between $c(i, i\Delta k)$ and $c(i, k)$. Similarly $a_k(j) = *$ and $a_i(j) = 1$ as many times as there are odd integers between $c(i, i\Delta k)$ and $c(i, k)$. So

$$\begin{aligned} d(\mathbf{a}_i, \mathbf{a}_k) &= |P(k) \setminus P(i)| + |P(i) \setminus P(k)| - c(i, k) \\ &= d_T(x_i, x_k) - c(i, k) = d_G(x_i, x_k). \end{aligned}$$

□

Therefore we have proved the following theorem.

Theorem 9.6. $N(G) \leq |V(G)| - 1$.

Problem 9A. If we use the scheme defined above, what are the addresses of x_2 and x_6 in Fig. 9.2?

Problem 9B. Let G be a cycle (polygon) on $2n$ vertices. Determine $N(G)$.

Problem 9C. Let G be a cycle (polygon) on $2n+1$ vertices. Prove that $N(G) = 2n$. Hint: if C_k is the permutation matrix with entries $c_{ij} = 1$ if and only if $j - i \equiv 1 \pmod{k}$ and $\zeta^k = 1$, then $(1, \zeta, \zeta^2, \dots, \zeta^{k-1})$ is an eigenvector of C_k .

* * *

We now look at a second problem involving k -tuples from the alphabet $\{0, 1, *\}$. The objects we shall study were introduced by Rivest (1974) and given the (unfortunate) name *associative block design*; cf. Chapter 19 for block designs. An $ABD(k, w)$ is a set of $b := 2^w$ elements of $\{0, 1, *\}^k$ with the following properties: if the elements are the rows of a $b \times k$ matrix C , then

- (i) each row of C has $k - w$ stars;
- (ii) each column of C has $b(k - w)/k$ stars;
- (iii) any two distinct rows have distance at least 1.

Note that the definition implies that each vector in \mathbb{F}_2^k has distance 0 to exactly one row of C .

The origin of the problem is the following. Consider a file of k -bit binary words. Each sequence in $\{0, 1, \star\}^k$ is called a *partial match query*. The partial match retrieval problem is to retrieve from the file all words agreeing with the query in those positions where the query specifies a bit. So-called *hash-coding* schemes divide a file into b disjoint lists L_1, L_2, \dots, L_b . A record x will be stored in the list with index $h(x)$, where h is the ‘hash-function’ mapping $\{0, 1\}^k$ onto $\{1, 2, \dots, b\}$. For a given partial match query, some of the lists must be searched. An analysis of the worst-case number of lists to be searched led to the concept of *ABD*. In this case $h(x)$ is the index of the unique row of C which has distance 0 to x .

Example 9.1. The following matrix is an $ABD(4, 3)$:

$$\begin{pmatrix} \star & 0 & 0 & 0 \\ 0 & \star & 1 & 0 \\ 0 & 0 & \star & 1 \\ 0 & 1 & 0 & \star \\ \star & 1 & 1 & 1 \\ 1 & \star & 0 & 1 \\ 1 & 1 & \star & 0 \\ 1 & 0 & 1 & \star \end{pmatrix}.$$

We first prove some elementary properties of an *ABD*.

Theorem 9.7. *If an $ABD(k, w)$ exists, then:*

- (1) *it has exactly $bw/(2k)$ zeros and $bw/(2k)$ ones in each column;*
- (2) *for each \mathbf{x} in \mathbb{F}_2^k it has exactly $\binom{w}{u}$ rows which agree with \mathbf{x} in u positions;*
- (3) *the parameters satisfy*

$$w^2 \geq 2k \left(1 - \frac{1}{b}\right);$$

- (4) for any row, the number of rows with stars in the same positions is even.

PROOF: Let C be the $ABD(k, w)$.

(1) A row of C with a star, respectively a zero, in column j represents (i. e. has distance 0 to) 2^{k-w-1} , respectively 2^{k-w} , elements of \mathbb{F}_2^k . From (i) and (ii) of the definition, it follows that column j must contain $bw/(2k)$ zeros.

(2) Let $\mathbf{x} \in \mathbb{F}_2^k$. Denote by n_i the number of rows of C which agree with \mathbf{x} in i positions. There are $\binom{k}{l}$ vectors in \mathbb{F}_2^k which agree with \mathbf{x} in exactly l positions. Therefore $\binom{k}{l} = \sum n_i \binom{k-w}{l-i}$, i. e.

$$(1+z)^k = (1+z)^{k-w} \cdot \sum n_i z^i.$$

This proves that $n_i = \binom{w}{i}$.

(3) The sum of the distances between pairs of rows of C is $k \left(\frac{bw}{2k}\right)^2$ by (1). Since any two rows have distance at least 1, this sum is at least $\binom{b}{2}$.

(4) Consider a row of C . Count vectors in \mathbb{F}_2^k which have zeros in the positions where the row has stars. Each row with a different star pattern represents an even number of such vectors whereas a row with the same star pattern represents exactly one such vector. \square

Note that property (1) in Theorem 9.7(3) implies that a necessary condition for the existence of an $ABD(k, w)$ is that k divides $w \cdot 2^{w-1}$.

The following strengthening of Theorem 9.7(3) is due to A. E. Brouwer (1999).

Theorem 9.8. *Let C be an $ABD(k, w)$ with $w > 3$.*

- (1) *If two rows of C agree in all but one position, then*

$$\binom{w}{2} \geq k;$$

- (2) *otherwise $w^2 > 2k$.*

PROOF: Suppose \mathbf{c}_1 and \mathbf{c}_2 are two rows of C which differ only in position one. Then all the other rows of C must differ from \mathbf{c}_1 in some other position. So, by (i) of the definition and Theorem 9.7(3), we find

$$b - 2 \leq (w - 1) \cdot \frac{bw}{2k}.$$

To prove the assertion, we must show that the right-hand side of the inequality cannot be equal to $b - 2$ or $b - 1$. In both cases, equality would imply $2^{w-1} | k$ which contradicts Theorem 9.7 unless $w = 4$, which is excluded by substitution.

(ii) Consider two rows of C which have the same star pattern. By hypothesis, they differ in more than one position. Again, count the sum of the distances of all the rows from one of this pair. This sum is at least $2 + (b - 2) = b$ and, by Theorem 9.7.1, it is equal to $w \cdot (bw)/(2k)$. So $w^2 \geq 2k$. We must show that equality cannot hold. By the argument above, equality would imply that rows with the same star pattern occur in pairs which have distance 2, and furthermore all the other rows have distance 1 to each row of such a pair. Without loss of generality, such a pair would be

$$(\star \star \cdots \star 00 \dots 000) \text{ and } (\star \star \cdots \star 00 \dots 011).$$

The $bw/(2k) - 1$ other rows ending in a 1 would have to end in 01, for otherwise they would have distance 0 to the second row or distance > 1 to the first row. Similarly, there would be $bw/(2k) - 1$ rows ending in 10. Since we now have rows with distance 2, we find that necessarily $bw/(2k) - 1 = 1$. Therefore $2^w = 2w$, which is impossible if $w \geq 3$. \square

Corollary. *An $ABD(8, 4)$ does not exist.*

Using these results, it is easy to find all $ABD(k, w)$ with $w \leq 4$. Of course, $w = 0$ is trivial. For $w = 1, 2$, or 4 , we must have $k = w$ (no stars). If $w = 3$, then either $k = 3$ (no stars) or $k = 4$. In that case there are two types of ABD , one given in Example 9.1.

Problem 9D. Construct an $ABD(4, 3)$ that has the same first four rows as Example 9.1 but differs in the others.

In 1987 La Poutré and Van Lint proved that an $ABD(10, 5)$ does not exist but the smaller possibility $ABD(8, 5)$ turned out to

be quite difficult to handle. In 1999 D. E. Knuth asked Brouwer whether any progress had been made in this area since the early results and this made Brouwer decide it was time the question was settled. An example can be found in Brouwer (1999). It does not seem to have any structure. Now the smallest open case is the question whether an $ABD(12, 6)$ exists.

We shall now describe some construction methods. Some of the ideas will be used in other chapters.

Theorem 9.9. *If an $ABD(k_i, w_i)$ exists for $i = 1, 2$, then an $ABD(k_1 k_2, w_1 w_2)$ exists.*

PROOF: We can assume $w_2 > 0$. Partition the rows of $ABD(k_2, w_2)$ into two classes R_0 and R_1 of equal size. In $ABD(k_1, w_1)$ we replace each star by a row of k_2 stars, each 0 by a row from R_0 and each 1 by a row from R_1 in all possible ways. A trivial calculation shows that the resulting matrix is an $ABD(k_1 k_2, w_1 w_2)$. \square

Corollary. *An $ABD(4^t, 3^t)$ exists.*

For the proof of the next theorem, we introduce a new symbol, namely $-$. A k -tuple consisting of the symbols $0, 1, \star$, and $-$ represents all possible words with only $0, 1, \star$ that can be obtained by replacing each $-$ by a 0 or a 1 in all possible ways.

Theorem 9.10. *Let $w > 0$. Suppose an $ABD(k, w)$ exists, where $k = k_0 \cdot 2^l$, k_0 odd. Then an $ABD(k, w + ik_0)$ exists for $0 \leq i \leq (k - w)/k_0$.*

PROOF: It is sufficient to consider $i = 1$. Let C be the $ABD(k, w)$. Define a matrix A of the same size by requiring $a_{ij} = 1$ if $C_{ij} = \star$ and $a_{ij} = 0$ otherwise. By Theorem 7.3, A is the sum of two matrices A_1 and A_2 , where A_1 has k_0 ones in each row and 2^{w-l} ones in each column. In a row of C , replace stars by $-$ if the star occurs in a position where A_1 has a one. This produces the required $ABD(k, w + k_0)$. \square

Theorem 9.11. *If $ABD(k, w)$ exists and $\alpha \geq 1$ is a number such that αk and αw are integers, then an $ABD(\alpha k, \alpha w)$ exists.*

PROOF: It is sufficient to show that $ABD(k + l, w + m)$ exists for $(k + l)/(w + m) = k/w$ and $(l, m) = 1$. Let $k = k_0 \cdot 2^e$, k_0 odd.

From (ii) of the definition we know that $k_0|w$. Therefore $wl = mk$ and $(l, m) = 1$ imply that l is a power of 2. Consider the $l \times l$ circulant matrix with a row of $l - m$ stars and m minus signs as first row. Since l divides b we can adjoin a column of b/l copies of this circulant to the matrix C of the $ABD(k, w)$. It is easy to check that this larger matrix is an $ABD(k + l, w + m)$. \square

Example 9.2. From the corollary to Theorem 9.9 we have an $ABD(64, 27)$. Theorem 9.10 then shows that an $ABD(64, w)$ exists for $27 \leq w \leq 64$. In particular, there is an $ABD(64, 32)$. Then Theorem 9.11 implies that an $ABD(2w, w)$ exists for all $w \geq 32$. As mentioned before, nonexistence has been shown for $w = 4$ and $w = 5$ and the case $w = 6$ is still open.

Notes.

The first problem considered in this chapter was introduced by J. R. Pierce at Bell Laboratories as the *loop switching problem*. Several people (including one of the present authors) tried in vain to solve it. Shortly after R. L. Graham raised the reward for the solution to \$200, it was solved by P. Winkler. It is worth noting that Winkler stated that the idea of numbering the vertices as was done in the proof was a regular habit due to his background in computer science. Going over the proof, one sees that this numbering indeed played a crucial role.

References.

- A. E. Brouwer (1999), An Associative Block Design $ABD(8, 5)$, *SIAM J. Comput.* **28**, 1970–1971.
- R. L. Graham and H. O. Pollak (1971), On the addressing problem for loop switching, *Bell System Tech. J.* **50**, 2495–2519.
- B. W. Jones (1950), *The Theory of Quadratic Forms*, Carus Math. Monogr. **10**, Math. Assoc. of America.
- J. A. La Poutré and J. H. van Lint (1985), An associative block design $ABD(10, 5)$ does not exist, *Utilitas Math.* **31**, 219–225.
- P. Winkler (1983), Proof of the squashed cube conjecture, *Combinatorica* **3**, 135–139.

10

The principle of inclusion and exclusion; inversion formulae

As we have seen in several of the previous chapters, many problems of combinatorial analysis involve the *counting* of certain objects. We now treat one of the most useful methods for counting. It is known as the *principle of inclusion and exclusion*. The idea is as follows. If A and B are subsets of S and we wish to count the elements of $S \setminus \{A \cup B\}$, then the answer is not $|S| - |A| - |B|$ because the elements of $A \cap B$ have been subtracted twice. However $|S| - |A| - |B| + |A \cap B|$ is correct. The following theorem generalizes this idea.

Theorem 10.1. *Let S be an N -set; E_1, \dots, E_r not necessarily distinct subsets of S . For any subset M of $\{1, \dots, r\}$, we define $N(M)$ to be the number of elements of S in $\bigcap_{i \in M} E_i$ and for $0 \leq j \leq r$, we define $N_j := \sum_{|M|=j} N(M)$. Then the number of elements of S not in any of the subsets E_i , $1 \leq i \leq r$, is*

$$(10.1) \quad N - N_1 + N_2 - N_3 + \dots + (-1)^r N_r.$$

PROOF: (i) If $x \in S$ and x is in none of the E_i , then x contributes 1 to the expression (10.1).

(ii) If $x \in S$ and x is in exactly k of the sets E_i , then the contribution to (10.1) equals

$$1 - \binom{k}{1} + \binom{k}{2} - \dots + (-1)^k \binom{k}{k} = (1 - 1)^k = 0.$$

□

Remark. If we truncate the sum in (10.1) after a positive (respectively, negative) term, then we have an upper (respectively, lower) bound for the number of elements of S not in any of the E_i .

Because this method is of great importance, we shall give several examples as illustration.

Example 10.1. Let d_n denote the number of permutations π of $1, 2, \dots, n$ such that $\pi(i) \neq i$ for all i (these are called *derangements*). Let $S := S_n$, and let E_i be the subset of those permutations π with $\pi(i) = i$. By (10.1) we find

$$(10.2) \quad d_n = \sum_{i=0}^n (-1)^i \binom{n}{i} (n-i)! = n! \sum_{i=0}^n \frac{(-1)^i}{i!}.$$

From this formula, we see that for large values of n the probability that a permutation is a derangement is nearly e^{-1} . From (10.2) for n and $n-1$, we find a recursion formula for d_n :

$$(10.3) \quad d_n = nd_{n-1} + (-1)^n.$$

The formula (10.2) can also be obtained by inversion as follows. Consider the power series $D(x) := \sum_{n=0}^{\infty} d_n \frac{x^n}{n!}$ ($d_0 = 1$). Now if $F(x) := e^x D(x)$, then

$$F(x) = \sum_{m=0}^{\infty} \left(\sum_{r=0}^m \binom{m}{r} d_{m-r} \right) \frac{x^m}{m!}$$

and since $\sum_{r=0}^m \binom{m}{r} d_{m-r} = m!$, we find $F(x) = (1-x)^{-1}$. It follows that $D(x) = e^{-x}(1-x)^{-1}$ and by multiplying the power series for the two factors, we find (10.2) again.

Example 10.2. Let X be an n -set, $Y = \{y_1, \dots, y_k\}$ a k -set. We count the surjections of X to Y . Let S be the set of all mappings from X to Y , E_i the subset of mappings for which y_i is not in the image of X . By (10.1) we find the number of surjections to be $\sum_{i=0}^k (-1)^i \binom{k}{i} (k-i)^n$. Now this number is trivially 0 if $k > n$ and clearly $n!$ if $k = n$. So we have proved:

$$(10.4) \quad \sum_{i=0}^k (-1)^i \binom{k}{i} (k-i)^n = \begin{cases} n! & \text{if } k = n, \\ 0 & \text{if } k > n. \end{cases}$$

There are many formulae like (10.4) that are often quite hard to prove directly. The occurrence of $(-1)^i$ is usually a sign that counting the right kind of objects using the principle of inclusion and exclusion can produce the formula, as in this example. Nevertheless it is useful in this case to see another proof.

Let $P(x)$ be a polynomial of degree n , with highest coefficient a_n . We denote the sequence of values $P(0), P(1), \dots$ by \mathbf{P} . We now consider the sequence of differences $P(1) - P(0), P(2) - P(1), \dots$. This is \mathbf{Q}_1 , where $Q_1(x) := P(x+1) - P(x)$, a polynomial of degree $n-1$ with highest coefficient na_n . By repeating this procedure a number of times, we find a sequence \mathbf{Q}_k whose terms are $\sum_{i=0}^k (-1)^i \binom{k}{i} P(x+k-i)$, corresponding to the polynomial $Q_k(x)$ of degree $n-k$ with highest coefficient $n(n-1)\dots(n-k+1)a_n$. If $k = n$, then all the terms of \mathbf{Q}_k are $n!a_n$ and if $k > n$, then they are all 0. Take $P(x) = x^n$. We again find (10.4).

Example 10.3. The following identity is a well known relation between binomial coefficients:

$$(10.5) \quad \sum_{i=0}^n (-1)^i \binom{n}{i} \binom{m+n-i}{k-i} = \begin{cases} \binom{m}{k} & \text{if } m \geq k, \\ 0 & \text{if } m < k. \end{cases}$$

We see that if we wish to prove this using inclusion-exclusion, then the sets E_i that we wish to exclude involve choosing from an n -set, and after choosing i of them, we must choose $k-i$ elements from some set of size $m+n-i$. This shows us that the following combinatorial problem will lead us to the result (10.5). Consider a set $Z = X \cup Y$, where $X = \{x_1, \dots, x_n\}$ is an n -set of blue points and Y is an m -set of red points. How many k -subsets consist of red points only? The answer is trivially the right-hand side of (10.5). If we take S to be all the k -subsets of Z and E_i those k -subsets that contain x_i , then (10.1) gives us the left-hand side of (10.5).

Again we can ask whether this result can be proved directly. The answer is yes. To do this, we use the following expansion:

$$(10.6) \quad \sum_{j=0}^{\infty} \binom{a+j}{j} x^j = (1-x)^{-a-1}.$$

Note that $(-1)^i \binom{n}{i}$ is the coefficient of x^i in the expansion of $(1-x)^n$. From (10.6) we find that $\binom{m+n-i}{k-i}$ is the coefficient of x^{k-i} in the expansion of $(1-x)^{k-m-n-1}$. So the left-hand side of (10.5) is the coefficient of x^k in the expansion of $(1-x)^{k-m-1}$. If $m \leq k-1$, this is obviously 0 and if $m \geq k$, it is $\binom{m}{k}$, again by (10.6).

Example 10.4. (The *Euler function*) Let $n = p_1^{a_1} p_2^{a_2} \dots p_r^{a_r}$ be a positive integer. We denote by $\phi(n)$ the number of integers k with $1 \leq k \leq n$ such that the g.c.d. $(n, k) = 1$. We apply Theorem 10.1 with $S := \{1, 2, \dots, n\}$ and E_i the set of integers divisible by p_i , $1 \leq i \leq r$. Then (10.1) yields

$$(10.7) \quad \phi(n) = n - \sum_{i=1}^r \frac{n}{p_i} + \sum_{1 \leq i < j \leq r} \frac{n}{p_i p_j} - \dots = n \prod_{i=1}^r \left(1 - \frac{1}{p_i}\right).$$

The next theorem is used quite often.

Theorem 10.2. $\sum_{d|n} \phi(d) = n$.

PROOF: Consider $\{1, 2, \dots, n\} = N$. For each $m \in N$, we have $(m, n) | n$. The number of integers m with $(m, n) = d$, i.e. $m = m_1 d$, $n = n_1 d$ and $(m_1, n_1) = 1$ clearly equals $\phi(n_1) = \phi(n/d)$. So $n = \sum_{d|n} \phi(n/d)$ which is equivalent to the assertion. \square

At this point, it is useful to introduce the so-called *Möbius function*:

$$(10.8) \quad \mu(d) := \begin{cases} 1 & \text{if } d = \text{product of an even number of distinct primes,} \\ -1 & \text{if } d = \text{product of an odd number of distinct primes,} \\ 0 & \text{otherwise, i.e. } d \text{ not squarefree.} \end{cases}$$

Theorem 10.3.

$$\sum_{d|n} \mu(d) = \begin{cases} 1 & \text{if } n = 1, \\ 0 & \text{otherwise.} \end{cases}$$

PROOF: If $n = 1$, there is nothing to prove. If $n = p_1^{a_1} \dots p_r^{a_r}$, then

by (10.8) we have

$$\sum_{d|n} \mu(d) = \sum_{i=0}^r \binom{r}{i} (-1)^i = (1-1)^r = 0.$$

□

Note how similar the proofs of Theorems 10.1 and 10.3 are.

Using the Möbius function, we can reformulate (10.7) as follows:

$$(10.9) \quad \frac{\phi(n)}{n} = \sum_{d|n} \frac{\mu(d)}{d}.$$

Problem 10A. How many positive integers less than 1000 have no factor between 1 and 10?

Problem 10B. How many monic polynomials of degree n are there in $\mathbb{F}_p[x]$ that do not take on the value 0 for $x \in \mathbb{F}_p$?

Problem 10C. Determine $\sum_{n \leq x} \mu(n) \lfloor \frac{x}{n} \rfloor$.

Problem 10D. One of the most famous functions in complex analysis is the so-called *Riemann ζ -function* $\zeta(s) := \sum_{n=1}^{\infty} n^{-s}$, defined in the complex plane for $\operatorname{Re}(s) > 1$. Prove that $1/\zeta(s) = \sum_{n=1}^{\infty} \mu(n) n^{-s}$.

Problem 10E. Let $f_n(z)$ be the function that has as its zeros all numbers η for which $\eta^n = 1$ but $\eta^k \neq 1$ for $1 \leq k < n$. Prove that

$$f_n(z) = \prod_{k|n} (z^k - 1)^{\mu(n/k)}.$$

Theorem 10.3 makes it possible to derive a very useful inversion formula known as the *Möbius inversion formula*.

Theorem 10.4. Let $f(n)$ and $g(n)$ be functions defined for every positive integer n satisfying

$$(10.10) \quad f(n) = \sum_{d|n} g(d).$$

Then g satisfies

$$(10.11) \quad g(n) = \sum_{d|n} \mu(d) f\left(\frac{n}{d}\right).$$

PROOF: By (10.10) we have

$$\begin{aligned} \sum_{d|n} \mu(d) f\left(\frac{n}{d}\right) &= \sum_{d|n} \mu\left(\frac{n}{d}\right) f(d) \\ &= \sum_{d|n} \mu\left(\frac{n}{d}\right) \sum_{d'|d} g(d') = \sum_{d'|n} g(d') \sum_{m|(n/d')} \mu(m). \end{aligned}$$

By Theorem 10.3 the inner sum on the right-hand side is 0 unless $d' = n$. \square

Remark. The equation (10.11) also implies (10.10).

Example 10.5. We shall count the number N_n of circular sequences of 0's and 1's, where two sequences obtained by a rotation are considered the same. Let $M(d)$ be the number of circular sequences of length d that are not periodic. Then $N_n = \sum_{d|n} M(d)$. We observe that $\sum_{d|n} dM(d) = 2^n$ since this counts all possible circular sequences. By Theorem 10.4 we find from this equation that $nM(n) = \sum_{d|n} \mu(d)2^{n/d}$ and therefore

$$(10.12) \quad \begin{aligned} N_n &= \sum_{d|n} M(d) = \sum_{d|n} \frac{1}{d} \sum_{l|d} \mu\left(\frac{d}{l}\right) 2^l \\ &= \sum_{l|n} \frac{2^l}{l} \sum_{k|\frac{n}{l}} \frac{\mu(k)}{k} = \frac{1}{n} \sum_{l|n} \phi\left(\frac{n}{l}\right) 2^l. \end{aligned}$$

The final expression has the advantage that all the terms are positive. This raises the question whether we could have obtained that expression by some other counting technique. We shall see that the following theorem, known as *Burnside's lemma* (although the theorem is actually due to Cauchy and Frobenius; see the notes), provides the answer.

Theorem 10.5. *Let G be a permutation group acting on a set X . For $g \in G$ let $\psi(g)$ denote the number of points of X fixed by g . Then the number of orbits of G is equal to $\frac{1}{|G|} \sum_{g \in G} \psi(g)$.*

PROOF: Count pairs (g, x) , where $g \in G$, $x \in X$, $x^g = x$. Starting with g , we find $\sum_{g \in G} \psi(g)$. For each $x \in X$ there are $|G|/|O_x|$ such pairs, where O_x is the orbit of x . So the total number equals $|G| \sum_{x \in X} 1/|O_x|$. The orbits of G partition X , and if we sum the terms $1/|O_x|$ over all x in a particular orbit, we obtain 1. Thus $\sum_{x \in X} 1/|O_x|$ is the number of orbits. \square

Example 10.5 (continued). *Let G be the cyclic group of order n , i.e. the group of rotations of a circular sequence of 0's and 1's. If $d|n$ there are $\phi(n/d)$ integers g such that $(n, g) = d$ and for each such g there are 2^d circular sequences that are fixed by the rotation over g positions. So Theorem 10.5 immediately yields the result (10.12).*

Example 10.6. The following problem, introduced by Lucas in 1891, is known as the '*problème des ménages*'. We wish to seat n couples at a circular table so that men and women are in alternate places and no husband will sit on either side of his wife. In how many ways can this be done? We assume that the women have been seated at alternate places. Call the ladies 1 to n and the corresponding men also 1 to n . The problem amounts to placing the integers 1 to n on a circle with positions numbered 1 to n such that for all i the integer i is not in position i or position $i + 1 \pmod{n}$. Let E_i be the set of seatings in which husband i is sitting next to his wife. We now wish to use inclusion-exclusion and we must therefore calculate in how many ways it is possible to seat r husbands incorrectly. Call this number A_r . We do this as follows. Consider a circular sequence of $2n$ positions. Put a 1 in position $2i - 1$ if husband i is sitting to the right of his wife; put a 1 in position $2i$ if he is sitting to the left of his wife. Put zeros in the remaining positions. The configurations that we wish to count therefore are circular sequences of $2n$ zeros and ones, with exactly r ones, no two adjacent. Let A'_r be the number of sequences starting with a 1 (followed by a 0). By considering 10 as one symbol, we see that we must choose $r - 1$ out of $2n - r - 1$ positions. To count

the number A_r'' of sequences starting with a 0, we place the 0 at the end, and then it amounts to choosing r out of $2n - r$ places. Hence

$$A_r = A_r' + A_r'' = \binom{2n - r - 1}{r - 1} + \binom{2n - r}{r} = \frac{2n}{2n - r} \binom{2n - r}{r}.$$

By (10.1) we find that the number of ways to seat the men is

$$(10.13) \quad \sum_{r=0}^n (-1)^r (n - r)! \binom{2n - r}{r} \frac{2n}{2n - r}.$$

Problem 10F. We color the integers 1 to $2n$ red or blue in such a way that if i is red then $i - 1$ is not blue. Prove that

$$\sum_{k=0}^n (-1)^k \binom{2n - k}{k} 2^{2n - 2k} = 2n + 1.$$

Can you prove this identity directly?

Problem 10G. Count the number of permutations x_1, x_2, \dots, x_{2n} of the integers 1 to $2n$ such that $x_i + x_{i+1} \neq 2n + 1$ for $i = 1, 2, \dots, 2n - 1$.

Problem 10H. Prove that for $0 \leq k \leq n$

$$\sum_{i=0}^k \binom{k}{i} D_{n-i} = \sum_{j=0}^{n-k} (-1)^j \binom{n-k}{j} (n-j)!.$$

Notes.

The principle of inclusion and exclusion occurred as early as 1854 in a paper by Da Silva and later in a paper by Sylvester in 1883. For this reason (10.1) and similar formulae are sometimes called the formula of Da Silva, respectively Sylvester. A better name that is also often used is ‘sieve formula’. The formula is indeed an example of a principle that is used extensively in number theory, referred to as ‘sieve methods’. An example that is probably familiar to most readers is the sieve of Eratosthenes: to find the primes $\leq n^2$, take the integers $\leq n^2$ and sieve out all the multiples of primes $\leq n$.

The derangements treated in Example 10.1 occur again in Example 14.1 and Example 14.10. The first occurrence of this question is in one of the early books on games of chance: *Essai d'analyse sur les jeux de hazard* by P. R. de Montmort (1678–1719). It is still often referred to by the name that he gave it: ‘problème des rencontres’. Formula (10.2) is sometimes stated as follows. If n persons check their umbrellas (a typical Dutch example; it’s always raining in Holland) and subsequently pick one at random in the dark after a power failure, then the probability that nobody gets his own umbrella is roughly e^{-1} (if n is large).

The second proof in Example 10.2 is an example of the use of ‘calculus of finite differences’, used extensively in numerical analysis.

A. F. Möbius (1790–1868) was an astronomer (and before that an assistant to Gauss) who made important contributions to geometry and topology (e.g. the Möbius band).

G. F. B. Riemann (1826–1866) was professor in Göttingen, where he also obtained his doctorate under Gauss. He is famous for many of his ideas, which include the Riemann integral, Riemann surfaces and manifolds, and of course the so-called *Riemann hypothesis* on the location of the zeros of the ζ -function. One wonders what he would have left us if he had not died so young.

In most books in which it occurs, Theorem 10.5 is called Burnside’s lemma. This is just one of many examples of theorems, etc. attributed to the wrong person. For a history of this misnomer, we refer to Neumann (1979).

F. E. A. Lucas (1842–1891) was a French number theorist. He is known for his books on number theory and mathematical recreations. The former book contained the problem of Example 10.6. The *Fibonacci numbers* were given this name by Lucas. See the notes to Chapter 14.

References.

- F. E. A. Lucas (1891), *Théorie des nombres*, Gauthier-Villars, Paris.
- P. M. Neumann (1979), A lemma that is not Burnside’s, *Math. Scientist*, **4**, 133–141.

11

Permanents

Before introducing the main topic of this chapter, we present a generalization of Theorem 10.1. As in Theorem 10.1, let S be an n -set, E_1, \dots, E_r (not necessarily distinct) subsets of S . Let \mathbb{F} be any field. To each element $a \in S$, we assign a *weight* $w(a)$ in \mathbb{F} . For any subset M of $\{1, 2, \dots, r\}$, we define $W(M)$ to be the sum of the weights of the elements of S in $\bigcap_{i \in M} E_i$. For $0 \leq j \leq r$, we define $W_j := \sum_{|M|=j} W(M)$ (so $W_0 = \sum_{a \in S} w(a)$).

Theorem 11.1. *If $E(m)$ denotes the sum of the weights of the elements of S that are contained in exactly m of the subsets E_i , $1 \leq i \leq r$, then*

$$(11.1) \quad E(m) = \sum_{i=0}^{r-m} (-1)^i \binom{m+i}{i} W_{m+i}.$$

PROOF: The proof is nearly the same as for Theorem 10.1. If $x \in S$ and x is contained in exactly m of the subsets E_i , then the contribution of x to the sum in (11.1) is $w(x)$. If $x \in S$ and x is contained in exactly $m+k$ of the subsets E_i , then the contribution to the sum equals

$$\begin{aligned} w(x) \sum_{i=0}^k (-1)^i \binom{m+i}{i} \binom{m+k}{m+i} \\ = w(x) \binom{m+k}{k} \sum_{i=0}^k (-1)^i \binom{k}{i} = 0. \end{aligned}$$

□

We now give the definition of a *permanent*. Let $A = (\mathbf{a}_1, \dots, \mathbf{a}_n)$ be an $n \times n$ matrix with columns $\mathbf{a}_j = (a_{1j}, \dots, a_{nj})^\top$. Then per A , the permanent of A , is defined by

$$(11.2) \quad \text{per } A := \sum_{\pi \in S_n} a_{1\pi(1)} \cdots a_{n\pi(n)}.$$

So the permanent is defined in the same way as the determinant but without the signs depending on whether the permutation π is even or odd.

From the definition, the following properties of the permanent are obvious.

$$(11.3) \quad \text{per } A = \text{per } A^\top;$$

$$(11.4) \quad \text{if } P \text{ and } Q \text{ are permutation matrices, then per } A = \text{per } PAQ;$$

$$(11.5) \quad \text{per } A \text{ is a linear function of } \mathbf{a}_j, \quad 1 \leq j \leq n.$$

Of course per A is also a linear function of each of the rows of A . The permanent of A is much more difficult to calculate than its determinant. However, it is clear from (11.2) that expansion by rows or columns is possible. So define A_{ij} to be the matrix obtained from A by deleting row i and column j . Then

$$(11.6) \quad \text{per } A = \begin{cases} \sum_{i=1}^n a_{ij} \text{per } A_{ij}, & 1 \leq j \leq n, \\ \sum_{j=1}^n a_{ij} \text{per } A_{ij}, & 1 \leq i \leq n. \end{cases}$$

The following method of calculating a permanent (due to Ryser) is an application of Theorem 11.1.

Theorem 11.2. *Let A be an $n \times n$ matrix. If A_r is obtained from A by deleting r columns, then $S(A_r)$ denotes the product of the row-sums of A_r . We define Σ_r to be the sum of the values of $S(A_r)$ for all possible choices of A_r . Then*

$$(11.7) \quad \text{per } A = \sum_{r=0}^{n-1} (-1)^r \Sigma_r.$$

PROOF: Let S be the set of all products $p = a_{1i_1} \dots a_{ni_n}$ and define $w(p) := p$. Define E_j to be the set of products p for which $j \notin \{i_1, \dots, i_n\}$. Then the permanent of A is the sum of the weights of the elements of S that are not in any of the subsets E_j . So (11.7) is an immediate consequence of (11.1). \square

Problem 11A. Prove (10.4) using Theorem 11.2.

Remark. If A_1, \dots, A_n are subsets of $\{1, \dots, n\}$ and $a_{ij} = 1$ if $j \in A_i$, 0 otherwise, then $\text{per } A$ counts the number of SDRs of the sets A_1, \dots, A_n .

Example 11.1. We find another formula for the number of derangements of $1, 2, \dots, n$. The permanent of the matrix $J - I$ of size n is clearly d_n . From (11.7) we find

$$(11.8) \quad d_n = \sum_{r=0}^{n-1} (-1)^r \binom{n}{r} (n-r)^r (n-r-1)^{n-r}.$$

By expanding the term $(n-1-r)^{n-r}$ and applying (10.4) after changing the order of summation, we find a complicated proof of (10.2).

During the 1970's, several well known conjectures on permanents of (0,1)-matrices were proved, often by ingenious arguments. In fact, much of the research on permanents was motivated by these conjectures. Therefore we will devote attention to a number of these results in this and the next chapter. As an introduction, we consider (0,1)-matrices with two ones in each row and column.

Theorem 11.3. *If A is a (0,1)-matrix in which all row-sums and column-sums are 2, then*

$$\text{per } A \leq 2^{\lfloor \frac{1}{2}n \rfloor}.$$

PROOF: Consider the graph G whose vertices correspond to the rows of A , whose edges correspond to the columns of A , and where vertex i and edge j are incident exactly when $A(i, j) = 1$. This graph is regular of degree 2, and hence is the disjoint union of polygons. The submatrix corresponding to the vertices and edges

of a polygon is, after reordering rows and columns if necessary, a circulant

$$\begin{pmatrix} 1 & 1 & 0 & 0 & \cdots & 0 & 0 \\ 0 & 1 & 1 & 0 & \cdots & 0 & 0 \\ 0 & 0 & 1 & 1 & \cdots & 0 & 0 \\ \vdots & \vdots & \vdots & \vdots & \ddots & \vdots & \vdots \\ 0 & 0 & 0 & 0 & \cdots & 1 & 1 \\ 1 & 0 & 0 & 0 & \cdots & 0 & 1 \end{pmatrix}.$$

(This may degenerate into a 2 by 2 matrix of 1's.) The matrix A is the direct sum of such matrices, each of which has permanent 2. The number of factors is at most $\lfloor \frac{1}{2}n \rfloor$ and we see that equality holds in the theorem if A is the direct sum of $\lfloor \frac{1}{2}n \rfloor$ matrices J of size 2. \square

This elementary theorem is concerned with the relationship between the row-sums of a matrix and the permanent of that matrix, and the same is true for many of the following theorems. This brings us to the first difficult question. It was conjectured by H. Minc in 1967 that if A is a (0,1)-matrix with row-sums r_1, \dots, r_n , then

$$(11.9) \quad \text{per } A \leq \prod_{j=1}^n (r_j!)^{1/r_j}.$$

Observe that the proof of Theorem 11.3 shows that equality can hold in (11.9) and in fact, we have equality if A is the direct sum of matrices J_m . Several results that were weaker than (11.9) were proved, often by intricate and long arguments. The conjecture was finally proved in 1973 by L. M. Brégman. All the more surprising is the fact that A. Schrijver came up with an extremely elegant and very short proof of Minc's conjecture in 1977. The proof depends on the following lemma.

Lemma 11.4. *If t_1, t_2, \dots, t_r are nonnegative real numbers, then*

$$\left(\frac{t_1 + \cdots + t_r}{r} \right)^{t_1 + \cdots + t_r} \leq t_1^{t_1} \cdots t_r^{t_r}.$$

PROOF: Since $x \log x$ is a convex function, we have

$$\frac{t_1 + \cdots + t_r}{r} \log \left(\frac{t_1 + \cdots + t_r}{r} \right) \leq \frac{t_1 \log t_1 + \cdots + t_r \log t_r}{r},$$

which proves the assertion. \square

In the following, we use (11.6) in the following form:

$$\text{per } A = \sum_{k, a_{ik}=1} \text{per } A_{ik}.$$

Theorem 11.5. *Let A be an $n \times n$ $(0, 1)$ -matrix with r_i ones in row i , $1 \leq i \leq n$. Then*

$$\text{per } A \leq \prod_{i=1}^n (r_i)!^{1/r_i}.$$

PROOF: The proof is by induction on n . For $n = 1$, the theorem is trivial. We assume that the theorem is true for matrices of size $n-1$. The idea is to estimate $(\text{per } A)^{n \text{ per } A}$ and to split this expression into several products. Now note that r_i is the number of values of k for which $a_{ik} = 1$ and apply the lemma. We find:

$$(11.10) \quad (\text{per } A)^{n \text{ per } A} = \prod_{i=1}^n (\text{per } A)^{\text{per } A} \\ \leq \prod_{i=1}^n \left(r_i^{\text{per } A} \prod_{k, a_{ik}=1} \text{per } A_{ik}^{\text{per } A_{ik}} \right).$$

Now, let S denote the set of all permutations ν of $\{1, \dots, n\}$ for which $a_{i\nu_i} = 1$ for $i = 1, \dots, n$. So $|S| = \text{per } A$. Furthermore, the number of $\nu \in S$ such that $\nu_i = k$ is $\text{per } A_{ik}$ if $a_{ik} = 1$ and 0 otherwise. So the right-hand side of (11.10) is equal to

$$(11.11) \quad \prod_{\nu \in S} \left\{ \left(\prod_{i=1}^n r_i \right) \cdot \left(\prod_{i=1}^n \text{per } A_{i\nu_i} \right) \right\}.$$

We now apply the induction hypothesis to each $A_{i\nu_i}$. This yields

$$(11.12) \quad (\text{per } A)^{n \text{ per } A} \leq \\ \prod_{\nu \in S} \left\{ \left(\prod_{i=1}^n r_i \right) \cdot \prod_{i=1}^n \left[\prod_{\substack{j \neq i, \\ a_{j\nu_i}=0}} (r_j!)^{1/r_j} \prod_{\substack{j \neq i, \\ a_{j\nu_i}=1}} ((r_j - 1)!)^{1/(r_j-1)} \right] \right\}.$$

Since the number of i such that $i \neq j$ and $a_{j\nu_i} = 0$ is $n - r_j$, and the number of i such that $i \neq j$ and $a_{j\nu_i} = 1$ is $r_j - 1$, we can replace the right-hand side of (11.12) by

$$\prod_{\nu \in S} \left\{ \left(\prod_{i=1}^n r_i \right) \cdot \left[\prod_{j=1}^n (r_j!)^{(n-r_j)/r_j} (r_j - 1)! \right] \right\} =$$

$$\prod_{\nu \in S} \prod_{i=1}^n (r_i)^{n/r_i} = \left(\prod_{i=1}^n (r_i!)^{1/r_i} \right)^{n \text{ per } A}$$

and the assertion is proved. □

We now shall consider a special class of (0,1)-matrices, namely the (0,1)-matrices that have exactly k ones in each row and column. We denote this class by $\mathcal{A}(n, k)$. We define:

$$(11.13) \quad M(n, k) := \max\{\text{per } A : A \in \mathcal{A}(n, k)\},$$

$$(11.14) \quad m(n, k) := \min\{\text{per } A : A \in \mathcal{A}(n, k)\}.$$

By taking direct sums, we find the following inequalities:

$$(11.15) \quad M(n_1 + n_2, k) \geq M(n_1, k)M(n_2, k),$$

$$(11.16) \quad m(n_1 + n_2, k) \leq m(n_1, k)m(n_2, k).$$

These two inequalities allow us to introduce two more functions using the following result, known as *Fekete's lemma*.

Lemma 11.6. *Let $f : \mathbb{N} \rightarrow \mathbb{N}$ be a function for which $f(m + n) \geq f(m)f(n)$ for all $m, n \in \mathbb{N}$. Then $\lim_{n \rightarrow \infty} f(n)^{1/n}$ exists (possibly ∞).*

PROOF: Fix m and fix $l, l \leq m$. By induction, we find from the inequality for f that $f(l + km) \geq f(l)[f(m)]^k$. Therefore

$$\liminf f(l + km)^{1/(l+km)} \geq f(m)^{1/m}$$

and since there are m possible values for l , we in fact have

$$\liminf f(n)^{1/n} \geq f(m)^{1/m}.$$

Now let $m \rightarrow \infty$. We find that

$$\liminf f(n)^{1/n} \geq \limsup f(m)^{1/m},$$

but then these are equal. \square

The assertion of the lemma is also true if in the inequality for f we replace \geq by \leq . By applying the lemma to (11.15) and (11.16), we can define:

$$(11.17) \quad M(k) := \lim_{n \rightarrow \infty} \{M(n, k)\}^{1/n},$$

$$(11.18) \quad m(k) := \lim_{n \rightarrow \infty} \{m(n, k)\}^{1/n}.$$

Problem 11B. Prove that $M(n, k) \geq k!$. Prove that $M(k) \leq (k!)^{1/k}$. Show by example that $M(k) \geq (k!)^{1/k}$. This shows that $M(k) = (k!)^{1/k}$.

The function $m(n, k)$ is much more difficult to handle. What we should expect is based on a famous problem still referred to as the *Van der Waerden conjecture*, although in 1981 two different proofs of the conjecture appeared (after nearly 50 years of research on this question!). We formulate the conjecture below, and the proof will be given in the next chapter.

Conjecture. *If A is an $n \times n$ matrix with nonnegative entries in which all row-sums and column-sums are 1, then*

$$(11.19) \quad \text{per } A \geq n! n^{-n}.$$

The matrices considered in the conjecture are usually called *doubly stochastic matrices*. If $A \in \mathcal{A}(n, k)$, then dividing all the elements of A by k yields a doubly stochastic matrix. Therefore the conjecture (now a theorem) shows that $m(k) \geq k/e$. This is remarkable because the value of $M(k)$ given in Problem 11B tends

to k/e for $k \rightarrow \infty$ (see the notes). This means that for large n , and A an arbitrary element of $\mathcal{A}(n, k)$, the value of $(\text{per } A)^{1/n}$ is nearly k/e . For a long time, the best lower bound for $m(n, 3)$ was $n + 3$ and even that was not easy to prove. Once again, the next improvement was both considerable and elementary. We now give the proof of that result, due to Voorhoeve (1979).

Theorem 11.7. $m(n, 3) \geq 6 \cdot (\frac{4}{3})^{n-3}$.

PROOF: Let U_n denote the set of $n \times n$ matrices with nonnegative integers as entries and all row-sums and column-sums 3; $u(n) := \min\{\text{per } A : A \in U_n\}$. Denote by V_n the set of all matrices obtained from elements of U_n by decreasing one positive entry by 1; $v(n) := \min\{\text{per } A : A \in V_n\}$. We first show that

$$(11.20) \quad u(n) \geq \left\lceil \frac{3}{2}v(n) \right\rceil.$$

Let A be an element of U_n with first row $\mathbf{a} = (\alpha_1, \alpha_2, \alpha_3, 0, \dots, 0)$, where $\alpha_i \geq 0$ for $i = 1, 2, 3$. Since

$$\begin{aligned} 2\mathbf{a} &= \alpha_1(\alpha_1 - 1, \alpha_2, \alpha_3, 0, \dots, 0) + \alpha_2(\alpha_1, \alpha_2 - 1, \alpha_3, 0, \dots, 0) \\ &\quad + \alpha_3(\alpha_1, \alpha_2, \alpha_3 - 1, 0, \dots, 0), \end{aligned}$$

we find from (11.5) that $2u(n) \geq (\alpha_1 + \alpha_2 + \alpha_3)v(n) = 3v(n)$, proving the assertion.

Next, we show that

$$(11.21) \quad v(n) \geq \left\lceil \frac{4}{3}v(n-1) \right\rceil.$$

We must distinguish between two cases. In the first one, A is an element of V_n with first row $(1, 1, 0, \dots, 0)$ and the matrix obtained from A by deleting the first row has the form $(\mathbf{c}_1, \mathbf{c}_2, B)$. The column-sum of $\mathbf{c}_3 := \mathbf{c}_1 + \mathbf{c}_2$ is either 3 or 4. By (11.6), we have

$$\text{per } A = \text{per } (\mathbf{c}_1, B) + \text{per } (\mathbf{c}_2, B) = \text{per } (\mathbf{c}_3, B).$$

If the column-sum of \mathbf{c}_3 is 3, then the matrix (\mathbf{c}_3, B) is in U_{n-1} and we are done by (11.20). If the sum is 4, then we use the same trick as

above: write $3\mathbf{c}_3$ as a linear combination of four vectors \mathbf{d}_i such that each matrix (\mathbf{d}_i, B) is in V_{n-1} and we find that $3 \text{ per } A \geq 4v(n-1)$. The second case that we have to consider is that A has $(2, 0, \dots, 0)$ as first row. If we delete the first row and column of A , then there are again two possibilities. We obtain a matrix B that is either in U_{n-1} or in V_{n-1} . So we have $\text{per } A \geq 2 \min\{u(n-1), v(n-1)\}$ and we are done by (11.20). By combining (11.20) and (11.21) with the trivial value $v(1) = 2$, the assertion of the theorem follows. \square

We now consider a larger class of $n \times n$ matrices, namely those with nonnegative integers as entries and all row-sums and column-sums equal to k . We denote this class by $\Lambda(n, k)$ and the minimal permanent within the class by $\lambda(n, k)$. Again we have $\lambda(m+n, k) \leq \lambda(m, k)\lambda(n, k)$ and by Fekete's lemma, we can define

$$(11.22) \quad \theta(k) := \lim_{n \rightarrow \infty} (\lambda(n, k))^{1/n}.$$

From Theorem 11.3 and Theorem 11.7, we know that $\lambda(n, 2) = 2$ and $\lambda(n, 3) \geq 6 \cdot (\frac{4}{3})^{n-3}$. From (11.19), we have seen above that $\lambda(n, k) \geq n! (\frac{k}{n})^n$. We have also seen that there is a connection between permanents and SDRs. We now show a proof in which this connection is exploited.

Theorem 11.8. $\lambda(n, k) \leq k^{2n} / \binom{nk}{n}$.

PROOF: We denote by $P_{n,k}$ the collection of all ordered partitions of the set $\{1, 2, \dots, nk\}$ into classes of size k . We have

$$(11.23) \quad p_{n,k} := |P_{n,k}| = \frac{(nk)!}{(k!)^n}.$$

Now let $\mathcal{A} := (A_1, \dots, A_n)$ be such a partition. The number of SDRs of the subsets A_1, \dots, A_n is k^n . Consider a second partition $\mathcal{B} := (B_1, \dots, B_n)$. We denote by $s(\mathcal{A}, \mathcal{B})$ the number of common SDRs of \mathcal{A} and \mathcal{B} . We define an $n \times n$ matrix A with entries α_{ij} by $\alpha_{ij} := |A_i \cap B_j|$. The point of the proof is the fact that $\text{per } A$ counts the number of common SDRs of \mathcal{A} and \mathcal{B} . Furthermore, by definition of the partitions, the matrix A is in $\Lambda(n, k)$. Therefore

$$s(\mathcal{A}, \mathcal{B}) = \text{per } A \geq \lambda(n, k).$$

If $\mathcal{A} \in P_{n,k}$ is given and some SDR of \mathcal{A} is given, then there are $n!p_{n,k-1}$ ordered partitions \mathcal{B} that have this same SDR. Hence we have

$$\sum_{\mathcal{B} \in P_{n,k}} s(\mathcal{A}, \mathcal{B}) = k^n \cdot n! p_{n,k-1}.$$

Combining this with (11.23) and the inequality for $\lambda(n, k)$, we find

$$\lambda(n, k) \leq \frac{k^n \cdot n! p_{n,k-1}}{p_{n,k}} = \frac{k^{2n}}{\binom{nk}{n}}.$$

□

This proof is due to Schrijver and Valiant (1980) who also gave the following corollary.

Corollary. $\theta(k) \leq \frac{(k-1)^{k-1}}{k^{k-2}}.$

PROOF: This follows in the usual way from the previous theorem by using Stirling's formula: $n! \sim n^n e^{-n} (2\pi n)^{1/2}$. □

The corollary combined with Theorem 11.7 gives us one more value of $\theta(k)$, namely $\theta(3) = \frac{4}{3}$.

Problem 11C. Consider the set of integers $1, 2, \dots, 64$. We first remove the integers $\equiv 1 \pmod{9}$, i.e. $x_1 = 1, \dots, x_8 = 64$. Then we remove the integers $x_i + 8$, where 72 is to be interpreted as 8. This leaves us with a set S of 48 elements. We partition S into subsets A_1, \dots, A_8 and also into subsets B_1, \dots, B_8 , where A_i contains integers in the interval $(8(i-1), 8i]$ and B_i contains the integers $\equiv i \pmod{8}$. How many common SDRs are there for the systems A_1, \dots, A_8 and B_1, \dots, B_8 ?

Problem 11D. We return to Problem 5G. Again, consider a bipartite graph on $2n$ vertices that is regular of degree 3. Give a lower bound for the number of perfect matchings.

Problem 11E. On a circular arrangement of the integers $1, 2, \dots, n$ consider the subsets $\{i, i+1, i+2\}$ where $i = 1, 2, \dots, n$ and integers are interpreted mod n . How many SDR's does this collection of sets have?

Notes.

In his book *Permanents*, H. Minc (1978) mentions that the name permanent is essentially due to Cauchy (1812) although the word as such was first used by Muir in 1882. Nevertheless, a referee of one of Minc's earlier papers admonished him for inventing this ludicrous name! For an extensive treatment of permanents, we refer to Minc's book. There, one can find much of the theory that was developed mainly to solve the Van der Waerden conjecture (without success at the time of writing of the book).

Theorem 11.2 is from Ryser (1963).

For a number of results related to the Minc conjecture, we refer to Van Lint (1974).

The lemma known as *Fekete's lemma* occurs in Fekete (1923). For another application, we refer to J. W. Moon (1968).

The term *doubly stochastic matrix* can be motivated by considering the entries to be conditional probabilities. However, permanents do not seem to play a role of importance in probability theory.

The remarks concerning $m(k)$ and $M(k)$ preceding Theorem 11.7 are based on Stirling's formula and the related inequality $n! \geq n^n e^{-n}$. This inequality is easily proved by induction, using the fact that $(1+n^{-1})^n$ is increasing with limit e . Actually Stirling's formula was first given by de Moivre. Stirling derived an asymptotic series for the gamma function which leads to the estimate

$$\Gamma(x) = x^{x-\frac{1}{2}} e^{-x} (2\pi)^{\frac{1}{2}} e^{\theta/(12x)},$$

where $0 < \theta < 1$. ($n! = \Gamma(n+1)$.)

A. Schrijver (1998) has established equality in the Corollary to Theorem 11.8 by proving that

$$\lambda(n, k) \geq \left(\frac{(k-1)^{k-1}}{k^{k-2}} \right)^n.$$

References.

L. M. Brégman (1973), Certain properties of nonnegative matrices and their permanents, *Dokl. Akad. Nauk SSSR* **211**, 27–30 (*Soviet Math. Dokl.* **14**, 945–949).

- M. Fekete (1923), Über die Verteilung der Wurzeln bei gewissen algebraischen Gleichungen mit ganzzahligen Koeffizienten, *Math. Zeitschr.* **17**, 228–249.
- J. H. van Lint (1974), *Combinatorial Theory Seminar Eindhoven University of Technology*, Lecture Notes in Mathematics **382**, Springer-Verlag.
- H. Minc (1967), An inequality for permanents of $(0,1)$ matrices, *J. Combinatorial Theory* **2**, 321–326.
- H. Minc (1978), *Permanents*, Encyclopedia of Mathematics and its Applications, vol. 6, Addison-Wesley, reissued by Cambridge University Press.
- J. W. Moon (1968), *Topics on Tournaments*, Holt, Rinehart and Winston.
- H. J. Ryser (1963), *Combinatorial Mathematics*, Carus Math. Monograph **14**.
- A. Schrijver (1978), A short proof of Minc's conjecture, *J. Combinatorial Theory (A)* **25**, 80–83.
- A. Schrijver and W. G. Valiant (1980), On lower bounds for permanents, *Proc. Kon. Ned. Akad. v. Wetensch. A* **83**, 425–427.
- A. Schrijver (1998), Counting 1-factors in regular bipartite graphs, *J. Combinatorial Theory (B)* **72**, 122–135.
- M. Voorhoeve (1979), A lower bound for the permanents of certain $(0,1)$ -matrices, *Proc. Kon. Ned. Akad. v. Wetensch. A* **82**, 83–86.

12

The Van der Waerden conjecture

In this chapter, we denote the set of all doubly stochastic matrices of size $n \times \Omega_n$. The subset consisting of matrices for which all entries are *positive* is denoted by Ω_n^* . We define $J_n := n^{-1}J$, where J denotes the $n \times n$ matrix for which all entries are 1. The vector $(1, 1, \dots, 1)^\top$ is denoted by \mathbf{j} .

In 1926, B. L. van der Waerden proposed as a problem to determine the minimal permanent among all doubly stochastic matrices. It was natural to assume that this minimum is per $J_n = n! n^{-n}$ (as stated in (11.19)). The assertion

$$(12.1) \quad (A \in \Omega_n \text{ and } A \neq J_n) \Rightarrow (\text{per } A > \text{per } J_n)$$

became known as the ‘Van der Waerden conjecture’ (although in 1969 he told one of the present authors that he had not heard this name before and that he had made no such conjecture). In 1981 two different proofs of the conjecture appeared, one by D. I. Falikman, submitted in 1979, and one by G. P. Egoritsjev, submitted in 1980. We shall give our version of Egoritsjev’s proof which had a slightly stronger result than Falikman’s, cf. Van Lint (1981).

In the following, we shall use the term *minimizing matrix* for a matrix $A \in \Omega_n$ such that $\text{per } A = \min\{\text{per } S : S \in \Omega_n\}$. As usual, the matrix obtained from A by deleting row i and column j is denoted by A_{ij} . We often consider A as a sequence of n columns and write $A = (\mathbf{a}_1, \dots, \mathbf{a}_n)$. Later on, we shall consider permanents of matrices of size $n-1$ but we wish to use the notation for matrices of size n . The trick is to write $\text{per } (\mathbf{a}_1, \dots, \mathbf{a}_{n-1}, \mathbf{e}_j)$, where \mathbf{e}_j denotes the j -th standard basis vector. This permanent does not change

value if the j -th row and n -th column are deleted. We remind the reader that by Problem 5C (Birkhoff), the set Ω_n is a convex set with the permutation matrices as vertices.

We need a few elementary results on matrices in Ω_n . The first statement is the same as Theorem 5.4.

Theorem 12.1. *If A is an $n \times n$ matrix with nonnegative entries, then $\text{per } A = 0$ if and only if A contains an $s \times t$ zero submatrix such that $s + t = n + 1$.*

We shall call an $n \times n$ matrix *partly decomposable* if it contains a $k \times n - k$ zero submatrix. So A is partly decomposable if there exist permutation matrices P and Q such that

$$PAQ = \begin{pmatrix} B & C \\ O & D \end{pmatrix},$$

where B and D are square matrices. If a matrix is not partly decomposable, then we shall say that it is *fully indecomposable*. If $A \in \Omega_n$ and A is partly decomposable, then, in the representation given above, we must have $C = O$, because the sum of the entries of B equals the number of columns of B and the sum of the entries of B and C is equal to the number of rows of B . So in that case, A is the direct sum $B \dot{+} D$ of an element of Ω_k and an element of Ω_{n-k} .

Problem 12A. Let A be an $n \times n$ matrix with nonnegative entries ($n \geq 2$). Prove that A is fully indecomposable if and only if $\text{per } A_{ij} > 0$ for all i and j .

Problem 12B. Let A be an $n \times n$ matrix with nonnegative entries. Prove that if A is fully indecomposable, then AA^\top and $A^\top A$ are also fully indecomposable.

Theorem 12.2. *A minimizing matrix is fully indecomposable.*

PROOF: Let $A \in \Omega_n$ be a minimizing matrix and suppose that A is partly decomposable. Then, as we saw above, $A = B \dot{+} C$, where $B \in \Omega_k$ and $C \in \Omega_{n-k}$. By Theorem 12.1, we have $\text{per } A_{k,k+1} = 0$ and $\text{per } A_{k+1,k} = 0$. By Birkhoff's theorem, we may assume that B and C have positive elements on their diagonals. In A we replace

b_{kk} by $b_{kk} - \epsilon$ and c_{11} by $c_{11} - \epsilon$ and we put an ϵ in the positions $k, k + 1$ and $k + 1, k$. The new matrix is again in Ω_n , if ϵ is small enough. The permanent of the new matrix is equal to

$$\text{per } A - \epsilon \text{ per } A_{kk} - \epsilon \text{ per } A_{k+1, k+1} + O(\epsilon^2).$$

Since $\text{per } A_{kk}$ and $\text{per } A_{k+1, k+1}$ are both positive, this new permanent is smaller than $\text{per } A$ if ϵ is sufficiently small. This contradiction proves the assertion. \square

Corollary. (i) *A row of a minimizing matrix has at least two positive entries.*

(ii) *For any a_{ij} in a minimizing matrix, there is a permutation σ such that $\sigma(i) = j$ and $a_{s, \sigma(s)} > 0$ for $1 \leq s \leq n$, $s \neq i$.*

PROOF: Clearly (i) is trivial, and (ii) follows from Problem 12A. \square

Let us now look at how far we can get with *calculus*. A very important step in the direction of a proof of (12.1) is the following surprising result due to Marcus and Newman (1959).

Theorem 12.3. *If $A \in \Omega_n$ is a minimizing matrix and $a_{hk} > 0$, then $\text{per } A_{hk} = \text{per } A$.*

PROOF: Let S be the subset of Ω_n consisting of the doubly stochastic matrices X for which $x_{ij} = 0$ if $a_{ij} = 0$. Then A is an interior point of the set S , which is a subset of \mathbb{R}^m for some m . If we denote the set of pairs (i, j) for which $a_{ij} = 0$ by Z , we can describe S by the relations:

$$\begin{aligned} \sum_{i=1}^n x_{ij} &= 1, & j &= 1, \dots, n; \\ \sum_{j=1}^n x_{ij} &= 1, & i &= 1, \dots, n; \\ x_{ij} &\geq 0, & i, j &= 1, \dots, n; \\ x_{ij} &= 0, & (i, j) &\in Z. \end{aligned}$$

Since A is minimizing, the permanent function has a relative minimum in the interior point A of the set S and we can use Lagrange

multipliers to describe the situation. So we define:

$$F(X) := \text{per } X - \sum_{i=1}^n \lambda_i \left(\sum_{k=1}^n x_{ik} - 1 \right) - \sum_{j=1}^n \mu_j \left(\sum_{k=1}^n x_{kj} - 1 \right).$$

For $(i, j) \notin Z$, we have:

$$\partial F(X) / \partial x_{ij} = \text{per } X_{ij} - \lambda_i - \mu_j.$$

It follows that $\text{per } A_{ij} = \lambda_i + \mu_j$ and from this we find that for $1 \leq i \leq n$

$$(12.2) \quad \text{per } A = \sum_{j=1}^n a_{ij} \text{per } A_{ij} = \sum_{j=1}^n a_{ij} (\lambda_i + \mu_j) = \lambda_i + \sum_{j=1}^n a_{ij} \mu_j,$$

and similarly for $1 \leq j \leq n$,

$$(12.3) \quad \text{per } A = \mu_j + \sum_{i=1}^n a_{ij} \lambda_i.$$

We introduce the vectors $\lambda = (\lambda_1, \dots, \lambda_n)^\top$ and $\mu = (\mu_1, \dots, \mu_n)^\top$. From (12.2) and (12.3), we find

$$(12.4) \quad (\text{per } A)\mathbf{j} = \lambda + A\mu = \mu + A^\top \lambda.$$

Multiplying by A^\top gives us

$$(\text{per } A)\mathbf{j} = A^\top \lambda + A^\top A\mu,$$

and hence $\mu = A^\top A\mu$, and similarly $\lambda = AA^\top \lambda$. The matrices AA^\top and $A^\top A$ are both in Ω_n and by Problem 12B and Theorem 12.2, they have eigenvalue 1 with multiplicity one corresponding to the eigenvector \mathbf{j} . So we see that both λ and μ are multiples of \mathbf{j} . By (12.4), we have $\lambda_i + \mu_j = \text{per } A$ and since $\text{per } A_{ij} = \lambda_i + \mu_j$, we are finished. \square

Remark. It was shown by Marcus and Newman that Theorem 12.3 implies that a minimizing matrix in Ω_n^* must be J_n . The proof depends on the following idea. Let A be an element of Ω_n with the property that $\text{per } A_{hk} = \text{per } A$ for all h, k . If we replace any column of A by a vector \mathbf{x} for which $\sum_{i=1}^n x_{ij} = 1$, then the value of the permanent does not change (by (11.6)). We shall refer to this idea as the *substitution principle*. If A is a minimizing matrix in Ω_n^* , then the substitution principle allows us to replace any two columns of A by their average and thus obtain a new minimizing matrix. In this way, one constructs a sequence of minimizing matrices which tends to J_n . The uniqueness of the minimum takes a little extra work.

A final result that uses ideas from calculus is the following generalization of Theorem 12.3 due to London (1971).

Theorem 12.4. *If $A \in \Omega_n$ is a minimizing matrix, then $\text{per } A_{ij} \geq \text{per } A$ for all i and j .*

PROOF: Let i and j be given. By Corollary (ii) of Theorem 12.2, there is a permutation σ such that $\sigma(i) = j$ and $a_{s,\sigma(s)} > 0$ for $1 \leq s \leq n$, $s \neq i$. Let P be the corresponding permutation matrix. For $0 \leq \theta \leq 1$ we define $f(\theta) := \text{per}((1 - \theta)A + \theta P)$. Since A is a minimizing matrix, $f'(0) \geq 0$, i.e.

$$0 \leq \sum_{i=1}^n \sum_{j=1}^n (-a_{ij} + p_{ij}) \text{per } A_{ij} = -n \text{per } A + \sum_{s=1}^n \text{per } A_{s,\sigma(s)}.$$

By Theorem 12.3 we have $\text{per } A_{s,\sigma(s)} = \text{per } A$ for $s \neq i$ and therefore $\text{per } A_{ij} \geq \text{per } A$. \square

Problem 12C. Show that Theorem 12.3 implies that if $A \in \Omega_5^*$ is a minimizing matrix, then there is a minimizing matrix $B \in \Omega_5^*$ that has aJ of size 4 as a principal submatrix. Then show that a must be $\frac{1}{5}$.

We now come to the main tool in the proof of the Van der Waerden conjecture. This time we need *linear algebra*. We shall give a direct proof of a theorem on symmetric bilinear forms which leads

to the inequality that was derived by Egoritsjev from the so-called Alexandroff–Fenchel inequalities (which we do not treat).

Consider the space \mathbb{R}^n with a symmetric inner product $\langle \mathbf{x}, \mathbf{y} \rangle = \mathbf{x}^\top Q \mathbf{y}$. If Q has one positive eigenvalue and $n - 1$ negative eigenvalues, we shall speak of a *Lorentz space*. We use the following standard terminology: a nonzero vector \mathbf{x} is *isotropic* if $\langle \mathbf{x}, \mathbf{x} \rangle = 0$, *positive*, respectively *negative*, if $\langle \mathbf{x}, \mathbf{x} \rangle$ is positive, respectively negative.

Every nonzero vector in the $(n - 1)$ -dimensional span of the negative eigenvectors is negative, so if \mathbf{a} is positive and \mathbf{b} is not a scalar multiple of \mathbf{a} , then the plane spanned by \mathbf{a} and \mathbf{b} must contain a negative vector. Therefore the quadratic form in λ given by $\langle \mathbf{a} + \lambda \mathbf{b}, \mathbf{a} + \lambda \mathbf{b} \rangle$ must have a positive discriminant. Thus we have the following inequality, which is like the Cauchy inequality but the other way around.

Theorem 12.5. *If \mathbf{a} is a positive vector in a Lorentz space and \mathbf{b} is arbitrary, then*

$$\langle \mathbf{a}, \mathbf{b} \rangle^2 \geq \langle \mathbf{a}, \mathbf{a} \rangle \langle \mathbf{b}, \mathbf{b} \rangle$$

and equality holds if and only if $\mathbf{b} = \lambda \mathbf{a}$ for some constant λ .

The connection with permanents is provided by the following definition. Consider vectors $\mathbf{a}_1, \dots, \mathbf{a}_{n-2}$ in \mathbb{R}^n with *positive* coordinates. As usual, let $\mathbf{e}_1, \dots, \mathbf{e}_n$ be the standard basis of \mathbb{R}^n . We define an inner product on \mathbb{R}^n by

$$(12.5) \quad \langle \mathbf{x}, \mathbf{y} \rangle := \text{per} (\mathbf{a}_1, \mathbf{a}_2, \dots, \mathbf{a}_{n-2}, \mathbf{x}, \mathbf{y}),$$

i.e.

$$\langle \mathbf{x}, \mathbf{y} \rangle = \mathbf{x}^\top Q \mathbf{y},$$

where Q is given by

$$(12.6) \quad q_{ij} := \text{per} (\mathbf{a}_1, \mathbf{a}_2, \dots, \mathbf{a}_{n-2}, \mathbf{e}_i, \mathbf{e}_j).$$

Note that if A is a matrix with columns $\mathbf{a}_1, \dots, \mathbf{a}_n$ and we delete the last two columns and the rows with index i and j , then the reduced matrix has permanent equal to q_{ij} .

Theorem 12.6. *The space \mathbb{R}^n with the inner product defined by (12.5) is a Lorentz space.*

PROOF: The proof is by induction. For $n = 2$, we have $Q = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}$ and the assertion is true. Now assume the theorem is true for \mathbb{R}^{n-1} . In the first step of the proof, we show that Q does not have the eigenvalue 0. Suppose $Q\mathbf{c} = 0$, i.e.

$$(12.7) \quad \text{per}(\mathbf{a}_1, \dots, \mathbf{a}_{n-2}, \mathbf{c}, \mathbf{e}_j) = 0 \quad \text{for } 1 \leq j \leq n.$$

By deleting the last column and the j -th row, we can consider (12.7) as a relation for vectors in \mathbb{R}^{n-1} . We consider the inner product given by

$$(12.8) \quad \text{per}(\mathbf{a}_1, \dots, \mathbf{a}_{n-3}, \mathbf{x}, \mathbf{y}, \mathbf{e}_j)_{jn}$$

and apply the induction hypothesis, (12.7) and Theorem 12.5. Substitution of $\mathbf{x} = \mathbf{a}_{n-2}$, $\mathbf{y} = \mathbf{a}_{n-2}$ in (12.8) gives a positive value, and $\mathbf{x} = \mathbf{a}_{n-2}$, $\mathbf{y} = \mathbf{c}$ gives the value 0. Therefore

$$(12.9) \quad \text{per}(\mathbf{a}_1, \dots, \mathbf{a}_{n-3}, \mathbf{c}, \mathbf{c}, \mathbf{e}_j) \leq 0 \quad \text{for } 1 \leq j \leq n$$

and for each j equality holds if and only if all coordinates of \mathbf{c} except c_j are 0. If we multiply the left-hand side of (12.9) by the j -th coordinate of \mathbf{a}_{n-2} and sum over j , we find $\mathbf{c}^\top Q\mathbf{c}$. Therefore the assumption $Q\mathbf{c} = 0$ implies that $\mathbf{c} = 0$.

For $0 \leq \theta \leq 1$, we define a matrix Q_θ by taking (12.5) and replacing every \mathbf{a}_i by $\theta\mathbf{a}_i + (1 - \theta)\mathbf{j}$. From what we have shown above, it follows that for every θ in $[0, 1]$ the matrix Q_θ does not have the eigenvalue 0. Therefore the number of positive eigenvalues is constant. Since this number is one for $\theta = 0$, it is also one for $\theta = 1$, which proves our assertion. \square

We formulate the combination of Theorem 12.5 and Theorem 12.6 as a corollary. (The final assertion follows by continuity.)

Corollary. *If $\mathbf{a}_1, \dots, \mathbf{a}_{n-1}$ are vectors in \mathbb{R}^n with positive coordinates and $\mathbf{b} \in \mathbb{R}^n$, then*

$$\begin{aligned} & (\text{per}(\mathbf{a}_1, \dots, \mathbf{a}_{n-1}, \mathbf{b}))^2 \\ & \geq \text{per}(\mathbf{a}_1, \dots, \mathbf{a}_{n-1}, \mathbf{a}_{n-1}) \cdot \text{per}(\mathbf{a}_1, \dots, \mathbf{a}_{n-2}, \mathbf{b}, \mathbf{b}) \end{aligned}$$

and equality holds if and only if $\mathbf{b} = \lambda \mathbf{a}_{n-1}$ for some constant λ . Furthermore, the inequality also holds if some of the coordinates of the \mathbf{a}_i are 0, but the assertion about the consequence of equality then cannot be made.

We are now able to generalize Theorem 12.3.

Theorem 12.7. *If $A \in \Omega_n$ is a minimizing matrix, then $\text{per } A_{ij} = \text{per } A$ for all i and j .*

PROOF: Suppose that the statement is false. Then by Theorem 12.4, there is a pair r, s such that $\text{per } A_{rs} > \text{per } A$.

Choose t such that $a_{rt} > 0$. Consider the product of two factors $\text{per } A$. In the first of these we replace \mathbf{a}_s by \mathbf{a}_t , and in the second, we replace \mathbf{a}_t by \mathbf{a}_s . Subsequently, we develop the first permanent by column s and the second permanent by column t . By Theorem 12.5 and the Corollary to Theorem 12.6, we have

$$(\text{per } A)^2 \geq \left(\sum_{k=1}^n a_{kt} \text{per } A_{ks} \right) \left(\sum_{k=1}^n a_{ks} \text{per } A_{kt} \right).$$

By Theorem 12.4, every subpermanent on the right-hand side is at least $\text{per } A$ and $\text{per } A_{rs} > \text{per } A$. Since $\text{per } A_{rs}$ is multiplied by a_{rt} which is positive, we see that the right-hand side is larger than $(\text{per } A)^2$, a contradiction. \square

We now use the substitution principle as follows. Take a minimizing matrix A and let \mathbf{u} and \mathbf{v} be two columns of A . Replace \mathbf{u} and \mathbf{v} by $\frac{1}{2}(\mathbf{u} + \mathbf{v})$. The new matrix is again a minimizing matrix by Theorem 12.7.

Let A be any minimizing matrix and let \mathbf{b} be any column of A , say the last column. From Corollary (i) to Theorem 12.2, we know that in every row of A there are at least two positive elements. We now apply the substitution principle (as sketched above) a number of times but we never change the last column. In this way, we can find a minimizing matrix $A' = (\mathbf{a}'_1, \dots, \mathbf{a}'_{n-1}, \mathbf{b})$ for which $\mathbf{a}'_1, \dots, \mathbf{a}'_{n-1}$ all have *positive* coordinates. Now apply the Corollary to Theorem 12.6. By the substitution principle, equality must hold. Hence \mathbf{b} is a multiple of \mathbf{a}'_i for any i with $1 \leq i \leq n-1$. This implies that $\mathbf{b} = n^{-1}\mathbf{j}$ and therefore $A = n^{-1}J_n$, which completes the proof of the Van der Waerden conjecture.

Theorem 12.8. *The implication (12.1) is true.*

Notes.

For a survey of the two proofs of the Van der Waerden conjecture, we refer to Van Lint (1982). There one also finds historical comments and a nice anecdote concerning the conjecture.

B. L. van der Waerden (1903–1996), a Dutch mathematician, was known mostly for his work in algebra, although he published in several fields. His work *Moderne Algebra* (1931) set the trend for many decades.

Minc's book on permanents is the best reference for all the work that was done in relation to the Van der Waerden conjecture up to 1978.

The name *Lorentz space* is related to relativity theory and the group of transformations that leave the quadratic form $x^2 + y^2 + z^2 - t^2$ invariant. H. A. Lorentz was a Dutch physicist who won the Nobel prize for his work.

References.

- J. H. van Lint (1981), Notes on Egoritsjev's proof of the Van der Waerden conjecture, *Linear Algebra and its Applications* **39**, 1–8.
- J. H. van Lint (1982), The van der Waerden Conjecture: Two proofs in one year, *The Math. Intelligencer* **39**, 72–77.
- D. London (1971), Some notes on the van der Waerden conjecture, *Linear Algebra and its Applications* **4**, 155–160.
- M. Marcus and M. Newman (1959), On the minimum of the permanent of a doubly stochastic matrix, *Duke Math. J.* **26**, 61–72.
- H. Minc (1978), *Permanents*, Encyclopedia of Mathematics and its Applications, vol. 6, Addison-Wesley, reissued by Cambridge University Press (1984).
- B. L. van der Waerden (1926), *Jber. D. M. V.* **35**.

13

Elementary counting; Stirling numbers

The next few chapters will be devoted to counting techniques and some special combinatorial counting problems. We start with several elementary methods that are used quite often. Consider mappings from $\{1, 2, \dots, n\}$ to $\{1, 2, \dots, k\}$. Their total number is k^n . In Example 10.2, we studied the case where the mappings were required to be surjective. We return to this question in Theorem 13.5. If the mappings are injections, then their number is the *falling factorial*

$$(13.1) \quad (k)_n := k(k-1)\dots(k-n+1) = k!/(k-n)!.$$

We now consider a similar problem. The n objects to be mapped are no longer distinguishable but the images are. We formulate this as follows. We have n indistinguishable balls that are to be placed in k boxes, marked $1, 2, \dots, k$. In how many different ways can this be done? The solution is found by using the following trick. Think of the balls as being colored blue and line them up in front of the boxes that they will go into. Then insert a red ball between two consecutive boxes. We end up with a line of $n+k-1$ balls, $k-1$ of them red, describing the situation. So the answer to the problem is $\binom{n+k-1}{k-1}$. We formulate this as a theorem.

Theorem 13.1. *The number of solutions of the equation*

$$(13.2) \quad x_1 + x_2 + \dots + x_k = n$$

in nonnegative integers is $\binom{n+k-1}{k-1}$.

PROOF: Interpret x_i as the number of balls in box i . □

Corollary. *The number of solutions of the equation (13.2) in positive integers is $\binom{n-1}{k-1}$.*

PROOF: Replace x_i by $y_i := x_i - 1$. Then $\sum y_i = n - k$. Apply Theorem 13.1. \square

Example 13.1. By analogy with the question we encountered in Example 10.6, we consider the problem of selecting r of the integers $1, 2, \dots, n$ such that no two selected integers are consecutive. Let $x_1 < x_2 < \dots < x_r$ be such a sequence. Then $x_1 \geq 1$, $x_2 - x_1 \geq 2, \dots, x_r - x_{r-1} \geq 2$. Define

$$y_1 := x_1, y_i := x_i - x_{i-1} - 1, 2 \leq i \leq r, y_{r+1} := n - x_r + 1.$$

Then the y_i are positive integers and $\sum_{i=1}^{r+1} y_i = n - r + 2$. By the Corollary to Theorem 13.1, we see that there are $\binom{n-r+1}{r}$ solutions.

Problem 13A. On a circular array with n positions, we wish to place the integers $1, 2, \dots, r$ in order, clockwise, such that consecutive integers, including the pair $(r, 1)$, are not in adjacent positions on the array. Arrangements obtained by rotation are considered the same. In how many ways can this be done?

Example 13.2. In how many ways can we arrange r_1 balls of color 1, r_2 balls of color 2, \dots, r_k balls of color k in a sequence of length $n := r_1 + r_2 + \dots + r_k$? If we number the balls 1 to n , then there are $n!$ arrangements. Since we ignore the numbering, any permutation of the set of r_i balls of color i , $1 \leq i \leq k$, produces the same arrangement. So the answer to the question is the multinomial coefficient $\binom{n}{r_1, \dots, r_k}$; see (2.1).

Example 13.3. We wish to split $\{1, 2, \dots, n\}$ into b_1 subsets of size 1, b_2 subsets of size 2, \dots, b_k subsets of size k . Here $\sum_{i=1}^k ib_i = n$. The same argument as used in Example 13.2 applies. Furthermore, the subsets of the same cardinality can be permuted among themselves without changing the configuration. So the solution is

$$(13.3) \quad \frac{n!}{b_1! \dots b_k! (1!)^{b_1} (2!)^{b_2} \dots (k!)^{b_k}}.$$

Several counting problems (often involving binomial coefficients) can be done in a more or less obvious way that leads to a (sometimes

difficult) calculation. Often there is a less obvious ‘combinatorial’ way to do the counting that produces an immediate answer. We give a few examples.

Example 13.4. Let A run through all subsets of $\{1, 2, \dots, n\}$. Calculate $S = \sum |A|$. Since there are $\binom{n}{i}$ subsets of size i , we apparently must calculate $\sum_{i=0}^n i \binom{n}{i}$. By differentiating $(1+x)^n$, we find

$$\sum_{i=1}^n i \binom{n}{i} x^{i-1} = n(1+x)^{n-1}$$

and substitution of $x = 1$ yields the answer $S = n \cdot 2^{n-1}$. If we had spent a little more time thinking, then this answer would have been obvious! A set A and its complement together contain n elements and there are exactly 2^{n-1} such pairs.

Example 13.5. In Chapter 10 we saw some examples of formulae involving binomial coefficients for which a combinatorial proof was easier than a direct proof. The familiar relation

$$(13.4) \quad \sum_{k=0}^n \binom{n}{k}^2 = \binom{2n}{n}$$

is another example. Of course one can calculate this sum by determining the coefficient of x^n in $(1+x)^n(1+x)^n$ and using the binomial formula. However, each side of (13.4) just counts (in two ways) the number of ways of selecting n balls from a set consisting of n red balls and n blue balls.

Problem 13B. Show that the following formula for binomial coefficients is a direct consequence of (10.6):

$$\binom{n+1}{a+b+1} = \sum_{k=0}^n \binom{k}{a} \binom{n-k}{b}.$$

Give a combinatorial proof by considering $(a+b+1)$ -subsets of the set $\{0, 1, \dots, n\}$, ordering them in increasing order, and then looking at the value of the integer in position $a+1$.

Example 13.6. We consider a slightly more complicated example where our previous knowledge could lead us to an involved solution. How many sequences A_1, \dots, A_k are there for which $A_i \subseteq$

$\{1, 2, \dots, n\}$, $1 \leq i \leq k$, and $\bigcup_{i=1}^k A_i = \{1, 2, \dots, n\}$? Since we wish to avoid that j , $1 \leq j \leq n$, is not an element of the union of the A_i 's, we are tempted to use inclusion-exclusion. If we choose i elements from $\{1, 2, \dots, n\}$ and consider all sequences A_1, \dots, A_k not containing any of these i elements, then we find $(2^{n-i})^k$ sequences. So by Theorem 10.1, the solution to the problem is

$$\sum_{i=0}^n (-1)^i \binom{n}{i} 2^{(n-i)k} = (2^k - 1)^n.$$

This answer shows that another approach would have been better. If we describe a sequence A_1, \dots, A_k by a $(0, 1)$ -matrix A of size $k \times n$, with the characteristic functions of the subsets as its rows, then the condition on the sequences states that A has no column of zeros. So there are $(2^k - 1)^n$ such matrices!

Problem 13C. Give a solution involving binomial coefficients and a combinatorial solution to the following question. How many pairs (A_1, A_2) of subsets of $\{1, 2, \dots, n\}$ are there such that $A_1 \cap A_2 = \emptyset$?

Problem 13D. Consider the set S of all ordered k -tuples $\mathcal{A} = (A_1, \dots, A_k)$ of subsets of $\{1, 2, \dots, n\}$. Determine

$$\sum_{\mathcal{A} \in S} |A_1 \cup A_2 \cup \dots \cup A_k|.$$

Problem 13E. The familiar relation

$$\sum_{m=k}^l \binom{m}{k} = \binom{l+1}{k+1}$$

is easily proved by induction. The reader who wishes to, can find a more complicated proof by using (10.6). Find a combinatorial proof by counting paths from $(0, 0)$ to $(l+1, k+1)$ in the X - Y plane where each step is of type $(x, y) \rightarrow (x+1, y)$ or $(x, y) \rightarrow (x+1, y+1)$. Then use the formula to show that the number of solutions of

$$x_1 + x_2 + \dots + x_k \leq n$$

in nonnegative integers is $\binom{n+k}{k}$. Can you prove this result combinatorially?

It is often possible to prove relations between binomial coefficients by considering $\binom{a}{k}$ formally as a polynomial in a defined by

$$\binom{a}{k} := \frac{a(a-1)\cdots(a-k+1)}{k!}.$$

If two polynomials of degree $\leq k$ agree for $k+1$ values of the variable, they are identical. We give an example.

Let

$$F(a) := \sum_{k=0}^n \binom{a}{k} x^k y^{n-k}, \quad G(a) := \sum_{k=0}^n \binom{n-a}{k} (-x)^k (x+y)^{n-k}.$$

From the binomial theorem we know that if a is an integer in the interval $[0, n]$, then $F(a) = (x+y)^a y^{n-a}$ but so is $G(a)$, again by the binomial theorem. So, the polynomials are identical and we can substitute any numbers for a, x , and y to obtain relations for binomial coefficients. For instance, $y = 2x$ and $a = 2n+1$ yields:

$$\sum_{k=0}^n \binom{2n+1}{k} 2^{n-k} = \sum_{k=0}^n \binom{n+k}{k} 3^{n-k},$$

a relation that would be extremely difficult to prove by counting.

Two kinds of numbers that come up in many combinatorial problems are the so-called *Stirling numbers of the first and second kind*. The numbers are often defined by the formulae (13.8) and (13.12) given below. We prefer a combinatorial definition.

Let $c(n, k)$ denote the number of permutations $\pi \in S_n$ with exactly k cycles. (This number is called a *signless* Stirling number of the first kind.) Furthermore define $c(0, 0) = 1$ and $c(n, k) = 0$ if $n \leq 0$ or $k \leq 0$, $(n, k) \neq (0, 0)$. The Stirling numbers of the first kind $s(n, k)$ are defined by

$$(13.5) \quad s(n, k) := (-1)^{n-k} c(n, k).$$

Theorem 13.2. *The numbers $c(n, k)$ satisfy the recurrence relation*

$$(13.6) \quad c(n, k) = (n - 1)c(n - 1, k) + c(n - 1, k - 1).$$

PROOF: If π is a permutation in S_{n-1} with k cycles, then there are $n - 1$ positions where we can insert the integer n to produce a permutation $\pi' \in S_n$ with k cycles. We can also adjoin (n) as a cycle to any permutation in S_{n-1} with $k - 1$ cycles. This accounts for the two terms on the right-hand side of (13.6). \square

Theorem 13.3. *For $n \geq 0$ we have*

$$(13.7) \quad \sum_{k=0}^n c(n, k)x^k = x(x + 1) \dots (x + n - 1)$$

and

$$(13.8) \quad \sum_{k=0}^n s(n, k)x^k = (x)_n,$$

where $(x)_n$ is defined as in (13.1).

PROOF: Write the right-hand side of (13.7) as

$$F_n(x) = \sum_{k=0}^n b(n, k)x^k.$$

Clearly $b(0, 0) = 1$. Define $b(n, k) := 0$ if $n \leq 0$ or $k \leq 0$, $(n, k) \neq (0, 0)$. Since

$$\begin{aligned} F_n(x) &= (x + n - 1)F_{n-1}(x) \\ &= \sum_{k=1}^n b(n - 1, k - 1)x^k + (n - 1) \sum_{k=0}^{n-1} b(n - 1, k)x^k, \end{aligned}$$

we see that the numbers $b(n, k)$ satisfy the same recurrence relation as the $c(n, k)$, namely (13.6). Since the numbers are equal if $n \leq 0$ or $k \leq 0$, they are equal for all n and k .

To prove (13.8) replace x by $-x$ and use (13.5). \square

We remark that it is possible to give a combinatorial proof of (13.7) by showing that both sides of the equation count the same objects.

We now define the Stirling numbers of the second kind: denote by $P(n, k)$ the set of all partitions of an n -set into k nonempty subsets (blocks). Then

$$(13.9) \quad S(n, k) := |P(n, k)|.$$

Again we have $S(0, 0) = 1$ and take the numbers to be 0 for all values of the parameters not covered by the previous definition. Again we have an easy recurrence relation.

Theorem 13.4. *The Stirling numbers of the second kind satisfy the relation*

$$(13.10) \quad S(n, k) = kS(n-1, k) + S(n-1, k-1).$$

PROOF: The proof is nearly the same as for Theorem 13.3. A partition of the set $\{1, 2, \dots, n-1\}$ can be made into a partition of $\{1, 2, \dots, n\}$ by adjoining n to one of the blocks or by increasing the number of blocks by one by making $\{n\}$ a block. \square

We define the *Bell number* $B(n)$ to be the *total* number of partitions of an n -set, i.e.

$$(13.11) \quad B(n) := \sum_{k=1}^n S(n, k), \quad (n \geq 1).$$

For the Stirling numbers of the second kind there is a formula similar to (13.8).

Theorem 13.5. *For $n \geq 0$ we have*

$$(13.12) \quad x^n = \sum_{k=0}^n S(n, k)(x)_k.$$

PROOF: We first remark that by (13.9) the number of surjective mappings from an n -set to a k -set is $k!S(n, k)$ (a block of the partition is the inverse image of an element of the k -set). So by Example 10.2, we have

$$(13.13) \quad S(n, k) = \frac{1}{k!} \sum_{i=0}^k (-1)^i \binom{k}{i} (k-i)^n = \frac{1}{k!} \sum_{i=0}^k (-1)^{k-i} \binom{k}{i} i^n.$$

Now let x be an integer. There are x^n mappings from the n -set $N := \{1, 2, \dots, n\}$ to the x -set $\{1, 2, \dots, x\}$. For any k -subset Y of $\{1, 2, \dots, x\}$, there are $k!S(n, k)$ surjections from N to Y . So we find

$$x^n = \sum_{k=0}^n \binom{x}{k} k!S(n, k) = \sum_{k=0}^n S(n, k)(x)_k.$$

□

In Example 10.1, we saw that it can be useful to associate a so-called *generating function* with a sequence a_1, a_2, \dots of numbers. In Chapter 14, we will see many uses of the generating function. At this point we treat the generating functions for the Stirling numbers.

Theorem 13.6. $\sum_{n \geq k} S(n, k) \frac{x^n}{n!} = \frac{1}{k!} (e^x - 1)^k \quad (k \geq 0).$

PROOF: Let $F_k(x)$ denote the sum on the left-hand side. By (13.10) we have

$$F'_k(x) = kF_k(x) + F_{k-1}(x).$$

The result now follows by induction. Since $S(n, 1) = 1$, the assertion is true for $k = 1$ and the induction hypothesis yields a differential equation for F_k , which with the condition $S(k, k) = 1$ has the right-hand side of the assertion as unique solution. □

For the Stirling numbers of the first kind, it is slightly more difficult to find the generating function.

Theorem 13.7. $\sum_{n=k}^{\infty} s(n, k) \frac{z^n}{n!} = \frac{1}{k!} (\log(1+z))^k.$

PROOF: Since

$$(1+z)^x = e^{x \log(1+z)} = \sum_{k=0}^{\infty} \frac{1}{k!} (\log(1+z))^k x^k,$$

the right-hand side in the assertion is the coefficient of x^k in the expansion of $(1+z)^x$. On the other hand, we have for $|z| < 1$,

$$\begin{aligned} (1+z)^x &= \sum_{n=0}^{\infty} \binom{x}{n} z^n = \sum_{n=0}^{\infty} \frac{1}{n!} (x)_n z^n \\ &= \sum_{n=0}^{\infty} \frac{z^n}{n!} \sum_{r=0}^n s(n,r) x^r = \sum_{r=0}^{\infty} x^r \sum_{n=r}^{\infty} s(n,r) \frac{z^n}{n!}. \end{aligned}$$

This completes the proof. \square

Problem 13F. Show directly that the number of permutations of the integers 1 to n with an even number of cycles is equal to the number of permutations with an odd number of cycles ($n > 1$). Also show that this is a consequence of Theorem 13.7.

Finally we mention that the Stirling numbers of the first and second kind are related by

$$(13.14) \quad \sum_{k=m}^n S(n,k) s(k,m) = \delta_{mn}.$$

This follows immediately if we substitute (13.8) in (13.12). Since the functions x^n , respectively $(x)_n$, with $n \geq 0$ both form a basis of the vector space $\mathbb{C}[x]$, the formula (13.14) is just the standard relation between the matrices for basis transformation.

Problem 13G. Show that (13.12) leads to $B(n) = \frac{1}{e} \sum_{k=0}^{\infty} \frac{k^n}{k!}$.

Problem 13H. Let A be the $n \times n$ matrix with $a_{ij} := \binom{i}{j}$ for $i, j = 0, \dots, n-1$. Determine A^{-1} .

Problem 13I. From (10.6) one finds, by taking $x = \frac{1}{2}$, that $\sum_{j=0}^{\infty} \binom{a+j}{j} 2^{-j} = 2^{a+1}$. Using a method from this chapter prove that

$$\sum_{j=0}^a \binom{a+j}{j} 2^{-j} = 2^a.$$

Prove the same result directly by defining

$$a_n = \sum_{j=0}^a \binom{a+j}{j} 2^{-a-j},$$

substituting the basic recurrence for binomial coefficients, thus finding that $a_n = \frac{1}{2}a_n + \frac{1}{2}a_{n-1}$.

Problem 13J. Suppose we call a set *nice* if its cardinality is divisible by 3. How many nice subsets does an n -set have?

Problem 13K. Prove that $\sum_{n=1}^{\infty} S(n, n-2)x^n = \frac{x(1+2x)}{(1-x)^5}$.

Notes.

Stirling numbers of the first and second kind appear in many areas of mathematics; for example, they play a role in a number of interpolation formulae and in the calculus of finite differences. There are tables of the numbers in several books on tables of mathematical functions.

Later, in Chapter 37, these numbers will reappear.

James Stirling (1692–1770), a Scottish mathematician, studied at Oxford. He taught mathematics at Venice and London but switched to a career in business at the age of 43.

14

Recursions and generating functions

Many combinatorial counting problems with a solution a_n depending on a parameter n , can be solved by finding a recursion relation for a_n and then solving that recursion. Sometimes this is done by introducing an *ordinary generating function*

$$f(x) := \sum_{n \geq 0} a_n x^n,$$

or an *exponential generating function*

$$f(x) := \sum_{n \geq 0} a_n \frac{x^n}{n!},$$

and using the recursion to find an equation or a differential equation for $f(x)$, and solving that equation. We shall demonstrate several of the techniques involved.

Example 14.1. As an introduction, consider once again Example 10.1. Let π be a derangement of $\{1, 2, \dots, n+1\}$. There are n choices for $\pi(n+1)$. If $\pi(n+1) = i$ and $\pi(i) = n+1$, then π is also a derangement on the set $\{1, 2, \dots, n\} \setminus \{i\}$. If $\pi(n+1) = i$ and $\pi(i) \neq n+1 = \pi(j)$, then replacing $\pi(j)$ by i yields a derangement on the set $\{1, 2, \dots, n\}$. Therefore

$$(14.1) \quad d_{n+1} = n(d_n + d_{n-1}),$$

which is also an immediate consequence of (10.3). Let $D(x)$ be the *exponential generating function* for the sequence $d_0 = 1, d_1 = 0, d_2, \dots$. From (14.1) we immediately find

$$(1-x)D'(x) = xD(x),$$

and from this we find $D(x) = e^{-x}/(1-x)$ and (10.2).

In many cases, we use the generating functions only as a bookkeeping device, and our operations of addition, multiplication (and even substitution and derivation, as we shall see below) are to be interpreted formally. It is possible to give a completely rigorous theory of formal power series (as algebraic objects) and we give an introduction to this theory in Appendix 2. In most cases, it is intuitively clear and easy to check that the operations are legitimate. If the series that we use actually converge, then we can use all appropriate knowledge from analysis concerning these series, as we did in Example 14.1. We give another elementary example.

Example 14.2. Suppose that we have k boxes numbered 1 to k and suppose that box i contains r_i balls, $1 \leq i \leq k$. A formal bookkeeping device to list all possible configurations is to let the named one correspond to the term $x_1^{r_1} x_2^{r_2} \cdots x_k^{r_k}$ in the product

$$(1 + x_1 + x_1^2 + \cdots)(1 + x_2 + x_2^2 + \cdots) \cdots (1 + x_k + x_k^2 + \cdots).$$

We can collect all the terms involving exactly n balls by taking $x_i = x$ for all i , and considering the terms equal to x^n . Therefore we find that the number of ways to divide n balls over k distinguishable boxes is the coefficient of x^n in the expansion of $(1-x)^{-k}$, and by (10.6) this is $\binom{k-1+n}{n}$, giving a second proof of Theorem 13.1.

In many cases, the combinatorial problem that we are interested in leads to a linear recursion relation with constant coefficients, which is easily solved by standard methods.

Example 14.3. We consider paths of length n in the X - Y plane starting from $(0,0)$ with steps $R : (x, y) \rightarrow (x+1, y)$, $L : (x, y) \rightarrow (x-1, y)$, and $U : (x, y) \rightarrow (x, y+1)$ (i.e. to the right, to the left, or up). We require that a step R is not followed by a step L and vice versa. Let a_n denote the number of such paths. First observe that if we denote by b_n the number of paths of length n starting with a step U , then $b_n = a_{n-1}$ and furthermore trivially $b_{n+m} \geq b_n b_m$ and $b_n \leq 3^{n-1}$. So by Fekete's lemma, Lemma 11.6, $\lim_{n \rightarrow \infty} b_n^{1/n}$ exists and is at most 3. Next, note that $a_0 = 1$ and $a_1 = 3$. We split the set of paths of length n into subsets depending on the last one

or two steps. Clearly there are a_{n-1} paths ending with the step U . Take a path of length $n - 1$ and repeat the last step if it is L or R , and adjoin a step L if the last step was U . In this way, we obtain all the paths of length n that end in LL , RR , or UL . So there are a_{n-1} of these. It remains to count the paths ending with UR and again it is trivial that there are a_{n-2} of these. We have shown that

$$a_n = 2a_{n-1} + a_{n-2} \quad (n \geq 2).$$

Let $f(x) = \sum_{n=0}^{\infty} a_n x^n$. Then the recursion implies that

$$f(x) = 1 + 3x + 2x(f(x) - 1) + x^2 f(x),$$

i.e.

$$f(x) = \frac{1+x}{1-2x-x^2} = \frac{\frac{1}{2}\alpha}{1-\alpha x} + \frac{\frac{1}{2}\beta}{1-\beta x},$$

where $\alpha = 1 + \sqrt{2}$, $\beta = 1 - \sqrt{2}$. Therefore

$$a_n = \frac{1}{2}(\alpha^{n+1} + \beta^{n+1})$$

and we find $\lim_{n \rightarrow \infty} a_n^{1/n} = 1 + \sqrt{2}$.

Problem 14A. (i) Let a_n denote the number of sequences of 0's and 1's that do not contain two consecutive 0's. Determine a_n .
(ii) Let b_n denote the number of sequences of 0's and 1's with no two consecutive 1's and for which a run of 0's always has length 2 or 3, including possibly at the beginning or end of the sequence. Show that $b_n^{1/n} \rightarrow c$ for some c and approximate c .

Example 14.4. Let $a(r, n)$, where $0 \leq r \leq n$, denote the number of solutions of the problem of Example 13.1 ($a(0, 0) = 1$). We divide the set of possible sequences into two subsets: those with $x_1 = 1$ and those with $x_1 > 1$. The first subset clearly contains $a(r - 1, n - 2)$ elements, the second one $a(r, n - 1)$ elements. So

$$(14.2) \quad a(r, n) = a(r, n - 1) + a(r - 1, n - 2) \quad (n > 1).$$

From this recursion, we can prove the result $a(r, n) = \binom{n-r+1}{r}$ by induction. Using the generating function is more difficult. Try

$$f(x, y) := \sum_{n=0}^{\infty} \sum_{r=0}^{\infty} a(r, n) x^n y^r.$$

From (14.2) we find

$$f(x, y) = 1 + x + xy + x(-1 + f(x, y)) + x^2 y f(x, y),$$

i.e.

$$f(x, y) = \frac{1 + xy}{1 - x - x^2 y} = \frac{1}{1 - x} + \sum_{a=1}^{\infty} \frac{x^{2a-1} y^a}{(1 - x)^{a+1}}.$$

Substitution of (10.6) for $(1-x)^{-a-1}$ produces the required binomial coefficient for $a(r, n)$.

As we saw in Example 14.3 (and Problem 14A) a linear recursion with constant coefficients leads to a rational function as generating function (and vice versa). Indeed, if $a_n = \sum_{k=1}^l \alpha_k a_{n-k}$ ($n > l$) and $f(x) = \sum_{n=0}^{\infty} a_n x^n$, then $(1 - \sum_{k=1}^l \alpha_k x^k) f(x)$ is a power series for which the coefficient of x^n is 0 if $n > l$.

The following example due to Klarner (1967) shows an interesting case of a linear recursion that is found with the help of the generating function and that is not at all obvious in a combinatorial way.

Example 14.5. Consider configurations in the plane, called *polyominoes*, as in Fig. 14.1. The configuration consists of layers, each consisting of consecutive squares. Two consecutive layers meet along the edges of a number (≥ 1) of squares. (More precisely, we are considering *horizontally convex polyominoes*.)




Figure 14.1

Let a_n denote the number of polyominoes with n squares and define $f(x) := \sum_{n=1}^{\infty} a_n x^n$. To find f , we introduce $a(m, n)$ for the number of polyominoes for which the bottom layer has m squares (and a total of n). We define $a(m, n) := 0$ if $m > n$. Clearly

$$(14.3) \quad a(m, n) = \sum_{l=1}^{\infty} (m+l-1)a(l, n-m).$$

We define

$$(14.4) \quad F(x, y) := \sum_{n=1}^{\infty} \sum_{m=1}^{\infty} a(m, n) x^n y^m.$$

Then $f(x) = F(x, 1)$. Because the series will turn up below, we also define

$$g(x) := \sum_{n=1}^{\infty} \sum_{m=1}^{\infty} m a(m, n) x^n.$$

We would like to write

$$(14.5) \quad g(x) = \left(\frac{\partial F}{\partial y} \right)_{y=1}.$$

Even though we have a theory of formal power series, it may be instructive to show that the righthand side of (14.4) converges in a sufficiently large region. This gives us the opportunity to show a quick way of getting a rough estimate for a_n . Number the squares of the polyomino in the obvious way as in Fig. 14.1. To each square associate a quadruple (x_0, x_1, x_2, x_3) of 0's and 1's, where $x_0 = 1$ means that there is a square of the polyomino below this square, $x_1 = 1$ means that there is a square of the polyomino to the left, $x_2 = 1$ means that there is a square above, and $x_3 = 1$ means that there is a square to the right. For example, in Fig. 14.1 the first quadruple is $(0,0,1,1)$. The sequence of quadruples uniquely determines the polyomino (e.g. the fifth quadruple is the first one in the sequence that ends in a 0, showing that $m = 5$, etc.). This shows that $a_n \leq 15^n$. From this and (14.3) we find $a(m, n) \leq$

$n \cdot 15^{n-m}$ which is enough to justify (14.5). From (14.4) we find by substituting (14.3) and a straightforward calculation

$$(14.6) \quad F(x, y) = \frac{xy}{1-xy} + \frac{(xy)^2}{(1-xy)^2}f(x) + \frac{xy}{1-xy}g(x).$$

Differentiation of both sides of (14.6) with respect to y and taking $y = 1$ yields (using (14.5)):

$$(14.7) \quad g(x) = \frac{x}{(1-x)^2} + \frac{2x^2}{(1-x)^3}f(x) + \frac{x}{(1-x)^2}g(x).$$

From (14.7) we can find $g(x)$ and substitute this in (14.6); then take $y = 1$, which yields

$$(14.8) \quad f(x) = \frac{x(1-x)^3}{1-5x+7x^2-4x^3}.$$

From (14.8) we see that a_n satisfies the recurrence relation

$$(14.9) \quad a_n = 5a_{n-1} - 7a_{n-2} + 4a_{n-3} \quad (n \geq 5).$$

As we remarked above, it is not at all clear how one could prove this directly; it has been done however.

Remark. From (14.9) we find that $\lim_{n \rightarrow \infty} a_n^{1/n} = \theta$, where θ is the zero with largest absolute value of the polynomial $x^3 - 5x^2 + 7x - 4$ ($\theta \approx 3.2$).

The following example produces a result that is important for the theory of finite fields. In this example, we combine a generalization of the idea of Example 14.2 with the method of formal operations with power series. The reader should convince herself that the operations with logarithms are correct without using convergence.

Example 14.6. We shall count the number of irreducible polynomials of degree n over a field of q elements.

Number all the monic irreducible polynomials of degree at least one over a field of q elements:

$$f_1(x), f_2(x), f_3(x), \dots$$

with, say, respective degrees d_1, d_2, d_3, \dots . Let N_d denote the number of degree d , $d = 1, 2, 3, \dots$.

Now for any sequence i_1, i_2, i_3, \dots of nonnegative integers (all but finitely many of which are zero), we get a monic polynomial

$$f(x) = (f_1(x))^{i_1} (f_2(x))^{i_2} (f_3(x))^{i_3} \dots$$

whose degree is $n = i_1 d_1 + i_2 d_2 + i_3 d_3 + \dots$. By unique factorization, every monic polynomial of degree n arises exactly once in this way. To repeat, there is a one-to-one correspondence between monic polynomials of degree n and sequences i_1, i_2, \dots of nonnegative integers satisfying $n = i_1 d_1 + i_2 d_2 + i_3 d_3 + \dots$.

Of course, the number of monic polynomials of degree n is q^n , i.e. the coefficient of x^n in

$$\frac{1}{1 - qx} = 1 + qx + (qx)^2 + (qx)^3 + \dots$$

Clearly (cf. Example 14.2), the number of sequences i_1, i_2, \dots with $n = i_1 d_1 + i_2 d_2 + \dots$ is the coefficient of x^n in the formal power series

$$(1 + x^{d_1} + x^{2d_1} + x^{3d_1} + \dots)(1 + x^{d_2} + x^{2d_2} + x^{3d_2} + \dots) \dots$$

Thus we conclude

$$\frac{1}{1 - qx} = \prod_{i=1}^{\infty} \frac{1}{1 - x^{d_i}} = \prod_{d=1}^{\infty} \left(\frac{1}{1 - x^d} \right)^{N_d}.$$

Recalling that $\log \frac{1}{1-z} = z + \frac{1}{2}z^2 + \frac{1}{3}z^3 + \dots$, we take (formal) logarithms of both extremes of the above displayed equation to find

$$\sum_{n=1}^{\infty} \frac{(qx)^n}{n} = \sum_{d=1}^{\infty} N_d \sum_{j=1}^{\infty} \frac{x^{jd}}{j}.$$

Then, comparing coefficients of x^n on both sides, we get

$$\frac{q^n}{n} = \sum_{d|n} N_d \frac{1}{n/d},$$

i.e.

$$q^n = \sum_{d|n} dN_d.$$

This last equation was our goal. We have derived it combinatorially from unique factorization, but we remark that it has in fact an elegant interpretation in terms of the factorization of $x^{q^n} - x$ over the field of q elements. Applying Möbius inversion (cf. Theorem 10.4), we obtain the following theorem.

Theorem 14.1. *For a prime power q , the number of monic irreducible polynomials of degree n over the field of q elements is given by*

$$N_n = \frac{1}{n} \sum_{d|n} \mu\left(\frac{n}{d}\right) q^d.$$

We note that a direct consequence of Theorem 14.1 is that $N_d > 0$, that is, there exist irreducible polynomials of every degree d . This immediately leads to a proof of the existence of fields of p^d elements for every prime p , without the usual expedient of reference to the algebraic closures of the prime fields.

* * *

We now come to a large class of counting problems, all with the same solution. The class is known as the *Catalan family* because Catalan (1838) treated Example 14.7. Actually, the equivalent problem called Question 3 in Example 14.9 below was treated by von Segner and Euler in the 18th century. We denote the solutions to the problems by u_n . We shall show that $u_n = \frac{1}{n} \binom{2n-2}{n-1}$. These numbers are called *Catalan numbers*.

Example 14.7. Suppose that we have a set S with a *nonassociative* product operation. An expression $x_1x_2\dots x_n$ with $x_i \in S$ does not make sense, and brackets are needed to indicate the order in which the operations are to be carried out. Let u_n denote the number of ways to do this if there are n factors x_i . For example, $u_4 = \frac{1}{4} \binom{6}{3} = 5$ corresponding to the products $(a(b(cd)))$, $(a((bc)d))$, $((ab)(cd))$, $((a(bc))d)$, and $((ab)c)d$. Each product contains within the outer brackets two expressions, the first a product of m factors

and the second a product of $n - m$ factors, where $1 \leq m \leq n - 1$. It follows that the numbers u_n satisfy the recurrence relation

$$(14.10) \quad u_n = \sum_{m=1}^{n-1} u_m u_{n-m} \quad (n \geq 2).$$

From (14.10) and $u_1 = 1$, we find that the generating function $f(x) := \sum_{n=1}^{\infty} u_n x^n$ satisfies the equation

$$(14.11) \quad f(x) = x + \sum_{n=2}^{\infty} \left(\sum_{m=1}^{n-1} u_m u_{n-m} \right) x^n = x + (f(x))^2.$$

Solving the quadratic equation and taking into account that $f(0) = 0$, we find

$$f(x) = \frac{1 - \sqrt{1 - 4x}}{2}.$$

From the binomial series we then obtain

$$(14.12) \quad u_n = \frac{1}{n} \binom{2n-2}{n-1}.$$

The operations carried out above can all be justified as formal operations on power series, and the binomial series can also be treated formally without being concerned about convergence. If one feels uneasy about this approach, there are two remedies. The first is to find the solution as we did above and afterwards prove that it is correct by using (14.10) and induction. If one really wishes to be sure that the generating function is defined by a convergent power series, then use the result of the calculation to find some rough estimate for u_n and prove that the estimate is correct using (14.11), and then show that the series converges. For example, we could try $u_n \leq c^{n-1}/n^2$. This is true for $n = 1$ and any positive c and it is true for $n = 2$ if $c \geq 4$. The induction step with (14.11) yields

$$u_n \leq c^{n-2} \sum_{m=1}^{n-1} \frac{1}{m^2(n-m)^2} \leq c^{n-2} \frac{2}{(n/2)^2} \sum_{m=1}^{\infty} \frac{1}{m^2} < \frac{c^{n-1}}{n^2}$$

if $c > \frac{4}{3}\pi^2$. So the radius of convergence of $\sum_{n=1}^{\infty} u_n x^n$ is positive.

Remark. Formula (14.10) shows that $u_n \geq u_m u_{n-m}$, and then Fekete's lemma implies that $\lim_{n \rightarrow \infty} u_n^{1/n}$ exists. In fact, (14.12) now shows that this limit is 4.

As we remarked above, the Catalan numbers reappear regularly in combinatorial counting problems. This has led to the question of proving the other results combinatorially, i.e. by showing that there is a one-to-one correspondence between the objects to be counted and those of Example 14.7. Some of these will be treated in Example 14.9. First we look at another famous counting problem that has the Catalan numbers as solution.

Example 14.8. Consider walks in the X - Y plane where each step is $U : (x, y) \rightarrow (x+1, y+1)$ or $D : (x, y) \rightarrow (x+1, y-1)$. We start at $(0,0)$ and ask in how many ways we can reach $(2n,0)$ without *crossing* the X -axis. The solution of this problem uses an elegant trick known as André's *reflection principle* (1887). In Fig. 14.2 we consider two points A and B in the upper halfplane and a possible path between them which meets and/or crosses the X -axis.

By reflecting the part of the path between A and the first meeting with the X -axis (i.e. C in Fig. 14.2) with respect to the X -axis, we find a path from the reflected point A' to B . This establishes a one-to-one correspondence between paths from A' to B and paths from A to B that meet or cross the X -axis.




Figure 14.2

It follows that if $A = (0, k)$ and $B = (n, m)$, then there are $\binom{n}{l_1}$ paths from A to B that cross or meet the X -axis, where $2l_1 := n - k - m$. Since there are $\binom{n}{l_2}$ paths from A to B , where $2l_2 := n - m + k$,

we find $\binom{n}{l_2} - \binom{n}{l_1}$ paths from A to B that do not meet the X -axis. Any path from $(0,0)$ to $(2n, 0)$ in the upper halfplane that does not meet the X -axis between these points goes from $(0,0)$ to $(1,1):=A$, from A to $B := (2n - 1, 1)$ without meeting the X -axis, and then from $(2n - 1, 1)$ to $(2n, 0)$. By the argument above, we find that there are u_n such paths. If we allow the paths to meet the X -axis without crossing, then there are u_{n+1} such paths.

We remark that the number of paths from $(0,0)$ to $(2n, 0)$ in the upper halfplane that do not meet the X -axis between these points is equal to the number of sequences of zeros and ones $(x_1, x_2, \dots, x_{2n})$ with

$$(14.13) \quad x_1 + x_2 + \dots + x_j \begin{cases} < \frac{1}{2}j & \text{for } 1 \leq j \leq 2n - 1, \\ = n & \text{for } j = 2n. \end{cases}$$

The correspondence is given by letting a 1 correspond to a step D of the path.

We now show by combinatorial arguments that several counting problems lead to the Catalan numbers.

Example 14.9. Consider the following three questions.

Question 1. A tree that is drawn in the plane is called a *plane tree*. How many rooted plane trees are there with n vertices and a root with degree 1 (so-called *planted plane trees*)?

Question 2. A planted plane tree is called *trivalent* or a *binary tree* if every vertex has degree 1 or 3. How many trivalent planted plane trees are there with n vertices of degree 1?

Question 3. In how many ways can one decompose a convex n -gon into triangles by $n - 3$ nonintersecting diagonals?

The first correspondence we shall show is between Question 2 and Example 14.7.

For this, Fig. 14.3 suffices.




Figure 14.3

It follows that the solution to Question 2 is u_{n-1} .

The correspondence between Question 1 and Example 14.8 is also seen from a figure, namely Fig. 14.4.




Figure 14.4

In the figure, the tree can be described by a walk around it as shown by the dotted line. This walk can be described by calling the steps U for a step going up, and D for a step going down. This yields a sequence of twelve steps. Replacing U by 0 and D by 1 yields a sequence that obviously satisfies (14.13). This shows that the solution to Question 1 is also u_{n-1} .

Finally, we show a correspondence between Question 3 and Question 2. Consider an n -gon decomposed into triangles and distinguish some edge. We now construct a tree as in Fig. 14.5.




Figure 14.5

The tree is a binary tree with vertices of degree 1 corresponding to the sides of the n -gon, and vertices of degree 3 corresponding to the triangles. The tree is planted at the vertex corresponding to the special edge. So again we find that the number of solutions is u_{n-1} .

Problem 14B. Describe (with a figure) a correspondence between the graphs of Question 1 and those of Question 2.

Problem 14C. Find a direct one-to-one mapping from the n -gons of Question 3 to the products of Example 14.7.

We now turn to several problems in which the exponential generating function turns out to be useful. We shall give a somewhat more systematic treatment for this case. For a complete treatment of the methods, we refer to A. Joyal (1981).

Let M denote a ‘type’ of combinatorial structure. For example, trees, polygons, sets (the ‘uniform’ structures), permutations, etc. Let m_k be the number of ways of giving a labeled k -set such a structure. In each separate case we shall specify whether we take $m_0 = 0$ or $m_0 = 1$. We use capital letters for the structure and lower case letters for the counting sequence. We define

$$(14.14) \quad M(x) := \sum_{k=0}^{\infty} m_k \frac{x^k}{k!}.$$

So if T denotes the structure (labeled) tree, then we know from

Theorem 2.1 that

$$T(x) = \sum_{k=0}^{\infty} k^{k-2} \frac{x^k}{k!}.$$

If S denotes the uniform structure (a set) then $s_k = 1$ for all k and therefore $S(x) = e^x$. If C denotes ‘oriented circuit’, then we can start at vertex 1 and there are clearly $(k-1)!$ ways to proceed. Therefore $C(x) = -\log(1-x)$.

Suppose we wish to consider the number of ways a labeled n -set can be partitioned into two parts, one with a structure of type A and the other with a structure of type B . It is easy to see that the number of ways that we can do this is $\sum_{k=0}^n \binom{n}{k} a_k b_{n-k}$. It follows that if we call this a structure of type $A \cdot B$, then

$$(14.15) \quad (A \cdot B)(x) = \sum_{n=0}^{\infty} \left(\sum_{k=0}^n \binom{n}{k} a_k b_{n-k} \right) \frac{x^n}{n!} = A(x) \cdot B(x).$$

The reader should be careful with the result (14.15). The assertion is only true if, from the compound structure there is a unique way of finding the partition into the two parts that led to this structure. For example, if A and B are the same, the result is clearly false.

Example 14.10. Once again we consider derangements. Call this a structure of type D and let Π denote the structure ‘permutation’. Clearly $\Pi(x) = (1-x)^{-1}$. Any permutation consists of a set of fixed points (that we interpret as just a set) and a derangement on the remaining points. So by (14.15) we have

$$(1-x)^{-1} = D(x) \cdot S(x), \text{ i.e. } D(x) = e^{-x}(1-x)^{-1}$$

as was shown in Example 10.1.

Example 14.11. In how many ways can a labeled n -set be split into a number of pairs ($= P$) and a number of singletons ($= S$)? First, observe that if we wish to split $2k$ points into pairs, we must choose a point x_1 to go with point 1 and then split the remaining $2k-2$ points into pairs. Therefore $p_{2k} = (2k-1)!!$ and we find that

$$P(x) = \sum_{k=0}^{\infty} (2k-1)!! \frac{x^{2k}}{(2k)!} = \exp\left(\frac{1}{2}x^2\right).$$

It follows that

$$(14.16) \quad (P \cdot S)(x) = \exp\left(x + \frac{1}{2}x^2\right).$$

Let us now try to find the same result using a recursion relation. We denote the structure $P \cdot S$ by B . In the set $\{1, 2, \dots, n\}$ we can either let n be a singleton or make a pair $\{x, n\}$ with $1 \leq x \leq n-1$. So

$$b_n = b_{n-1} + (n-1)b_{n-2} \quad (n \geq 1).$$

It follows that

$$B'(x) = (1+x)B(x),$$

and since $B(0) = 1$, we again find (14.16) as solution.

We return to the recurrence of Example 14.11 in Example 14.15.

Problem 14D. Consider the structures M_0 := mapping of a set to itself with no fixed point, M_1 := mapping of a set to itself with exactly one fixed point, and A := arborescence. Find a relation between $M_0(x)$, $M_1(x)$, and $A(x)$ and check the first few terms to see if the result is correct.

We make things slightly more difficult. We wish to partition an n -set into parts and then impose structure N on each of the parts, where $n_0 = 0$. We claim that the exponential generating function for the compound structure is $\exp(N(x))$. A simple example is the case where N is the uniform structure (with the convention $n_0 = 0$) and hence $N(x) = e^x - 1$. The compound structure is of course ‘partition’ for which we know from Theorem 13.6 that the exponential generating function is equal to

$$\sum_{n=0}^{\infty} \left(\sum_{k=0}^n S(n, k) \right) \frac{x^n}{n!} = \sum_{k=0}^{\infty} \frac{(e^x - 1)^k}{k!} = \exp(e^x - 1) = \exp(N(x)).$$

We formulate this method as a theorem.

Theorem 14.2. *If the compound structure $S(N)$ is obtained by splitting a set into parts, each of which gets a structure of type N , then*

$$S(N)(x) = \exp(N(x)).$$

PROOF: By a slight generalization of (13.3) we see that if the partition of the n -set consists of b_1 parts of size 1, b_2 parts of size 2, \dots , b_k parts of size k , where $b_1 + 2b_2 + \dots + kb_k = n$, then there are

$$\binom{n_1}{1!}^{b_1} \cdots \binom{n_k}{k!}^{b_k} \cdot \frac{n!}{b_1! \dots b_k!}$$

ways to make the compound structure, and this has to be divided by $n!$ to obtain the contribution to the coefficient of x^n in the exponential generating function. If $b_1 + \dots + b_k = m$, then this same contribution is found in $\exp(N(x))$ from the term $(N(x))^m/m!$, namely as

$$\frac{1}{m!} \binom{m}{b_1, \dots, b_k} \left(n_1 \frac{x}{1!} \right)^{b_1} \cdots \left(n_k \frac{x^k}{k!} \right)^{b_k}.$$

This proves the assertion. \square

In fact, it is not difficult to see that this theorem is a special case of a more general method. Interpret the previous situation as follows. We have a uniform structure on a k -set of points and we replace each point by some structure of type N . The resulting configuration is an element of the compound structure that we just discussed. If the first of the structures is not uniform but, say, of type R , then the exponential generating function for the compound structure will be $R(N(x))$ by the same argument as we used above. We sometimes call this procedure the substitution of N into R , and it is nice that we then must do the same for the generating functions!

Example 14.12. If we substitute the structure ‘oriented cycle’ into the uniform structure, then we are considering the compound structure consisting of a partition of an n -set into oriented cycles, i.e. the structure Π with as usual $\pi_0 = 1$. So we must have $\Pi(x) = \exp(C(x))$ and, indeed, $\Pi(x) = (1-x)^{-1}$ and $C(x) = -\log(1-x)$.

Example 14.13. Let us look at Fig. 2.2 again, adding loops at 1 and 21. We then have a description of a mapping of an n -set (with $n = 21$ in this case) to itself. But we can also interpret the figure as an element of the structure Π , namely $(1)(4, 5, 3)(7)(20, 12)(21)$ in

which each point has been replaced by an arborescence with that point as root. Letting A denote arborescence, we find from Cayley's theorem, Theorem 2.1, that

$$(14.17) \quad A(x) = \sum_{n=1}^{\infty} n^{n-1} \frac{x^n}{n!}.$$

(The extra factor n comes from the choice of the root.) Since there are n^n mappings from an n -set to itself, the method of Theorem 14.2 shows that the following relation must hold:

$$(14.18) \quad \Pi(A(x)) = \frac{1}{1 - A(x)} = \sum_{n=0}^{\infty} n^n \frac{x^n}{n!}.$$

We shall verify this after the next example.

The following well known result from complex analysis often plays a role in combinatorial problems involving generating functions. It is known as the *Lagrange inversion formula*. It may be found in textbooks on analysis with analytic proofs; see the notes. It is possible to prove the theorem within the theory of formal power series (using formal derivation, etc.) and we give such a formal proof in Appendix 2.

Theorem 14.3. *Let f be analytic in a neighborhood of $z = 0$ and $f(0) \neq 0$. Then, if $w = z/f(z)$, z can be expressed as a power series $z = \sum_{k=1}^{\infty} c_k w^k$ with a positive radius of convergence, in which*

$$(14.19) \quad c_k = \frac{1}{k!} \left\{ \left(\frac{d}{dz} \right)^{k-1} (f(z))^k \right\}_{z=0}.$$

Example 14.14. We shall find a fourth proof of Theorem 2.1. Let T be the structure 'labeled tree'. We wish to show that $t_n = n^{n-2}$ for $n \geq 1$. If A denotes arborescences as before, then obviously $a_n = nt_n$, i.e. $A(x) = xT'(x)$. Furthermore, from Theorem 14.2 we see that $\exp(A(x))$ is the exponential generating function for the structure 'rooted forest' ($= F$). Consider a labeled tree on $n + 1$ vertices as an arborescence with vertex $n + 1$ as its root and

then delete the root and all incident edges. The result is a rooted forest on n vertices. Since we can reverse this process, we have a one-to-one correspondence. Therefore

$$(14.20) \quad e^{A(x)} = 1 + \sum_{n=1}^{\infty} f_n \frac{x^n}{n!} = \sum_{n=0}^{\infty} t_{n+1} \frac{x^n}{n!} = T'(x) = x^{-1}A(x),$$

i.e.

$$(14.21) \quad \frac{A(x)}{e^{A(x)}} = x.$$

We apply Theorem 14.3 to (14.21) with $z = A(x)$, $f(z) = e^z = e^{A(x)}$, $w = x$. We find $A(x) = \sum_{k=1}^{\infty} c_k x^k$ with

$$c_k = \frac{1}{k!} \left\{ \left(\frac{d}{dz} \right)^{k-1} e^{kz} \right\}_{z=0} = \frac{k^{k-1}}{k!}$$

and it follows that $t_n = n^{n-2}$. Furthermore we see that the number of labeled rooted forests on n vertices is $(n+1)^{n-1}$.

Remark. We now have verification of (14.18) because (14.20) implies that $A'(x) = e^{A(x)} + xe^{A(x)}A'(x)$, i.e.

$$\sum_{n=1}^{\infty} n^n \frac{x^n}{n!} = xA'(x) = \frac{xe^{A(x)}}{1 - xe^{A(x)}} = \frac{A(x)}{1 - A(x)}.$$

Remark. The procedure of removing a point from a combinatorial structure with $n+1$ points that we used in Example 14.14 is called *derivation* and it indeed corresponds to the derivation of generating functions. Another example is removing a vertex from an oriented cycle on $n+1$ vertices. This yields an oriented path on n vertices, of which there are $n!$. So their exponential generating function is $(1-x)^{-1}$ and that is $C'(x)$.

Problem 14E. Let a_n denote the number of ways of decomposing a convex $n+1$ -gon into quadrilaterals by inserting a number of nonintersecting chords. By convention $a_0 = 0$, $a_1 = 1$. Show that $\sum_{k+l+m=n} a_k a_l a_m = a_n$ for $n \geq 3$. If $f(x)$ is the ordinary generating

function for the sequence a_n , then find a functional equation for $f(x)$ and solve this equation using Theorem 14.3. (We remark that the result that is obtained can also be proved combinatorially.)

Although we have stressed that in most cases the power series can be considered as formal power series, it has been clear in a number of examples that analysis can be an important tool in many combinatorial problems. We give one more example that shows a method that can be used for many recurrences.

Example 14.15. In Example 14.11 we encountered the recursion

$$(14.22) \quad a_n = a_{n-1} + (n-1)a_{n-2}$$

and the corresponding exponential generating function. In previous examples we showed that the counting function grows more or less as c^n for some constant c . Clearly a_n grows more rapidly, but what is a good approximation for its asymptotic behavior? The first step in obtaining the answer to this question involves a method that is applicable to many recurrences. In (14.22) we substitute

$$(14.23) \quad a_n = \int_C \psi(z) z^n dz,$$

where C is a path in \mathbb{C} that we can still choose and ψ is a function also still to be determined. We substitute (14.23) into (14.22). The term $(n-1)a_{n-2}$ yields $\int_C \psi(z)(n-1)z^{n-2} dz$, and we require that integration by parts yields only the integral involving $\psi'(z)$, the other term being 0 by a suitable choice of C . Then (14.22) becomes

$$(14.24) \quad \int_C \{\psi(z)[z^n - z^{n-1}] + \psi'(z)z^{n-1}\} dz = 0,$$

which is true for all $n \in \mathbb{N}$ if $\psi(z)(1-z) = \psi'(z)$, i.e. $\psi(z) = \alpha e^{z-\frac{1}{2}z^2}$. Once we know ψ , the requirement on C shows that the real axis from $-\infty$ to ∞ is a good choice for the path of integration. From $a_0 = 1$ we find that $\alpha = (2\pi e)^{-\frac{1}{2}}$.

To find the asymptotic behavior of a_n , we must now analyze the behavior of

$$(14.25) \quad I := \int_{-\infty}^{\infty} e^{x-\frac{1}{2}x^2} x^n dx.$$

Since the integrand is maximal near $x = \sqrt{n}$, we substitute $x = y + \sqrt{n}$ and find

(14.26)

$$I = e^{-\frac{1}{2}n + \sqrt{n}} n^{\frac{1}{2}n} \int_{-\infty}^{\infty} e^{y - \frac{1}{2}y^2} \exp\left(-y\sqrt{n} + n \log\left(1 + \frac{y}{\sqrt{n}}\right)\right) dy.$$

Now note that if u and v are negative, then $|e^u - e^v| < |u - v|$ and use the representation $\log(1 + t) = \int_0^t \frac{ds}{1+s} = s - \frac{s^2}{2} + \int_0^t \frac{s^2}{1+s} ds$ to obtain

$$\left| -y\sqrt{n} + n \log\left(1 + \frac{y}{\sqrt{n}}\right) + \frac{y^2}{2} \right| \leq \frac{|y|^3}{\sqrt{n}}.$$

Substitution in (14.26) shows that the integral tends to

$$\int_{-\infty}^{\infty} e^{y-y^2} dy = \sqrt{\pi} e^{\frac{1}{4}}.$$

We have proved that

$$(14.27) \quad a_n \sim \frac{e^{-\frac{1}{4}}}{\sqrt{2}} n^{\frac{1}{2}n} e^{-\frac{1}{2}n + \sqrt{n}}.$$

It is clear that this result cannot be found in an easy way!

Problem 14F. Let $F_n(x)$ denote the expansion of $(1 - x^n)^{-\mu(n)/n}$ in a power series. Also consider the expansion of e^x as a formal power series. Prove that

$$e^x = \prod_{n=1}^{\infty} F_n(x)$$

is true as a relation between formal power series.

Problem 14G. Find the exponential generating function for the number of symmetric $n \times n$ permutation matrices.

Problem 14H. On a circle we place n symbols 0 and n symbols 1 in an arbitrary order. Show that it is possible to number the positions on the circle consecutively from 1 to $2n$ such that the

sequence satisfies (14.13) if we replace the strict inequality ' $<$ ' with ' \leq '.

Problem 14I. Let the points $1, \dots, 2n$ be on a circle (consecutively). We wish to join them in pairs by n nonintersecting chords. In how many ways can this be done?

Problem 14J. Find the exponential generating function for the number of labeled regular graphs of valency 2, with n vertices.

Problem 14K. Consider walks in the X - Y plane where each step is $R : (x, y) \rightarrow (x+1, y)$ or $U : (x, y) \rightarrow (x, y+1)$. We start at $(0, 0)$ and ask in how many ways we can reach $(2n, 2n)$ without passing through one of the points $(2i-1, 2i-1)$, $i = 1, \dots, n$. Prove that this number is the Catalan number u_{2n+1} .

Problem 14L. Consider walks in the X - Y plane where each step is $R : (x, y) \rightarrow (x+1, y)$ or $U_a : (x, y) \rightarrow (x, y+a)$, with a a positive integer. There are five walks that contain a point on the line $x+y=2$, namely: RR , RU_1 , U_1R , U_1U_1 , and U_2 . Let a_n denote the number of walks that contain a point on the line $x+y=n$ (so $a_2=5$). Show that $a_n = F_{2n}$, where F_n are the Fibonacci numbers starting with $F_0 = F_1 = 1$.

Problem 14M. Count pairs (f, g) of functions f, g , where f maps $\{1, 2, \dots, r\}$ to $\{1, 2, \dots, n\}$ and g is a permutation of $\{1, 2, \dots, n\}$ that fixes the image of f pointwise. Doing this in two ways prove that for $n \geq r$

$$\sum_{k=1}^n \binom{n}{k} k^r d_{n-k} = B(r) \cdot n!,$$

where d_m denotes the number of derangements of $1, 2, \dots, m$ and $B(r)$ is a Bell number.

Problem 14N. Consider walks in the X - Y plane where each step is $R : (x, y) \rightarrow (x+1, y)$, $U : (x, y) \rightarrow (x, y+1)$, or $D : (x, y) \rightarrow (x+1, y+1)$. We wish to count walks from $(0, 0)$ to (n, n) that are below or on the line $x = y$. Find a recurrence for the number of walks like (14.10).

Notes.

For an extensive treatment of the material in this chapter, we refer to Goulden and Jackson (1983) and Stanley (1986). A very readable survey is Stanley (1978).

The first of the references mentioned above has much on the theory of formal power series. For this topic also see Niven (1969) and Appendix 2. Generally speaking, operations with power series are ‘formal’ and require no discussion of convergence when the coefficient of any monomial x^n , say, in a sum or product is determined by a finite number of operations (i.e. no limits). For example, $\sum_{n=0}^{\infty} (\frac{1}{2} + x)^n$ is not allowed in formal operations since even the constant term is not a finite sum; but $\sum_{n=0}^{\infty} (n!x + x^2)^n$ is allowed (even though it does not converge for $x \neq 0$) since the coefficient of any power of x requires only a finite computation (cf. Problem 14F).

The first linear recurrence that one usually learns to solve is $a_{n+1} = a_n + a_{n-1}$. It leads to the famous *Fibonacci sequence*; cf. Problem 14A. As we observed in Chapter 10, this name is due to Lucas. The sequence is related to a problem occurring in the book *Liber abaci* (1203) by Leonardo of Pisa (known as Fibonacci).

The number a_n of polyominoes of size n , treated in Example 14.5, was shown to be less than c^n (where we used $c = 15$). Note that this assertion also follows from Fekete’s lemma. We derived the inequality by using a suitable coding for the cells. The reader may wish to try to prove that $a(m, n) < m \cdot c^n$ for a suitable c by using (14.3) and induction. The remark following (14.9) is based on a statement in Stanley (1986), attributing an unpublished combinatorial proof to D. Hickerson.

The result of Example 14.6 is related to the fact that \mathbb{F}_{p^n} has as subfields the fields \mathbb{F}_{p^d} , where d divides n . From this, one finds that $x^{p^n} - x$ is the product of all the irreducible polynomials over \mathbb{F}_p with a degree d dividing n . This yields the formula proved in the example.

Despite the fact that there is extensive literature on all the problems with the Catalan numbers as solution, the problems reappear regularly (e.g. in problem sections of journals). As stated earlier, the Belgian mathematician E. Catalan (1814–1894) studied well-

formed bracketings (as in Example 14.7).

The reflection principle of Fig. 14.2 was used by the French combinatorialist D. André (1840–1917) in his solution of Bertrand's famous *ballot problem*: if, at the end of an election, candidate P has p votes and Q has q votes, $p < q$, then the probability that Q was ahead all the time during the election is $(q - p)/(q + p)$.

The Lagrange inversion formula is one of the many contributions to analysis by J. L. Lagrange (see notes to Chapter 19). For a proof see §7.32 in Whittaker and Watson (1927). The theorem was published in 1770. We also refer the reader to G. N. Raney (1960).

References.

- E. Catalan (1838), Note sur une équation aux différences finies, *J. M. Pures Appl.* **3**, 508–516.
- I. P. Goulden and D. M. Jackson (1983), *Combinatorial Enumeration*, Wiley-Interscience.
- A. Joyal (1981), Une théorie combinatoire des séries formelles, *Advances in Mathematics* **42**, 1–82.
- D. A. Klarner (1967), Cell growth problem, *Canad. J. Math.* **19**, 851–863.
- I. Niven (1969), Formal power series, *Amer. Math. Monthly* **76**, 871–889.
- G. N. Raney (1960), Functional composition patterns and power series reversion, *Trans. Amer. Math. Soc.* **94**, 441–451.
- R. P. Stanley (1978), Generating functions, pp. 100–141 in *Studies in Combinatorics* (G.-C. Rota, ed.), Studies in Math. **17**, Math. Assoc. of America.
- R. P. Stanley (1986), *Enumerative Combinatorics*, Vol. I, Wadsworth and Brooks/Cole.
- E. T. Whittaker and G. N. Watson (1927), *A Course in Modern Analysis*, Cambridge University Press.

15

Partitions

We have considered several partition problems in the previous chapters. We now come to the most difficult one, namely the problem of *unordered* partitions of n into k parts, respectively any number of parts. We define $p_k(n)$ as the number of solutions of

$$(15.1) \quad n = x_1 + x_2 + \cdots + x_k, \quad x_1 \geq x_2 \geq \cdots \geq x_k \geq 1.$$

For example, $7 = 5 + 1 + 1 = 4 + 2 + 1 = 3 + 3 + 1 = 3 + 2 + 2$, so $p_3(7) = 4$.

Using the same idea as in the Corollary to Theorem 13.1, we see that $p_k(n)$ equals the number of solutions of $n - k = y_1 + \cdots + y_k$ with $y_1 \geq \cdots \geq y_k \geq 0$. If exactly s of the integers y_i are positive, then by (15.1) there are $p_s(n - k)$ solutions (y_1, \dots, y_k) . Therefore

$$(15.2) \quad p_k(n) = \sum_{s=1}^k p_s(n - k).$$

Problem 15A. Show that $p_k(n) = p_{k-1}(n - 1) + p_k(n - k)$ and use this to prove (15.2).

Since we have the trivial initial conditions $p_k(n) = 0$ for $n < k$ and $p_k(k) = 1$, we can recursively calculate the numbers $p_k(n)$. Clearly $p_1(n) = 1$ and $p_2(n) = \lfloor n/2 \rfloor$.

Example 15.1. We shall show that $p_3(n) = \{\frac{n^2}{12}\}$, i.e. the number nearest to $\frac{n^2}{12}$, using a method that can be used for other values of k . Let $a_3(n)$ denote the number of solutions of $n = x_1 + x_2 + x_3$, $x_1 \geq x_2 \geq x_3 \geq 0$. Then $a_3(n) = p_3(n + 3)$ and writing $y_3 = x_3$, $y_2 = x_2 - x_3$, $y_1 = x_1 - x_2$, we see that $a_3(n)$ is the number of

solutions of $n = y_1 + 2y_2 + 3y_3$, $y_i \geq 0$, $i = 1, 2, 3$. Therefore (cf. Example 14.2)

$$(15.3) \quad \sum_{n=0}^{\infty} a_3(n)x^n = (1-x)^{-1}(1-x^2)^{-1}(1-x^3)^{-1}.$$

Let $\omega = e^{2\pi i/3}$. The partial fraction decomposition of (15.3) yields

$$(15.4) \quad \sum_{n=0}^{\infty} a_3(n)x^n = \frac{1}{6}(1-x)^{-3} + \frac{1}{4}(1-x)^{-2} + \frac{17}{72}(1-x)^{-1} \\ + \frac{1}{8}(1+x)^{-1} + \frac{1}{9}(1-\omega x)^{-1} + \frac{1}{9}(1-\omega^2 x)^{-1}.$$

Using (10.6), we find from (15.4)

$$a_3(n) = \frac{1}{12}(n+3)^2 - \frac{7}{72} + \frac{(-1)^n}{8} + \frac{1}{9}(\omega^n + \omega^{2n}),$$

and this implies that

$$|a_3(n) - \frac{1}{12}(n+3)^2| \leq \frac{7}{72} + \frac{1}{8} + \frac{2}{9} < \frac{1}{2}.$$

Therefore

$$(15.5) \quad p_3(n) = \left\{ \frac{1}{12}n^2 \right\}.$$

Problem 15B. We choose three vertices of a regular n -gon and consider the triangle they form. Prove directly that there are $\left\{ \frac{1}{12}n^2 \right\}$ mutually incongruent triangles that can be formed in this way, thereby providing a second proof of (15.5).

We shall now show that (15.5) is an example of a more general result.

Theorem 15.1. *If k is fixed then*

$$p_k(n) \sim \frac{n^{k-1}}{k!(k-1)!} \quad (n \rightarrow \infty).$$

PROOF: (i) If $n = x_1 + \cdots + x_k$, $x_1 \geq \cdots \geq x_k \geq 1$, then the $k!$ permutations of (x_1, \dots, x_k) yield solutions of (13.2) in positive integers, not necessarily all different. So

$$(15.6) \quad k! p_k(n) \geq \binom{n-1}{k-1}.$$

If $n = x_1 + \cdots + x_k$, $x_1 \geq \cdots \geq x_k \geq 1$, then if $y_i := x_i + (k-i)$, $1 \leq i \leq k$, the integers y_i are distinct and $y_1 + \cdots + y_k = n + \frac{k(k-1)}{2}$. Therefore

$$(15.7) \quad k! p_k(n) \leq \binom{n + \frac{k(k-1)}{2} - 1}{k-1}.$$

The result follows from (15.6) and (15.7). □

Problem 15C. Let a_1, a_2, \dots, a_t be positive integers (not necessarily distinct) with greatest common divisor 1. Let $f(n)$ denote the number of solutions of

$$n = a_1 x_1 + a_2 x_2 + \cdots + a_t x_t$$

in nonnegative integers x_1, \dots, x_t . What is the generating function $F(x) := \sum f(n)x^n$? Show that $f(n) \sim cn^{t-1}$ for some constant c and explicitly give c as a function of a_1, \dots, a_t .

The problem that we considered in the Corollary to Theorem 13.1 concerns what is called the number of *compositions* of n into k parts. By this corollary the total number of compositions of n equals $\sum_{k=1}^n \binom{n-1}{k-1} = 2^{n-1}$. The method that we used in Theorem 13.1 shows this directly as follows: consider n blue balls with a space between any two of them in which we can place a red ball if we wish. The total number of configurations that can be made in this way is clearly 2^{n-1} and they represent all compositions of n . We could have proved the same result without our knowledge of Chapter 13 as follows. Let c_{nk} denote the number of compositions of n into k parts. Define

$$c_k(x) := \sum_{n=k}^{\infty} c_{nk} x^n.$$

Then, using a method that we have used several times before, we find

$$c_k(x) = (x + x^2 + x^3 + \cdots)^k = x^k(1-x)^{-k} = \sum_{n=k}^{\infty} \binom{n-1}{k-1} x^n$$

and

$$\sum_{k=1}^{\infty} c_k(x) = \sum_{k=1}^{\infty} x^k(1-x)^{-k} = \frac{x}{1-2x},$$

i.e. n has 2^{n-1} compositions.

Problem 15D. Show that in a list of all 2^{n-1} compositions of n , $n \geq 4$, the integer 3 occurs exactly $n \cdot 2^{n-5}$ times.

The most difficult and mathematically the most interesting and important function of all in this area of combinatorics is defined by

$$(15.8) \quad p(n) := \text{number of unordered partitions of } n.$$

For example, $p(5) = 7$, the partitions of 5 being

$$1+1+1+1+1 = 2+1+1+1 = 3+1+1 = 2+2+1 = 4+1 = 3+2 = 5.$$

Clearly, $p(n)$ is the number of solutions of

$$(15.9) \quad n = x_1 + x_2 + \cdots + x_n \quad (x_1 \geq x_2 \geq \cdots x_n \geq 0).$$

As we saw above, this can also be formulated as the number of solutions of $n = y_1 + 2y_2 + \cdots + ny_n$, where $y_i \geq 0$, $1 \leq i \leq n$. (Here y_i denotes the number of terms x_k equal to i in the first definition.)

The study of the so-called *partition function* $p(n)$ has led to some of the most fascinating areas of analytic number theory, analysis, algebraic geometry, etc. We shall obviously only be able to look at properties that are proved by combinatorial arguments.

Theorem 15.2. *The generating function for the partition function is*

$$P(x) := \sum_{n=0}^{\infty} p(n)x^n = \prod_{k=1}^{\infty} (1-x^k)^{-1}.$$

PROOF: We again use the idea of Example 14.2. The partition of $n = \sum_{i=1}^m ir_i$ with r_i terms equal to i (for $1 \leq i \leq m$) corresponds to the term $x_1^{r_1} \cdots x_m^{r_m}$ in the (formal) infinite product $\prod(1 + x_k + x_k^2 + \cdots)$. Replacing x_k by x^k , we find the result. \square

Many theorems about partitions can be proved easily by representing each partition by a diagram of dots, known as a *Ferrers diagram*. Here we represent each term of the partition by a row of dots, the terms in descending order, with the largest at the top. Sometimes it is more convenient to use squares instead of dots (in this case the diagram is called a *Young diagram* by some authors but we shall use Ferrers diagram as the name for the figure). For example, the partition $(5,4,2,1)$ of 12 is represented by each of the diagrams of Fig. 15.1.




Figure 15.1

The partition we get by reading the Ferrers diagram by columns instead of rows is called the *conjugate* of the original partition. So the conjugate of $12 = 5 + 4 + 2 + 1$ is $12 = 4 + 3 + 2 + 2 + 1$. The relationship is symmetric. We first show a few easy examples of the use of a Ferrers diagram.

Theorem 15.3. *The number of partitions of n into parts, the largest of which is k , is $p_k(n)$.*

PROOF: For each partition for which the largest part is k , the conjugate partition has k parts (and vice versa). \square

Problem 15E. Show with a Ferrers diagram that the number of partitions of $n + k$ into k parts equals the number of partitions of n into at most k parts. (This is (15.2).)

In some cases a proof using generating functions requires less ingenuity than using a Ferrers diagram would. The next theorem can be proved with a diagram similar to a Ferrers diagram though we shall use generating functions instead.

Theorem 15.4. *The number of partitions of n into odd parts equals the number of partitions of n into unequal parts.*

PROOF: The generating function for the number of partitions of n into odd parts is (by an obvious generalization of Theorem 15.2) equal to $\prod_{m=1}^{\infty} (1 - x^{2m-1})^{-1}$, and the generating function for the number of partitions of n into unequal parts is (by the same argument as used in the proof of Theorem 15.2) $\prod_{k=1}^{\infty} (1 + x^k)$. Since

$$\begin{aligned} \prod_{k=1}^{\infty} (1 + x^k) &= \prod_{k=1}^{\infty} \frac{(1 - x^{2k})}{(1 - x^k)} \\ &= \prod_{k=1}^{\infty} (1 - x^{2k}) \prod_{l=1}^{\infty} (1 - x^l)^{-1} = \prod_{m=1}^{\infty} (1 - x^{2m-1})^{-1}, \end{aligned}$$

the proof is complete. □

Now consider the function $(P(x))^{-1} = \prod_{k=1}^{\infty} (1 - x^k)$. In the expansion of this product, a partition of n into unequal parts contributes $+1$ to the coefficient of x^n if the number of parts is even, and -1 if the number of parts is odd. So the coefficient of x^n is $p_e(n) - p_o(n)$, where $p_e(n)$, respectively $p_o(n)$, denotes the number of partitions of n into an even, respectively odd, number of unequal parts. It was shown by Euler that $p_e(n) = p_o(n)$ unless n has the form $n = \omega(m) := (3m^2 - m)/2$ or $n = \omega(-m) = (3m^2 + m)/2$, in which case $p_e(n) - p_o(n) = (-1)^m$. The numbers $\omega(m)$ and $\omega(-m)$ are called *pentagonal numbers*. This name is explained by the relation $\omega(m) = \sum_{k=0}^{m-1} (3k + 1)$ and Fig. 15.2.




Figure 15.2

The following extremely elegant pictorial proof of *Euler's identity* is due to Franklin (1881).

Theorem 15.5. We have

$$\prod_{k=1}^{\infty} (1 - x^k) = 1 + \sum_{m=1}^{\infty} (-1)^m \left(x^{\omega(m)} + x^{\omega(-m)} \right).$$

PROOF: Consider a Ferrers diagram of a partition of n into unequal parts as for $23 = 7 + 6 + 5 + 3 + 2$ in Fig. 15.3.




Figure 15.3

The last row is called the *base* of the diagram. The number of dots in the base is denoted by b . In Fig. 15.3 the base is indicated by a line segment with $b = 2$ dots. The longest 45° line segment joining the last point in the top row with other points of the diagram is called the *slope* of the diagram. Its number of points is denoted by s . In Fig. 15.3 the slope is indicated by a segment with $s = 3$ points. We now define two operations on the diagram, which we call A and B .

A : If $b \leq s$, then remove the base and adjoin it to the diagram at the right to form a new slope parallel to the original one, unless $b = s$ and the base and the slope have a point in common. This exception is considered below.

B : If $b > s$, remove the slope and adjoin it at the bottom of the diagram as a new base, except if $b = s + 1$ and the base and the slope have a point in common.

In Fig. 15.3 operation A can be carried out and it yields the partition $23 = 8 + 7 + 5 + 3$. An example of the exceptional situation for operation B is shown in Fig. 15.4.




Figure 15.4

The exception for operation A can occur only if

$$n = b + (b + 1) + \cdots + (2b - 1),$$

i.e. $n = \omega(b)$. The exception for operation B occurs if $n = (s + 1) + \cdots + 2s$, i.e. $n = \omega(-s)$. In all other cases exactly one of the operations can be carried out and we thus have a one-to-one correspondence between partitions of n into an even number of unequal parts and partitions of n into an odd number of unequal parts; and hence for these values of n , we have $p_e(n) - p_o(n) = 0$. In the exceptional cases the difference is $+1$ or -1 . \square

Euler used Theorem 15.5 to find the following recursion formula for $p(n)$.

Theorem 15.6. *Let $p(n) = 0$ for $n < 0$. Then for $n \geq 1$,*

$$(15.10) \quad p(n) = \sum_{m=1}^{\infty} (-1)^{m+1} \{p(n - \omega(m)) + p(n - \omega(-m))\}.$$

PROOF: This is an immediate consequence of Theorem 15.2 and Theorem 15.5. \square

Note that the sum in (15.10) is finite. With this recursion one can rapidly generate a table for $p(n)$ for small values of n .

The first two terms of the recursion formula are the same as in the famous Fibonacci recursion (cf. Problem 5E). Although these are followed by two negative terms, one might think that $p(n)$ will increase in a way similar to the Fibonacci numbers, i.e. as c^n for some constant c . This is not the case. We shall show that $p(n)$ grows much more slowly. The actual asymptotics of $p(n)$ involve complicated methods from analytic number theory. We mention only the main term of the asymptotic formula:

$$\lim_{n \rightarrow \infty} n^{-\frac{1}{2}} \log p(n) = \pi \sqrt{\frac{2}{3}}.$$

One can show that in fact $p(n)$ is much smaller than $\exp\left(\pi \sqrt{\frac{2}{3}n}\right)$.

Theorem 15.7. For $n > 2$ we have

$$p(n) < \frac{\pi}{\sqrt{6(n-1)}} e^{\pi\sqrt{\frac{2}{3}n}}.$$

PROOF: Let $f(t) := \log P(t)$. From Theorem 15.2 we find

$$f(t) = -\sum_{k=1}^{\infty} \log(1-t^k) = \sum_{k=1}^{\infty} \sum_{j=1}^{\infty} \frac{t^{kj}}{j} = \sum_{j=1}^{\infty} \frac{j^{-1}t^j}{1-t^j}.$$

From now on let $0 < t < 1$. Then from

$$(1-t)^{-1}(1-t^j) = 1+t+\cdots+t^{j-1} > jt^{j-1},$$

we find

$$f(t) < \frac{t}{1-t} \sum_{j=1}^{\infty} j^{-2} = \frac{1}{6}\pi^2 \frac{t}{1-t}.$$

Since $p(n)$ is increasing, we have $P(t) > p(n)t^n(1-t)^{-1}$. By combining the two inequalities and then substituting $t = (1+u)^{-1}$, we find

$$\begin{aligned} \log p(n) &< f(t) - n \log t + \log(1-t) \\ &< \frac{\pi^2}{6} \cdot \frac{t}{1-t} - n \log t + \log(1-t) \\ &= \frac{\pi^2}{6} u^{-1} + n \log(1+u) + \log \frac{u}{1+u}. \end{aligned}$$

Therefore

$$\log p(n) < \frac{1}{6}\pi^2 u^{-1} + (n-1)u + \log u.$$

We get the required inequality by substituting $u = \pi\{6(n-1)\}^{-\frac{1}{2}}$. \square

Euler's identity is a special case of a famous identity of Jacobi that is important in the theory of theta functions. We would not mention this so-called *Jacobi triple product identity* if we had not known of the beautiful combinatorial proof using a Ferrers diagram, due to Wright (1965).

Theorem 15.8. *We have*

$$\prod_{n=1}^{\infty} (1 - q^{2n})(1 + q^{2n-1}t)(1 + q^{2n-1}t^{-1}) = \sum_{r=-\infty}^{\infty} q^{r^2} t^r.$$

PROOF: We rewrite the assertion as

$$\prod_{n=1}^{\infty} (1 + q^{2n-1}t)(1 + q^{2n-1}t^{-1}) = \sum_{r=-\infty}^{\infty} q^{r^2} t^r \prod_{n=1}^{\infty} (1 - q^{2n})^{-1},$$

and substitute $x = qt$, $y = qt^{-1}$. This yields the relation

$$(15.11) \quad \prod_{n=1}^{\infty} \{(1 + x^n y^{n-1})(1 + x^{n-1} y^n)\} \\ = \sum_{r=-\infty}^{\infty} x^{\frac{1}{2}r(r+1)} y^{\frac{1}{2}r(r-1)} \prod_{n=1}^{\infty} (1 - x^n y^n)^{-1}.$$

We shall prove this relation by interpreting both sides as generating functions corresponding to the counting of appropriate combinatorial objects, and then showing a one-to-one mapping between these objects. For the left-hand side, we find as a combinatorial interpretation the generating function for the number of partitions of the Gaussian integer $n + mi$ into parts $a + (a - 1)i$ and $(b - 1) + bi$ ($a \geq 1, b \geq 1$), with no two parts equal. Call this number $\alpha(n, m)$. So the left-hand side of (15.11) is $\sum_{n=1}^{\infty} \sum_{m=1}^{\infty} \alpha(n, m) x^n y^m$. On the right-hand side, we use Theorem 15.2 and replace the product by $\sum_{k=1}^{\infty} p(k) x^k y^k$. We must therefore prove that $\alpha(n, m) = p(k)$, where $n = k + \frac{1}{2}r(r + 1)$ and $m = k + \frac{1}{2}r(r - 1)$. Without loss of generality, we may assume that $n \geq m$, i.e. $r \geq 0$. A partition of $n + mi$ must have $v \geq 0$ terms of type $(b - 1) + bi$ and $v + r$ terms of type $a + (a - 1)i$, and therefore $n \geq \frac{1}{2}r(r + 1)$, so $k \geq 0$. In Fig. 15.5 below, we consider the example $(n, m) = (47, 44)$, so $r = 3$ and $k = 41$. We have taken the Ferrers diagram of the partition $41 = 12 + 10 + 8 + 5 + 2 + 2 + 2$ and above the top row we have added rows of length $r, r - 1, \dots, 1$.




Figure 15.5

The resulting diagram is split into two parts. The shaded part on the left is determined by the ‘staircase’ starting with the part that was added at the top. We read the shaded part by columns. By the construction, the sequence is decreasing. These numbers are the a ’s for terms of type $a + (a - 1)i$. The unshaded part is read by rows and again the numbers are decreasing. These are the $b - 1$ ’s for terms of type $(b - 1) + bi$ (the last b could be 1, corresponding to one empty unshaded row). The number of a ’s exceeds the number of $b - 1$ ’s by r and the sum of the a ’s and $b - 1$ ’s is clearly $k + \frac{1}{2}r(r + 1)$. So we have indeed produced a partition of $n + mi$ of the required type. It is easy to see that the procedure can be reversed, i.e. we have defined the one-to-one mapping we were looking for. \square

Problem 15F. Prove that the number of self-conjugate partitions of n equals the number of partitions of n into unequal odd parts.

As a final problem related to partitions we shall consider objects known as *Young tableaux* or *standard tableaux*. A Young tableau of shape (n_1, n_2, \dots, n_m) is a Ferrers diagram (or Young diagram) of squares in which the integers 1 to n have been inserted (one in each square) in such a way that all rows and columns are increasing. For example, in Fig. 15.6 we display a Young tableau of shape $(5, 4, 2, 1)$.

1	3	4	7	11
2	5	10	12	
6	9			
8				

Figure 15.6

We are interested in determining the number of Young tableaux of a given shape. At first, this may seem like a somewhat unnatural problem. However, Young tableaux play an important role in the theory of group representations (and other areas). One of the interesting facts concerning these tableaux is that there is a one-to-one correspondence between the Young tableaux with n squares (that we shall call ‘cells’) and involutions of 1 to n , where we include the identity as an involution. (Note that we can therefore count the total number of tableaux using Problem 14G.) For a treatment of this one-to-one correspondence and several related problems we refer to D. Knuth (1973).

In order to count the Young tableaux of a given shape, we need to introduce the function $\Delta(x_1, \dots, x_m)$ defined by

$$(15.12) \quad \Delta(x_1, \dots, x_m) := \prod_{1 \leq i < j \leq m} (x_i - x_j).$$

(Note that Δ is the value of the Vandermonde determinant.)

Lemma 15.9. *Let*

$$g(x_1, \dots, x_m; y) := x_1 \Delta(x_1 + y, x_2, \dots, x_m) \\ + x_2 \Delta(x_1, x_2 + y, \dots, x_m) + \dots + x_m \Delta(x_1, x_2, \dots, x_m + y).$$

Then

$$g(x_1, \dots, x_m; y) = \left(x_1 + \dots + x_m + \binom{m}{2} y \right) \Delta(x_1, \dots, x_m).$$

PROOF: Clearly the function g is a homogeneous polynomial of degree $1 + \deg \Delta(x_1, \dots, x_m)$ in the variables x_1, \dots, x_m, y . If we interchange x_i and x_j , then g changes sign. So if $x_i = x_j$, then

g must be 0, i.e. g is divisible by $x_i - x_j$ and hence by the polynomial $\Delta(x_1, \dots, x_m)$. If $y = 0$, the assertion is obvious. Therefore we only have to prove the coefficient $\binom{m}{2}$ for y . If we expand g , then the terms of degree 1 in y are $\frac{x_i y}{x_i - x_j} \Delta(x_1, \dots, x_m)$ and $\frac{-x_j y}{x_i - x_j} \Delta(x_1, \dots, x_m)$ for all pairs (i, j) with $1 \leq i < j \leq m$. The sum of these terms is clearly $\binom{m}{2} \Delta(x_1, \dots, x_m)$. \square

We introduce a function f defined on all m -tuples (n_1, \dots, n_m) , $m \geq 1$, with the following properties:

$$(15.13) \quad f(n_1, \dots, n_m) = 0 \quad \text{unless } n_1 \geq n_2 \geq \dots \geq 0;$$

$$(15.14) \quad f(n_1, \dots, n_m, 0) = f(n_1, \dots, n_m);$$

$$(15.15) \quad \begin{aligned} f(n_1, \dots, n_m) &= f(n_1 - 1, n_2, \dots, n_m) + \\ &f(n_1, n_2 - 1, \dots, n_m) + \dots + f(n_1, n_2, \dots, n_m - 1), \\ &\text{if } n_1 \geq n_2 \geq \dots \geq n_m \geq 0; \end{aligned}$$

$$(15.16) \quad f(n) = 1 \quad \text{if } n \geq 0.$$

Clearly f is well defined. We claim that $f(n_1, \dots, n_m)$ counts the number of Young tableaux of shape (n_1, \dots, n_m) . Condition (15.13) is obvious and so are (15.14) and (15.16). To see that the number of Young tableaux of shape (n_1, \dots, n_m) satisfies (15.15), we consider the entry n . It must be the last entry in one of the rows, and if we remove the square with n , then we obtain a Young tableau for $n - 1$. In fact, if two or more rows of the tableau have the same length, then n can only be the last entry in the lowest of these; but including all terms in (15.15) does not matter since if, say, $n_1 = n_2$, then $f(n_1 - 1, n_2, \dots, n_m) = 0$.

Theorem 15.10. *The number of Young tableaux that have shape (n_1, \dots, n_m) satisfies*

$$(15.17) \quad f(n_1, \dots, n_m) = \frac{\Delta(n_1 + m - 1, n_2 + m - 2, \dots, n_m) n!}{(n_1 + m - 1)! (n_2 + m - 2)! \dots n_m!},$$

and in fact this formula for f is correct if $n_1 + m - 1 \geq n_2 + m - 2 \geq \dots \geq n_m$.

PROOF: We first observe that, if for some i we have $n_i + m - i = n_{i+1} + m - i - 1$, then the expression Δ on the right-hand side of (15.17) is 0, in accordance with the fact that the shape is not allowed. We must show that the right-hand side of (15.17) satisfies (15.13) to (15.16). All but (15.15) are trivial. We find the relation (15.15) by substituting $x_i = n_i + m - i$ and $y = -1$ in Lemma 15.9. \square

There is a formulation of this theorem that makes it more interesting. We introduce the concept of ‘hook’ in a Young tableau. The hook corresponding to a cell in a tableau is the union of the cell and all cells to the right in the same row and all cells below it in the same column. The ‘hook-length’ is the number of cells in the hook. In Fig. 15.7 we show a Young diagram with in each cell a number equal to the length of the corresponding hook. The shaded area is the hook corresponding to the cell in row 2 and column 3.




Figure 15.7

We now have the following remarkable theorem due to J. S. Frame, G. de Beauregard Robinson and R. M. Thrall (1954).

Theorem 15.11. *The number of Young tableaux of a given shape and a total of n cells is $n!$ divided by the product of all hook-lengths.*

PROOF: If we have a Young tableau of shape (n_1, \dots, n_m) , then the hook-length for the cell in row 1 and column 1 is $n_1 + m - 1$. Consider the hook-lengths for the cells in row 1. In Fig. 15.7 the second column has the same length as column 1 and hence the hook-length for the next cell is $n_1 + m - 2$. For the next cell the length drops by 2 because of the ‘missing cell’ indicated by a dot in the last row. Similarly, there is a jump of 3 for the column with two dots. So in row 1 we find as hook-lengths the numbers from 1 to $n_1 + m - 1$ with

the exception of the numbers $(n_1 + m - 1) - (n_j + m - j)$, $2 \leq j \leq m$. Similarly row i contains the integers from 1 to $n_i + m - i$ except for $(n_i + m - i) - (n_j + m - j)$, $i + 1 \leq j \leq m$. It follows that the product of the hook-lengths is $\{\prod_{i=1}^m (n_i + m - i)!\} / \Delta(n_1 + m - 1, \dots, n_m)$. By Lemma 15.9 we are done. \square

Problem 15G. Consider a Young tableau of shape (n, n) . Define a sequence a_k , $1 \leq k \leq 2n$, by $a_k := i$ if k is in row i of the tableau, $i = 1, 2$. Use this to show that the number of Young tableaux of this shape is the Catalan number u_{n+1} (in accordance with Theorem 15.11).

Problem 15H. How many Ferrers diagrams are there that fit in a box of size $k \times n - k$?

Problem 15I. Prove that the number of partitions of n into parts not divisible by d equals the number of partitions in which no part occurs more than $d - 1$ times.

Problem 15J. Define $P_n := \prod_{k=1}^n k!$. Prove that $P_{n-1}^2 \cdot (n^2)!$ is divisible by P_{2n-1} .

Notes.

The use of Ferrers diagrams to prove theorems such as Theorem 15.3 was introduced by Sylvester in 1853. He wrote that the proof had been communicated to him by N. M. Ferrers.

For other proofs involving Ferrers diagrams and analogues (e.g. a proof of Theorem 15.4) we refer to Hardy and Wright (1954), MacMahon (1916), and Van Lint (1974).

Euler's proof of Theorem 15.5 was by induction. Polygonal numbers occurred in ancient mathematics, e.g. triangular numbers were considered by Pythagoras before 500 BC.

Theorem 15.7 is due to Van Lint (1974).

The asymptotic behavior of the partition function $p(n)$ was given by G. H. Hardy and S. Ramanujan (1918) in the paper in which they developed the famous 'circle method' that has had so many applications in number theory. A further asymptotic result was given by H. Rademacher (1937). The proofs depend on the remarkable

functional equation for the famous Dedekind η -function

$$\eta(z) := e^{\frac{\pi iz}{12}} \prod_{n=1}^{\infty} (1 - e^{2\pi inz}).$$

For an exposition of these proofs see Chandrasekharan (1970).

C. G. J. Jacobi (1804–1851) is best known for developing the theory of elliptic functions. He became professor at Königsberg at the age of 23. Two years later he published his book *Fundamenta Nova Theoriae Functionum Ellipticarum*. In §64 we find what is now known as the triple product identity.

The first to use tableaux such as in Fig. 15.6 was Frobenius! A year later (1901) A. Young independently introduced them in his work on matrix representations of permutation groups. The name *Young tableaux* has become standard terminology.

References.

- K. Chandrasekharan (1970), *Arithmetical Functions*, Springer-Verlag.
- J. S. Frame, G. de Beauregard Robinson, and R. M. Thrall (1954), The hook graphs of S_n , *Canad. J. Math.* **6**, 316–324.
- F. Franklin (1881), Sur le développement du produit infini $(1 - x)(1 - x^2)(1 - x^3)(1 - x^4) \dots$, *Comptes Rendus Acad. Sci.* (Paris) **92**, 448–450.
- G. H. Hardy and S. Ramanujan (1918), Asymptotic formulae in combinatory analysis, *Proc. London Math. Soc.* (2) **17**, 75–115.
- G. H. Hardy and E. M. Wright (1954), *An Introduction to the Theory of Numbers*, 3d edn., Clarendon Press.
- D. Knuth (1973), *The Art of Computer Programming*, Vol. 3, Addison-Wesley .
- J. H. van Lint (1974), *Combinatorial Theory Seminar Eindhoven University of Technology*, Lecture Notes in Math. **382**, Springer-Verlag.
- P. A. MacMahon (1916), *Combinatory Analysis* Vol. II, Cambridge University Press.
- H. Rademacher (1937), On the partition function $p(n)$, *Proc. London Math. Soc.* **43**, 241–254.

- E. M. Wright (1965), An enumerative proof of an identity of Jacobi, *J. London Math. Soc.* **40**, 55–57.
- A. Young (1901), On quantitative substitutional analysis, *Proc. London Math. Soc.* **33**, 97–146.

16

(0,1)-Matrices

In the previous chapters (0,1)-matrices have turned up a number of times; and especially those with constant line-sums led to interesting problems. In this chapter we shall consider the existence problem for (0,1)-matrices with given line-sums, and try to count or estimate how many there are in the case of constant line-sums. In the first problem, the matrices are not necessarily square. If the row-sums of a matrix A are r_1, r_2, \dots, r_k , then we shall call the vector $\mathbf{r} := (r_1, r_2, \dots, r_k)$ the *row-sum* of A , and similarly for the column-sums.

We consider the problem of the existence of a (0,1)-matrix with given row-sum \mathbf{r} and column-sum \mathbf{s} . For convenience, we shall assume that the coordinates of \mathbf{r} and \mathbf{s} are nonincreasing; that is, \mathbf{r} and \mathbf{s} are *partitions* (we may allow trailing zero coordinates in partitions for the purposes of this chapter).

Given two partitions $\mathbf{r} = (r_1, r_2, \dots, r_n)$ and $\mathbf{s} = (s_1, s_2, \dots, s_m)$ of the same integer N , we say that \mathbf{r} *majorizes* \mathbf{s} when

$$r_1 + r_2 + \dots + r_k \geq s_1 + s_2 + \dots + s_k$$

for all k , interpreting r_k or s_k as 0 when k exceeds n or m , respectively. Recall that the *conjugate* of a partition \mathbf{r} is the partition \mathbf{r}^* where r_i^* is the number of j such that $r_j \geq i$.

Problem 16A. Prove the following assertion: \mathbf{r} majorizes \mathbf{s} if and only if the latter can be obtained from the former by a sequence of operations ‘pick two parts (coordinates) a and b so that $a \geq b + 2$ and replace them by $a - 1$ and $b + 1$ ’. (That is, \mathbf{s} is ‘more average’ than \mathbf{r} .) For example, $(5, 4, 1)$ majorizes $(3, 3, 3, 1)$ and the latter

can be obtained from the former in several ways with sequences of such operations, including

$$(5, 4, 1, 0) \rightarrow (5, 3, 2, 0) \rightarrow (5, 3, 1, 1) \rightarrow (4, 3, 2, 1) \rightarrow (3, 3, 3, 1)$$

and

$$(5, 4, 1, 0) \rightarrow (4, 4, 1, 1) \rightarrow (4, 3, 2, 1) \rightarrow (3, 3, 3, 1).$$

Theorem 16.1. *Let r_1, r_2, \dots, r_n and s_1, s_2, \dots, s_m be two nonincreasing sequences of nonnegative integers each summing to a common value N . There exists an $n \times m$ $(0, 1)$ -matrix with row-sum \mathbf{r} and column-sum \mathbf{s} if and only if \mathbf{r}^* majorizes \mathbf{s} .*

PROOF: To prove necessity, let k be given and consider the first k columns of a hypothetical $(0, 1)$ -matrix with row-sum \mathbf{r} and column-sum \mathbf{s} . The number of 1's in these columns is

$$s_1 + s_2 + \dots + s_k \leq \sum_{i=1}^n \min(k, r_i) = \sum_{j=1}^k r_j^*.$$

The latter equality is most evident from the Ferrers diagram of the partition \mathbf{r} (see Fig. 16.1) where we see both expressions count the number of cells in the first k columns.




Figure 16.1

We now introduce a transportation network with a source S , a sink T , one vertex x_i for each row, and one vertex y_j for each column. There is to be an edge of capacity r_i directed from S to x_i , $1 \leq i \leq n$, an edge of capacity s_j from y_j to T , $1 \leq j \leq m$, and an edge of capacity 1 from x_i to y_j , $1 \leq i \leq n$, $1 \leq j \leq m$. We claim

that a (0,1)-matrix $M = (a_{ij})$ with row-sum \mathbf{r} and column-sum \mathbf{s} exists if and only if this network admits a flow of strength N (there are at least two cuts of capacity N , so this would be a maxflow). Given such a matrix, we get a flow of strength N by saturating the edges incident with S and T and assigning flow a_{ij} to the edge from x_i to y_j . Conversely, if the network admits a flow of strength N , then there exists an *integral* flow of that strength (cf. Theorem 7.2); clearly, the edges incident with either S or T must be saturated, and on the other edges the flow must be either 0 or 1.

Consider a cut A, B in this network which separates S and T . Say A consists of S , n_0 vertices of $X := \{x_i : i = 1, \dots, n\}$, and m_0 vertices of $Y := \{y_i : i = 1, \dots, m\}$. The edges crossing from A to B include $n - n_0$ edges leaving S , m_0 edges into T , and $n_0(m - m_0)$ edges from X to Y . The capacity of this cut is at least

$$r_{n_0+1} + r_{n_0+2} + \dots + r_n + s_{m-m_0+1} + s_{m-m_0+2} + \dots + s_m + n_0(m - m_0).$$




Figure 16.2

It is again convenient to refer to the Ferrers diagram of the partition \mathbf{r} (see Fig. 16.2). The number of cells in the Ferrers diagram is N . So clearly N is at most $n_0(m - m_0)$ plus the number of cells in the last $n - n_0$ rows plus the number of cells in the last m_0 columns. The number of cells in the last m_0 columns is the sum of the last m_0 parts of the conjugate \mathbf{r}^* . But under the assumption that \mathbf{r}^* majorizes \mathbf{s} ,

$$r_{m-m_0+1}^* + r_{m-m_0+2}^* + \dots + r_m^* \leq s_{m-m_0+1} + s_{m-m_0+2} + \dots + s_m,$$

and we conclude that the capacity of any cut is at least N . By the maxflow-minicut theorem, Theorem 7.1, the required flow of strength N exists. \square

We have given the above proof in order to establish the connection between flows and $(0, 1)$ -matrices, but it is possible to give a more direct proof of sufficiency of the condition in Theorem 16.1. Our exposition is similar to that given by Krause (1996).

First suppose we have a $(0, 1)$ -matrix A_1 with row-sum \mathbf{r} and column-sum \mathbf{s}_1 , and that \mathbf{s}_2 is obtained from \mathbf{s}_1 by the operation of Problem 16A. Then we claim it is easy to construct a $(0, 1)$ -matrix A_2 with row-sum \mathbf{r} and column-sum \mathbf{s}_2 : If the parts a, b with $a \geq b + 2$ in \mathbf{s}_1 (that are replaced by $a - 1$ and $b + 1$ to obtain \mathbf{s}_2) are the sums of columns j and k , respectively, there must be a row i so that the (i, j) -entry in A_1 is 1 and the (i, k) -entry in A_1 is 0; if we interchange these two entries, we obtain a matrix A_2 as desired.

Now assume \mathbf{r}^* majorizes \mathbf{s} . Start with the matrix A_0 corresponding to the Ferrers diagram of \mathbf{r} , adding columns of 0's if necessary to obtain size $n \times m$. The column-sum of A_0 is \mathbf{r}^* . If \mathbf{r}^* majorizes \mathbf{s} , we can find a sequence of partitions

$$\mathbf{r}^* = \mathbf{s}_0, \mathbf{s}_1, \mathbf{s}_2, \dots, \mathbf{s}_\ell = \mathbf{s}$$

so that each partition in the sequence is obtained from the preceding one by the operation of Problem 16A. Then a $(0, 1)$ -matrix A with row-sum \mathbf{r} and column-sum \mathbf{s} can, by the observation of the preceding paragraph, be obtained from A_0 by a sequence of ℓ interchanges.

Example 16.1. Take $\mathbf{r} = (3, 2, 2, 2, 1)$ and $\mathbf{s} = (3, 3, 3, 1)$. Then $\mathbf{r}^* = (5, 4, 1)$, and this majorizes \mathbf{s} . The algorithm described above might give rise to the following sequence of matrices:

$$\begin{pmatrix} 1 & 1 & 1 & 0 \\ 1 & 1 & 0 & 0 \\ 1 & 1 & 0 & 0 \\ 1 & 1 & 0 & 0 \\ 1 & 0 & 0 & 0 \end{pmatrix} \rightarrow \begin{pmatrix} 1 & 1 & 1 & 0 \\ 0 & 1 & 1 & 0 \\ 1 & 1 & 0 & 0 \\ 1 & 1 & 0 & 0 \\ 1 & 0 & 0 & 0 \end{pmatrix} \rightarrow \begin{pmatrix} 1 & 1 & 1 & 0 \\ 0 & 1 & 1 & 0 \\ 0 & 1 & 1 & 0 \\ 1 & 1 & 0 & 0 \\ 1 & 0 & 0 & 0 \end{pmatrix} \rightarrow \begin{pmatrix} 1 & 0 & 1 & 1 \\ 0 & 1 & 1 & 0 \\ 0 & 1 & 1 & 0 \\ 1 & 1 & 0 & 0 \\ 1 & 0 & 0 & 0 \end{pmatrix}$$

Here the column-sum vectors are

$$(5, 4, 1, 0) \rightarrow (4, 4, 2, 0) \rightarrow (3, 4, 3, 0) \rightarrow (3, 3, 3, 1).$$

(We do not care if the vectors are not always nonincreasing.)

We extend the idea of the algorithm in the theorem below, and find a (rough) estimate for the number of $(0, 1)$ -matrices with certain line-sums as a consequence.

Theorem 16.2. *Given partitions \mathbf{r} and \mathbf{s} of an integer N , let $M(\mathbf{r}, \mathbf{s})$ denote the number of $(0, 1)$ -matrices A with row-sum \mathbf{r} and column-sum \mathbf{s} . If \mathbf{r} majorizes \mathbf{r}_0 and \mathbf{s} majorizes \mathbf{s}_0 , then*

$$M(\mathbf{r}_0, \mathbf{s}_0) \geq M(\mathbf{r}, \mathbf{s}).$$

PROOF: We will establish the following simple observation. Let us fix a row-sum vector $\mathbf{r} = (r_1, r_2, \dots, r_n)$ of length n and a column-sum vector $\mathbf{s} = (s_1, s_2, \dots, s_m)$ of length m that have equal sums. (We do not require them to be nonincreasing.) If $s_1 > s_2$, then we claim that

$$M(\mathbf{r}, (s_1 - 1, s_2 + 1, s_3, \dots, s_m)) \geq M(\mathbf{r}, (s_1, s_2, s_3, \dots, s_m)).$$

Of course, the same will hold for any two columns (we have used the first two only for notational convenience). The same idea applies to the transpose, where keeping \mathbf{s} constant and replacing r_i and r_j ($r_i > r_j$) by $r_i - 1$ and $r_j + 1$ will not decrease the number of associated $(0, 1)$ -matrices. The inequality of the theorem then follows from this observation and the result of Problem 16A.

To prove the observation, consider $(0, 1)$ -matrices A of size $n \times (m - 2)$ with column-sum (s_3, s_4, \dots, s_m) . For a given matrix A , it may or may not be possible to prepend two columns to A to get row-sum \mathbf{r} ; if it is possible, we need to add two 1's to a rows, one 1 to b rows, and no 1's to c rows, say, where $a + b + c = n$ and $2a + b = s_1 + s_2$. But the number of ways to prepend the two columns to get new column-sums s_1 and s_2 is

$$\binom{b}{s_1 - a} = \binom{b}{s_2 - a},$$

and this is at most the number

$$\binom{b}{s_1 - 1 - a} = \binom{b}{s_2 + 1 - a}$$

of ways to prepend the two columns to get new column-sums $s_1 - 1$ and $s_2 + 1$ since the latter sums are closer to $b/2$. \square

The sufficiency of the condition of Theorem 16.1 is a quick corollary of Theorem 16.2. If \mathbf{r}^* majorizes \mathbf{s} , then

$$M(\mathbf{r}, \mathbf{s}) \geq M(\mathbf{r}, \mathbf{r}^*) \geq 1.$$

Problem 16B. Prove that $M(\mathbf{r}, \mathbf{r}^*) = 1$.

We will use $A(n, k)$ to denote the number of $n \times n$ $(0, 1)$ -matrices with all line-sums equal to k .

Corollary.

$$A(n, k) \geq \left\{ \binom{n}{k} / 2^{k+1} \right\}^n.$$

PROOF: The number of $(0, 1)$ -matrices with row-sum (k, k, \dots, k) is $\binom{n}{k}^n$. Each has a column-sum $\mathbf{s} = (s_1, s_2, s_3, \dots, s_n)$ satisfying $0 \leq s_i \leq n$, $s_1 + \dots + s_n = nk$. Ignoring the restriction $s_i \leq n$, we see that by Theorem 13.1 there are at most $\binom{nk+n-1}{n-1} \leq 2^{n(k+1)}$ such column-sums. Since the greatest number of associated $(0, 1)$ -matrices occurs for column-sum (k, k, \dots, k) , the number of such matrices is at least the average number. \square

Problem 16C. Prove the following theorem.

Theorem 16.3. Let \mathbf{d} and \mathbf{d}' be two partitions of an (even) integer N . If \mathbf{d} majorizes \mathbf{d}' , then there are at least as many labeled simple graphs with degree sequence \mathbf{d}' as with degree sequence \mathbf{d} .

Problem 16D. If n is even, then

$$A\left(n, \frac{1}{2}n\right) \geq \frac{2^{n^2}}{n^{2n}}.$$

Show this by modifying the proof of the Corollary to Theorem 16.2. (Substituting $k = \frac{1}{2}n$ in the corollary would give a poor result.)

Problem 16E. Let $\mathbf{d} = (d_1, d_2, \dots, d_n)$ be a partition (possibly including 0's) of $\binom{n}{2}$. Prove that there exists a tournament on the

vertex set $1, 2, \dots, n$ (an orientation of K_n) so that vertex i has outdegree d_i for all i if and only if \mathbf{d} is majorized by

$$(n-1, n-2, \dots, 2, 1, 0).$$

Problem 16F. (i) Given an integer $m \leq \binom{n}{2}$, consider the graph with vertex set $1, 2, \dots, n$ and whose edges are the first m of the 2-subsets in lexicographical order:

$$\{1, 2\}, \{1, 3\}, \dots, \{1, n\}, \{2, 3\}, \{2, 4\}, \dots, \{2, n\}, \{3, 4\}, \dots$$

This graph has a certain degree sequence \mathbf{r} , which is a partition of $2m$. For example, when $n = 8$ and $m = 20$, $\mathbf{r} = (7, 7, 7, 5, 4, 4, 3, 3)$. Given n , $m \leq \binom{n}{2}$, and a partition \mathbf{d} (possibly including 0's) of $2m$, prove that there exists a simple graph on n vertices with degree sequence \mathbf{d} if and only if \mathbf{d} is majorized by the partition \mathbf{r} as described above.

(ii) Generalize for simple k -uniform hypergraphs (a set of points and a set of k -element subsets).

* * *

As in Chapter 11, let $\mathcal{A}(n, 2)$ denote the set of $(0, 1)$ -matrices of size n with all line-sums equal to 2. A method that we learned in Chapter 14 allows us to count the number $A(n, 2)$ of elements of $\mathcal{A}(n, 2)$.

Let $\mathcal{A}(n, 2)^*$ denote the subset of $\mathcal{A}(n, 2)$ consisting of indecomposable matrices (cf. Chapter 11). Define $a_n := |\mathcal{A}^*(n, 2)|$. It is easy to see that $a_n = \frac{1}{2}n!(n-1)!$ as follows. We have $\binom{n}{2}$ choices for the first row. If we choose $(1 \ 1 \ 0 \ \dots \ 0)$ as first row, then there is one more row (out of $n-1$) with a 1 in the first column and a second 1 not in the second column (so $n-2$ choices). This gives us $(n-1)(n-2)$ possibilities, etc.

Now define

$$m_n := A(n, 2)/(n!)^2,$$

$$b_k := a_k/(k!)^2.$$

Then by the same argument as was used in Theorem 14.2, we have

$$(16.1) \quad 1 + \sum_{n=2}^{\infty} m_n x^n = \exp \left(\sum_{k=2}^{\infty} b_k x^k \right).$$

Therefore we find

$$(16.2) \quad 1 + \sum_{n=2}^{\infty} m_n x^n = \exp \left(\frac{-x - \log(1-x)}{2} \right) = e^{-\frac{1}{2}x} (1-x)^{-\frac{1}{2}}.$$

It is an easy exercise to show that from the expansion

$$(1-x)^{-\frac{1}{2}} = \sum_{n=0}^{\infty} \binom{2n}{n} \left(\frac{x}{4}\right)^n,$$

we can conclude that

$$m_n \sim e^{-\frac{1}{2}} \binom{2n}{n} 4^{-n} \quad \text{for } n \rightarrow \infty.$$

We have thus proved the following theorem.

Theorem 16.4.

$$A(n, 2) \sim e^{-\frac{1}{2}} \frac{(2n)!}{(2!)^{2n}}.$$

This theorem is a special case of the following theorem (that we shall only prove for $k = 3$, using a method that can be applied for other values of k).

Theorem 16.5.

$$A(n, k) = \frac{(nk)!}{(k!)^{2n}} \exp \left[-\frac{(k-1)^2}{2} \right] \left\{ 1 + O \left(\frac{1}{n^{\frac{3}{4}}} \right) \right\} \quad (n \rightarrow \infty),$$

uniformly in k for $1 \leq k < \log n$.

For more information on this question and generalizations to the case where the line-sums are not constant we refer to B. D. McKay (1984).

For the case $k = 3$, we now prove a result slightly stronger than obtained by setting k to 3 above. We shall use the truncated form of the principle of inclusion and exclusion (cf. Theorem 10.1, Remark).

Consider $N := 3n$ elements, numbered

$$1_a, 1_b, 1_c, 2_a, 2_b, 2_c, \dots, n_a, n_b, n_c.$$

Form a permutation of these N elements and subsequently form the corresponding ordered partition into triples: $(x, y, z)(u, v, w) \dots$. We shall say that a *repetition* occurs if, in at least one of these triples, some number occurs more than once, as in $(5_a, 3_b, 5_c)$. Assume that the chosen permutation results in a sequence of n triples with *no* repetition. In that case, we associate an $n \times n$ $(0, 1)$ -matrix with the permutation as follows. If the i -th triple is $(x_\alpha, y_\beta, z_\gamma)$, where $\{\alpha, \beta, \gamma\} \subseteq \{a, b, c\}$, then the matrix has ones in row i in the columns numbered x, y, z , and zeros elsewhere. Since the indices a, b, c do not influence the matrix, and the order of the three elements within one triple is also irrelevant, each such matrix corresponds to $(3!)^{2n}$ different permutations. Clearly the matrix is in $\mathcal{A}(n, 3)$. We must find an estimate for the number P of permutations with no repetition among all $N_0 := N!$ permutations of the $3n$ elements.

Let $1 \leq r \leq n$. Specify r triples and count the permutations that have a repetition in these triples. Then sum this over all choices of the r triples. As in Theorem 10.1, we call this number N_r . Then if R is *even*, we have

$$(16.3) \quad \sum_{r=0}^{R+1} (-1)^r N_r \leq P \leq \sum_{r=0}^R (-1)^r N_r.$$

The difficult part of the proof is finding a suitable upper estimate and lower estimate for N_r .

We start with the upper estimate. The r triples can be chosen in $\binom{n}{r}$ ways. Within each triple we specify two positions, where we require a repetition. This can be done in 3^r ways. Now we choose r numbers that will occur in the repetitions, and the indices a, b, c . This can also be done in $\binom{n}{r} \cdot 3^r$ ways. Subsequently we distribute the chosen numbers over the chosen positions, and that can be

done in $2^r \cdot r!$ ways. Finally, we distribute the remaining $N - 2r$ numbers arbitrarily. Clearly, a permutation with a repetition of type $(5_a, 5_b, 5_c)$ has been counted more than once. So we have

(16.4)

$$\begin{aligned} N_r &\leq \binom{n}{r}^2 \cdot 3^{2r} \cdot 2^r \cdot r! \cdot (N - 2r)! \\ &\leq \frac{2^r}{r!} (3^2 \cdot n^2)^r (N - 2r)! \leq N! \frac{2^r}{r!} \left(\frac{N - 2r}{N} \right)^{-2r} \\ &\leq N! \frac{2^r}{r!} \left(1 + \frac{8r^2}{N} \right), \end{aligned}$$

if $r < \frac{1}{2}\sqrt{n}$. Here the last step is based on the power series expansion of $(1 - \frac{2r}{N})^{-2r}$, and choosing r in such a way that each term is at most half of the previous term.

For the lower estimate, we start in the same way. After the r pairs have been chosen and distributed over the chosen positions, we first complete the r triples that have a repetition, using elements with a number that differs from the two repeated numbers for each triple. This can clearly be done in more than $(N - 3r)^r$ ways. Then we distribute the remaining numbers. Some permutations that should be counted are not, i.e.

(16.5)

$$\begin{aligned} N_r &\geq \binom{n}{r}^2 \cdot 3^{2r} \cdot 2^r \cdot r! \cdot (N - 3r)^r (N - 3r)! \\ &\geq N! \frac{2^r}{r!} (3^2 \cdot n^2)^r \left[\frac{n(n-1) \dots (n-r+1)}{n^r} \right]^2 \frac{(N - 3r)^r}{N^{3r}} \\ &\geq N! \frac{2^r}{r!} \left(1 - \frac{r}{n} \right)^{2r} \left(1 - \frac{3r}{N} \right)^r \\ &\geq N! \frac{2^r}{r!} \left(1 - \frac{3r^2}{n} \right) \end{aligned}$$

if $r < \sqrt{n}$. Here in the last step, we used the well known inequality

$$\left(1 - \frac{r}{n} \right)^r \geq 1 - \frac{r^2}{n} \quad \text{if } 1 \leq r \leq \sqrt{n}.$$

We now combine (16.3), (16.4) and (16.5). We take $R = \lfloor \frac{1}{2}\sqrt{n} \rfloor$. We find

$$\frac{P}{N!} = e^{-2} + \Delta, \quad \text{where} \quad |\Delta| < \frac{2^{R+1}}{(R+1)!} + \frac{3}{n} \sum_{r=0}^{\infty} \frac{2^r r^2}{r!},$$

and hence

$$|\Delta| < \frac{48}{n} + \frac{18e^2}{n} < \frac{200}{n}.$$

We have therefore found the following estimate (in accordance with Theorem 16.5).

Theorem 16.6. *We have*

$$A(n, 3) = \frac{(3n)!}{(3!)^{2n}} e^{-2} \left(1 + O\left(\frac{1}{n}\right) \right) \quad (n \rightarrow \infty).$$

Remark. Note that for $k = 3$, we find from the Corollary to Theorem 16.2 that $A(n, 3)$ grows at least as fast as $(cn^3)^n$, for a suitable constant c , and this differs from Theorem 16.6 only in the constant.

Problem 16G. Determine $A(5, 3)$.

We now describe another connection between (16.2) and Chapter 14. Note that squaring the right-hand side of (16.2) yields the exponential generating function for the number of derangements as given in Example 14.10. This means that we should be able to show combinatorially that

$$(16.6) \quad n!d_n = \sum_{k=0}^n \binom{n}{k}^2 A_k A_{n-k},$$

where we have used A_n for $A(n, 2)$.

As a preparation, consider an indecomposable component of an element of $\mathcal{A}(n, 2)$, for example the following 5×5 submatrix for the case $n = 9$:

	1	3	4	5	9
1	1	1	0	0	0
2	1	0	1	0	0
3	0	1	0	0	1
7	0	0	1	1	0
9	0	0	0	1	1

Starting with the two 1's in the top row, there are two ways to describe the cyclic structure:

$$(1, 3), (3, 9), (9, 5), (5, 4), (4, 1)$$

corresponding to the permutation $(1\ 3\ 9\ 7\ 2)$ of the rows and

$$(3, 1), (1, 4), (4, 5), (5, 9), (9, 3)$$

corresponding to the reversed permutation $(1\ 2\ 7\ 9\ 3)$.

The first case $(1 < 3)$ we call the *red* variety, the second the *blue* variety.

Consider the set S consisting of elements of $\mathcal{A}(n, 2)$ with the 1's colored red or blue in such a way that in an indecomposable component all 1's have the same color. Clearly

$$|S| = \sum_{k=0}^n \binom{n}{k}^2 A_k A_{n-k}.$$

We define a one-to-one mapping from S to the set of pairs of permutations $(a_1, a_2, \dots, a_n), (b_1, b_2, \dots, b_n)$ of $1, 2, \dots, n$ in which the first is a derangement. There are $n!d_n$ such pairs. We do this by example.

Let

$$a := (a_1, a_2, \dots, a_9) = (2, 7, 1, 8, 4, 5, 9, 6, 3),$$

$$b := (b_1, b_2, \dots, b_9) = (3, 1, 4, 5, 9, 2, 6, 8, 7).$$

The canonical cycle decomposition of a is $(1\ 2\ 7\ 9\ 3)(4\ 8\ 6\ 5)$. We split b accordingly into $(3\ 1\ 4\ 5\ 9)$ and $(2\ 6\ 8\ 7)$. The first pair describes the 5×5 blue submatrix treated above; the second describes a red 4×4 submatrix.

This establishes (16.6).

The following problem gives one more relation with Chapter 14.

Problem 16H. Again let $A_n := A(n, 2)$. Consider a matrix in $\mathcal{A}(n, 2)$. There are $\binom{n}{2}$ ways to choose the two 1's in row 1. Suppose these are in the first two columns. Possibly some other row also has

two 1's in the first two columns. Now, consider the other possibility and show that

$$(16.7) \quad A_n = \frac{n(n-1)}{2}(2A_{n-1} + (n-1)A_{n-2}).$$

Problem 16I. Let $f(x)$ be the function defined by the left-hand side of (16.1). From (16.7) derive the differential equation

$$2(1-x)f' - xf = 0$$

and give a second proof of (16.2).

Notes.

Theorem 16.1 is due to D. Gale (1957) and to H. J. Ryser (1957). For a more extensive treatment of the classes of (0,1)-matrices that we have considered, we refer to Ryser (1963).

The relation between (16.2) and the generating function for derangements was pointed out to us by D. G. E. D. Rogers. The proof of (16.6) is due to P. Diaconis and D. E. Knuth (private communication).

The relation (16.7) was announced without proof by R. Bricard (1901).

References.

- R. Bricard (1901), Problème de combinaisons, *L'Intermédiaire des Mathématiciens* **8**, 312–313.
- D. Gale (1957), A theorem on flows in networks, *Pacific J. Math.* **7**, 1073–1082.
- M. Krause (1996), A simple proof of the Gale-Ryser theorem, *Amer. Math. Monthly* **103**, 335–337.
- B. D. McKay (1984), Asymptotics for (0,1)-matrices with prescribed line sums, in: *Enumeration and Design* (D. M. Jackson and S. A. Vanstone, eds.), Academic Press.
- H. J. Ryser (1957), Combinatorial properties of matrices of zeros and ones, *Canad. J. Math.* **9**, 371–377.
- H. J. Ryser (1963), *Combinatorial Mathematics*, Carus Math. Monograph **14**.

17

Latin squares

A *Latin square of order n* is a quadruple $(R, C, S; L)$ where R , C , and S are sets of cardinality n and L is a mapping $L : R \times C \rightarrow S$ such that for any $i \in R$ and $x \in S$, the equation

$$L(i, j) = x$$

has a unique solution $j \in C$, and for any $j \in C$, $x \in S$, the same equation has a unique solution $i \in R$. That is, any two of $i \in R$, $j \in C$, $x \in S$ uniquely determine the third so that $L(i, j) = x$. Elements of R are called *rows*, elements of C are called *columns*, and elements of S are called the *symbols* or *entries* of the Latin square. A Latin square is usually written as an $n \times n$ array for which the cell in row i and column j contains the symbol $L(i, j)$. In Fig. 17.1 we have an example of a Latin square of order 5.

a	b	c	d	e
b	a	e	c	d
c	d	b	e	a
d	e	a	b	c
e	c	d	a	b

Figure 17.1

The terminology ‘Latin square’ originated with Euler who used a set of Latin letters for S .

A *quasigroup* is a Latin square $(X, X, X; \circ)$ with a common row, column, and symbol set X . Here we abbreviate the quadruple and simply denote the quasigroup by (X, \circ) . The mapping \circ is now a binary operation on X and the image of (x, y) under \circ is denoted

by $x \circ y$. So as a special case, we obtain Latin squares that are the multiplication tables of groups.

Problem 17A. If we fix the first two rows in Fig. 17.1, then there are many ways to fill in the remaining three rows to obtain a Latin square (in fact 24 ways). Show that none of these Latin squares is the multiplication table of a group.

Note that if $(R, C, S; L)$ is a Latin square and the mappings $\sigma : R \rightarrow R'$, $\tau : C \rightarrow C'$, $\pi : S \rightarrow S'$ are bijections, and if we define $L'(\sigma(i), \tau(j)) := \pi(L(i, j))$, then $(R', C', S'; L')$ is a Latin square. The two Latin squares are called *equivalent*. So with this notion of equivalence, we may assume that a Latin square of order n on the set $S := \{1, 2, \dots, n\}$ has the integers from 1 to n in that order as its first row and as its first column. Note that two Latin squares that are normalized in this way and different, can still be equivalent.

Sometimes we denote a Latin square as just ' $L : R \times C \rightarrow S$ '.

An *orthogonal array* $OA(n, 3)$ of order n and depth 3 is a 3 by n^2 array with the integers 1 to n as entries, such that for any two rows of the array, the n^2 vertical pairs occurring in these rows are different. Suppose that we have such an array. Call the rows \mathbf{r} , \mathbf{c} , and \mathbf{s} , in any order. For any pair (i, j) , there is a k such that $r_k = i$, $c_k = j$. We make a square with entry s_k in the i -th row and j -th column (for all i, j). The definition of orthogonal array ensures that this is a Latin square and we can reverse the procedure. Therefore the concepts of Latin square and orthogonal array are equivalent. Fig. 17.2 shows an $OA(4, 3)$ and two corresponding Latin squares.

Two Latin squares for which the corresponding orthogonal arrays have the same three rows (possibly in different order) are called *conjugates*. For example, one of the conjugates of a Latin square (with $R = C$) is its transpose. As an exercise the reader should write out the six conjugates of the Latin square in Fig. 17.2. Two orthogonal arrays are called *isomorphic* if one can be obtained from the other by permutations of the elements in each of the rows and permutations of the rows and columns of the array. Two Latin squares for which the corresponding orthogonal arrays are isomorphic are also called *isomorphic*. This means that one is equivalent to a conjugate of the other.




Figure 17.2

Problem 17B. Consider the two Latin squares obtained from Fig. 17.3 by setting $a = 1, b = 2$, respectively $a = 2, b = 1$.

1	2	3	4	5
2	1	4	5	3
3	5	a	b	4
4	3	5	a	b
5	4	b	3	a

Figure 17.3

Show that these two squares are equivalent. Show that a square that is not equivalent to these corresponds to the cyclic group of order 5.

One can also interpret a Latin square as a three-dimensional array of 0's and 1's with exactly one 1 in each line of the array that is parallel to one of the sides. For example, in Fig. 17.3 the entry 4 in row 2 and column 3 should then be interpreted as an entry 1 in position $(2, 3, 4)$ of the array.

In a later chapter we shall consider orthogonal arrays with depth greater than 3. These are often much more difficult to construct than the arrays $OA(n, 3)$.

Problem 17C. Construct an $OA(4, 4)$, i.e. a 4 by 16 matrix A with entries 1,2,3,4, such that for any two rows of A , say row i and row j , the 16 pairs $(a_{ik}, a_{jk}), 1 \leq k \leq 16$, are all different.

A *sub-Latin square* (or *subsquare*) of a Latin square $(R, C, S; L)$ is a Latin square $(R_1, C_1, S_1; L_1)$ with $R_1 \subseteq R$, $C_1 \subseteq C$, $S_1 \subseteq S$, and $L_1(i, j) = L(i, j)$ for $(i, j) \in R_1 \times C_1$.

Problem 17D. Let m and n be positive integers, $m < n$. Show that $m \leq \frac{1}{2}n$ is a necessary and sufficient condition for the existence of a Latin square of order n containing a subsquare of order m .

The following problems are all of a similar nature. They concern a problem similar to the situation of Problems 17B and 17D, namely the completion of a square that has been partly filled. An $n \times n$ array A with cells which are either empty or contain exactly one symbol is called a *partial* Latin square if no symbol occurs more than once in any row or column. (It might be better to say that the array ‘has the Latin property’, but we will use the former terminology.) We are interested in conditions that ensure that a partial Latin square can be *completed* to a Latin square of order n , i.e. when the empty cells can be filled with symbols so that a Latin square is obtained. For example, if A is a partial Latin square with filled (i.e. nonempty) cells everywhere except in the last row, there is clearly a unique way to complete A to a Latin square. On the other hand, the two partial Latin squares of Fig. 17.4 are clearly not completable.

1	2	3	4	
				5

1				
	1			
		1		
			1	
				2

Figure 17.4

To a partial Latin square we can associate an array in the same way that we did for Latin squares by only considering filled cells. This allows us to define the conjugate of a partial Latin square. The two partial Latin squares in Fig. 17.4 are not really essentially different but are conjugates, as is evident from their ‘partial

$OA(5, 3)$'s' shown below:

$$\begin{array}{l} \text{rows} \\ \text{columns} \\ \text{symbols} \end{array} \quad \begin{pmatrix} 1 & 1 & 1 & 1 & 2 \\ 1 & 2 & 3 & 4 & 5 \\ 1 & 2 & 3 & 4 & 5 \end{pmatrix} \quad \begin{pmatrix} 1 & 2 & 3 & 4 & 5 \\ 1 & 2 & 3 & 4 & 5 \\ 1 & 1 & 1 & 1 & 2 \end{pmatrix}$$

If the first k rows of a partial Latin square ($k \leq n$) are filled and the remaining cells are empty, then A is called a $k \times n$ Latin rectangle.

Theorem 17.1. *A $k \times n$ Latin rectangle, $k < n$, can be extended to a $k + 1 \times n$ Latin rectangle (and hence it can be completed).*

PROOF: Let B_j denote the set of positive integers that do *not* occur in column j of A . Each of the numbers 1 to n occurs k times in A and therefore $n - k$ times in the sets B_j . Any l of the sets B_j together contain $l(n - k)$ elements, and therefore at least l different ones. So the sets B_j , $1 \leq j \leq n$, have property H of Chapter 5, and by Theorem 5.1 they therefore have an SDR. This SDR can be adjoined as the $(k + 1)$ -st row of the Latin rectangle. \square

We denote by $L(n)$ the total number of different Latin squares of order n . The exact value of $L(n)$ is known only for $n \leq 9$. The numbers grow very rapidly, e.g. although there are only two inequivalent Latin squares of order 5, there are $5! \cdot 4! \cdot 56$ different ones.

Theorem 17.2. $L(n) \geq (n!)^{2n}/n^{n^2}$.

PROOF: To construct a Latin square of order n , we can take any permutation of 1 to n as the first row. If we have constructed a Latin rectangle with k rows, then by the proof of Theorem 17.1, the number of choices for the next row is per B where $b_{ij} = 1$ if $i \in B_j$. By Theorem 12.8 (the Van der Waerden conjecture) this permanent is at least $(n - k)^n \cdot n!/n^n$. So we find

$$(17.1) \quad L(n) \geq n! \prod_{k=1}^{n-1} \{(n - k)^n n!/n^n\} = (n!)^{2n}/n^{n^2}.$$

\square

Remark. If we had applied Theorem 5.3, we would have found the estimate $L(n) \geq n!(n-1)! \cdots 1!$ (H. J. Ryser, 1969), which is better for small n but asymptotically much smaller than (17.1).

For $n = 8$, the estimate (17.1) is less than 10^{-4} times the true value but asymptotically (17.1) is best possible as the next theorem shows.

Theorem 17.3. *If we define $\mathcal{L}(n) := \{L(n)\}^{1/n^2}$, then*

$$\mathcal{L}(n) \sim e^{-2}n \quad \text{for } n \rightarrow \infty.$$

PROOF: From (17.1) and Stirling's formula we find $n^{-1}\mathcal{L}(n) \geq e^{-2}$. By the same argument as in the proof of Theorem 17.2, and by estimating per B using Theorem 11.5, we find

$$L(n) \leq \prod_{k=1}^n M(n, k) \leq \prod_{k=1}^n (k!)^{n/k}.$$

Hence, again using Stirling's formula with C some constant $> \sqrt{2\pi}$, we have

$$\begin{aligned} \log \mathcal{L}(n) &\leq \frac{1}{n} \sum_{k=1}^n \frac{1}{k} \log k! \\ &\leq \frac{1}{n} \sum_{k=1}^n \left\{ \log k - 1 + \frac{1}{2k} \log k + \frac{1}{k} \log C \right\} \\ &= \frac{1}{n} \sum_{k=1}^n \log k - 1 + o(1) \\ &= -2 + \log n + o(1) \text{ for } n \rightarrow \infty. \end{aligned}$$

Combining this with the lower bound, we find the result. \square

The following theorem due to H. J. Ryser (1951) is a generalization of Problem 17D.

Theorem 17.4. *Let A be a partial Latin square of order n in which cell (i, j) is filled if and only if $i \leq r$ and $j \leq s$. Then A can*

be completed if and only if $N(i) \geq r + s - n$ for $i = 1, \dots, n$, where $N(i)$ denotes the number of elements of A that are equal to i .

PROOF: First, observe that in a Latin square of order n , the first r rows contain exactly r elements equal to i of which at most $n - s$ are in the last $n - s$ columns. So the condition on $N(i)$ is trivially necessary. We show that the condition is also sufficient. Let B be the $(0, 1)$ -matrix of size $r \times n$ with $b_{ij} = 1$ if and only if the element j does not occur in row i of A . Clearly every row of B has sum $n - s$. The j -th column of B has sum $r - N(j) \leq n - s$. By Theorem 7.5 (with $d := n - s$) we have

$$B = L^{(s+1)} + \dots + L^{(n)}$$

where each $L^{(t)}$ is an $r \times n$ $(0, 1)$ -matrix with one 1 in each row and at most one 1 in each column.

As an example, suppose $r = s = 4$, $n = 7$, and the first four rows of A are

1	2	3	4			
5	3	1	6			
3	1	5	2			
7	4	2	5			

Then e.g.

$$B := \begin{pmatrix} 0 & 0 & 0 & 0 & 1 & 1 & 1 \\ 0 & 1 & 0 & 1 & 0 & 0 & 1 \\ 0 & 0 & 0 & 1 & 0 & 1 & 1 \\ 1 & 0 & 1 & 0 & 0 & 1 & 0 \end{pmatrix} = L^{(5)} + L^{(6)} + L^{(7)} = \begin{pmatrix} 0 & 0 & 0 & 0 & 0 & 0 & 1 \\ 0 & 0 & 0 & 1 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 & 0 & 1 & 0 \\ 1 & 0 & 0 & 0 & 0 & 0 & 0 \end{pmatrix} + \begin{pmatrix} 0 & 0 & 0 & 0 & 0 & 1 & 0 \\ 0 & 0 & 0 & 0 & 0 & 0 & 1 \\ 0 & 0 & 0 & 1 & 0 & 0 & 0 \\ 0 & 0 & 1 & 0 & 0 & 0 & 0 \end{pmatrix} + \begin{pmatrix} 0 & 0 & 0 & 0 & 1 & 0 & 0 \\ 0 & 1 & 0 & 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 & 0 & 0 & 1 \\ 0 & 0 & 0 & 0 & 0 & 1 & 0 \end{pmatrix}.$$

Say $L^{(t)} = [l_{ij}^{(t)}]$. Then we fill the cell in position (i, j) of A , $i = 1, \dots, r$, $j = s + 1, \dots, n$, by k if $l_{ik}^{(j)} = 1$. In our example, we would fill in the last three columns with

7	,	6	,	5
4		7		2
6		4		7
1		3		6

Thus A is changed into a partial Latin square of order n with r complete rows, i.e. a Latin rectangle. By Theorem 17.1 this can be completed to a Latin square of order n . \square

The examples of partial Latin squares that cannot be completed that were given in Fig. 17.4 both have n filled cells. The conjecture that a partial Latin square with less than n filled cells is completable to a Latin square was known as the *Evans conjecture* until it was finally proved by B. Smetaniuk (1981). Perhaps the most important part of Smetaniuk's proof is the construction of Theorem 17.5.

Theorem 17.5. *Let A be a Latin square of order n . Let B be an $(n+1) \times (n+1)$ array whose (i, j) -entry is the (i, j) -entry of A for $i, j \geq 1, i+j \leq n+1$, which has a new symbol α on the back-diagonal, and whose cells below the back-diagonal are empty. Then B can be completed to a Latin square of order $n+1$.*

An example of a Latin square A of order 5 and the corresponding array B are shown below.

1	2	3	4	5
4	3	5	1	2
2	5	1	3	4
5	1	4	2	3
3	4	2	5	1

1	2	3	4	5	α
4	3	5	1	α	
2	5	1	α		
5	1	α			
3	α				
α					

PROOF: Let C be the $n \times n$ array obtained from B by dropping the last row and column. In our example, C is the array below.

1	2	3	4	5
4	3	5	1	α
2	5	1	α	
5	1	α		
3	α			

We describe an algorithm that fills in the empty cells of C row by row subject to the constraint that after the first r rows are filled in, we will have $r \times n$ a Latin rectangle on $n+1$ symbols

$1, 2, \dots, n, \alpha$ so that the j -th column contains the same symbols, in some order, as there were in the first r rows of A , except for one so-called ‘missing’ symbol in each of the columns containing x , and such that the $r - 1$ missing symbols are all distinct. This is trivial for $r = 1$ and $r = 2$. Assume this has been done for some r , $2 \leq r < n$ and that the missing symbols at this point are

$$x_{n-r+2}, x_{n-r+3}, \dots, x_n.$$

To fill in the $(r + 1)$ -st row, we proceed as follows.

Let the last r symbols in row $r + 1$ of A (that have been removed in constructing C) be

$$y_{n-r+1}, y_{n-r+2}, y_{n-r+3}, \dots, y_n.$$

Here y_{n-r+1} is the symbol displaced by α and must be the new missing element in that column. We may consider filling in row $r + 1$ with

$$y_{n-r+2}, y_{n-r+3}, \dots, y_n,$$

and this is satisfactory if

$$y_{n-r+1}, x_{n-r+2}, x_{n-r+3}, \dots, x_n$$

(which would be the new missing symbols) are distinct. If not, consider the sequence

$$\begin{aligned} y_{n-r+1} &= x_{k_1} \\ y_{k_1} &= x_{k_2} \\ &\vdots \\ y_{k_{m-1}} &= x_{k_m} \end{aligned}$$

extended as far as it can go, i.e. so that y_{k_m} is not equal to any of the x_j 's. We then fill in row $r + 1$ with $y_{n-r+2}, y_{n-r+3}, \dots, y_n$ except that $y_{k_1}, y_{k_2}, \dots, y_{k_m}$ are omitted and replaced, respectively, by $x_{k_1}, x_{k_2}, \dots, x_{k_m}$. It must be checked that the entire row $r + 1$ contains distinct symbols. The new missing symbols will be y_{n-r+1} and $x_{n-r+2}, x_{n-r+3}, \dots, x_n$ except that $x_{k_1}, x_{k_2}, \dots, x_{k_m}$ are omitted

and replaced, respectively, by $y_{k_1}, y_{k_2}, \dots, y_{k_m}$. It must be checked that these are distinct.

Once the empty cells of C are filled, the first n cells of the last row of B are to be filled with x and the missing symbols (when $r = n$). We now have an $(n+1) \times n$ Latin rectangle, which completes uniquely to a Latin square of order $n+1$. \square

Problem 17E. Let A denote the Latin square of order 10 on the left below, and let C be the partial 10 by 10 Latin rectangle on the 11 symbols $0, 1, 2, \dots, 9, \alpha$ on the right (not including the last row and column). Use the algorithm of the proof of Theorem 17.5 to complete C to a 10 by 10 Latin rectangle on the symbols $0, 1, 2, \dots, 9, \alpha$. Then complete this Latin rectangle to a Latin square of order 11.

4	1	3	5	9	6	0	2	8	7
5	8	9	2	6	7	3	4	1	0
9	4	5	6	0	3	7	8	2	1
1	3	4	7	5	2	8	9	0	6
2	6	1	3	7	4	5	0	9	8
7	9	0	1	4	8	2	3	6	5
6	7	8	9	1	0	4	5	3	2
8	5	6	0	2	9	1	7	4	3
3	0	2	4	8	5	6	1	7	9
0	2	7	8	3	1	9	6	5	4

4	1	3	5	9	6	0	2	8	7	α
5	8	9	2	6	7	3	4	1	α	
9	4	5	6	0	3	7	8	α		
1	3	4	7	5	2	8	α			
2	6	1	3	7	4	α				
7	9	0	1	4	α					
6	7	8	9	α						
8	5	6	α							
3	0	α								
0	α									
α										

(For example, the algorithm fills in the first five rows of C as indicated on the right below. The elements ‘missing’ from the seventh through tenth columns at this point are, respectively, 5, 9, 2, 0. Now consider the sixth row. The α in column six forces 8 to be the missing element from column six. But 8 is distinct from the elements currently missing from the other columns. So there is nothing more to do; we just fill in row six with the entries 2, 3, 6, 5 from the sixth row of A .)

4	1	3	5	9	6	0	2	8	7
5	8	9	2	6	7	3	4	1	0
9	4	5	6	0	3	7	8	2	1
1	3	4	7	5	2	8	9	0	6
2	6	1	3	7	4	5	0	9	8
7	9	0	1	4	8	2	3	6	5

4	1	3	5	9	6	0	2	8	7
5	8	9	2	6	7	3	4	1	α
9	4	5	6	0	3	7	8	α	1
1	3	4	7	5	2	8	α	0	6
2	6	1	3	7	4	α	0	9	8
7	9	0	1	4	α				

Problem 17F.

(i) Let A and B be Latin squares of order n on symbols $1, 2, \dots, n$. Let A' and B' be the Latin squares on symbols $1, 2, \dots, n+1$ (with $n+1$'s on their back diagonals) that agree with A and B , respectively, above their back diagonals as constructed in the proof of Theorem 17.5. Show that if A and B are distinct, then A' and B' are distinct. This proves that the number of Latin squares of order $n+1$ with $n+1$ on the back diagonal is greater than or equal to the number $N(n)$ of Latin squares of order n .

(ii) Explain how part (i) leads to the result

$$L(n) \geq n!(n-1)! \cdots 2!1!$$

mentioned in the Remark following Theorem 17.2.

Theorem 17.6. *A partial Latin square of order n with at most $n-1$ filled cells can be completed to a Latin square of order n .*

PROOF: The theorem will be proved by induction. Assume it holds for n and let L be a partial Latin square of order $n+1$ with at most n filled cells.

First, suppose there is a symbol x of L that occurs only once in L . We propose to permute rows and columns to move the filled cells above the back-diagonal, except that the single symbol x will be on the back diagonal. Say that the rows with filled cells have f_1, f_2, \dots, f_k filled cells, where $f_1 + \dots + f_k \leq n$, and where x is in the row with f_1 filled cells. Put the row with f_1 filled cells in position $n+1-f_1$; permute columns to push the filled cells to the left. Put the row with f_2 filled cells in position $n+1-f_1-f_2$; permute columns, other than the first f_1 , to move the filled cells to the left; the first f_1+f_2 cells in that row will contain the filled cells. Put the row with f_3 filled cells in position $n+1-f_1-f_2-f_3$,

etc., and continue until all filled cells are above the back-diagonal. Then, if the cell containing x in row $n + 1 - f_1$ is in column j , interchange column j and column $f_1 + 1$.

By the induction hypothesis, the part *above* the back diagonal, which has at most $n - 1$ filled cells, can be completed to a Latin square A of order n based on symbols other than x . The array B as described in the statement of Theorem 17.5 contains the original filled cells of a partial Latin square that differs from L only by row and column permutations. The theorem says that B can be completed, and hence so can L .

At this point we can also assert that L can be completed if there is a row that contains exactly one filled cell, or a column that contains exactly one filled cell, because a conjugate of L will have the property that some symbol appears exactly once (for example, every row of the partial square on the right of Fig 17.4 contains exactly one filled cell, and its conjugate on the left has the property that every symbol occurs exactly once) and a conjugate of L can be completed if and only if L can be completed.

So we may now assume that no row or column contains exactly one filled cell. Thus the filled cells are contained in at most m rows and m columns, where $m := \lfloor n/2 \rfloor$. We may permute rows and columns so that all filled cells lie in the upper left subarray of order m . Theorem 17.4 implies that every $m \times m$ Latin rectangle can be completed to a Latin square of order $n + 1$. So it will suffice to fill in the unfilled cells of the the upper left subarray of order m to get a Latin rectangle. But this is easy, as we have $n + 1$ symbols available and we may proceed in any order, filling in a cell of the subsquare with a symbol not yet used in the row or column containing the cell. \square

We now come to a generalization of the idea of a Latin square. Suppose we are given a collection \mathcal{C} of n -sets $C(i, j)$, $i, j = 1, 2, \dots, n$. One can ask the question whether there exists a matrix A of size $n \times n$ in which in each row, respectively column, all the entries a_{ij} are different and for which $a_{ij} \in C(i, j)$ for all i and j . If all the n -sets are $\{1, 2, \dots, n\}$, the answer is yes since any Latin square is a solution. If the elements of \mathcal{C} are pairwise disjoint, the question is trivial. It is perhaps surprising that the increased freedom of not

requiring the n -sets to be the same makes the question harder. In fact, an analog of Theorem 17.1 does not hold in this case. Until it was proved by F. Galvin (1995), the conjecture that such a matrix A indeed exists was known as the *Dinitz conjecture*.

We shall use the terminology of colorings of graphs (a problem treated extensively in Chapter 33). Let G be a simple graph. A *list assignment* of G is a function C that assigns a set $C(v)$ to each vertex v of G . A C -coloring of G is a function A defined on the vertex set such that $A(v) \in C(v)$ and such that $A(v)$ and $A(w)$ are different if v and w are adjacent in G .

Let f be a function from the vertex set of G to the integers. We say that G is f -colorable if a C -coloring of G exists for every C with the property $|C(v)| \geq f(v)$ for all $v \in G$. If k is an integer, a graph is called k -list-colorable if G is f -colorable for the constant function $f(v) = k$. Clearly, if G is k -list-colorable, then k is at least the chromatic number $\chi(G)$, defined in Chapter 3.

The *line graph* $L = L(G)$ of a simple graph G is the simple graph with vertex set $V(L) := E(G)$ and where $a, b \in E(G)$ are adjacent as vertices of L if and only if, as edges in G , a and b have a common incident vertex. Now, consider the line graph $L_2(n)$ of $K_{n,n}$ (see Chapter 21). It has n^2 vertices $\{i, j\}$, $i, j = 1, 2, \dots, n$, where pairs are joined if and only if they have an element in common. The Dinitz conjecture can be formulated as follows: $L_2(n)$ is n -list-colorable. The theorem proved by Galvin states that for a bipartite graph G , the line graph $L = L(G)$ is $\chi(L)$ -list-colorable. Since Latin squares exist, $L_2(n)$ has chromatic number n and the Dinitz conjecture is therefore true.

We shall prove two propositions from which the theorem will follow.

A subset K of the vertex set of a digraph D is called a *kernel* of D if no two vertices of K are joined by an edge and for every $v \notin K$ there is a $w \in K$ such that there is an edge in D from v to w .

Proposition 17.7. *Let D be a digraph for which every induced subgraph has a kernel. Let $f(v) := 1 + \text{outdegree}(v)$ for every vertex v of D . Then D is f -colorable.*

PROOF: We use induction on the number of vertices. Small cases are easily checked. (Note that the only digraph on three vertices for which the condition and the assertion of the problem do not hold is the directed circuit.)

Let C be a list assignment of D with $|C(v)| \geq f(v)$ for all v . Pick an element x from one of the sets in C and consider all vertices v such that $x \in C(v)$. We call the induced subgraph on these vertices D_1 . By our assumption, D_1 has a kernel K . Let D_2 be the induced subgraph on the vertices in $D \setminus K$. For a vertex $v \notin K$ define $C'(v) := C(v) \setminus \{x\}$. By the induction hypothesis D_2 has a C' -coloring A' . If we define A on D by

$$A(v) := \begin{cases} A'(v) & \text{if } v \notin K, \\ x & \text{if } v \in K, \end{cases}$$

then A is clearly a C -coloring of D . □

For the next proposition we define an orientation of a graph G to be *normal* if every clique in G is a transitive tournament.

Proposition 17.8. *Every normal orientation of the line graph $L = L(G)$ of a bipartite graph G has a kernel.*

PROOF: We use induction on the number of edges of G . For small numbers, the statement is easily checked. Suppose $V(G) = X \cup Y$ (and all edges between X and Y). We may assume that every vertex of G has a positive degree. Let D be a normal orientation of $L(G)$. The cliques in $L(G)$ correspond to vertices in X or in Y .

For every vertex $x \in X$, we consider the corresponding clique in $L(G)$ and define $e(x) := \{x, y(x)\}$ to be the sink of this clique (with respect to D). First, assume that for every $x \in X$, this vertex $e(x)$ of $L(G)$ is the source of the clique defined by $y(x) \in Y$. It is then obvious that all the $y(x)$ for $x \in X$ are distinct. Therefore $K := \{\{x, y(x)\} : x \in X\}$ is a kernel of $L(G)$.

Next, assume that for some $x \in X$, $e(x) := \{x, y(x)\}$ is the sink of the clique corresponding to x but that $e' := \{x', y(x)\}$, where $x' \neq x$, is the source of the clique corresponding to $y(x)$. Remove the edge $\{x', y(x)\}$ from G . The resulting line graph has a kernel K by the induction hypothesis. We claim that K is also a kernel for

D. We have to show that there is an edge from e' to K . If $e(x) \in K$ we are done (because e' is a source). However, if $e(x) \notin K$, then there is an edge from $e(x)$ to some element in K , which must be of type $\{x'', y(x)\}$ by definition of $e(x)$. Because the tournament defined by $y(x)$ is transitive, we are again done. \square

We can now prove the main result.

Theorem 17.9. *If G is a bipartite graph, then $L = L(G)$ is $\chi(L)$ -colorable.*

PROOF: Let G be a bipartite graph on the vertex set $X \cup Y$. Let g be a coloring of the vertices of $L = L(G)$ with colors $1, 2, \dots, \chi(L)$. We orient L to form a digraph D as follows: if $e_1 = \{x_1, y_1\}$ and $e_2 = \{x_2, y_2\}$ are adjacent vertices of L and $g(e_1) < g(e_2)$, then

$$\begin{cases} \text{the edge is from } e_1 \text{ to } e_2 \text{ if } x_1 = x_2, \\ \text{the edge is from } e_2 \text{ to } e_1 \text{ if } y_1 = y_2. \end{cases}$$

Since every clique in L corresponds to a vertex $x \in X$ or $y \in Y$, this orientation is normal. By Proposition 17.8 every induced subgraph of D has a kernel. Clearly, $1 + \text{outdegree}(e) \leq \chi(L)$ for every vertex $e \in D$. So, by Proposition 17.7 the proof is complete. \square

Problem 17G.

(a) Let n be even. Find a permutation x_1, x_2, \dots, x_n of the elements of \mathbb{Z}_n such that the differences $x_{i+1} - x_i$, $1 \leq i < n$, are all different.

(b) Show that this is not possible if n is odd.

(c) Consider the permutation of (a). Define $a_{ij} := x_i + x_j$. Show that the square with entries a_{ij} , $1 \leq i, j \leq n$, is a Latin square that has the following property: The $n(n-1)$ adjacent pairs $(a_{ij}, a_{i,j+1})$ are different. Such a square is called *row-complete*. This square is also column-complete.

Problem 17H. Describe a one-to-one correspondence between symmetric Latin squares of order n in which all symbols appear on the main diagonal and symmetric Latin squares of order $n+1$ with all $(n+1)$'s on the diagonal.

Problem 17I. Let $1, 2, \dots, n$ be the first row of a Latin square and $2, 3, \dots, n, 1$ the second row. How many candidates are there for the third row?

Problem 17J. Let $1, 2, \dots, 2n - 1, 2n$ be the first row of a Latin square of order $2n$. Let $2, 1, 4, 3, \dots, 2n, 2n - 1$ be the second row.
(i) Find a formula for the number of candidates for the third row.
(ii) Give a permanent that has this number as value.

Notes.

Although Latin squares have been studied for more than 200 years, much of the material in this chapter is recent. Theorem 17.1 is the oldest; it is due to M. Hall, Jr. (1945).

Theorem 17.2 and the remark following it can be found in H. J. Ryser (1969). At the time that paper was written, the Van der Waerden conjecture was still open.

Theorem 17.3 is new.

Theorem 17.4 is again due to H. J. Ryser (1951).

The so-called Evans conjecture occurs as a question (not as a conjecture) in a paper by T. Evans (1960). Before the proof by B. Smetaniuk appeared, several partial results were published.

Our treatment of the Galvin proof of the Dinitz conjecture is based on some unpublished notes of D. Hoffman.

The most extensive treatment of Latin squares can be found in the book *Latin Squares* by J. Dénes and A. D. Keedwell (1991).

References.

- J. Dénes and A. D. Keedwell (1991), *Latin squares. New developments in the theory and applications.*, Annals of Discrete Mathematics **46**, North-Holland.
- T. Evans (1960), Embedding incomplete Latin squares, *Amer. Math. Monthly* **67**, 958–961.
- F. Galvin (1995), The list chromatic index of a bipartite multi-graph, *J. Combin. Theory Ser. B* **63**, 153–158.
- M. Hall, Jr. (1945), An existence theorem for Latin squares, *Bull. Amer. Math. Soc.* **51**, 387–388.
- H. J. Ryser (1951), A combinatorial theorem with an application to Latin rectangles, *Proc. Amer. Math. Soc.* **2**, 550–552.

- H. J. Ryser (1969), Permanents and systems of distinct representatives, in: *Combinatorial Mathematics and its Applications*, University of North Carolina Press.
- B. Smetaniuk (1981), A new construction on Latin squares I: A proof of the Evans conjecture, *Ars Combinatoria* **11**, 155–172.

18

Hadamard matrices, Reed–Muller codes

Hadamard considered the following question. Let A be an $n \times n$ matrix with real entries of absolute value at most 1. How large can the determinant of A be (in absolute value)? Since each row of A is a vector with length $\leq \sqrt{n}$, the determinant cannot be larger than $n^{n/2}$. (The absolute value of the determinant is the n -dimensional volume of the parallelepiped spanned by the row vectors in Euclidean n -space.) Can equality hold? In that case all entries must be $+1$ or -1 and furthermore any two rows must be orthogonal, i.e. they have inner product 0. This leads to the following definition.

A *Hadamard matrix* of order n is an $n \times n$ matrix H with entries $+1$ and -1 , such that

$$(18.1) \quad HH^\top = nI.$$

Of course, any two columns of H are also orthogonal. This property does not change if we permute rows or columns or if we multiply some rows or columns by -1 . Two such Hadamard matrices are called equivalent. For a given Hadamard matrix, we can find an equivalent one for which the first row and the first column consist entirely of $+1$'s. Such a Hadamard matrix is called *normalized*. Clearly the remaining rows (if any) have as many $+1$'s as -1 's, i.e. if $n \neq 1$ then n must be even. Some small examples are

$$(1), \quad \begin{pmatrix} 1 & 1 \\ 1 & -1 \end{pmatrix}, \quad \begin{pmatrix} + & + & + & + \\ + & + & - & - \\ + & - & + & - \\ + & - & - & + \end{pmatrix},$$

where, in the last example, we have only indicated the sign of the entry.

Problem 18A. Show that any two Hadamard matrices of order 12 are equivalent.

Theorem 18.1. *If H is a Hadamard matrix of order n , then $n = 1$, $n = 2$, or $n \equiv 0 \pmod{4}$.*

PROOF: Let $n > 2$. Normalize H . We can permute columns in such a way that the first three rows of H become

$$\begin{array}{cccc} ++\cdots++ & ++\cdots++ & ++\cdots++ & ++\cdots++ \\ ++\cdots++ & ++\cdots++ & --\cdots-- & --\cdots-- \\ \underbrace{++\cdots++}_{a \text{ columns}} & \underbrace{--\cdots--}_{b \text{ columns}} & \underbrace{++\cdots++}_{c \text{ columns}} & \underbrace{--\cdots--}_{d \text{ columns}} \end{array}$$

We have $a + b + c + d = n$ and the three inner products formed from these rows yield $a + b - c - d = 0$, $a - b + c - d = 0$, and $a - b - c + d = 0$. If we add these equations, we find $n = 4a$, proving the theorem. (In a similar way we see that $4b = 4c = 4d = n$.) \square

One of the famous conjectures in the area of combinatorial designs states that a Hadamard matrix of order n exists for every $n \equiv 0 \pmod{4}$. We are still very far from a proof of this conjecture. The smallest n for which a Hadamard matrix could exist but no example is known is presently 428. There are very many construction methods for Hadamard matrices, of which we shall treat a few. First we define a second class of matrices, very similar to Hadamard matrices.

A *conference matrix* C of order n is an $n \times n$ matrix with 0's on the diagonal, +1 or -1 in all other positions and with the property

$$(18.2) \quad CC^T = (n-1)I.$$

The name conference matrix originates from an application to conference telephone circuits. V. Belevitch (1950) studied so-called ideal nondissipative networks consisting of ideal transformers, to be used to set up a conference telephone network. The theory led to a necessary condition for the existence of such a network, namely the existence of a conference matrix of order n , where n is the number of terminals of the network. This explains the name of these matrices.

Problem 18B. Let C be a conference matrix of order $n \neq 1$. Show that n is even. Show that by permuting rows and columns, and multiplying certain rows and columns by -1 , we can find an equivalent conference matrix that is symmetric if $n \equiv 2 \pmod{4}$, and antisymmetric if $n \equiv 0 \pmod{4}$.

Theorem 18.2. If C is an antisymmetric conference matrix, then $I + C$ is a Hadamard matrix.

PROOF: $(I+C)(I+C)^\top = I+C+C^\top+CC^\top = I+(n-1)I = nI$. \square

Theorem 18.3. If C is a symmetric conference matrix of order n , then

$$H = \begin{pmatrix} I + C & -I + C \\ -I + C & -I - C \end{pmatrix}$$

is a Hadamard matrix of order $2n$.

PROOF: Again calculate HH^\top and the result follows. \square

One of the most common construction methods for several combinatorial structures is the so-called *recursive* method in which a large object of the required type is made by applying some procedure to two or more smaller objects of the same type. In the next theorem we demonstrate such a method for the construction of Hadamard matrices.

Let A be an $m \times n$ matrix with entries a_{ij} and B another matrix. The matrix

$$\begin{pmatrix} a_{11}B & a_{12}B & \dots & a_{1n}B \\ a_{21}B & a_{22}B & \dots & a_{2n}B \\ \vdots & \vdots & \ddots & \vdots \\ a_{m1}B & a_{m2}B & \dots & a_{mn}B \end{pmatrix}$$

consisting of mn blocks with the size of B is called the *Kronecker product* $A \otimes B$ of the matrices A and B .

Theorem 18.4. If H_m and H_n are Hadamard matrices of order m and n respectively, then $H_m \otimes H_n$ is a Hadamard matrix of order mn .

PROOF: By straightforward calculation one sees that

$$(A \otimes B)(C \otimes D) = (AC) \otimes (BD)$$

and that

$$(A \otimes B)^\top = A^\top \otimes B^\top.$$

We take $A = C = H_m$ and $B = D = H_n$. The result follows from the definition of a Hadamard matrix and the fact that $I_m \otimes I_n = I_{mn}$. \square

By repeatedly applying this theorem to $\mathbf{H}_2 := \begin{pmatrix} + & + \\ + & - \end{pmatrix}$, we find a sequence of Hadamard matrices that we shall denote by \mathbf{H}_n , where $n = 2^m$, $m = 1, 2, \dots$.

We now come to a direct construction method for conference matrices, and these can then be used with Theorems 18.2 and 18.3 to construct Hadamard matrices. In the following, q is a power of an odd prime. On the field \mathbb{F}_q , we define a function χ (a so-called *character*) by

$$\chi(x) := \begin{cases} 0 & \text{if } x = 0, \\ 1 & \text{if } x \text{ is a nonzero square,} \\ -1 & \text{if } x \text{ is a nonsquare.} \end{cases}$$

For any x and y in \mathbb{F}_q , we have $\chi(x)\chi(y) = \chi(xy)$, and since there are as many nonzero squares as nonsquares we also have

$$(18.3) \quad \sum_{x \in \mathbb{F}_q} \chi(x) = 0.$$

Now let $0 \neq c \in \mathbb{F}_q$. Then (18.3) implies that

$$(18.4) \quad \sum_{b \in \mathbb{F}_q} \chi(b)\chi(b+c) = -1.$$

This is seen by ignoring the term with $b = 0$, which is 0, and then writing $\chi(b+c) = \chi(b)\chi(1+cb^{-1})$; (note that $\chi(b)^2 = 1$ if $b \neq 0$). If b runs through all nonzero elements of the field, then $1+cb^{-1}$ takes on every value except 1.

Number the elements of \mathbb{F}_q : $0 = a_0, a_1, \dots, a_{q-1}$. We define a $q \times q$ matrix Q by

$$q_{ij} := \chi(a_i - a_j), \quad 0 \leq i, j < q.$$

Note that Q is symmetric if $q \equiv 1 \pmod{4}$, and antisymmetric if $q \equiv 3 \pmod{4}$. As a direct consequence of the elementary properties of χ and of (18.4), we find that $QQ^\top = qI - J$ and $QJ = JQ = O$. A matrix C of size $q + 1 \times q + 1$ is defined by

$$(18.5) \quad C := \begin{pmatrix} 0 & 1 & 1 & \dots & 1 \\ \pm 1 & & & & \\ \vdots & & Q & & \\ \pm 1 & & & & \end{pmatrix},$$

where the signs of the terms ± 1 are chosen in such a way that C is symmetric or antisymmetric. From the properties of Q , it now follows that C is a conference matrix of order $q + 1$. This construction is due to Paley (1933) and the conference matrices of this type are usually called *Paley matrices*. For the special case that q is a prime, the matrix Q is a circulant. We summarize the constructions as a theorem.

Theorem 18.5. *If q is a power of an odd prime, then a Hadamard matrix of order $q + 1$ exists if $q \equiv 3 \pmod{4}$, and a Hadamard matrix of order $2(q + 1)$ exists if $q \equiv 1 \pmod{4}$.*

+	+	+	+	+	+	+	+	+	+	+	+
-	+	+	-	+	+	+	-	-	-	+	-
-	-	+	+	-	+	+	+	-	-	-	+
-	+	-	+	+	-	+	+	+	-	-	-
-	-	-	+	-	+	+	-	+	+	+	-
-	-	-	-	+	-	+	+	-	+	+	+
-	+	-	-	-	+	-	+	+	-	+	+
-	+	+	+	-	-	+	-	+	+	-	+
-	+	+	+	+	-	-	+	-	+	+	+
-	+	-	+	+	+	-	-	-	+	-	+

Figure 18.1

+	+	+	+	+	+	-	+	+	+	+	+
+	+	+	-	-	+	+	-	+	-	-	+
+	+	+	+	-	-	+	+	-	+	-	-
+	-	+	+	+	-	+	-	+	-	+	-
+	-	-	+	+	+	+	-	-	+	-	+
+	+	-	-	+	+	+	+	-	-	+	-
-	+	+	+	+	+	-	-	-	-	-	-
+	-	+	-	-	+	-	-	-	+	+	-
+	+	-	+	-	-	-	-	-	-	+	+
+	-	+	-	+	-	-	+	-	-	-	+
+	-	-	+	-	+	-	+	+	-	-	-
+	+	-	-	+	-	-	-	+	+	-	-

Figure 18.2

Figures 18.1 and 18.2 illustrate Hadamard matrices of order 12 constructed from Paley matrices of orders $11 + 1$ and $5 + 1$, respectively.

Problem 18C. Show that a Hadamard matrix of order n exists if $n \equiv 0 \pmod{4}$, $n \leq 100$, except possibly for $n = 92$.

There was a period of thirty years between Paley's result and the discovery of a Hadamard matrix of order 92 by L. D. Baumert, S. W. Golomb, and M. Hall. The method that they used was developed by Williamson in 1944 but a computer search was necessary to find the actual matrix. Williamson's method is based on the following observation. Let the matrices A_i , $1 \leq i \leq 4$, of order n , n odd, be symmetric and assume that they commute with each other. Consider the matrix H defined by

$$(18.6) \quad \begin{pmatrix} A_1 & A_2 & A_3 & A_4 \\ -A_2 & A_1 & -A_4 & A_3 \\ -A_3 & A_4 & A_1 & -A_2 \\ -A_4 & -A_3 & A_2 & A_1 \end{pmatrix}.$$

We then have

$$(18.7) \quad HH^\top = I_4 \otimes (A_1^2 + A_2^2 + A_3^2 + A_4^2).$$

To construct a Hadamard matrix in this way, we have to find matrices A_i that satisfy the conditions stated above, have entries ± 1 , and furthermore satisfy

$$(18.8) \quad A_1^2 + A_2^2 + A_3^2 + A_4^2 = 4nI_n.$$

Let U be the permutation matrix of order n corresponding to the permutation $(12\dots n)$, i.e. $u_{ij} = 1$ if and only if $j - i \equiv 1 \pmod n$. Then $U^n = I$ and any circulant is a linear combination of powers of U . If we assume that the matrices A_i have the form $A_i = \sum_{j=0}^{n-1} a_{ij}U^j$ with $a_{i0} = 1$ and $a_{ij} = a_{i,n-j}$, then the matrices do indeed commute and they are symmetric. From now on, we also assume that all the a_{ij} are ± 1 and that (18.8) is satisfied. A simple example of a Hadamard matrix constructed in this way is found by taking $n = 3$, $A_1 = J$, and $A_i = J - 2I$, $i = 2, 3, 4$. We find a Hadamard matrix of order 12; see Fig. 18.3.

+	+	+	-	+	+	-	+	+	-	+	+
+	+	+	+	-	+	+	-	+	+	-	+
+	+	+	+	+	-	+	+	-	+	+	-
+	-	-	+	+	+	+	-	-	-	+	+
-	+	-	+	+	+	-	+	-	+	-	+
-	-	+	+	+	+	-	-	+	+	+	-
+	-	-	-	+	+	+	+	+	+	-	-
-	+	-	+	-	+	+	+	+	-	+	-
-	-	+	+	+	-	+	+	+	-	-	+
+	-	-	+	-	-	-	+	+	+	+	+
-	+	-	-	+	-	+	-	+	+	+	+
-	-	+	-	-	+	+	+	-	+	+	+

Figure 18.3

Example 18.1. Note that our construction implies that A_i has constant row-sum a_i (odd) and by (18.8) we have $a_1^2 + \dots + a_4^2 = 4n$. If we wish to use this method to find a Hadamard matrix of order 20, we first write 20 as a sum of four odd squares: $20 = 9 + 9 + 1 + 1$. From this we see that two of the matrices A_i must be $2I - J$ and then it is not difficult to see that the other two have as first row $+ - + + -$, respectively $+ + - - +$.

To analyze the situation a little further, we introduce matrices W_i and P_i as follows:

$$(18.9) \quad 2W_i := (A_1 + \cdots + A_4) - 2A_i,$$

$$(18.10) \quad A_i = 2P_i - J.$$

Our conventions on the coefficients a_{ij} imply that if p_i is defined by $p_i J := P_i J$, then p_i is an odd integer. Furthermore (18.8) and (18.9) imply that

$$(18.11) \quad W_1^2 + W_2^2 + W_3^2 + W_4^2 = 4nI.$$

By substituting (18.10) in (18.8), we find

$$(18.12) \quad \sum_{i=1}^4 P_i^2 = \left(\sum_{i=1}^4 p_i - n\right)J + nI.$$

Suppose the term U^k , $k \neq 0$, occurs in α of the matrices P_i . Considering the equation (18.12) mod 2, we find U^{2k} on the left-hand side with coefficient α and on the right-hand side with coefficient 1. So α is odd and this implies that U^k occurs in exactly *one* of the matrices W_i (with coefficient ± 2). From Example 18.1 and (18.9), we see that the constant row-sums w_i of the matrices W_i satisfy $w_1^2 + \cdots + w_4^2 = 4n$. These facts reduce the number of possibilities for matrices W_i also satisfying (18.11) sufficiently to make a computer search for such matrices feasible. The A_i are then found from (18.9). We list the first rows of the four matrices of order 23 that produced the first Hadamard matrix of order 92:

- A_1 : + + - - - + - - - + - + + - + - - - + - - - +
- A_2 : + - + + - + + - - + + + + + - - + + - + + -
- A_3 : + + + - - - + + - + - + + - + - + + - - - + +
- A_4 : + + + - + + + - + - - - - - - - + - + + + - + +

Problem 18D. Construct a Hadamard matrix of order 28 using Williamson’s method.

We look at a different problem concerning Hadamard matrices. If a Hadamard matrix of order n is normalized, then it obviously

has exactly n more entries $+1$ than entries -1 . We define the *excess* of a Hadamard matrix to be the sum of all the entries, and then define $\sigma(n)$ as the maximal value of the excess of all Hadamard matrices of order n . The following bound due to Best (1977) shows that $\sigma(n)$ grows as $n^{3/2}$.

Theorem 18.6. $n^2 2^{-n} \binom{n}{\frac{1}{2}n} \leq \sigma(n) \leq n\sqrt{n}$.

PROOF: (a) Let H be a Hadamard matrix of order n . Let s_k be the sum of the k -th column of H . Let \mathbf{c}_i be the i -th row of H , $1 \leq i \leq n$. We calculate $\sum_{1 \leq i, j \leq n} \langle \mathbf{c}_i, \mathbf{c}_j \rangle$ in two ways. By the definition of Hadamard matrix this sum is n^2 . On the other hand

$$\sum_{1 \leq i, j \leq n} \sum_{k=1}^n c_{ik} c_{jk} = \sum_{k=1}^n s_k^2.$$

From this and the Cauchy-Schwarz inequality we find

$$\sum_{k=1}^n s_k \leq \left(n \sum_{k=1}^n s_k^2 \right)^{1/2} = n\sqrt{n},$$

so $\sigma(n) \leq n\sqrt{n}$.

(b) Let \mathbf{x} be any vector in $\{+1, -1\}^n$. We multiply column j of H by x_j , $1 \leq j \leq n$. Subsequently, multiply those rows that have more terms -1 than $+1$ by -1 . Call the resulting matrix $H_{\mathbf{x}}$ and define $\sigma(H_{\mathbf{x}}) := \sum_{i=1}^n |\langle \mathbf{x}, \mathbf{c}_i \rangle|$. Clearly $\sigma(n)$ is at least equal to the average value of $\sigma(H_{\mathbf{x}})$. So we find

$$\begin{aligned} \sigma(n) &\geq 2^{-n} \sum_{\mathbf{x} \in \{+1, -1\}^n} \sigma(H_{\mathbf{x}}) = 2^{-n} \sum_{\mathbf{x}} \sum_{i=1}^n |\langle \mathbf{x}, \mathbf{c}_i \rangle| \\ &= 2^{-n} \sum_{i=1}^n \sum_{d=0}^n \sum_{\mathbf{x}, d(\mathbf{x}, \mathbf{c}_i)=d} |n - 2d| \\ &= 2^{-n} n \sum_{d=0}^n |n - 2d| \binom{n}{d} = n^2 2^{-n} \binom{n}{\frac{1}{2}n}. \end{aligned}$$

□

Corollary. $2^{-1/2}n^{3/2} \leq \sigma(n) \leq n^{3/2}$.

PROOF: That the left-hand side of the inequality in Theorem 18.6 is asymptotically equal to $2^{1/2}\pi^{-1/2}n^{3/2}$ follows from Stirling's formula. To obtain an inequality that holds for all n , we must replace the constant by $2^{-1/2}$. \square

Example 18.2. Consider a square of size 4 by 4, divided into 16 cells that we number from 1 to 16. A matrix A with rows \mathbf{a}_i , $1 \leq i \leq 16$, is defined by taking $a_{ij} = -1$ if j occurs in the square in the same row or column as i , but $j \neq i$; otherwise $a_{ij} = 1$. For any two rows of A , there are two positions where they both have entry -1 . It follows that A is a Hadamard matrix of order 16 with excess 64, i.e. for this matrix we have equality for the upper bound in Theorem 18.6.

This Hadamard matrix can also be constructed as follows. Define $H := J - 2I$, a Hadamard matrix of order 4 with maximal excess, namely 8. Every row of H has the same number of terms $+1$, namely 3. The matrix $H \otimes H$ is a Hadamard matrix of order 16, with 10 terms $+1$ in each row, and the maximal excess 64. If we take the Kronecker product of this matrix with H , we again find a Hadamard matrix with constant row-sums and maximal excess, etc. In general, a Hadamard matrix of order $4u^2$, all row-sums equal to $2u$, and hence maximal excess, is called a *regular* Hadamard matrix. Other constructions of such matrices are known.

One of the very interesting and successful applications of Hadamard matrices was their use as so-called *error-correcting codes*. Many readers will have seen the excellent pictures that were taken of Mars, Saturn and other planets by satellites such as the Mariners, Voyagers, etc. To transmit such a picture to Earth, it is first divided into very small (*pixels*) and for each such square the degree of blackness is measured and expressed, say in a scale of 0 to 63. These numbers are expressed in the binary system, i.e. each pixel produces a string of six 0's and 1's (bits). The bits are transmitted to the receiver station on Earth (the Jet Propulsion Laboratory at Caltech). Due to a number of sources of *noise*, one of which is thermal noise from the amplifier, it happens occasionally that a signal that was transmitted as a 0, respectively a 1, is interpreted

by the receiver as a 1, respectively a 0. If each sextuple corresponding to a pixel is transmitted as such, then the *errors* made by the receiver would make the pictures very poor. Since there is only a limited amount of time to transmit the pictures and it is known how much energy is available from the solar panels, we know the average energy per user bit available to generate signals to be sent to the receiver. From this we can calculate the error probability p (per bit).

Suppose that for a useful picture, each sextuple may be wrong with a probability P_E at most 10^{-4} . To achieve this by simply transmitting the bits, we need $p \approx 10^{-4}/6$ since $P_E = 1 - (1-p)^6 \approx 10^{-4}$. Let us first assume that the required energy is available and try to improve the picture by doing the following. Instead of sending a bit, say 0, we could send five 0's and the receiver translates a received fivetuple into the bit that occurs most. We say that we are using a *code*, called the *repetition code*, with two *words* of *length* 5, namely 00000 and 11111. The number $1/5$ is called the *information rate* of this code. The power constraint allows us to calculate how much energy we have available per channel bit. Subsequently, it is possible to calculate the new error rate p' (per channel bit). Of course $p' > p$ and in our example we in fact have $p' = 0.035$ (nearly 2000 times as large as without coding). The coding only makes sense if error correction more than makes up for the loss of energy per bit.

The probability that a transmitted pixel is received correctly now becomes

$$[(1-p')^5 + 5p'(1-p')^4 + 10(p')^2(1-p')^3]^6$$

and this is ≈ 0.997 . In other words, we have completely spoiled our picture!

Let us now look at what was actually done in the Mariner 1969 expedition. The 64 possible information strings (corresponding to the possible degrees of blackness of a pixel) were mapped onto the rows of the matrices \mathbf{H}_{32} and $-\mathbf{H}_{32}$. Since we now have codewords of length 32 representing information words of length 6, the information rate is $6/32$, nearly the same as for the repetition code. Note that any two of these codewords either differ in all 32 positions or differ in exactly 16 of the positions. It follows that if a

received word contains at most 7 errors, then it resembles the correct word more than any of the 63 other words. (We have changed our symbols to ± 1 instead of 0 and 1.) We say that this code is a 7-error-correcting code. The new error probability now is $p' \approx 0.036$ (again larger). The probability that a received word is *decoded* incorrectly now is

$$\sum_{i=8}^{32} \binom{32}{i} (p')^i (1 - p')^{32-i}$$

and this is roughly $1.4 \cdot 10^{-5}$ which is an order of magnitude better than P_E .

In practice, there was not enough energy to transmit good pictures but by using this code, that problem was solved.

What we have seen is one example of a sequence of (low rate) codes, known as *first order Reed–Muller codes*. Consider once again the construction of the Hadamard matrices \mathbf{H}_n , where $n = 2^m$. In Fig. 18.4 we show \mathbf{H}_8 .

In the matrix \mathbf{H}_n we replace each $+1$ by 0 and each -1 by 1. Number the rows from 0 to $n - 1 = 2^m - 1$. What happens in the Kronecker product construction when we go from m to $m + 1$, i.e. double the order of the matrix? The new rows (now interpreted as vectors in \mathbb{F}_2^{2n}) have the form $(\mathbf{c}_i, \mathbf{c}_i)$ for $0 \leq i < n$ and they have the form $(\mathbf{c}_i, \mathbf{c}_i + \mathbf{1})$ for $n \leq i < 2n$, where $\mathbf{1}$ denotes the all-one vector.

+	+	+	+	+	+
+	-	+	-	+	-
+	+	-	-	+	+
+	-	-	+	+	-
+	+	+	+	-	-
+	-	+	-	-	+
+	+	-	-	-	+
+	-	-	+	-	+

Figure 18.4

Theorem 18.7. Let $R'(1, m)$ denote the set of row vectors in \mathbb{F}_2^n

obtained from \mathbf{H}_n as described above. Then $R'(1, m)$ is an m -dimensional subspace of \mathbb{F}_2^n .

PROOF: For $m = 1$, the assertion is trivial. We proceed by induction. Let $\mathbf{v}_1, \mathbf{v}_2, \dots, \mathbf{v}_m$ be a basis of $R'(1, m)$. Our observation made above shows that $R'(1, m + 1)$ consists of all linear combinations of the vectors $(\mathbf{v}_i, \mathbf{v}_i)$ and the vector $(\mathbf{0}, \mathbf{1})$. This completes the proof. \square

We now define the first order Reed–Muller code $R(1, m)$ of length $n = 2^m$ and dimension $m + 1$ to be the subspace of \mathbb{F}_2^n spanned by the space $R'(1, m)$ and the all-one vector of length n . In this terminology, the code used by Mariner 1969 was $R(1, 5)$. From the properties of Hadamard matrices, we immediately see that any two codewords in $R(1, m)$ differ in at least $\frac{1}{2}n$ places. We say that the code has *minimum distance* $d = 2^{m-1}$. Therefore the code can correct up to $2^{m-2} - 1$ errors.

We can give the codewords a nice geometric interpretation. Let us number the points of the space \mathbb{F}_2^m by considering a vector as the binary representation of its number. For example, $(0, 1, 1, 0, 1)$ is considered as the point P_{22} in \mathbb{F}_2^5 . Let these representations be the columns of an $m \times n$ matrix. Let \mathbf{v}_i be the i -th row of this matrix, $1 \leq i \leq m$. Then from Fig. 18.4 and the observations above, we see that the vectors \mathbf{v}_i are the natural basis for $R'(1, m)$. The basis vector \mathbf{v}_i is the characteristic function of the hyperplane $\{(x_1, x_2, \dots, x_m) \in \mathbb{F}_2^m : x_i = 1\}$. By taking linear combinations, we see that the codewords of $R(1, m)$ are exactly all the characteristic functions of the affine hyperplanes in the vector space and the characteristic function of the space itself (for $\mathbf{1}$) and of the empty set (for $\mathbf{0}$). Any two affine hyperplanes are either parallel or they meet in an affine subspace of dimension $m - 2$, in accordance with the fact that two rows of the Hadamard matrix have the same entries in exactly half of the positions.

As our definition of $R(1, m)$ suggests, Reed–Muller codes of higher order are also defined in the theory of error-correcting codes. They also have a geometric interpretation that we shall not go into here (but see Example 26.4).

Problem 18E. For $n = 2^m$ and $1 \leq i \leq m$, we define the matrix

$M_n^{(i)}$ by

$$M_n^{(i)} := I_{2^{m-i}} \otimes \mathbf{H}_2 \otimes I_{2^{i-1}}.$$

Prove that

$$\mathbf{H}_n = M_n^{(1)} M_n^{(2)} \dots M_n^{(m)}.$$

A received word \mathbf{x} is decoded by calculating $\mathbf{x}\mathbf{H}_n^\top$. If there are not too many errors, then all entries of this product will be nearly 0 except one with an absolute value close to n , telling us what the true message was. A multiplication by ± 1 is called an operation. Compare the number of operations that are necessary for decoding when \mathbf{H}_n is used and when the representation of \mathbf{H}_n as a product of matrices $M_n^{(i)}$ is used. (This is an example of what is known as a *Fast Fourier Transform*.)

Problem 18F. Let \mathbf{v}_i , $0 \leq i \leq m$, where $\mathbf{v}_0 = \mathbf{1}$, be the basis of $R(1, m)$ given above. We consider the subspace $R(2, m)$ of \mathbb{F}_2^n , where $n = 2^m$, spanned by all the vectors

$$\mathbf{v}_i \cdot \mathbf{v}_j := (v_{i0}v_{j0}, \dots, v_{i,n-1}v_{j,n-1}).$$

What is the dimension of this space? Show that any two vectors of $R(2, m)$ differ in at least $\frac{1}{4}n$ places.

Problem 18G. Suppose M is an $m \times n$ $(0, 1)$ -matrix so that the Hamming distance between any two distinct rows is at least d . (If M is the result of stacking a Hadamard matrix H on top of $-H$ and changing the symbols to 0's and 1's, we have an example with $m = 2n$ and $d = n/2$.)

(1) Count the number of ordered triples (i, j, k) such that i and j are (indices of) distinct rows and k is a column where $M(i, k) \neq M(j, k)$ in two ways—one yielding an inequality involving d and the other involving the column-sums of M . Prove that if $2d > n$, then

$$m \leq \frac{2d}{2d - n}.$$

(This is known as *Plotkin's bound* in coding theory.) What conditions ensure equality?

(2) Suppose $d = n/2$. Prove that $m \leq 2n$ and show that equality implies the existence of a Hadamard matrix of order n .

Problem 18H. Let H be a Hadamard matrix of order m and let C be a symmetric conference matrix of order n . Let P be the matrix of size m with the form $\begin{pmatrix} O & -I \\ I & O \end{pmatrix}$ where the submatrices have size $m/2$. Prove that $(H \otimes C) + (PH \otimes I)$ is a Hadamard matrix of size mn .

Problem 18I. Let q be a prime power $\equiv 1 \pmod{4}$. Let C be the matrix of (18.5). Choose H and P as in Problem 18H. Prove that

$$(H \otimes C \otimes Q) + (PH \otimes C \otimes I_q) + (H \otimes I_{q+1} \otimes J_q)$$

is a Hadamard matrix of size $mq(q+1)$.

Notes.

J. Hadamard (1865–1963) was a leading mathematician around the turn of the century. His most important work was in the theory of analytic functions and in mathematical physics. He is best known for the proof of the so-called *prime number theorem*, jointly with C. J. De La Vallée-Poussin.

R. E. A. C. Paley (1907–1933) died in an avalanche while skiing at the age of 26. In his short life he produced 26 papers of excellent quality (mostly on Fourier Theory).

A long outstanding conjecture of H. J. Ryser asserts that no Hadamard matrix of order $n > 4$ can be a circulant.

J. S. Wallis (aka J. Seberry) (1976) proved that for any integer s , Hadamard matrices of orders $2^t s$ exist whenever $t > 2 \log_2(s-3)$. However, it is still not known whether the set of orders of Hadamard matrices has ‘positive density’.

For more on error-correcting codes, see Chapter 20.

The codes that are now called Reed–Muller codes were (surprisingly?) indeed first treated by D. E. Muller (1954) and I. S. Reed (1954).

For a detailed account of the coding and decoding for the Mariner missions, see E. C. Posner (1968).

References.

- L. D. Baumert, S. W. Golomb, and M. Hall, Jr. (1962), Discovery of a Hadamard matrix of order 92, *Bull. Amer. Math. Soc.* **68**, 237–238.
- V. Belevitch (1950), Theory of $2n$ -terminal networks with applications to conference telephony, *Electrical Communication* **27**, 231–244.
- M. R. Best (1977), The excess of a Hadamard matrix, *Proc. Kon. Ned. Akad. v. Wetensch.* **80**, 357–361.
- D. E. Muller (1954), Application of Boolean algebra to switching circuit design and to error detection, *IEEE Trans. Computers* **3**, 6–12.
- R. E. A. C. Paley (1933), On orthogonal matrices, *J. Math. Phys.* **12**, 311–320.
- E. C. Posner (1968), Combinatorial structures in planetary reconnaissance, in: *Error Correcting Codes* (H. B. Mann, ed.), J. Wiley and Sons.
- I. S. Reed (1954), A class of multiple-error-correcting codes and the decoding scheme, *IEEE Trans. Information Theory* **4**, 38–49.
- J. S. Wallis (1976), On the existence of Hadamard matrices, *J. Combinatorial Theory (A)* **21**, 188–195.
- J. Williamson (1944), Hadamard's determinant theorem and the sum of four squares, *Duke Math. J.* **11**, 65–81.

19

Designs

In this chapter we give an introduction to a large and important area of combinatorial theory which is known as *design theory*. The most general object that is studied in this theory is a so-called *incidence structure*. This is a triple $\mathbf{S} = (\mathcal{P}, \mathcal{B}, \mathbf{I})$, where:

- (1) \mathcal{P} is a set, the elements of which are called *points*;
- (2) \mathcal{B} is a set, the elements of which are called *blocks*;
- (3) \mathbf{I} is an incidence relation between \mathcal{P} and \mathcal{B} (i.e. $\mathbf{I} \subseteq \mathcal{P} \times \mathcal{B}$).
The elements of \mathbf{I} are called *flags*.

If $(p, B) \in \mathbf{I}$, then we say that point p and block B are *incident*. We allow two different blocks B_1 and B_2 to be incident with the same subset of points of \mathcal{P} . In this case one speaks of ‘repeated blocks’. If this does not happen, then the design is called a *simple* design and we can then consider blocks as subsets of \mathcal{P} . In fact, from now on we shall always do that, taking care to realize that different blocks are possibly the same subset of \mathcal{P} . This allows us to replace the notation $(p, B) \in \mathbf{I}$ by $p \in B$, and we shall often say that point p is ‘in block B ’ instead of incident with B .

It has become customary to denote the cardinality of \mathcal{P} by v and the cardinality of \mathcal{B} by b . So the incidence structure then is a set of v points and a collection of b not necessarily distinct subsets of the point set. The structure obtained by replacing each block by its complement is, of course called the *complement* of the structure. (This means that we replace \mathbf{I} by its complement in $\mathcal{P} \times \mathcal{B}$.)

To obtain an interesting theory, we must impose some regularity conditions on the structure \mathbf{S} . As a first example, we mention incidence structures that have the confusing name ‘*linear spaces*’. Here the blocks are usually called *lines* and the regularity conditions

are that every line contains (i.e. is incident with) at least two points and any two points are on exactly one line. Example 19.6 below shows a simple but important linear space. The following theorem is due to De Bruijn and Erdős (1948). The elegant proof is due to Conway.

Theorem 19.1. *For a linear space we have $b = 1$ or $b \geq v$, and equality implies that for any two lines there is exactly one point incident with both.*

PROOF: For $x \in \mathcal{P}$, denote by r_x the number of lines incident with x , and similarly for $B \in \mathcal{B}$, let k_B be the number of points on B . Let there be more than one line. If $x \notin L$ then $r_x \geq k_L$ because there are k_L lines ‘joining’ x to the points on L . Suppose $b \leq v$. Then $b(v - k_L) \geq v(b - r_x)$ and hence

$$1 = \sum_{x \in \mathcal{P}} \sum_{L \not\ni x} \frac{1}{v(b - r_x)} \geq \sum_{L \in \mathcal{B}} \sum_{x \notin L} \frac{1}{b(v - k_L)} = 1$$

and this implies that in all the inequalities, equality must hold. Therefore $v = b$, and $r_x = k_L$ if $x \notin L$. \square

A trivial example of equality in Theorem 19.1 is a so-called *near pencil*, a structure with one line that contains all the points but one, and all pairs containing that point as lines of size two. Much more interesting examples are the projective planes that we shall define later in this chapter. These are the only possibilities. See Problem 23C. The reader can prove this fact for linear spaces as an exercise.

In the rest of this chapter, we shall be interested in highly regular incidence structures called ‘ t -designs’. Let v, k, t and λ be integers with $v \geq k \geq t \geq 0$ and $\lambda \geq 1$. A t -design on v points with *block-size* k and *index* λ is an incidence structure $\mathcal{D} = (\mathcal{P}, \mathcal{B}, \mathbf{I})$ with:

- (i) $|\mathcal{P}| = v$,
- (ii) $|B| = k$ for all $B \in \mathcal{B}$,
- (iii) for any set T of t points, there are exactly λ blocks incident with all points in T .

So all blocks have the same size and every t -subset of the point set is contained in the same number of blocks. Two different notations

for such a design are widely used, namely t - (v, k, λ) design and $S_\lambda(t, k, v)$. We shall use both of them. A *Steiner system* $S(t, k, v)$ is a t -design with $\lambda = 1$, and we suppress the index in the notation. Most of the early theory of designs originated in statistics, where 2-designs are used in the design of experiments for statistical analysis. These designs are often called *balanced incomplete block designs* (BIBDs). Usually trivial designs are excluded from the theory: a design with one block that contains all the points or a design that has all the k -subsets of the point set as blocks is of course a t -design for $t \leq k$, but is not very interesting.

We give a few examples; more will follow further on.

Example 19.1. Let the nonzero vectors of \mathbb{F}_2^4 be the points. As blocks we take all triples $\{\mathbf{x}, \mathbf{y}, \mathbf{z}\}$ with $\mathbf{x} + \mathbf{y} + \mathbf{z} = \mathbf{0}$. Any pair \mathbf{x}, \mathbf{y} with $\mathbf{x} \neq \mathbf{y}$ uniquely determines a third element \mathbf{z} , different from both, satisfying this equation. So we have constructed an $S(2, 3, 15)$. The blocks are the 2-dimensional subspaces of \mathbb{F}_2^4 with $\mathbf{0}$ deleted.

We construct a second design by taking all the vectors as point set and defining blocks to be 4-tuples $\{\mathbf{w}, \mathbf{x}, \mathbf{y}, \mathbf{z}\}$ for which $\mathbf{w} + \mathbf{x} + \mathbf{y} + \mathbf{z} = \mathbf{0}$. This defines an $S(3, 4, 16)$. Note that if we take the blocks that contain $\mathbf{0}$ and delete this vector, we find the blocks of the previous design.

Example 19.2. We take the ten edges of a K_5 as point set. Each of the three kinds of 4-tuples shown in Fig. 19.1 will be a block.




Figure 19.1

There are $5 + 10 + 15 = 30$ blocks. No triple (of edges) is contained in more than one block. Therefore the blocks contain 120 different triples, i.e. all the triples. We have constructed an $S(3, 4, 10)$.

Example 19.3. Let H be a normalized Hadamard matrix of order $4k$. Delete the first row and the first column. We now identify points with rows of this matrix. Each column defines a subset of the rows, namely those rows for which there is a $+$ in that column. These subsets are the blocks. From the argument in Theorem 18.1, we see that any pair of points is contained in exactly $k-1$ blocks and clearly all blocks have size $2k-1$. We have a $2-(4k-1, 2k-1, k-1)$ design and such a design is called a *Hadamard 2-design*.

Consider the same matrix H but now delete only the first row. Each of the other rows determines two $2k$ -subsets of the set of columns. This partition is unaffected if we change the sign of the row. The argument of Theorem 18.1 now shows that for any three columns, there are exactly $k-1$ of the subsets that have three elements in these columns. So these $2k$ -sets are the blocks of a $3-(4k, 2k, k-1)$ design called a *Hadamard 3-design*.

Example 19.4. Consider a regular Hadamard matrix of order $4u^2$ (see Example 18.2). If we replace $+$ by 1 and $-$ by 0, we find a $(0,1)$ -matrix with $2u^2 + u$ ones in every row and column, and furthermore, any two rows or columns have inner product $u^2 + u$. Let the columns be the characteristic functions of the blocks of a design on $4u^2$ points. The properties of the matrix show that this is a $2-(4u^2, 2u^2 + u, u^2 + u)$ design. One usually prefers considering the complement of this design, i.e. a $2-(4u^2, 2u^2 - u, u^2 - u)$ design.

Problem 19A. Here are two more examples in the spirit of Example 19.2.

(i) Take the edges of K_6 as points of an incidence structure. The blocks are to be all sets of three edges that either are the edges of a perfect matching, or the edges of a triangle. Show that this is an $S(2, 3, 15)$ and show that it is isomorphic to the design in Example 19.1.

(ii) Take the edges of K_7 as points of an incidence structure. The blocks are to be all sets of five edges of these three types: (a) ‘claws’ with five edges incident with a common vertex, (b) edge sets of pentagon subgraphs, and (c) five edges that form a triangle and two disjoint edges. Show that this is an $S_3(3, 5, 21)$.

We now give two elementary theorems on t -designs.

Theorem 19.2. *The number of blocks of an $S_\lambda(t, k, v)$ is*

$$(19.1) \quad b = \lambda \binom{v}{t} / \binom{k}{t}.$$

PROOF: Count in two ways the number of pairs (T, B) , where T is a t -subset of \mathcal{P} and B is a block incident with all points of T . We find $\lambda \binom{v}{t} = b \binom{k}{t}$. \square

Theorem 19.3. *Given i , $0 \leq i \leq t$, the number of blocks incident with all the points of an i -subset I of \mathcal{P} is*

$$(19.2) \quad b_i = \lambda \binom{v-i}{t-i} / \binom{k-i}{t-i}.$$

That is, every $S_\lambda(t, k, v)$ is also an i -design for $i \leq t$.

PROOF: Count in two ways the number of pairs (T, B) , where T is a t -subset of \mathcal{P} that contains I and B is a block that is incident with all the points of T . \square

Corollary. *If \mathcal{D} is a t -design with point set \mathcal{P} and block set \mathcal{B} and if I is a subset of \mathcal{P} with $|I| \leq t$, then the point set $\mathcal{P} \setminus I$ and the blocks $\{B \setminus I : I \subseteq B\}$ form an $S_\lambda(t-i, k-i, v-i)$. This design is called the derived design \mathcal{D}_I .*

In Example 19.1 we already saw an example of a derived design. If we take $I = \{\mathbf{0}\}$, the derived design for $S(3, 4, 16)$ is $S(2, 3, 15)$.

Problem 19B. Show that if an $S(3, 6, v)$ exists, then $v \equiv 2$ or $6 \pmod{20}$.

The number of blocks incident with any point, i.e. b_1 , is usually denoted by r (*replication number*). Two special cases of Theorem 19.3 are the following relations for the parameters of a 2-design:

$$(19.3) \quad bk = vr,$$

$$(19.4) \quad \lambda(v-1) = r(k-1).$$

Theorem 19.4. *Let $0 \leq j \leq t$. The number of blocks of an $S_\lambda(t, k, v)$ that are incident with none of the points of a j -subset J of \mathcal{P} is*

$$(19.5) \quad b^j = \lambda \binom{v-j}{k} / \binom{v-t}{k-t}.$$

PROOF: For $x \in \mathcal{P}$, let \mathcal{B}_x be the set of blocks incident with x . We use inclusion-exclusion, Theorem 10.1. We find that

$$b^j = \sum_{i=0}^j (-1)^i \binom{j}{i} b_i.$$

The result follows by substitution of (19.2) and then using (10.5).

It is quicker to observe that b^j apparently does not depend on the particular set J and then count in two ways the pairs (J, B) , where J is a j -subset of \mathcal{P} and $J \cap B = \emptyset$. So $\binom{v}{j} b^j = b \binom{v-k}{j}$. Then the result follows from Theorem 19.2. \square

Corollary. *If $i + j \leq t$, then the number of blocks of an $S_\lambda(t, k, v)$ that are incident with all of a set of i points and none of a disjoint set of j points is a constant*

$$(19.6) \quad b_i^j = \lambda \frac{\binom{v-i-j}{k-i}}{\binom{v-t}{k-t}}.$$

PROOF: The result follows upon application of Theorem 19.4 to the $(t-i)$ -design \mathcal{D}_I , where I is the set of i points. \square

Corollary. *If J is a j -subset of \mathcal{P} , $j \leq t$, then the point set $\mathcal{P} \setminus J$ and the blocks B with $B \cap J = \emptyset$ form an $S_\mu(t-j, k, v-j)$ called the residual design \mathcal{D}^J .*

Problem 19C. (i) Prove that an $S_\lambda(t, k, v)$ with $v \leq k+t$ is trivial. (ii) Prove that the complement of an $S_\lambda(t, k, v)$ with $v \geq k+t$ is a t -design and determine its parameters.

Example 19.5. Consider a Hadamard 3-design $3-(4k, 2k, k-1)$ and form the residual with respect to a set with one point. We find

a Hadamard 2-design $2-(4k - 1, 2k, k)$, i.e. the complement of the design of Example 19.3.

An obvious necessary condition for the existence of an $S_\lambda(t, k, v)$ is that the numbers b_i of (19.2) are integers. However, this condition is not sufficient. An $S(10, 16, 72)$ does not exist, as is demonstrated by the following theorem due to Tits (1964).

Theorem 19.5. *In any nontrivial Steiner system $S(t, k, v)$,*

$$v \geq (t + 1)(k - t + 1).$$

PROOF: In a Steiner system, any two distinct blocks have at most $t - 1$ points in common. Choose a set S of $t + 1$ points not contained in any block. For each set $T \subseteq S$ with $|T| = t$, there is a unique block B_T containing T . Each such B_T is incident with $k - t$ points not in S , and any point not in S is incident with at most one such block B_T since two such blocks already have $t - 1$ points of S in common. This shows that the union of all blocks B_T contains $(t + 1) + (t + 1)(k - t)$ points and the result follows. \square

Given an incidence structure with $|\mathcal{P}| = v$ and $|\mathcal{B}| = b$, the *incidence matrix* N is the $v \times b$ matrix with rows indexed by the elements p of \mathcal{P} , columns indexed by the elements B of \mathcal{B} , and with the entry $N(p, B) = 1$ if p is incident with B , $N(p, B) = 0$ otherwise. Note that the entry in row p and column q of NN^\top is the sum of $N(p, B)N(q, B)$ over all blocks B , and this is the number of blocks that contain both p and q . Dually, the entry in row A and column B of $N^\top N$ is the cardinality of $A \cap B$.

Two designs \mathcal{D} and \mathcal{D}' with incidence matrices N and N' are called *isomorphic* or *equivalent* if there are permutation matrices P and Q such that $N' = PNQ$.

We shall often identify N with the design, i.e. we refer to the columns as blocks instead of as characteristic functions of blocks.

Now if N is the incidence matrix of a 2-design, then NN^\top has the entry r everywhere on the diagonal and entries λ in all other positions, i.e.

$$(19.7) \quad NN^\top = (r - \lambda)I + \lambda J,$$

where I and J are $v \times v$ matrices.

Problem 19D. Let N be an 11 by 11 (0,1)-matrix with the following properties: (i) every row of N has six ones; (ii) the inner product of any two distinct rows of N is at most 3. Show that N is the incidence matrix of a 2-(11,6,3) design. Furthermore show that this design is unique (up to isomorphism).

The following theorem is known as *Fisher's inequality*.

Theorem 19.6. For a 2-(v, k, λ) design with b blocks and $v > k$ we have

$$b \geq v.$$

PROOF: Since $v > k$, we have $r > \lambda$ by (19.4). Since J has one eigenvalue v and its other eigenvalues are 0, the matrix on the right-hand side of (19.7) has $v - 1$ eigenvalues $(r - \lambda)$ and one eigenvalue $(r - \lambda) + \lambda v = rk$. So it has determinant $rk(r - \lambda)^{v-1} \neq 0$ and hence N has rank v . This implies that $b \geq v$. \square

From the argument in the preceding proof, we can make a very important conclusion, given in the next theorem.

Theorem 19.7. If a 2-(v, k, λ) design has $b = v$ blocks and v is even, then $k - \lambda$ must be a square.

PROOF: Since $b = v$, we have $r = k$. Now N is a $v \times v$ matrix and by (19.7)

$$(\det N)^2 = k^2(k - \lambda)^{v-1}.$$

Since $\det N$ is an integer, we are done. \square

Theorem 19.6 was generalized by A. Ya. Petrenjuk (1968) to $b \geq \binom{v}{2}$ for any $S_\lambda(4, k, v)$ with $v \geq k + 2$ and finally generalized to arbitrary t -designs by Ray-Chaudhuri and Wilson (1975).

Theorem 19.8. For an $S_\lambda(t, k, v)$ with $t \geq 2s$ and $v \geq k + s$, we have $b \geq \binom{v}{s}$.

PROOF: We introduce the *higher incidence matrices* of the t -design $\mathcal{D} = S_\lambda(t, k, v)$. For $i = 0, 1, 2, \dots$, let N_i denote the $\binom{v}{i} \times b$ matrix with rows indexed by the i -element subsets of points, columns indexed by the blocks, and with entry 1 in row Y and column B if $Y \subseteq B$, 0 otherwise. For $0 \leq i \leq j \leq v$, we use W_{ij} to denote the i -th incidence matrix of the incidence structure whose blocks

are all the j -element subsets of a v -set. Thus W_{ij} is a $\binom{v}{i} \times \binom{v}{j}$ matrix.

We claim that

$$N_s N_s^\top = \sum_{i=0}^s b_{2s-i}^i W_{is}^\top W_{is}.$$

To see this, note that $N_s N_s^\top$ has rows indexed by s -element subsets E and columns indexed by s -element subsets F of the points, and for given E and F , the entry in row E and column F of $N_s N_s^\top$ is the number of blocks that contain both E and F . This number is $b_{2s-\mu}$, where $\mu := |E \cap F|$. The entry in row E and column F of $W_{is}^\top W_{is}$ is the number of i -subsets of the points contained in both E and F , i.e. $\binom{\mu}{i}$. So the (E, F) -entry on the right-hand side of the equation is $\sum_{i=1}^s b_{2s-i}^i \binom{\mu}{i}$, and from (19.6) it follows that this is $b_{2s-\mu}$.

The $\binom{v}{s} \times \binom{v}{s}$ matrices $b_{2s-i}^i W_{is}^\top W_{is}$ are all positive semidefinite, and $b_s^s W_{ss}^\top W_{ss} = b_s^s I$ is positive definite since $b_s^s > 0$ ($v \geq k + s$). Therefore $N_s N_s^\top$ is positive definite and hence nonsingular. The rank of $N_s N_s^\top$ is equal to the rank of N_s , i.e. N_s has rank $\binom{v}{s}$, and this cannot exceed the number of columns of N_s , which is b . \square

If equality holds in the Wilson–Petrenjuk inequality, Theorem 19.8, then the $2s$ -design is called *tight*. The only known examples with $s > 1$ and $v > k + s$ are the unique Steiner system $S(4, 7, 23)$ that we treat in the next chapter, and its complement.

It is useful to give some idea of the history of t -designs. Only finitely many Steiner systems $S(t, k, v)$ with $t \geq 4$ are known. The most famous are the designs $S(5, 8, 24)$ and $S(5, 6, 12)$ found by E. Witt (1938) and the derived 4-designs. These will appear in the next chapter. R. H. F. Denniston (1976) constructed $S(5, 6, 24)$, $S(5, 7, 28)$, $S(5, 6, 48)$, and $S(5, 6, 84)$. W. H. Mills (1978) constructed an $S(5, 6, 72)$. Again, the derived designs are Steiner systems. M. J. Granell and T. S. Griggs (1994) constructed an $S(5, 6, 108)$. Since then, no others have been found. In 1972, W. O. Alltop constructed the first infinite sequence of 5-designs without repeated blocks. We remark that it is easy to show that t -designs with repeated blocks exist for any t , but for a long time many design theorists believed that nontrivial t -designs without repeated

blocks did not exist for $t > 6$. The first simple 6-design was found by D. W. Leavitt and S. S. Magliveras in 1982, and in 1986 D. L. Kreher and S. P. Radziszowski found the smallest possible simple 6-design, an $S_4(6, 7, 14)$. The big sensation in this area was the paper by L. Teirlinck (1987) proving that nontrivial simple t -designs exist for all t . His construction produces designs with tremendously large parameters and hence the construction of small examples is still an open problem. For a number of special parameter sets, it has been shown that the corresponding designs do not exist.

For the remainder of this chapter we shall mainly be interested in 2-designs. When $t = 2$, we often omit this parameter in the ' t - (v, k, λ) ' notation and speak of (v, k, λ) -designs.

A class of designs of special interest are the 2-designs with $b = v$. In this case the incidence matrix N of the design is a square matrix and these designs should be called *square designs*. However, the confusing name *symmetric designs* is standard terminology. (Note that N is *not* necessarily symmetric.) For a symmetric 2- (v, k, λ) design (19.4) becomes

$$\lambda(v - 1) = k(k - 1).$$

Some authors use the name *projective design*, a name derived from the fact that a 2- $(v, k, 1)$ design with $b = v$ is called a projective plane (see Example 19.7). Despite the fact that we are not happy with the name, we shall use the terminology *symmetric designs* for these designs.

Problem 19E. Let \mathcal{D} be a 2- (v, k, λ) design with b blocks and r blocks through every point. Let B be any block. Show that the number of blocks that meet B is at least

$$k(r - 1)^2 / [(k - 1)(\lambda - 1) + (r - 1)].$$

Show that equality holds if and only if any block not disjoint from B meets it in a constant number of points.

Example 19.6. Take as points the elements of \mathbb{Z}_7 and as blocks all triples $B_x := \{x, x + 1, x + 3\}$ with $x \in \mathbb{Z}_7$. It is easy to check that this yields an $S(2, 3, 7)$. The following Fig. 19.2 is often drawn.

The lines represent blocks, but one block must be represented by the circle.




Figure 19.2

This design is known as the *Fano plane*. The idea of the construction will be extended in Chapter 27. It is based on the fact that the six differences among the elements of $\{0, 1, 3\}$ are exactly all the nonzero elements of \mathbb{Z}_7 . If we wish to find the block containing say $\{1, 6\}$, we observe that $6 - 1 = 1 - 3$ and we therefore take $x = 5$ and find $x + 1 = 6$, $x + 3 = 1$, i.e. the pair is indeed in B_5 . The reader should have no difficulty finding an $S(2, 4, 13)$ in the same way, using \mathbb{Z}_{13} .

A symmetric design with $\lambda = 1$ is called a *projective plane*. If k is the size of the blocks, then $n = k - 1$ is called the *order* of the plane (why this is done will become clear in Example 19.7). Expressed in n , the parameters of a projective plane of order n are:

$$v = n^2 + n + 1, \quad k = n + 1, \quad \lambda = 1.$$

The blocks are usually called *lines*. The Fano plane is the (unique) projective plane of order 2.

Example 19.7. Consider the vector space \mathbb{F}_q^3 . This vector space contains $(q^3 - 1)/(q - 1) = q^2 + q + 1$ 1-dimensional subspaces and the same number of 2-dimensional subspaces. We now construct an incidence structure $(\mathcal{P}, \mathcal{B}, \mathbf{I})$, where \mathcal{P} and \mathcal{B} are these two classes of subspaces of \mathbb{F}_q^3 . If a 1-dimensional subspace is contained in a 2-dimensional subspace, we say they are incident. It is immediately clear that we have thus defined a projective plane of order q , i.e. a 2 - $(q^2 + q + 1, q + 1, 1)$ design. This design is usually denoted

by $PG(2, q)$ or $PG_2(q)$, which stands for projective geometry of dimension 2 and order q .

The construction defined above can also be applied if we replace \mathbb{F}_q by \mathbb{R} . We then obtain the classical real projective plane, where points are the 1-dimensional subspaces and lines are the 2-dimensional subspaces. This geometry contrasts with classical affine geometry in the fact that no two lines are parallel. When speaking about the designs defined above, we use terminology from geometry.

Problem 19F. Find a subset $S = \{s_1, \dots, s_5\}$ of \mathbb{Z}_{21} such that the elements of \mathbb{Z}_{21} as points and the 21 blocks $S + x$ ($x \in \mathbb{Z}_{21}$) form a projective plane of order 4. (Hint: there is a solution S for which $2S = S$.)

Problem 19G. Let $(R, C, S; L)$ be a Latin square of order 6. Define $\mathcal{P} := R \times C$. Let \mathcal{B} be the set of blocks

$$B_{ij} := \{(x, y) \in R \times C : x = i \text{ or } y = j \text{ or } L(x, y) = L(i, j)\} \setminus \{(i, j)\}$$

for $(i, j) \in R \times C$.

- (1) Show that this defines a 2-(36, 15, 6) design.
- (2) Show that a regular Hadamard matrix of order 36 exists.

Problem 19H. Let \mathcal{D} be a 3-(v, k, λ) design. Suppose that the derived design of \mathcal{D} with respect to a point p (i.e. the case $i = 1$ in the Corollary to Theorem 19.3) is a symmetric design.

- (1) Show that $\lambda(v - 2) = (k - 1)(k - 2)$.
- (2) Show that any two blocks of \mathcal{D} meet in 0 or $\lambda + 1$ points.
- (3) Show that the set of points not on a block B together with the blocks disjoint from B form a 2-design \mathcal{D}^B .
- (4) Apply Fisher's inequality to the design \mathcal{D}^B and deduce that $v = 2k$ or otherwise $k = (\lambda + 1)(\lambda + 2)$ or $k = 2(\lambda + 1)(\lambda + 2)$.

What are the possibilities for the design \mathcal{D} ? Do we know any designs with these properties?

Problem 19I. Let O be a subset of the points of a projective plane of order n such that no three points of O are on one line.

Show that $|O| \leq n + 1$ if n is odd and that $|O| \leq n + 2$ if n is even. A set of $n + 1$ points, no three on a line, is called an *oval*; a set of $n + 2$ points, no three on a line, is a *hyperoval*. Two constructions of $PG_2(4)$ were given in Example 19.7 and Problem 19F. In each case, construct a hyperoval.

Problem 19J. Let O be a hyperoval (with $q + 2$ points) in $PG_2(q)$, $q = 2^m$. Any of the $q^2 - 1$ points $p \notin O$ has the property that there are exactly $\frac{1}{2}(q + 2)$ secants of O through p . Take five points on O and split them into

$$\{\{p_1, p_2\}, \{p_3, p_4\}, \{p_5\}\}.$$

This can be done in 15 ways. The two pairs determine two secants that meet in a point $p \notin O$. The line through p and p_5 meets O in a point, that we call p_6 . This defines 15 (not necessarily distinct) 6-tuples of points on O , containing the given five points. This defines an $S_\lambda(5, 6, q + 2)$, a construction due to D. Jungnickel and S. A. Vanstone (1987). Show that the points with ‘coordinates’ (as in Example 19.7) $(1, t, t^2)$, $t \in \mathbb{F}_q$, with $(0, 1, 0)$ and $(0, 0, 1)$ form a hyperoval O in $PG_2(q)$. Show that a suitable choice of p_1 to p_5 on O with the construction explained above yields repeated blocks, i.e. the 5-design is not simple.

Any $2-(n^2, n, 1)$ design is called an *affine plane*. The points and lines of the plane (= 2-dimensional vector space) \mathbb{F}_q^2 form an affine plane of order q . For such a design we use the notation $AG_2(n)$ (2-dimensional affine geometry of order n).

Example 19.8. Let \mathcal{D} be a projective plane of order n . If we delete one line and all the points on that line, we find an affine plane of order n .

Problem 19K. Let \mathcal{D} be any affine plane of order n . If B_1 and B_2 are two blocks, then we write $B_1 \sim B_2$ if the two blocks are the same or if they have no points in common. Show that \sim is an equivalence relation. A class of this relation is called a *parallel class*. Show that there exists a projective plane of order n such that \mathcal{D} can be obtained from that plane by the construction of Example 19.8.

We shall now show that if N is the incidence matrix of a symmetric design \mathcal{D} , then N^\top is also the incidence matrix of a symmetric design \mathcal{D}^\top , called the *dual* of \mathcal{D} .

Theorem 19.9. *Let N be the incidence matrix of a symmetric 2 -(v, k, λ) design. Then N^\top is also the incidence matrix of a design.*

PROOF: Consider any block B of the design. For $0 \leq i \leq k$ let a_i be the number of blocks ($\neq B$) that have i points in common with B . Then counting blocks, pairs (p, B') with $p \in B \cap B'$ and triples (p, q, B') with $p \neq q$ and $\{p, q\} \subseteq B \cap B'$ we find:

$$\sum_{i=0}^k a_i = v - 1, \quad \sum_{i=0}^k i a_i = k(k - 1), \quad \sum_{i=0}^k \binom{i}{2} a_i = \binom{k}{2}(\lambda - 1),$$

from which we find $\sum_{i=0}^k (i - \lambda)^2 a_i = 0$. Hence, any block $B' \neq B$ has λ points in common with B , i.e. $N^\top N = (k - \lambda)I + \lambda J$. \square

Note that in Example 19.7, we did not need to specify whether the set \mathcal{P} was the 1-dimensional subspaces or the 2-dimensional subspaces. In the latter situation, we have the dual of the former.

In many cases the designs \mathcal{D} and \mathcal{D}^\top are not isomorphic.

Let \mathcal{D} be a symmetric 2 -(v, k, λ) design. There are two other ways to obtain a design from \mathcal{D} . These two designs are called the *derived* design and *residual* design of \mathcal{D} . This could be somewhat confusing since we have already introduced that terminology. We shall always indicate which of the two we mean. Take any block B of \mathcal{D} . The residual of \mathcal{D} with respect to B has $\mathcal{P} \setminus B$ as point set and as blocks all $B' \setminus B$ with $B' \neq B$. It is a 2 -($v - k, k - \lambda, \lambda$) design. The derived design has B as point set and as blocks all $B' \cap B$ with $B' \neq B$. It is a 2 -($k, \lambda, \lambda - 1$) design. If a design with parameters v, k, b, r, λ is the residual of a symmetric design, then $r = k + \lambda$. Any 2-design for which this equation holds is called a *quasiresidual* design. If such a design is not the residual of a symmetric design, then we say that it is *nonembeddable*. The assertion of Problem 19K is that every affine plane is embeddable in a projective plane. A theorem due to W. S. Connor (1952), that we shall leave until Chapter 21, states that every quasiresidual design with $\lambda = 2$ is embeddable.

Example 19.9. Let $C := \begin{pmatrix} 0 & 1 & 0 \\ 0 & 0 & 1 \\ 1 & 0 & 0 \end{pmatrix}$ and let E_i denote a 3 by 3 matrix with ones in column i and zeros elsewhere. Then

$$N := \begin{pmatrix} E_1 & I & I & I \\ E_2 & I & C & C^2 \\ E_3 & I & C^2 & C \end{pmatrix}$$

is the 9 by 12 incidence matrix of $AG_2(3)$. Define

$$A := \begin{pmatrix} 1 & 1 & 1 & 1 & 1 & 1 & 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0 \\ 1 & 1 & 1 & 0 & 0 & 0 & 1 & 1 & 1 & 0 & 0 & 0 & 0 & 0 \\ 1 & 1 & 1 & 0 & 0 & 0 & 0 & 0 & 0 & 0 & 1 & 1 & 1 & 1 \\ 0 & 0 & 0 & 1 & 1 & 1 & 1 & 1 & 1 & 0 & 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 1 & 1 & 1 & 0 & 0 & 0 & 1 & 1 & 1 & 1 & 1 \\ 0 & 0 & 0 & 0 & 0 & 0 & 1 & 1 & 1 & 1 & 1 & 1 & 1 & 1 \end{pmatrix}, \quad B := \begin{pmatrix} 1 & 1 & 0 & 0 \\ 1 & 1 & 0 & 0 \\ 1 & 1 & 0 & 0 \\ 1 & 0 & 1 & 0 \\ 1 & 0 & 1 & 0 \\ 1 & 0 & 1 & 0 \\ 1 & 0 & 0 & 1 \\ 1 & 0 & 0 & 1 \\ 1 & 0 & 0 & 1 \end{pmatrix}.$$

Form the 24 by 16 matrix

$$D := \begin{pmatrix} A & O \\ N & B \\ N & J - B \end{pmatrix}.$$

One easily checks that D^\top is the 16 by 24 incidence matrix of a 2-(16,6,3) design. This is a quasiresidual design. However, it cannot be the residual of a 2-(25,9,3) symmetric design because the inner product of row $i + 6$ and row $i + 15$ of D , $1 \leq i \leq 9$, equals 4 and, by Theorem 19.9, the inner product of the columns of the incidence matrix of a 2-(25,9,3) design is 3. This shows that nonembeddable designs with $\lambda = 3$ exist.

The combination of a counting argument and a suitable quadratic form that we used to prove Theorem 19.9 is widely used in combinatorics. However, sometimes it is easier to use algebraic methods as we shall demonstrate in the following theorem, due to Ryser. (The reader can try to prove the theorem by using counting arguments.)

Theorem 19.10. *Let $\mathcal{D} = (\mathcal{P}, \mathcal{B}, \mathbf{I})$ be an incidence structure with $|\mathcal{P}| = |\mathcal{B}| = v$, block-size k , such that any two blocks meet in λ points. Then \mathcal{D} is a symmetric 2-design.*

PROOF: Let N be the incidence matrix of \mathcal{D} . Then

$$(19.8) \quad N^{\top}N = (k - \lambda)I + \lambda J,$$

and

$$(19.9) \quad JN = kJ.$$

By Theorem 19.9, we are done if we can show that $NJ = kJ$. From (19.8) we see that N is nonsingular and hence (19.9) can be read as $J = kJN^{-1}$. From (19.8) we find $JN^{\top}N = (k - \lambda + \lambda v)J$ and therefore

$$JN^{\top} = (k - \lambda + \lambda v)JN^{-1} = (k - \lambda + \lambda v)k^{-1}J,$$

i.e. N has constant row-sums. Then these row-sums must be k . This proves the theorem and yields $(k - \lambda + \lambda v)k^{-1} = k$ as was to be expected from (19.3) and (19.4). \square

As a preparation for the best known nonexistence theorem for designs, we need two results, both due to Lagrange. For the first, consider the matrix H of (18.6) with $n = 1$, i.e. $A_i = (a_i)$. Define $\mathbf{y} = (y_1, y_2, y_3, y_4)$ by $\mathbf{y} := \mathbf{x}H$, where $\mathbf{x} = (x_1, x_2, x_3, x_4)$. Then from (18.7) we find

$$(19.10) \quad (a_1^2 + a_2^2 + a_3^2 + a_4^2)(x_1^2 + x_2^2 + x_3^2 + x_4^2) = (y_1^2 + y_2^2 + y_3^2 + y_4^2).$$

Using this identity, Lagrange proved that every integer is the sum of four squares. Clearly the identity shows that it is sufficient to prove this for primes. For an elegant proof that a prime is the sum of four squares we refer to Chandrasekharan (1968).

The following nonexistence theorem is known as the Bruck–Ryser–Chowla theorem.

Theorem 19.11. *If v, k, λ are integers such that $\lambda(v - 1) = k(k - 1)$, then for the existence of a symmetric 2- (v, k, λ) design it is necessary that:*

- (i) *if v is even then $k - \lambda$ is a square;*
- (ii) *if v is odd, then the equation $z^2 = (k - \lambda)x^2 + (-1)^{(v-1)/2}\lambda y^2$ has a solution in integers x, y, z , not all zero.*

PROOF: Assertion (i) was proved in Theorem 19.7. So assume that v is odd. Let \mathcal{D} be a symmetric $2-(v, k, \lambda)$ design with incidence matrix $N = (n_{ij})$ and write $n := k - \lambda$. We now introduce v linear forms L_i in the variables x_1, \dots, x_v by

$$L_i := \sum_{j=1}^v n_{ij} x_j, \quad 1 \leq i \leq v.$$

Then the equation $N^\top N = (k - \lambda)I + \lambda J$ implies that

$$(19.11) \quad L_1^2 + \dots + L_v^2 = n(x_1^2 + \dots + x_v^2) + \lambda(x_1 + \dots + x_v)^2.$$

By Lagrange's theorem, n can be written as $n = a_1^2 + \dots + a_4^2$. This and (19.10) allow us to take four of the variables x_j and write

$$(19.12) \quad n(x_i^2 + x_{i+1}^2 + x_{i+2}^2 + x_{i+3}^2) = (y_i^2 + y_{i+1}^2 + y_{i+2}^2 + y_{i+3}^2),$$

where each y_j is a linear form in the four variables x_i, \dots, x_{i+3} .

We now first assume that $v \equiv 1 \pmod{4}$. By applying this to (19.11), four variables at a time, and introducing w for $x_1 + \dots + x_v$, we reduce (19.11) to

$$(19.13) \quad L_1^2 + \dots + L_v^2 = y_1^2 + \dots + y_{v-1}^2 + nx_v^2 + \lambda w^2.$$

Since H in (18.6) is invertible, we can express the variables x_j for $1 \leq j \leq v - 1$ as linear forms in the corresponding y_j and hence w is a linear form in these variables and x_v . Next, we reduce the number of variables in the following way. If the linear form L_1 , expressed in y_1, \dots, y_{v-1}, x_v , does not have coefficient $+1$ for y_1 , then we set $L_1 = y_1$, and if the coefficient is $+1$, we set $L_1 = -y_1$, and in both cases, we subsequently solve this equation for y_1 as a linear expression in the remaining variables y_j and x_v . This is substituted in the expression w . So (19.11) has been reduced to

$$L_2^2 + \dots + L_v^2 = y_2^2 + \dots + y_{v-1}^2 + nx_v^2 + \lambda w^2.$$

We proceed in this way for y_2, \dots, y_{v-1} . In each step, w is replaced by another linear form in the remaining variables, and hence we end up with

$$L_v^2 = nx_v^2 + \lambda w^2,$$

in which both L_v and w are rational multiples of the variable x_v . If we multiply this by the common denominator of the factors, we find an equation

$$z^2 = (k - \lambda)x^2 + \lambda y^2$$

in integers. This proves the assertion if $v \equiv 1 \pmod{4}$. If $v \equiv 3 \pmod{4}$, the same procedure is applied to (19.13) after adding nx_{v+1}^2 to both sides, where x_{v+1} is a new variable. The equation is then finally reduced to $nx_{v+1}^2 = y_{v+1}^2 + \lambda w^2$ and again we multiply by a common denominator to find an equation of type

$$(k - \lambda)x^2 = z^2 + \lambda y^2$$

in accordance with assertion (ii). □

Example 19.10. From Example 19.7, we know that a projective plane of order n exists for $2 \leq n \leq 9$, except possibly for $n = 6$. By Theorem 19.11, a necessary condition for the existence of a projective plane of order 6 is that the equation $z^2 = 6x^2 - y^2$ has a nontrivial solution. If such a solution exists, then also one for which x , y , and z have no prime factor in common, i.e. z and y are both odd. Then z^2 and y^2 are both $\equiv 1 \pmod{8}$. Since $6x^2 \pmod{8}$ is either 0 or 6, we see that the equation has only the trivial solution $(0,0,0)$. Therefore a projective plane of order 6 does not exist.

If we try the same thing for a plane of order 10, we find the equation $z^2 = 10x^2 - y^2$, which has the solution $x = 1$, $y = 1$, $z = 3$. In this case Theorem 19.11 tells us nothing. In 1989, Lam et al. announced that a computer search involving several hundred hours on a Cray 1 had excluded the existence of a projective plane of order 10. This is the only case where the nonexistence of a symmetric 2-design has been shown using something other than Theorem 19.11.

Corollary. *If there exists a projective plane of order $n \equiv 1$ or $2 \pmod{4}$, then n is the sum of two integral squares.*

PROOF: The condition $n \equiv 1$ or $2 \pmod{4}$ implies that $v = n^2 + n + 1 \equiv 3 \pmod{4}$. Theorem 19.11 asserts that n is the sum of two rational squares. It is well known that n is the sum of two rational squares if and only if n is the sum of two integral squares. (This

follows from the condition that n is the sum of two integral squares if and only if no prime divisor of the square-free part of n is $\equiv 3 \pmod{4}$.) \square

Problem 19L. Show that a symmetric 2 -($29, 8, 2$) design does not exist.

Problem 19M. Suppose M is a rational square matrix of order v and that $MM^T = mI$. Show that if v is odd, then m is a square. Show that if $v \equiv 2 \pmod{4}$, then m is the sum of two rational squares.

(Note that one consequence of this latter result is that the existence of a conference matrix of order $n \equiv 2 \pmod{4}$ implies that $n - 1$ is the sum of two squares.)

A great deal of work has been done on the construction of 2 -designs. We shall only treat a number of examples that will give some idea of the kind of methods that have been used. The smallest nontrivial pair (k, λ) to consider is $(3, 1)$. A 2 -($v, 3, 1$) design is called a *Steiner triple system*. One uses the notation $STS(v)$ for such a design. By (19.3) and (19.4), a necessary condition for the existence of such a design is that $v \equiv 1 \pmod{6}$ or $v \equiv 3 \pmod{6}$. We shall show that this condition is also sufficient. This will be done by direct construction in Examples 19.11 and 19.15. However, it is useful to see a number of examples of a more complicated approach. The methods that we demonstrate can be used for the construction of other designs than Steiner triple systems. Furthermore, they can be used to produce designs with certain subdesigns (see Problem 19N) or prescribed automorphism group. The idea of this approach is to find direct constructions for small examples and some recursive constructions, and subsequently show that, for any v that satisfies the necessary conditions, an $STS(v)$ can be constructed by the recursive methods, using the list of known small examples. We shall see below that this in fact reduces to a (not very difficult) problem in number theory. As stated above, we restrict ourselves to a number of examples. The reader may wish to try to show that our examples suffice to find an $STS(v)$ for all possible values of v , without using Examples 19.11 and 19.15.

We consider the trivial design with only one block of size 3

as $STS(3)$. We have already seen constructions of $STS(7) = PG_2(2)$ and $STS(9) = AG_2(3)$. In Example 19.1, we constructed an $STS(15)$.

Example 19.11. Let $n = 2t + 1$. We define $\mathcal{P} := \mathbb{Z}_n \times \mathbb{Z}_3$. As blocks we take all triples $\{(x, 0), (x, 1), (x, 2)\}$ with $x \in \mathbb{Z}_n$ and all triples $\{(x, i), (y, i), (\frac{1}{2}(x + y), i + 1)\}$ with $x \neq y$ in \mathbb{Z}_n and $i \in \mathbb{Z}_3$. This simple construction provides an $STS(6t + 3)$ for every t .

Example 19.12. Let $q = 6t + 1$ be a prime power and let α be a primitive element in \mathbb{F}_q , i.e. \mathbb{F}_q^* is a cyclic group generated by α . We define

$$(19.14) \quad B_{i,\xi} := \{\alpha^i + \xi, \alpha^{2t+i} + \xi, \alpha^{4t+i} + \xi\}, \quad 0 \leq i < t, \quad \xi \in \mathbb{F}_q.$$

We claim that the elements of \mathbb{F}_q as points and the blocks $B_{i,\xi}$ form an $STS(q)$. The idea of the proof is the same as in Example 19.6. Note that $\alpha^{6t} = 1$, $\alpha^{3t} = -1$ and define s by $\alpha^s = (\alpha^{2t} - 1)$. We consider the six differences of pairs from $B_{0,0}$. These are:

$$\begin{aligned} \alpha^{2t} - 1 &= \alpha^s, & -(\alpha^{2t} - 1) &= \alpha^{s+3t}, \\ \alpha^{4t} - \alpha^{2t} &= \alpha^{s+2t}, & -(\alpha^{4t} - \alpha^{2t}) &= \alpha^{s+5t}, \\ \alpha^{6t} - \alpha^{4t} &= \alpha^{s+4t}, & -(1 - \alpha^{4t}) &= \alpha^{s+t}. \end{aligned}$$

It follows that for any $\eta \neq 0$ in \mathbb{F}_q , there is a unique i , $0 \leq i < t$, such that η occurs as the difference of two elements of $B_{i,0}$. Hence for any x and y in \mathbb{F}_q , there is a unique i and a unique $\xi \in \mathbb{F}_q$ such that the pair x, y occurs in the block $B_{i,\xi}$. \square

The method of Examples 19.6 and 19.12 is known as the *method of differences*. Example 19.15 will show a more complicated use of the same idea.

We now know that an $STS(v)$ exists for $v = 13, 19, 25, 31, 37, 43$ and 49 as well as the values mentioned above. This includes all $v \equiv 1 \pmod{6}$ less than 50 . In fact, we now know at least one $STS(v)$ for each feasible value of v less than 100 , except $v = 55$, $v = 85$, $v = 91$.

Example 19.13. Let there be an $STS(v_i)$ on the point set V_i ($i = 1, 2$). We take $V_1 \times V_2$ as a new point set and define as blocks all triples: $\{(x_1, y_1), (x_2, y_2), (x_3, y_3)\}$ for which

- (1) $x_1 = x_2 = x_3$ and $\{y_1, y_2, y_3\}$ is a block of $STS(v_2)$;
- (2) $\{x_1, x_2, x_3\}$ is a block of $STS(v_1)$ and $y_1 = y_2 = y_3$;
- (3) $\{x_1, x_2, x_3\}$ is a block of $STS(v_1)$ and $\{y_1, y_2, y_3\}$ is a block of $STS(v_2)$.

It is practically obvious that this defines an $STS(v_1v_2)$. The reader should check that we have defined the correct number of blocks.

This construction provides us with an $STS(91)$.

Example 19.14. We show a slightly more complicated construction. Suppose that we have an $STS(v_1)$ on the point set $V_1 = \{1, 2, \dots, v_1\}$ with block set S_1 , and furthermore suppose that the blocks that are completely contained in $V = \{s + 1, \dots, v_1\}$, where $s = v_1 - v$, form an $STS(v)$. Let S_2 be the set of triples of an $STS(v_2)$ on the point set $V_2 = \{1, 2, \dots, v_2\}$.

We consider a new point set

$$\mathcal{P} := V \cup \{(x, y) : 1 \leq x \leq s, 1 \leq y \leq v_2\}.$$

This set has $v + v_2(v_1 - v)$ points. We introduce a set \mathcal{B} of four kinds of blocks:

- (1) those of the subsystem $STS(v)$;
- (2) $\{(a, y), (b, y), c\}$ with $c \in V$, $\{a, b, c\} \in S_1$ and $y \in V_2$;
- (3) $\{(a, y), (b, y), (c, y)\}$ with $\{a, b, c\}$ a block in S_1 with no point in V , and $y \in V_2$;
- (4) $\{(x_1, y_1), (x_2, y_2), (x_3, y_3)\}$, where $\{y_1, y_2, y_3\}$ is a block in S_2 and the integers x_1, x_2, x_3 satisfy

$$x_1 + x_2 + x_3 \equiv 0 \pmod{s}.$$

Again, one easily checks that any two points of \mathcal{P} uniquely determine a block in \mathcal{B} . Hence \mathcal{P} and \mathcal{B} are the points and blocks of a Steiner triple system on $v + v_2(v_1 - v)$ points. A simple example is obtained by letting the subsystem be just one block, i.e. $v = 3$. Taking $v_1 = 7$, $v_2 = 13$, we find an $STS(55)$.

We have thus constructed an $STS(v)$ for every feasible value of v less than 100, except $v = 85$.

Problem 19N. (a) Show that if an $STS(v_1)$ and an $STS(v_2)$ both exist, then there is an $STS(v_1v_2 - v_2 + 1)$. Use this construction to find an $STS(85)$.

(b) Construct an $STS(15)$ on the set $\{0, 1, \dots, 14\}$ such that it contains a Fano plane on $\{0, 1, \dots, 6\}$ as a subsystem.

Example 19.15. Consider as point set $\mathbb{Z}_{2t} \times \mathbb{Z}_3 \cup \{\infty\}$. Addition of elements is coordinatewise with the extra convention $\infty + (x, i) = \infty$. For notational convenience we sometimes write the second coordinate as an index, i.e. x_i instead of (x, i) . We now define four types of ‘base blocks’:

- (1) $\{0_0, 0_1, 0_2\}$;
- (2) $\{\infty, 0_0, t_1\}, \{\infty, 0_1, t_2\}, \{\infty, 0_2, t_0\}$;
- (3) $\{0_0, i_1, (-i)_1\}, \{0_1, i_2, (-i)_2\}, \{0_2, i_0, (-i)_0\}, i = 1, \dots, t-1$;
- (4) $\{t_0, i_1, (1-i)_1\}, \{t_1, i_2, (1-i)_2\}, \{t_2, i_0, (1-i)_0\}, i = 1, \dots, t$.

We have $6t + 1$ base blocks. For $a = 0, 1, \dots, t - 1$ we add the element $(a, 0)$ (i.e. a_0) to each of the elements of every base block, thus producing $t(6t + 1)$ blocks. We claim that these are the triples of an $STS(6t + 1)$. It is trivial that the base blocks of type 2 yield a set of blocks in which every pair of points, one of which is ∞ , occurs exactly once. The cyclic nature of the definition of the base blocks shows that it is sufficient for us to check that all pairs $\{a_0, b_0\}$ with $a \neq b$ and all pairs $\{a_0, b_1\}$ occur in the triples we have defined. If $a < b$ and $b - a = 2s$, then the pair $\{a_0, b_0\}$ occurs in the triple obtained from $\{0_2, s_0, (-s)_0\}$ ‘translated’ by the element $(b - s, 0)$. Similarly, if $b - a$ is odd, we find the required pair by translating a base block of type 4. Now consider a pair $\{a_0, b_1\}$. If $a = b \leq t - 1$, we find the pair by translating the base block of type 1 by $(a, 0)$. If $a \neq b$ and $a < t$, we have to look for the pair in a translate of a base block of type 2 or of type 3. We must search for a base block in which the difference $b - a$ occurs as $y - x$ for two elements y_1, x_0 . For type 2, this difference is t and in the blocks $\{0_0, i_1, (-i)_1\}$ we find the differences $i, 1 \leq i \leq t - 1$, and $-i = 2t - i, 1 \leq i \leq t - 1$, indeed every difference once! Now, the rest of the details can be left as an exercise.

This example shows that if $v = 6t + 1$, then an $STS(v)$ exists. Combined with Example 19.11 we have a construction for every feasible value of v .

We end this chapter with an amusing application of the Fano plane. At present the idea is not used in practice but the problem itself has a practical origin, and maybe some day generalizations of the following method will be used. Suppose one wishes to store one of the integers 1 to 7 in a so-called ‘*write-once memory*’. This is a binary memory, originally filled with zeros, for which it is possible to change certain bits to ones but not back again, i.e. the state 1 is permanent. This happens in practice with paper tape, into which holes are punched, or compact discs, where a laser creates pits in certain positions. In both cases, we cannot erase what was written in the memory. To store the integers 1 to 7, we need a memory of three bits. What if one wishes to use the memory four consecutive times? The simplest solution is to have a 12-bit memory that is partitioned into four 3-bit sections, one for each consecutive usage. We assume that the memory is very expensive and we would like to be able to use a shorter memory for the same purpose. We shall now show that seven bits suffice, a saving of more than 40%.




Figure 19.3

Let $\mathcal{P} = \{1, 2, \dots, 7\}$ be the set of points of $PG_2(2)$ and let \mathcal{L} denote the set of lines. To store one of the integers 1 to 7 in a memory with positions numbered 1 to 7, we use the following rules. As a general rule: if we wish to store i and the memory is in a state corresponding to i (from a previous usage), then we do nothing. Otherwise the rules are:

- (1) if the memory is empty, store i by putting a 1 in position i ;
- (2) to store j when the memory is in state i , put a 1 in position k , where $\{i, j, k\} \in \mathcal{L}$;
- (3) to store i when the memory contains two 1's, not corresponding to i , put in two more 1's, such that i is one of the four

1's and the other three form a line in \mathcal{L} . No matter what the two original 1's were, this is possible (sometimes in two ways);

- (4) if the memory contains four 1's, we may assume that we are in the situation of Fig. 19.3. To store 3, we do nothing (by the general rule); to store one of the missing numbers, we put 1's in the other two positions; to store 1, 2, or 4, store a 1 in the empty position on the line through 3 and the number we wish to store.

We leave it as an exercise for the reader to formulate the rules for reading the memory. Note that the memory uniquely reads the integer presently stored in the memory but it cannot see how often an integer has been stored or what was stored on the previous usage.

Problem 19O. (i) Suppose \mathcal{A} is a family of subsets of an n -set X , so that any member of \mathcal{A} has odd cardinality, but such that any two distinct members of \mathcal{A} meet in an even number of points. Show that $|\mathcal{A}| \leq n$.

(ii) Suppose members of \mathcal{A} have even cardinality but any two intersect in an odd number of points. Show that $|\mathcal{A}| \leq n + 1$. Can you find examples where equality holds?

Problem 19P. Consider 2 -($v, k, \lambda = 2$) designs where $v = \binom{k+1}{2}$.

(i) Find an example with $k = 3$. (You might try five points on a circle and one in the middle.)

(ii) Let A_1, A_2, \dots, A_b be the blocks and for $i = 2, 3, \dots, b$, let $\mu_i = |A_i \cap A_1|$. Compute

$$\sum_{i=2}^b \mu_i, \quad \sum_{i=2}^b \mu_i(\mu_i - 1), \quad \sum_{i=2}^b (\mu_i - 1)(\mu_i - 2)$$

in terms of k . What can you say about the μ_i 's?

Problem 19Q. A *Generalized Steiner System* is an incidence structure with a point set \mathcal{P} of size v and a set \mathcal{B} of subsets of \mathcal{P} , again called blocks, where $|\mathcal{B}| = b$, such that every t -subset of \mathcal{P} is in a unique block. We do *not* require the blocks to have constant size

but we rule out the trivial case where $b = 1$. Denote by $b_{t,v}$ the minimal value of b for a nontrivial Generalized Steiner System. Prove that for $t \geq 2$

$$b_{t,v}(b_{t,v} - 1) \geq t \binom{v}{t}.$$

Note that for $t = 2$, this result is the same as Theorem 19.1. Much stronger bounds are known but not as easy to derive.

Problem 19R. We shall say that a point in the Fano plane is a representative of a line if it is incident with that line. How many SDR's does the Fano plane have?

Problem 19S. Construct 3 - $(2^k, 4, 1)$ designs, for all $k \geq 2$.

Problem 19T. We say that a design can be *extended* if it is a derived design of a design, called the extended design. Prove that if a symmetric design can be extended twice, it must be a 2 - $(21, 5, 1)$ design.

Problem 19U. Consider the graph G of Problem 1J. Define an incidence structure \mathbf{I} with as points the vertices of G and as lines the sets $\Gamma(x)$, for vertices $x \in G$. Show that the properties of G imply that \mathbf{I} is a projective plane. (Cf. Problem 21Q.)

Problem 19V. We use the hypothesis of, and the notation introduced in the proof of, Theorem 19.8.

(i) Check that $W_{is}N_s = \binom{k-i}{s-i}N_i$.

(ii) Show that the product of any two of $W_{is}^\top W_{is}$, $i = 0, 1, \dots, s$, is a linear combination of these $s + 1$ matrices. So the linear span \mathcal{A} of these matrices is closed under multiplication.

(iii) Suppose equality holds in Theorem 19.8 so that the matrix N_s is square. Then $N_s^\top M^{-1}N_s = I$ where $M := \sum_{i=0}^s b_{2s-i}^i W_{is}^\top W_{is}$. Since $M \in \mathcal{A}$, part (ii) implies $M^{-1} \in \mathcal{A}$. Use this to prove that there is a polynomial $f(x)$ of degree s so that $f(|A \cap B|) = 0$ for all distinct blocks A, B . (Hence there are at most s 'intersection numbers'.) This generalizes Theorem 19.9.

Notes.

The first occurrence of a 2 -design may be $AG_2(3)$ in a paper by Plücker (1839). One usually attributes the introduction of Steiner

systems to Woolhouse (1844); of course *not* to Steiner! Quite often they are said to originate with a problem of T. P. Kirkman (1847). T. P. Kirkman (1806–1895), a self-educated man, was a minister of the Church of England. He was an amateur mathematician with many contributions to the subject. Probably the best known is his *15 schoolgirls problem*. The problem is to arrange 15 schoolgirls in parties of three for seven days' walks such that every two of them walk together exactly once. This amounts to constructing an $STS(15)$ for which the set of triples can be partitioned into seven 'parallel classes'.

Jakob Steiner (1796–1863) was an important geometer of his time. He became interested in what we now call Steiner systems in 1853 when he studied the configuration of 28 double tangents of a plane quartic curve.

Sir Ronald A. Fisher (1890–1962) is considered to be one of the most prominent statisticians. Besides important contributions to statistics (multivariate analysis) and genetics, he is known for his work on the application of statistical theory to agriculture and the design of experiments. The applications to the design of agricultural experiments account for our usage of v for the number of points of a design (*varieties*) and r for the number of blocks through a point (*replication number*).

Theorem 19.7 is due to M. P. Schutzenberger (1949).

R. A. Fisher was not the only statistician to contribute to the mathematical theory of designs. In fact, we should probably consider the Indian mathematician R. C. Bose (1901–1987) to be the most important one. Many of the construction methods described in this chapter (such as the method of differences) are due to him.

G. Fano (1871–1952), whose name has become attached to the plane $PG_2(2)$, was important in the Italian school of projective geometry.

Projective planes over finite fields were first studied by K. G. C. von Staudt (1798–1867) in his book *Geometrie der Lage* (1856).

The first example of a nonembeddable quasiresidual design was given by Bhattacharya (1944). It was also a 2-(16,6,3) design. However, Example 19.9 is a much simpler example.

J. L. Lagrange (1736–1813) was born and educated in Italy but

he is considered a French mathematician (who studied in Berlin). Besides many important contributions to analysis, he is known for several theorems in number theory.

The Bruck–Ryser–Chowla theorem, Theorem 19.11, is so well known that it is often referred to as just BRC.

The idea of Example 19.15 is due to Skolem (1958). His method was actually slightly different. It has led to the term *Skolem sequences*. These have other applications, e.g. in radioastronomy. Here is the idea. Partition the set $\{1, 2, \dots, 2n\}$ into pairs $\{a_i, b_i\}$ such that $b_i - a_i = i$, $1 \leq i \leq n$. This is a Skolem sequence. For example, $\{9, 10\}$, $\{2, 4\}$, $\{5, 8\}$, $\{3, 7\}$, $\{1, 6\}$ is such a partition for $n = 5$. Now form the triples $\{0, a_i + n, b_i + n\}$ and consider these as base blocks (mod $6n + 1$). Since all the differences $1, 2, \dots, 3n$ and their negatives occur exactly once, the blocks form an $STS(6n + 1)$.

For an interesting application of the Golay code (see Chapter 20) to write-once memories, see Cohen *et al.* (1986). They show the possibility of three successive writings of 11 bits on 23 positions.

References.

- W. O. Alltop (1972), An infinite class of 5-designs, *J. Combinatorial Theory* (A) **12**, 390–395.
- K. N. Bhattacharya (1944), A new balanced incomplete block design, *Science and Culture* **9**, 108.
- R. H. Bruck and H. J. Ryser (1949), The non-existence of certain finite projective planes, *Canad. J. Math.* **1**, 88–93.
- N. G. de Bruijn and P. Erdős (1948), On a combinatorial problem, *Proc. Kon. Ned. Akad. v. Wetensch.* **51**, 1277–1279.
- K. Chandrasekharan (1968), *Introduction to Analytic Number Theory*, Springer-Verlag.
- S. Chowla and H. J. Ryser (1950), Combinatorial problems, *Canad. J. Math.* **2**, 93–99.
- G. D. Cohen, P. Godlewski, and F. Merks (1986), Linear binary codes for write-once memories, *IEEE Trans. Information Theory* **32**, 697–700.
- W. S. Connor, Jr. (1952), On the structure of balanced incomplete block designs, *Ann. Math. Stat.* **23**, 57–71; correction *ibid.* **24**, 135.

- R. H. F. Denniston (1976), Some new 5-designs, *Bull. London Math. Soc.* **8**, 263–267.
- G. Fano (1892), *Giornale di Matematiche* **30**, 114–124.
- M. J. Granell and T. S. Griggs (1994), A Steiner system $S(5, 6, 108)$, *Discrete Mathematics* **125**, 183–186.
- D. Jungnickel and S. A. Vanstone (1987), Hyperfactorizations of graphs and 5-designs, *J. Univ. Kuwait (Sci)* **14**, 213–223.
- T. P. Kirkman (1847), On a problem in combinations, *Cambridge and Dublin Math. J.* **2**, 191–204.
- D. L. Kreher and S. P. Radziszowski (1986), The existence of simple 6-(14,7,4) designs, *J. Combinatorial Theory (A)* **41**, 237–243.
- C. W. Lam, S. Swiercz, and L. Thiel (1989), The nonexistence of finite projective planes of order 10, *Canad. J. Math.* **41**, 1117–1123.
- D. W. Leavitt and S. S. Magliveras (1982), Simple 6-(33,8,36)-designs from $PGL_2(32)$, pp. 337–352, in: *Computational Group Theory, Proc. Durham 1982*.
- W. H. Mills (1978), A new 5-design, *Ars Combinatoria* **6**, 193–195.
- A. Ya. Petrenjuk (1968), On Fisher’s inequality for tactical configurations (in Russian), *Mat. Zametki* **4**, 417–425.
- D. K. Ray-Chaudhuri and R. M. Wilson (1975), On t -designs, *Osaka J. Math.* **12**, 737–744.
- H. J. Ryser (1963), *Combinatorial Mathematics*, Carus Math. Monograph **14**.
- M. P. Schutzenberger (1949), A non-existence theorem for an infinite family of symmetrical block designs, *Ann. Eugenics* **14**, 286–287.
- Th. Skolem (1958), Some remarks on the triple systems of Steiner, *Math. Scand.* **6**, 273–280.
- J. Steiner (1853), Combinatorische Aufgabe, *J. f. d. reine u. angew. Mathematik* **45**, 181–182.
- L. Teirlinck (1987), Nontrivial t -designs without repeated blocks exist for all t , *Discrete Math.* **65**, 301–311.
- J. Tits (1964), Sur les systèmes de Steiner associés aux trois ‘grands’ groupes de Mathieu, *Rend. Math. e Appl. (5)* **23**, 166–184.
- E. Witt (1938), Die 5-fach transitiven Gruppen von Mathieu, *Abh. Math. Sem. Univ. Hamburg* **12**, 256–264.

W. S. B. Woolhouse (1844), Prize question 1733, *Lady's and Gentleman's Diary*.

20

Codes and designs

We introduce some more terminology from the theory of error-correcting codes. In the most general sense, a *code* of length n is simply a subset $C \subseteq S^n$, where S is a finite set (the *alphabet*). Elements of C are called *codewords*. A *binary* code is one with alphabet $S = \{0, 1\}$; a *ternary* code is one with $S = \{0, 1, 2\}$. The *distance* $d(\mathbf{x}, \mathbf{y})$ between two words (vectors) \mathbf{x} and \mathbf{y} in S^n is defined to be the number of positions in which they differ, i.e.

$$(20.1) \quad d(\mathbf{x}, \mathbf{y}) := |\{i : 1 \leq i \leq n, x_i \neq y_i\}|.$$

This is indeed a distance function in the usual sense; check that it satisfies the triangle inequality.

The concept of distance has led to the usage of geometric terminology, e.g. the set $B_r(\mathbf{x}) := \{\mathbf{y} \in \mathbb{F}_q^n : d(\mathbf{x}, \mathbf{y}) \leq r\}$ is called the *sphere* with radius r and center \mathbf{x} , though actually the name ‘ball’ would be better.

The *minimum distance* d of the code C is

$$(20.2) \quad d := \min\{d(\mathbf{x}, \mathbf{y}) : \mathbf{x} \in C, \mathbf{y} \in C, \mathbf{x} \neq \mathbf{y}\}.$$

Much of coding theory is concerned with *linear* codes. By a $[n, k]$ code, we mean a linear subspace C of dimension k of the vector space \mathbb{F}_q^n .

The *weight* $w(\mathbf{x})$ of \mathbf{x} is defined by

$$(20.3) \quad w(\mathbf{x}) := d(\mathbf{x}, \mathbf{0}).$$

This can be defined whenever 0 is one of the symbols (elements of the alphabet), but is especially meaningful for linear codes. When

C is linear, the distance between codewords \mathbf{x} and \mathbf{y} is equal to the weight of $\mathbf{x} - \mathbf{y}$, which is another codeword, and so the minimum distance of C is equal to the *minimum weight*, i.e. the minimum of the weights of nonzero codewords. We use the notation $[n, k, d]$ code for an $[n, k]$ code with minimum distance at least d . If $d = 2e + 1$, then C is called an e -error-correcting code.

The *covering radius* $\rho(C)$ of the code C is defined to be the minimal R such that the spheres with radius R and codewords as centers cover S^n , i.e.

$$(20.4) \quad \rho(C) := \max\{\min\{d(\mathbf{x}, \mathbf{c}) : \mathbf{c} \in C\} : \mathbf{x} \in S^n\}.$$

In Chapter 18, we mentioned the repetition code in $\{0, 1\}^n$, i.e. the 1-dimensional subspace of \mathbb{F}_2^n containing only $\mathbf{0}$ and $\mathbf{1}$. If $n = 2e + 1$ then every word has distance $\leq e$ to exactly one codeword. So this code has covering radius e . The two spheres of radius e around the two codewords are disjoint and they cover the space.

In general, we call a not necessarily linear code $C \subseteq S^n$ an (e -error-correcting) *perfect code* when $|C| > 1$ and when every $\mathbf{x} \in S^n$ has distance $\leq e$ to *exactly* one codeword. This is equivalent to C having minimum distance $d = 2e + 1$ and covering radius e . Clearly, perfect codes are combinatorially interesting objects. However, they are extremely rare.

Theorem 20.1. *If C is a code in S^n with distance $d \geq 2e + 1$, then*

$$(20.5) \quad |C| \cdot \sum_{i=0}^e \binom{n}{i} (q-1)^i \leq q^n.$$

PROOF: The sum on the left-hand side of (20.5) counts the number of words in a sphere of radius e . \square

The bound given in this theorem is known as the *sphere packing bound* or as the *Hamming bound*. If equality holds, then the code is perfect.

Problem 20A. Show that if a $[23, 12, 7]$ binary code exists, then this code is perfect.

Problem 20B. By (20.5), a binary code of length 6 and minimum distance 3 has at most 9 codewords. Show that equality cannot hold. (However, 8 is possible.)

Two codes are called *equivalent* if one is obtained from the other by some permutation of the coordinate positions in S^n . Sometimes this definition is extended by also allowing a permutation of the elements of S such as interchanging $+1$ and -1 when $S = \mathbb{F}_3$.

A $k \times n$ matrix G is called a *generator matrix* of the $[n, k]$ code C if C is spanned by the rows of G . Elementary linear algebra shows that C is equivalent to a code with a generator matrix $G = (I_k \ P)$, where P is some $k \times n - k$ matrix. This is called the *reduced echelon form* for a generator.

The *dual* C^\perp of C is defined by

$$(20.6) \quad C^\perp := \{\mathbf{x} \in \mathbb{F}_q^n : \forall \mathbf{c} \in C \langle \mathbf{x}, \mathbf{c} \rangle = 0\}.$$

If H is a generator matrix for C^\perp , then clearly

$$(20.7) \quad C = \{\mathbf{x} \in \mathbb{F}_q^n : \mathbf{x}H^\top = \mathbf{0}\}.$$

H is called a *parity check matrix* for the code C . If $G = (I_k \ P)$ is a generator matrix, then $H = (-P^\top \ I_{n-k})$ is a parity check matrix. If $C = C^\perp$, then C is called a *self-dual code*. If $C \subseteq C^\perp$, then C is called *self-orthogonal*.

If C is a linear code in \mathbb{F}_q^n , then the *extended code* \overline{C} is defined by

$$(20.8) \quad \overline{C} := \{(c_1, \dots, c_n, c_{n+1}) : (c_1, \dots, c_n) \in C, c_1 + \dots + c_{n+1} = 0\}.$$

The symbol c_{n+1} is called the *parity check symbol*.

Example 20.1. Let $n = (q^k - 1)/(q - 1)$. Consider a matrix H of size $k \times n$, with entries in \mathbb{F}_q , for which the columns are pairwise linearly independent. Note that this is the maximal value of n for which this is possible. Then H is clearly the parity check matrix of an $[n, n - k]$ code with minimum distance 3. Such a code is called a q -ary *Hamming code*. If \mathbf{c} is a codeword, then

$|B_1(\mathbf{c})| = 1 + n(q-1) = q^k$. Since $|C| = q^{n-k}$, we see that this code is perfect (by (20.5)).

Problem 20C. Let H be the ternary $[4,2]$ Hamming code. Define a (nonlinear) ternary code C of length 9 with codewords

$$(x_0, x_1, \dots, x_4; y_1, \dots, y_4)$$

by requiring that $\sum_{i=0}^4 x_i \neq 0$ and that $(y_1 - x_1, \dots, y_4 - x_4)$ is a codeword in H . Show that C has covering radius 1. (No ternary code of length 9 with covering radius 1 and fewer than $2 \cdot 3^6$ codewords is known.)

Example 20.2. Consider the binary Hamming code C of length $n = 2^k - 1$. By definition, the dual code C^\perp has as generator matrix the $k \times n$ matrix that has all possible nonzero vectors of length k as columns. Therefore, the extension of C^\perp is the code $R'(1, k)$ of Chapter 18. C^\perp is usually called the *simplex code* of length n . We remark that the $[8,4]$ extended binary Hamming code is self-dual.

Problem 20D. Show that the covering radius of the code $R(1, 2k)$ is $2^{2k-1} - 2^{k-1}$. (Hint: use the ± 1 representation instead of $(0,1)$ and work over \mathbb{Q} to show that the covering radius is at most this large. Consider the word \mathbf{z} that is the characteristic function of

$$\{\mathbf{x} \in \mathbb{F}_2^{2k} : x_1x_2 + \dots + x_{2k-1}x_{2k} = 1\}$$

to show equality.)

We mention one easily proved bound for arbitrary codes, known as the *Singleton bound*.

Theorem 20.2. Let C be any code of length n and minimum distance d over \mathbb{F}_q . Then

$$|C| \leq q^{n-d+1}.$$

PROOF: From each codeword, we delete the last $d-1$ symbols. The set of ‘shortened’ words consists of words that are pairwise different! There can be no more than q^{n-d+1} of them. \square

Example 20.3. We give an example that shows a nice connection with Chapter 19. Let $q = 2^a$. Let S be a hyperoval in $PG_2(q)$. Using the terminology of Example 19.7, the elements of S are vectors in \mathbb{F}_q^3 with the property that no three of them are linearly dependent. We take the elements of S as the columns of a 3 by $q + 2$ matrix H . If we interpret H as the parity check matrix of a $[q + 2, q - 1]$ code over \mathbb{F}_q , then this code has minimum distance at least 4. So by Theorem 20.2, the distance is equal to 4. This is one of the rare examples of equality in Theorem 20.2. Codes for which equality holds in the Singleton bound are called *maximum distance separable* codes (MDS codes), another unfortunate name! There are many open problems concerning these codes.

If C is a q -ary $[n, k]$ code, and if A_i denotes the number of code-words in C with weight i , then

$$(20.9) \quad A(z) := \sum_{i=0}^n A_i z^i$$

is called the *weight enumerator* of C . Of course, $A_0 = 1$ and $A(1) = |C| = q^k$.

Problem 20E. Suppose C is a binary code, not necessarily linear, with length 23, minimum distance 7, and $|C| = 2^{12}$. Assume $\mathbf{0} \in C$. First show that C is a perfect code. Let the weight enumerator of C be given by (20.9). Count pairs (\mathbf{x}, \mathbf{c}) with $\mathbf{c} \in C$, $w(\mathbf{x}) = 4$, and $d(\mathbf{x}, \mathbf{c}) = 3$, and show that $A_7 = 253$. Then show that the weight enumerator of C is in fact completely determined by the fact that C is a perfect code and $\mathbf{0} \in C$.

The following theorem is one of the most useful in the theory of error-correcting codes. It is due to F. J. MacWilliams (1963).

Theorem 20.3. Let C be an $[n, k]$ code over \mathbb{F}_q with weight enumerator $A(z)$ and let $B(z)$ be the weight enumerator of C^\perp . Then

$$(20.10) \quad B(z) = q^{-k} (1 + (q - 1)z)^n A\left(\frac{1 - z}{1 + (q - 1)z}\right).$$

PROOF: We only give the proof for the case $q = 2$. For other values of q , the proof is essentially the same (instead of $(-1)^{\langle \mathbf{u}, \mathbf{v} \rangle}$ used below, one must use $\chi(\langle \mathbf{u}, \mathbf{v} \rangle)$, where χ is a character on \mathbb{F}_q).

Define

$$g(\mathbf{u}) := \sum_{\mathbf{v} \in \mathbb{F}_2^n} (-1)^{\langle \mathbf{u}, \mathbf{v} \rangle} z^{w(\mathbf{v})}.$$

Then

$$\sum_{\mathbf{u} \in C} g(\mathbf{u}) = \sum_{\mathbf{u} \in C} \sum_{\mathbf{v} \in \mathbb{F}_2^n} (-1)^{\langle \mathbf{u}, \mathbf{v} \rangle} z^{w(\mathbf{v})} = \sum_{\mathbf{v} \in \mathbb{F}_2^n} z^{w(\mathbf{v})} \sum_{\mathbf{u} \in C} (-1)^{\langle \mathbf{u}, \mathbf{v} \rangle}.$$

Here, if $\mathbf{v} \in C^\perp$, the inner sum is $|C|$. If $\mathbf{v} \notin C^\perp$, then half of the terms in the inner sum have value $+1$, the other half -1 . Therefore

$$(20.11) \quad \sum_{\mathbf{u} \in C} g(\mathbf{u}) = |C| \cdot B(z).$$

Now

$$\begin{aligned} g(\mathbf{u}) &= \sum_{(v_1, v_2, \dots, v_n) \in \mathbb{F}_2^n} \prod_{i=1}^n ((-1)^{u_i v_i} z^{v_i}) \\ &= \prod_{i=1}^n (1 + (-1)^{u_i} z) \\ &= (1 - z)^{w(\mathbf{u})} (1 + z)^{n - w(\mathbf{u})}. \end{aligned}$$

The result follows by substituting this in (20.11). \square

Corollary. *If we write $B(z) = \sum_{j=0}^n B_j z^j$, then for $q = 2$, we find from (20.10):*

$$(20.12) \quad B_j = 2^{-k} \sum_{i=0}^n A_i \sum_{l=0}^j (-1)^l \binom{i}{l} \binom{n-i}{j-l}.$$

These relations, known as the *MacWilliams relations*, are linearly independent equations for the coefficients A_i , given the coefficients B_j .

Many of the known nontrivial 5-designs were found by the following elegant application of MacWilliams' theorem, usually referred to as the *Assmus–Mattson theorem* (1969). Again we restrict the

proof to the binary case. For other q , the theorem has an obvious generalization with nearly the same proof. We identify the positions of a code of length n with the set $\mathcal{P} := \{1, 2, \dots, n\}$. This allows us to interpret a codeword in a binary code as a subset of \mathcal{P} (i.e. as the characteristic function of a subset). The *support* of a codeword is the set of coordinate positions where the codeword is not zero.

Problem 20F. Let C be a perfect binary e -error-correcting code of length n . Assume 0 is a symbol and that $\mathbf{0}$ is a codeword. Show that \mathcal{P} together with the supports of codewords of weight $d = 2e + 1$ is an $S(e + 1, 2e + 1, n)$.

Theorem 20.4. Let A be a binary $[n, k, d]$ code and let $B := A^\perp$ be the dual code, an $[n, n - k]$ code. Let $t < d$. Suppose the number of nonzero weights in B , that are less than or equal to $n - t$, is $\leq d - t$. Then for each weight w , the supports of the words of weight w in A form a t -design and the supports of the words of weight w in B form a t -design.

PROOF: If C is any code and a t -subset T of \mathcal{P} has been fixed, then we denote by C' the code of length $n - t$ obtained by deleting the coordinates in T from the codewords in C . We denote by C_0 the subcode of C' obtained by deleting the coordinates in T from the codewords in C that have zeros at all positions of T .

The proof is in four steps.

(i) Let T be a subset of \mathcal{P} of size t . Since t is less than the minimum distance of A , the code A' has as many codewords as A , i.e. has dimension k also. In fact, A' still has minimum distance $\geq d - t$. So the dual $(A')^\perp$ has dimension $n - k - t$. Clearly, B_0 is a subcode of $(A')^\perp$. Since the dimension of B_0 is at least $n - k - t$, we must have $B_0 = (A')^\perp$.

(ii) Let $\sum \alpha_i z^i$ and $\sum \beta_i z^i$ be the weight enumerators for A' and B_0 , respectively. We claim that these weight enumerators *do not* depend on the particular t -subset T , but only on the numbers t , n , k , and the weights of words in B .

Let $0 < \ell_1 < \ell_2 < \dots < \ell_r \leq n - t$, where $r \leq d - t$, be the nonzero weights $\leq n - t$ for the code B . These are the only possible weights

for B_0 . Then (20.12) gives

$$|B_0|\alpha_j = \binom{n-t}{j} + \sum_{i=1}^r \beta_{\ell_i} \sum_{m=0}^j (-1)^m \binom{\ell_i}{m} \binom{n-t-\ell_i}{j-m}.$$

By hypothesis, the minimum distance of A' is $\geq r$, so we know the values of α_j for $j < r$, namely $\alpha_0 = 1$, $\alpha_1 = \cdots = \alpha_{r-1} = 0$. Thus we have r linear equations in r unknowns β_{ℓ_i} . These unknowns are uniquely determined if the $r \times r$ coefficient matrix M that has (i, j) -entry $p_j(\ell_i)$ where

$$p_j(x) := \sum_{m=0}^j (-1)^m \binom{x}{m} \binom{n-t-x}{j-m},$$

$1 \leq i \leq r$, $0 \leq j \leq r-1$, is nonsingular. But $p_j(x)$ is a polynomial in x of exact degree j (the coefficient of x^j is $(-1)^j 2^j / j!$), so elementary column operations reduce M to the Vandermonde matrix

$$\begin{pmatrix} 1 & \ell_1 & \ell_1^2 & \cdots & \ell_1^{r-1} \\ 1 & \ell_2 & \ell_2^2 & \cdots & \ell_2^{r-1} \\ \vdots & \vdots & \vdots & & \vdots \\ 1 & \ell_r & \ell_r^2 & \cdots & \ell_r^{r-1} \end{pmatrix},$$

which is nonsingular since the ℓ_i 's are distinct.

Thus the weight enumerator $\sum \beta_i z^i$ does not depend on the choice of the subset T . Since A' is the dual of B_0 , $\sum \alpha_i z^i$ is also independent of T .

(iii) Let \mathcal{E} be the collection of words of weight w in B , interpreted as subsets of \mathcal{P} . The number of members of \mathcal{E} that *miss* all coordinates in T is the number of words of weight w in B_0 , and this is independent of T . That is, the *complement* of $(\mathcal{P}, \mathcal{E})$ is a t -design. By Problem 19C, the sets in \mathcal{E} also form the blocks of a t -design. This proves the second assertion of the theorem. (Remark: This might be criticized if $w > n - t$. But in this case our argument when applied to $t' := n - w$ shows that either every w -subset is the support of a codeword, or no w -subset is the support of a codeword; so the words of weight w , if any, form a trivial t -design.)

(iv) To prove the first assertion of the theorem, we proceed by induction. We start with $w = d$. Let \mathcal{D} be the collection of words of weight d in A . The number of sets in \mathcal{D} that contain a given t -subset T of \mathcal{P} is equal to the number of words of weight $d - t$ in A' , and as we saw above, this number does not depend on the choice of T . So \mathcal{D} is a t -design. Let $w > d$ and suppose the assertion is true for all w' with $w \geq w' > d$. Now let \mathcal{D} denote the collection of words of weight w in A . In this case the number of subsets in \mathcal{D} that contain a given t -subset T , is equal to the number of words of weight $w - t$ in A' corresponding to codewords of weight w in A . By (iii), the total number of words of weight $w - t$ in A' does not depend on the choice of T . By the induction hypothesis and (19.6), the number of words of weight $w - t$ in A' corresponding to codewords of weight less than w in A does not depend either on T . This proves the assertion. \square

Problem 20G. What is the weight enumerator of the dual of the binary Hamming code of length $2^r - 1$? Derive an expression for the weight enumerator of the Hamming code itself.

Example 20.4. Let A be the extended $[8, 4]$ binary Hamming code. We know that $A = A^\perp$. In the notation of Theorem 20.4, we have $d = 4$. Take $t = 3$. The conditions of Theorem 20.4 are satisfied. Hence the words of weight 4 form a 3-design, which is of course the Hadamard 3-(8,4,1) design corresponding to $R(1, 3)$.

Example 20.5. After the next example, we shall treat the famous binary Golay code and show that the corresponding extended code G_{24} is a self-dual $[24, 12, 8]$ code with weights 0, 8, 12, 16 and 24. So Theorem 20.4 shows that the words of weight 8 in this code form a 5-design. From Problem 20E, we know that there are 759 blocks and then (19.1) shows that $\lambda = 1$. This also follows from the fact that the code has distance 8, so two blocks have at most four points in common. This design is the Witt design $S(5, 8, 24)$ mentioned in Chapter 19. The words of other weights also yield 5-designs.

Example 20.6. The following 5-designs, and several others, were found by V. Pless (1972). Consider the 18 by 18 Paley matrix C given by (18.5). We consider a ternary $[36, 18]$ code Sym_{36} with generator $G = (I_{18} \ C)$. Such a code is called a *symmetry code*.

Since C is a Paley matrix, we have $GG^T = O$, i.e. Sym_{36} is a self-dual code. This implies that all weights in the code are divisible by 3. We claim that all the words in Sym_{36} have weight at least 12. Observe that since C is symmetric, the matrix $(-C \ I_{18})$ is a parity check matrix for the code, and, because the code is self-dual, this means that that matrix is also a generator matrix for the code. If (\mathbf{a}, \mathbf{b}) , where \mathbf{a} and \mathbf{b} are vectors in \mathbb{F}_3^{18} , is a codeword, then $(-\mathbf{b}, \mathbf{a})$ is also a codeword. This shows that if there is a codeword with weight less than 12, there is such a codeword that is a linear combination of at most four rows of G . These are easily checked by hand as follows; the reader should do it as an exercise. The fact that C is a Paley matrix and the argument used in the proof of Theorem 18.1 (and in Problem 18B) show that a linear combination of 1, 2, or 3 rows of G has weight 18, respectively 12, respectively 12 or 15. It remains to check combinations of four rows. Now use the fact that Q in (18.5) is cyclic, which implies that only a few essentially different combinations have to be examined. One can also extend the array used in the proof of Theorem 18.1 by one row. Both methods involve very little work and produce the result that the minimum weight is 12. (Originally this was done by computer.)

We now use the generalization of Theorem 20.4 to ternary codes. If one considers the words of some fixed weight in Sym_{36} (the generalization holds for weights 12, 15, 18, and 21), and if we replace each word by the set of positions where the nonzero coordinates occur, we find 5-designs. Since the codewords \mathbf{c} and $2\mathbf{c}$ yield the same set, we only consider this set as one block.

We now come to the most famous of all binary codes: the *binary Golay code* G_{23} . There are very many constructions of this code, some of them quite elegant and with short proofs of its properties. We show only one of these constructions related to design theory.

We consider the incidence matrix N of the (unique) 2-(11,6,3) design; see Problem 19D. We have $NN^T = 3I + 3J$. Consider N as a matrix with entries in \mathbb{F}_2 . Then $NN^T = I + J$. So N has rank 10 and the only vector \mathbf{x} with $\mathbf{x}N = \mathbf{0}$ is $\mathbf{1}$. The design properties imply trivially that any row has weight 6 and that the sum of two rows of N has weight 6. We also know that the sum of three or four rows of N is not $\mathbf{0}$.

Next, let G be the 12 by 24 matrix over \mathbb{F}_2 given by $G = (I_{12} P)$, where

$$(20.13) \quad P = \begin{pmatrix} 0 & 1 & \cdots & 1 \\ 1 & & & \\ \vdots & & N & \\ 1 & & & \end{pmatrix}.$$

Every row of G has a weight $\equiv 0 \pmod{4}$. Any two rows of G have inner product 0. This implies that the weight of any linear combination of the rows of G is $\equiv 0 \pmod{4}$; prove this by induction. The observations made about N then show that a linear combination of any number of rows of G has weight at least 8. Consider the code generated by G and call it G_{24} . Delete any coordinate to find a binary $[23, 12]$ code with minimum distance at least 7. By Problem 20A, this code must have minimum distance equal to 7 and, furthermore, it is a *perfect code*! We denote it by G_{23} . These two notations will be justified below, where we show that G_{24} , the extended binary Golay code, is unique, from which the uniqueness of G_{23} can be shown.

Theorem 20.5. *If C is a binary code of length 24, with $|C| = 2^{12}$, minimum distance 8, and if $\mathbf{0} \in C$, then C is equivalent to G_{24} .*

PROOF: (i) The difficult part of the proof is to show that C must be a linear code. To see this, observe that deleting any coordinate produces a code C' of length 23 and distance 7 with $|C'| = 2^{12}$. By Problem 20E, the weight enumerator of this perfect code is determined: $A_0 = A_{23} = 1$, $A_7 = A_{16} = 253$, $A_8 = A_{15} = 506$, $A_{11} = A_{12} = 1288$. From the fact that this is the case, no matter which of the 24 positions is deleted from C , it follows that all codewords in C have weight 0, 8, 12, 16, or 24. Furthermore a change of origin (i.e. adding a fixed codeword to all the codewords) shows that we can also infer that the distance of any two codewords is 0, 8, 12, 16, or 24. Since all weights and all distances are $\equiv 0 \pmod{4}$, any two codewords have inner product 0. Therefore the words of C span a code that is self-orthogonal. However, such a code can have at most 2^{12} words. Therefore, C itself must be a linear and self-dual code.

(ii) We form a generator matrix of C by taking as first row any word of weight 12. So after a permutation of positions, we have:

$$G = \begin{pmatrix} 1 & \dots & 1 & 0 & \dots & 0 \\ & A & & & B & \end{pmatrix}.$$

We know that any linear combination of the rows of B must have even weight $\neq 0$, so B has rank 11. Therefore the code generated by B is the $[12, 11, 2]$ even-weight code. We conclude that we may assume that B is the matrix I_{11} , bordered by a column of 1's. Another permutation of columns yields a generator matrix G' of the form $(I_{12} P)$, where P has the same form as in (20.13). What do we know about the matrix N ? Clearly any row of N must have weight 6. Furthermore, the sum of any two rows of N must have weight at least 6. By Problem 19D, N is the incidence matrix of the unique 2 -(11,6,3) design, i.e. C is equivalent to G_{24} . \square

As we saw in Example 20.5, the words of weight 8 in G_{24} form the blocks of the Witt design $\mathcal{D} = S(5, 8, 24)$. Denote by $\{0, 1, \dots, 23\}$ the point set of \mathcal{D} and consider $I = \{21, 22, 23\}$. By the Corollary to Theorem 19.3, \mathcal{D}_I is an $S(2, 5, 21)$, i.e. a projective plane of order 4 (which is also known to be unique). The following problem shows the beautiful combinatorial structure of the design \mathcal{D} .

Problem 20H. Let B be a block of \mathcal{D} with $|B \cap I| = \alpha$ and define $B^* := B \setminus I$. We saw that if $\alpha = 3$, then B^* is a line in $PG_2(4)$. Show that

(i) $\alpha = 2$ implies that B^* is a hyperoval in $PG_2(4)$;

(ii) $\alpha = 0$ implies that B^* is the symmetric difference of two lines.

(The ambitious reader may wish to show that if $\alpha = 1$, then the seven points of B^* and the lines of $PG_2(4)$ containing at least two such points, form a Fano plane. Such a plane is called a *Baer subplane* of $PG_2(4)$.)

By counting the hyperovals, pairs of lines, etc., one can show that each of the geometric configurations mentioned above is one of the sets B^* . In fact, one of the well known constructions of $S(5, 8, 24)$ starts with these objects and produces the design by appending suitable subsets of I . If one does not use the automorphism group of $PG_2(4)$ in the argument, then this construction is a nontrivial

combinatorial problem. (Again: the ambitious reader should try it.)

Problem 20I. Let $\mathbb{F}_4 = \{0, 1, \omega, \bar{\omega}\}$. Let C be the $[6, 3]$ code over \mathbb{F}_4 with codewords $(a, b, c, f(1), f(\omega), f(\bar{\omega}))$, where $f(x) := ax^2 + bx + c$.

(i) Show that C has minimum weight 4 and no words of weight 5.

(ii) Let G be the binary code with as codewords all 4 by 6 $(0,1)$ -matrices A with rows $\mathbf{a}_0, \mathbf{a}_1, \mathbf{a}_\omega, \mathbf{a}_{\bar{\omega}}$ such that:

- (1) every column of A has the same parity as its first row \mathbf{a}_0 ,
- (2) $\mathbf{a}_1 + \omega\mathbf{a}_\omega + \bar{\omega}\mathbf{a}_{\bar{\omega}} \in C$.

Show that G is a $[24, 12, 8]$ code, i.e. $G = G_{24}$.

Problem 20J. As in Example 20.6, we construct a ternary code Sym_{12} by using the Paley matrix C of order 6. Show that Sym_{12} is a $[12, 6, 6]$ self-dual code. Puncture the code (i.e. delete some coordinate) to obtain a $[11, 6, 5]$ ternary code G_{11} . Show that this code is perfect. It is the *ternary Golay code*.

We have now given several examples of designs constructed by using a suitable code. We reverse the procedure and study codes generated by the (characteristic functions of the) blocks of a design. Let N be the incidence matrix of a projective plane of order n . We consider the subspace C of \mathbb{F}_2^v , where $v = n^2 + n + 1$, generated by the rows of N . If n is odd, C is not very interesting. Namely, if we take the sum of the rows of N that have a 1 in a fixed position, the result is a row with a 0 in that position and 1's elsewhere. These vectors generate the $[v, v - 1, 2]$ even-weight code and this must be C , since C obviously has no words of odd weight. If n is even, the problem becomes more interesting. We restrict ourselves to $n \equiv 2 \pmod{4}$.

Theorem 20.6. *If $n \equiv 2 \pmod{4}$, the rows of the incidence matrix N of a projective plane of order n generate a binary code C with dimension $\frac{1}{2}(n^2 + n + 2)$.*

PROOF: (i) Since n is even, the code \bar{C} is self-orthogonal because every line has an odd number of points and any two lines meet in one point. Therefore $\dim C \leq \frac{1}{2}(n^2 + n + 2)$.

(ii) Let $\dim C = r$ and let $k := n^2 + n + 1 - r = \dim C^\perp$. Let H be a parity check matrix for C . Assume that the coordinate places have been permuted in such a way that H has the form $(I_k \ P)$. Define $A := \begin{pmatrix} I_k & P \\ 0 & I_r \end{pmatrix}$. Interpret the $(0,1)$ -matrices N and A as matrices over \mathbb{Q} . Then

$$\det NA^\top = \det N = (n+1)n^{\frac{1}{2}(n^2+n)}.$$

Since all entries in the first k columns of NA^\top are even integers, $\det N$ is apparently divisible by 2^k . So $\frac{1}{2}(n^2 + n) \geq k$, i.e. $r \geq \frac{1}{2}(n^2 + n + 2)$.

The result follows from (i) and (ii). \square

The theorem shows that the code C generated by the rows of N has the property that \bar{C} is self-dual. We shall now show an even more interesting property of this code, namely that one can recover the plane from the code.

Theorem 20.7. *The code C of Theorem 20.6 has minimum weight $n+1$ and every codeword of minimum weight corresponds to a line in the plane of order n .*

PROOF: As before, we interpret a codeword as a subset of the plane. So it will be clear what we mean by saying that a point is on the codeword \mathbf{c} . Let \mathbf{c} be a codeword with $w(\mathbf{c}) = d$. Since n is even, the codewords corresponding to lines in the plane have a 1 as parity check symbol in the extended code \bar{C} . This code is self-dual and this implies:

- (1) if d is odd then \mathbf{c} meets every line at least once;
- (2) if d is even then every line through a fixed point of \mathbf{c} meets \mathbf{c} in a second point.

In case (2) we immediately see that $d > n+1$. In case (1) we find: $(n+1)d \geq n^2 + n + 1$, i.e. $d \geq n+1$. If $w(\mathbf{c}) = n+1$, then there is a line L of the plane that meets \mathbf{c} in at least 3 points. If some point of L is not a point of \mathbf{c} , then every line $\neq L$ through that point must meet \mathbf{c} by (1). This would imply that $d \geq n+3$. So \mathbf{c} must be the line L . \square

Recall that in a projective plane of even order n , a *hyperoval* is a set of $n+2$ points such that no three are on one line.

Theorem 20.8. *The codewords of weight $n + 2$ in the code C of Theorem 20.6 are precisely all the hyperovals of the plane.*

PROOF: (i) Let $\mathbf{v} \in C$ and $w(\mathbf{v}) = n + 2$. Every line meets \mathbf{v} in an even number of points. Let L be a line of the plane and suppose that \mathbf{v} and L have $2a$ points in common. Each of the n lines $\neq L$ through one of these $2a$ points meets \mathbf{v} at least once more. Therefore $2a + n \leq n + 2$, i.e. $a = 0$ or $a = 1$.

(ii) Let V be a hyperoval. Let S be the set of $\binom{n+2}{2}$ secants of V . Each point not in V is on $\frac{1}{2}(n + 2)$ such lines; each point of V is on $n + 1$ secants. Since $n \equiv 2 \pmod{4}$, the sum of the codewords corresponding to secants is the characteristic function of V . So this is a codeword. \square

Theorems like the previous two yielded enough information about the code corresponding to a projective plane of order 10 to make possible the computer search that we mentioned earlier. The first important step was due to F. J. MacWilliams, N. J. A. Sloane, and J. G. Thompson (1973) who showed that this code could have no words of weight 15. Presently, the only known projective plane with order $n \equiv 2 \pmod{4}$ is the Fano plane.

Problem 20K. Find a 4×39 matrix of 0's, 1's, and -1 's so that (i) no column is all zero, and no column is ± 1 times another column, and (ii) each row contains 13 of each of 0, 1, -1 .

Generalize to construct r by $\frac{1}{2}(3^r - 1) - 1$ matrices with property (i) and (ii) (with 13 replaced by an appropriate value).

(The matrix above can be used for the following puzzle. Of 39 coins, one is counterfeit and weighs either more or less than the others. You have access to a balance with two pans; some coins can be put in one pan and some in the other, and the balance will tell you which subset has greater total weight. You must determine the counterfeit coin, and whether it is lighter or heavier, using a total of four weighings.)

Problem 20L. Körner and Simonyi called a code over an alphabet of $q > 2$ symbols *trifferent* if the codewords were not only different but for each *triple* of codewords there is a position where they have three different entries. Define $F(n, q)$ to be the maximal number of codewords in a trifferent code of length n . Prove that $F(n, q) \geq$

$6^{-1/2}(q/3)^{n/2}$. (Hint: Use Theorem 3.6. Consider a random code with N codewords. For each 3-subset S of $\{1, 2, \dots, n\}$ let A_S be the event that the three codewords with indices in S are not all different or not trifferent. Show that A_S has probability $(3q(q-1) + q)^n / q^{3n}$, etc.)

Notes.

We have not been concerned with the error-correcting properties of codes in this chapter. For a systematic treatment of coding theory we refer to Van Lint (1999). Much more material on the relation between design theory and coding theory can be found in Cameron and Van Lint (1991). The best reference book for coding theory is MacWilliams and Sloane (1977).

For some of the history of the origin of coding theory, we refer to Thompson (1983). There is some controversy about priority, but it is clear that both R. W. Hamming and M. J. E. Golay contributed to the ‘discovery’ of this fascinating topic in 1947 and 1948. The monumental paper by C. E. Shannon (1948) really started things going. It seems that Hamming was irritated by the fact that his computer kept stopping when it detected an error. He correctly decided that if it could detect errors, it should be able to locate them and correct them and then get on with the job! Golay published the two Golay codes by giving their generator matrices but without proof of the properties.

E. F. Assmus (1931–1998) died tragically at a meeting on Codes and Designs in a place he loved: the Mathematisches Forschungsinstitut in Oberwolfach. A large part of this chapter is based on his many contributions to the relations between coding theory and design theory (often written in collaboration with H. F. Mattson).

M. J. E. Golay (1902–1989) was a Swiss physicist who worked in many different fields. He is known for his work on infrared spectroscopy and the invention of the capillary column but to mathematicians mainly for his discovery of the two Golay codes.

For more about MDS codes, we refer to MacWilliams and Sloane (1977).

F. J. MacWilliams (1917–1990) made many contributions to coding theory. Of these, the theorem known by her name is the most

important. Her book with N. J. A. Sloane is the most important reference book on coding theory. As is the case with many important coding theorists, she spent most of her career at Bell Laboratories.

As mentioned earlier, there are many constructions of the Golay code G_{24} . Each of them shows that some group of permutations is contained in the automorphism group of the code. For example, one of the most common constructions displays an automorphism of order 23. Since the code is unique, its full automorphism group must contain all these groups as subgroups. In this way, one can prove that this automorphism group is the famous *Mathieu group* M_{24} . This group is of order $24 \cdot 23 \cdot 22 \cdot 21 \cdot 20 \cdot 16 \cdot 3$ and acts 5-transitively on the 24 coordinate positions of the codewords.

It has been shown that there are no other perfect e -error-correcting codes with $e > 2$ than the ones mentioned in this chapter. For more on this subject, see Van Lint (1999). Also see Chapter 30.

References.

- E. F. Assmus, Jr. and H. F. Mattson, Jr. (1969), New 5-designs, *J. Combinatorial Theory* **6**, 122–151.
- P. J. Cameron and J. H. van Lint (1991), *Designs, Graphs, Codes and their links*, London Math. Soc. Student Texts **22**, Cambridge University Press.
- J. H. van Lint (1999), *Introduction to Coding Theory*, Third edition, Springer-Verlag.
- F. J. MacWilliams (1963), A theorem on the distribution of weights in a systematic code, *Bell Syst. Tech. J.* **42**, 79–94.
- F. J. MacWilliams and N. J. A. Sloane (1977), *The Theory of Error-Correcting Codes*, North-Holland.
- F. J. MacWilliams, N. J. A. Sloane and J. G. Thompson (1973), On the existence of a projective plane of order 10, *J. Combinatorial Theory* (A) **14**, 66–78.
- V. Pless (1972), Symmetry codes over $GF(3)$ and new 5-designs, *J. Combinatorial Theory* (A) **12**, 119–142.
- C. E. Shannon (1948), A mathematical theory of communication, *Bell Syst. Tech. J.* **27**, 379–423 and 623–656.
- T. M. Thompson (1983), *From Error-Correcting Codes through Sphere Packings to Simple Groups*, Carus Math. Monograph **21**.

21

Strongly regular graphs and partial geometries

A *strongly regular graph* $srg(v, k, \lambda, \mu)$ is a graph with v vertices that is regular of degree k and that has the following properties:

- (1) For any two adjacent vertices x, y , there are exactly λ vertices adjacent to x and to y .
- (2) For any two nonadjacent vertices x, y , there are exactly μ vertices adjacent to x and to y .

A trivial example is a pentagon, an $srg(5, 2, 0, 1)$. Perhaps the most famous example is the graph of Fig. 1.4, the Petersen graph, an $srg(10, 3, 0, 1)$.

Clearly a graph that is the union of m complete graphs K_k is an $srg(km, k-1, k-2, 0)$. Sometimes we shall exclude trivial examples by requiring that a strongly regular graph and its complement are *connected*, i.e. we assume

$$(21.1) \quad 0 < \mu < k < v - 1.$$

(We remark that the fact that $\mu = 0$ implies that the graph is a union of complete graphs is most easily seen from (21.4) below.) It is not difficult to see that the complement \overline{G} of an $srg(v, k, \lambda, \mu)$ G is an

$$(21.2) \quad srg(v, v - k - 1, v - 2k + \mu - 2, v - 2k + \lambda)$$

and since the parameters are nonnegative, we find a simple condition on the parameters, namely

$$(21.3) \quad v - 2k + \mu - 2 \geq 0.$$

Another relation between the parameters is easily found as follows. Consider any vertex x and partition the other vertices into the set $\Gamma(x)$ of vertices joined to x and the set $\Delta(x)$ of vertices not joined to x . By the definition of strongly regular graphs, $\Gamma(x)$ consists of k vertices, each of which is joined to λ vertices of $\Gamma(x)$. Each vertex in $\Delta(x)$ is joined to μ vertices in $\Gamma(x)$. Counting edges with one end in $\Gamma(x)$ and one end in $\Delta(x)$ in two ways, we find

$$(21.4) \quad k(k - \lambda - 1) = \mu(v - k - 1).$$

Problem 21A. Show that a strongly regular graph is extremal in the following sense. Let G be a graph with v vertices, each of degree at most k . Suppose that any two adjacent vertices, respectively nonadjacent vertices, have at least λ , respectively μ , common neighbors. Then

$$k(k - 1 - \lambda) \geq \mu(v - k - 1)$$

and equality implies that G is strongly regular.

Before going into the fascinating theory of these graphs, we mention several classes of examples.

Example 21.1. The *triangular graph* $T(m)$, $m \geq 4$, has as vertices the 2-element subsets of a set of cardinality m ; two distinct vertices are adjacent if and only if they are not disjoint. $T(m)$ is an $srg\left(\binom{m}{2}, 2(m-2), m-2, 4\right)$. The Petersen graph is $\overline{T(5)}$ (see Problem 1A).

Example 21.2. The *lattice graph* $L_2(m)$, $m \geq 2$, has as vertex set $S \times S$, where S is a set of cardinality m ; two distinct vertices are adjacent if and only if they have a common coordinate. $L_2(m)$ is an $srg(m^2, 2(m-1), m-2, 2)$. $L_2(2)$ is a quadrangle which is a trivial example because its complement is not connected.

Example 21.3. Let q be a prime power with $q \equiv 1 \pmod{4}$. The *Paley graph* $P(q)$ has the elements of \mathbb{F}_q as vertices; two vertices are adjacent if and only if their difference is a nonzero square in \mathbb{F}_q . That this is an $srg\left(q, \frac{1}{2}(q-1), \frac{1}{4}(q-5), \frac{1}{4}(q-1)\right)$ is a direct

consequence of (18.4), but it is easier to show this using the matrix Q of (18.5) as we shall see below. Note that $P(5)$ is the pentagon.

Example 21.4. The Clebsch graph has as vertices all subsets of even cardinality of the set $\{1, \dots, 5\}$; two vertices are joined if and only if their symmetric difference has cardinality 4. This is an $srg(16, 5, 0, 2)$. One can also describe the vertices as the words of even weight in \mathbb{F}_2^5 , with an edge if the distance is 4. For any vertex x , the induced subgraph on $\Delta(x)$ is the Petersen graph. See Fig. 21.1 below.




Figure 21.1

Let us define the *adjacency matrix* A of a graph G with v vertices $1, \dots, v$ to be the $v \times v$ $(0,1)$ -matrix with $a_{ij} = a_{ji} = 1$ if and only if the vertices i and j are joined. Clearly A is symmetric with zeros on the diagonal. The statement that G is an $srg(v, k, \lambda, \mu)$ is equivalent to

$$(21.5) \quad AJ = kJ, \quad A^2 + (\mu - \lambda)A + (\mu - k)I = \mu J.$$

If Q is the matrix occurring in (18.5), then by (18.4) we have $Q^2 = qI - J$, and the adjacency matrix of the graph $P(q)$ defined in Example 21.3 is $A = \frac{1}{2}(Q + J - I)$. So A satisfies (21.5) with $k = \frac{1}{2}(q - 1)$, $\lambda = \frac{1}{4}(q - 5)$, $\mu = \frac{1}{4}(q - 1)$.

We have already seen one connection between strongly regular graphs and topics treated in earlier chapters. Several more will

follow. The theory of strongly regular graphs shows a completely different aspect of graph theory from what we studied in Chapters 1–4 and 8. We now rely heavily on *algebraic* methods. Nevertheless, we also wish to show some nice counting arguments that are used in this theory.

We define the *Bose–Mesner algebra* \mathfrak{A} of an *srg* G to be the 3-dimensional algebra \mathfrak{A} of linear combinations of I , J , and A . That this is indeed an algebra is a consequence of (21.5). This algebra consists of symmetric commuting matrices and therefore there is an orthogonal matrix that simultaneously diagonalizes them. This can also be seen in an elementary way from (21.5). In fact, we shall see in the next theorem that A has three distinct eigenspaces in \mathbb{R}^v and each of them is an eigenspace for any element of \mathfrak{A} .

Theorem 21.1. *If there is an srg(v, k, λ, μ), then the numbers*

$$f := \frac{1}{2} \left\{ v - 1 + \frac{(v-1)(\mu - \lambda) - 2k}{\sqrt{(\mu - \lambda)^2 + 4(k - \mu)}} \right\}$$

and

$$g := \frac{1}{2} \left\{ v - 1 - \frac{(v-1)(\mu - \lambda) - 2k}{\sqrt{(\mu - \lambda)^2 + 4(k - \mu)}} \right\}$$

are nonnegative integers.

PROOF: Let A be the adjacency matrix of the graph. By (21.5) the all-one vector $\mathbf{j} := (1, 1, \dots, 1)^\top$ is an eigenvector of A , with eigenvalue k , and of course it is also an eigenvector of I and of J . Application of (21.5) yields a second proof of (21.4). The multiplicity of this eigenvalue is one because the graph is connected. Any other eigenvector, say with eigenvalue x , is orthogonal to \mathbf{j} and therefore we find from (21.5),

$$x^2 + (\mu - \lambda)x + (\mu - k) = 0.$$

This equation has two solutions

$$(21.6) \quad r, s = \frac{1}{2} \left\{ \lambda - \mu \pm \sqrt{(\lambda - \mu)^2 + 4(k - \mu)} \right\}$$

Let f and g be the multiplicities of r and s as eigenvalues of A . Then we have

$$1 + f + g = v \quad \text{and} \quad \text{tr}(A) = k + fr + gs = 0.$$

If we solve these two linear equations, we find the assertion of the theorem. \square

Note that the multiplicities can also be expressed as

$$(21.7) \quad f = \frac{-k(s+1)(k-s)}{(k+rs)(r-s)} \quad \text{and} \quad g = \frac{k(r+1)(k-r)}{(k+rs)(r-s)}.$$

From (21.6) we can draw a further (surprising) conclusion. If $f \neq g$, then the square root in the denominator of the expressions for f and for g must be an integer, i.e. $(\mu - \lambda)^2 + 4(k - \mu)$ is a perfect square. It then follows from (21.6) that the eigenvalues r and s are *integers*!

The other case, i.e. when $f = g$, is usually called the *half-case*. We then have an $srg(4\mu + 1, 2\mu, \mu - 1, \mu)$. The Paley graphs are examples of the half-case. In his paper on conference telephony, mentioned in Chapter 18, Belevitch observed that a necessary condition for the existence of a conference matrix of order n is that $n - 1$ is the sum of two squares. See Problem 19M. We note that the parameters $v = 21$, $k = 10$, $\lambda = 4$, $\mu = 5$ satisfy all the necessary conditions for the existence of a strongly regular graph that we stated above, but the graph does not exist because, using (18.5), it would imply the existence of a conference matrix of order 22 and since 21 is not the sum of two squares, this is impossible.

The condition of Theorem 21.1 is known as the *integrality condition*. We shall call a parameter set (v, k, λ, μ) that satisfies these conditions and the earlier necessary conditions, a *feasible set*.

Problem 21B. Show that if an $srg(k^2 + 1, k, 0, 1)$ exists, then $k = 1, 2, 3, 7$ or 57 . (See the notes to Chapter 4.)

We have seen that the adjacency matrix of an $srg(v, k, \lambda, \mu)$ has three eigenvalues, one of which is k . There is a partial converse: If G is a connected regular graph of degree k with an adjacency matrix A with exactly three distinct eigenvalues, then G is strongly regular. This is Problem 31F of Chapter 31.

To obtain some more examples of strongly regular graphs, we consider another connection with an earlier topic, namely designs. This idea is due to J.-M. Goethals and J. J. Seidel (1970). A 2-design is called *quasisymmetric* if the cardinality of the intersection of two distinct blocks takes only two distinct values, say $x > y$. We introduce a graph, called the *block graph* of the design; the vertices are the blocks of the design and two vertices are adjacent if and only if their intersection has cardinality y .

Theorem 21.2. *The block graph of a quasisymmetric design is strongly regular.*

PROOF: Let N be the $v \times b$ incidence matrix of the design and A the adjacency matrix of its block graph G . We have (using the parameters v, k, b, r, λ of the 2-design):

$$\begin{aligned} NN^\top &= (r - \lambda)I + \lambda J, \\ N^\top N &= kI + yA + x(J - I - A). \end{aligned}$$

(The first equation is (19.7), the second is the definition of A .) We know that both NN^\top and $N^\top N$ have all-one eigenvectors \mathbf{j} (of different lengths!) with eigenvalue kr . Also, we know that NN^\top has only the eigenvalue $r - \lambda$ on \mathbf{j}^\perp , with multiplicity $v - 1$. Therefore $N^\top N$ has this same eigenvalue, with the same multiplicity, and the eigenvalue 0 with multiplicity $b - v$. Since $x \neq y$, A is a linear combination of I, J , and $N^\top N$. Therefore A has eigenvector \mathbf{j} and only two eigenvalues on the space \mathbf{j}^\perp . They are $(r - \lambda + k + x)/(y - x)$ with multiplicity $v - 1$ and $(x - k)/(y - x)$ with multiplicity $b - v$. By our observation above, G is strongly regular. \square

Now that we know that G is strongly regular, it is easy to calculate the parameters. We do not give the distasteful formulae.

Example 21.5. Consider the $S(5, 8, 24)$ of Chapter 20. We fix two points and consider the residual design with respect to these two points. This is a 3-(22, 6, 1). From Problem 20F we know that the 21 blocks of this design that contain a given point are the lines of $PG_2(4)$ (i.e. after the point is removed) and the 56 blocks that do not contain that point are hyperovals in this plane. They form a 2-(21, 6, 4) design. From the properties of $S(5, 8, 24)$ it follows that

any two of these hyperovals meet in 0 or in 2 points. Therefore, this derived design is a quasisymmetric design. From Theorem 21.2 it follows that the block graph of the design is a $(56, k, \lambda, \mu)$. Here, $k = 10$ because there are $45 = (4 - 1) \cdot \binom{6}{2}$ hyperovals that meet a given hyperoval in 2 points. From the design properties or from the conditions on strongly regular graphs, one then easily finds that $\lambda = 0, \mu = 2$. The graph constructed in this example is known as the *Gewirtz graph*. Note that if A is the adjacency matrix of the Gewirtz graph, then by (21.5) we have $(I + A)^2 = 9I + 2J$, and that means that $N := I + A$ is the incidence matrix of a 2- $(56, 11, 2)$ design (a so-called *biplane*). So in this case, we also find a new design from the strongly regular graph.

Problem 21C. Let $\mathcal{D} := (\mathcal{P}, \mathcal{B}, \mathbf{I})$ be the 3- $(22, 6, 1)$ design mentioned above; it is unique. We form a graph with as vertex set $\mathcal{P} \cup \mathcal{B} \cup \{\infty\}$. The vertex ∞ is joined to every element of \mathcal{P} . An element of \mathcal{P} is joined to an element of \mathcal{B} if they are incident. Finally, two elements of \mathcal{B} are joined if and only if the blocks are disjoint. Show that this defines an $srg(100, 22, 0, 6)$. This graph is called the *Higman-Sims graph*.

If at this point we were to make a list of feasible parameter sets for strongly regular graphs, then the list would contain many sets that do not correspond to such a graph. We shall prove a few of the theorems that exclude these sets. Again, the methods are algebraic. As preparation, the reader should try to do the following problem using purely combinatorial arguments.

Problem 21D. Show that an $srg(28, 9, 0, 4)$ does not exist.

That this graph does not exist is a consequence of the next theorem, known as the *Krein condition*.

Theorem 21.3. Let G be a strongly regular graph with adjacency matrix A , having eigenvalues k, r , and s . Then

$$(r + 1)(k + r + 2rs) \leq (k + r)(s + 1)^2,$$

and

$$(s + 1)(k + s + 2sr) \leq (k + s)(r + 1)^2.$$

PROOF: Let $B := J - I - A$. We know that the matrices of \mathfrak{A} have three common eigenspaces of dimension 1, f , and g , respectively. Call these spaces V_0 , V_1 , and V_2 . Here V_0 is the space spanned by \mathbf{j} , and V_1 and V_2 correspond to the eigenvalues r and s of A . For $i = 0, 1, 2$ let E_i be the matrix of the projection onto V_i , i.e. E_i has eigenvalue 1 on V_i and 0 on the other two eigenspaces. These matrices are what is called a basis of minimal *idempotents* of \mathfrak{A} . We now consider the same set \mathfrak{A} , but as multiplication we take the Hadamard product (see Problem 21E). It is obvious that any two of I , A , and B have product O . Any $(0,1)$ -matrix is idempotent for Hadamard multiplication. So we conclude that \mathfrak{A} is closed under Hadamard multiplication and that the matrices I , A , and B are a basis of minimal idempotents.

Note that the definition of E_i ($i = 0, 1, 2$) implies that

$$I = E_0 + E_1 + E_2, \quad A = kE_0 + rE_1 + sE_2,$$

and

$$B = (v - k - 1)E_0 + (-r - 1)E_1 + (-s - 1)E_2.$$

From this, we can express the E_i in I , A , and B .

Consider the behavior of the matrices E_i under the Hadamard product. Since they form a basis of \mathfrak{A} , we have

$$E_i \circ E_j = \sum_{k=0}^2 q_{ij}^k E_k,$$

where q_{ij}^k is the eigenvalue of $E_i \circ E_j$ on V_k . It is a tedious calculation, but the numbers q_{ij}^k can be expressed in terms of the parameters of G using the relations given above.

At this point we need the result of Problem 21E. The Hadamard product $E_i \circ E_j$ is a principal submatrix of the Kronecker product $E_i \otimes E_j$. This matrix is idempotent, hence its eigenvalues are 0 and 1. By the theorem alluded to in Problem 21E, the eigenvalues q_{ij}^k have to be between 0 and 1. It turns out (after one has done all the calculations) that all except two of the inequalities that one finds in this way are satisfied. These two are $q_{11}^1 \geq 0$ and $q_{22}^2 \geq 0$. These are the two equations of the assertion. \square

Problem 21E. Let A and B be two symmetric $n \times n$ matrices with eigenvalues $\lambda_1, \dots, \lambda_n$, respectively μ_1, \dots, μ_n . Determine the eigenvalues of $A \otimes B$. We define the Hadamard product $A \circ B$ of A and B to be the matrix with entries $a_{ij}b_{ij}$. Show that $A \circ B$ is a principal submatrix of $A \otimes B$. What can you conclude about the eigenvalues of $A \circ B$?

To appreciate the next theorem, the reader should first convince himself that the parameter set (50,21,4,12) is feasible and that it satisfies the Krein conditions. What should one count to show that the set nevertheless does not correspond to a strongly regular graph?

Theorem 21.4. Let k, r, s be the eigenvalues of the adjacency matrix A of an $srg(v, k, \lambda, \mu)$ and let the multiplicities be $1, f$ and g . Then

$$v \leq \frac{1}{2}f(f + 3) \quad \text{and} \quad v \leq \frac{1}{2}g(g + 3).$$

PROOF: Let B be $J - I - A$ and let the matrices E_i ($i = 0, 1, 2$) be as in the proof of the previous theorem. Let

$$E_1 = \alpha I + \beta A + \gamma B.$$

Since E_1 is symmetric, there is an orthogonal matrix $(H_1 \ K_1)$ such that

$$E_1 = (H_1 \ K_1) \begin{pmatrix} I & O \\ O & O \end{pmatrix} \begin{pmatrix} H_1^\top \\ K_1^\top \end{pmatrix} = H_1 H_1^\top.$$

Here H_1 is an $v \times f$ matrix with $H_1^\top H_1 = I$. We consider the rows of H_1 as v vectors in \mathbb{R}^f . It follows that each of these vectors has length $\alpha^{\frac{1}{2}}$ and any two distinct vectors from this set (call it S) have inner product β or γ . Such a set is called a *spherical 2-distance set* because we can interpret S as a set of points on a sphere with only two distinct (angular) distances. We must show that the cardinality of S is at most $\frac{1}{2}f(f + 3)$.

We normalize and obtain a set S' of v vectors on the unit sphere Ω in \mathbb{R}^f with only two inner products, say b and c . For every $\mathbf{v} \in S'$ we define a function $f_{\mathbf{v}} : \Omega \rightarrow \mathbb{R}$ by

$$f_{\mathbf{v}}(\mathbf{x}) := \frac{(\langle \mathbf{v}, \mathbf{x} \rangle - b)(\langle \mathbf{v}, \mathbf{x} \rangle - c)}{(1 - b)(1 - c)}.$$

These functions are polynomials of degree 2 in the coordinates of \mathbf{x} . If $\mathbf{v} \in S$, $\mathbf{w} \in S$, $\mathbf{v} \neq \mathbf{w}$, then $f_{\mathbf{v}}(\mathbf{v}) = 1$ and $f_{\mathbf{v}}(\mathbf{w}) = 0$. Therefore these functions are linearly independent. The spaces of homogeneous linear and quadratic forms on Ω have dimensions f and $\frac{1}{2}f(f+1)$ respectively; since $x_1^2 + \cdots + x_f^2 = 1$ on Ω , we can express constants in forms of degree 2 and 1. From the linear independence of the functions $f_{\mathbf{v}}$, it follows that there can be at most $f + \frac{1}{2}f(f+1) = \frac{1}{2}f(f+3)$ of them. \square

This theorem is known as the *absolute bound*. It was shown by A. Neumaier (1980) that the absolute bound can be improved to

$$v \leq \frac{1}{2}f(f+1) \text{ unless } q_{11}^1 = 0$$

(and similarly for the other inequality).

Before turning to the relation between strongly regular graphs and certain incidence structures, we show that nice counting arguments also play a role in this area.

Theorem 21.5. *Let G be a strongly regular graph with the same parameters as $T(n)$, i.e. $G = \text{srg}(\binom{n}{2}, 2(n-2), n-2, 4)$. If $n > 8$, then G is isomorphic to $T(n)$.*

PROOF: Fix a vertex x and denote by Γ the induced subgraph on $\Gamma(x)$. This is a regular graph on $2(n-2)$ vertices, with degree $n-2$. Let y and z be nonadjacent vertices of Γ and let there be m vertices in Γ adjacent to both. Since $\mu = 4$ and x is adjacent to y and z , we have $m \leq 3$. In the graph Γ , there are $n-2-m$ vertices adjacent to y but not to z , and the same number adjacent only to z . Hence there are $m-2$ vertices adjacent to neither of them. So $m \geq 2$. Suppose $m = 3$. Consider the unique vertex w adjacent to neither y nor z . Every vertex adjacent to w in Γ is adjacent to y or to z , which implies that $n-2 \leq 3+3 = 6$, a contradiction. Hence $m = 2$, and we also see that there are no triangles in the complement $\bar{\Gamma}$.

We now show that $\bar{\Gamma}$ is bipartite. On the contrary, assume there is a circuit of odd length in this graph. Choose such a circuit $C = (x_0, x_1, \dots, x_k = x_0)$ with k minimal. From the argument above we know that $k \neq 3$. In the graph Γ , the vertices x_0 and x_1

are nonadjacent and are both adjacent to x_3, x_4, \dots, x_{k-2} . By the argument above, $k \leq 6$ and since k is odd, $k = 5$. The vertex x_0 has degree $n - 3$ in $\bar{\Gamma}$, i.e. it is adjacent to $n - 5$ vertices, besides x_1 and x_4 . These must be nonadjacent in $\bar{\Gamma}$ to both x_1 and x_4 . A similar assertion can be made for x_2 , yielding $n - 5$ vertices outside C nonadjacent in $\bar{\Gamma}$ to both x_1 and x_3 . There are exactly $n - 4$ vertices outside C nonadjacent to x_1 ; hence at least $n - 6$ vertices nonadjacent in $\bar{\Gamma}$ to both x_3 and x_4 . The result of the first paragraph implies that $n - 6 \leq 1$, a contradiction.

The result of the second paragraph means that Γ contains two disjoint *cliques* (sets of vertices, any two of which are adjacent) of size $n - 2$. Since x was arbitrary, we have shown that any vertex in G lies in two cliques of size $n - 1$ (cliques of this size will be called *grand cliques*). The same argument shows that any edge is in one of these grand cliques. The number of grand cliques is $2\binom{n}{2}/(n - 1) = n$. Since any two grand cliques have at most one vertex in common, they must have exactly one vertex in common. If we consider grand cliques as ‘points’ and vertices as ‘blocks’, then we have just shown that these points and blocks form a 2 - $(n, 2, 1)$ design, i.e. the trivial design of all pairs from an n -set. G is the block graph of this design, i.e. G is indeed isomorphic to $T(n)$. \square

We remark that the theorem can also be proved, by case analysis, for $n < 8$ and that for $n = 8$ there are three other graphs with the parameters of $T(8)$, known as the Chang graphs.

Problem 21F. Let G be a strongly regular graph with the same parameters as $L_2(n)$, i.e. $G = \text{srg}(n^2, 2(n - 1), n - 2, 2)$. Prove that if $n > 4$, then G is isomorphic to $L_2(n)$.

R. C. Bose (1963) studied large cliques in more general strongly regular graphs. This led him to the concept of a *partial geometry*. A partial geometry $pg(K, R, T)$ is an incidence structure of points and lines with the following properties:

- (1) every line has K points and every point is on R lines;
- (2) any two points are incident with at most one line;
- (3) if point p is not on line L , then there are exactly T lines through p that meet L .

If two points x and y are on a line, we say that they are *collinear* and write $x \sim y$.

Problem 21G. Determine the number of points and lines of a partial geometry $pg(K, R, T)$.

By interchanging the roles of points and lines in a $pg(K, R, T)$, we find the so-called *dual* partial geometry, a $pg(R, K, T)$.

We introduce the *point graph* of a partial geometry as the graph with the points of the geometry as vertices, and an edge $\{x, y\}$ if and only if $x \sim y$.

Problem 21H. Show that the point graph of a $pg(K, R, T)$ is a (possibly trivial) $srg(v, k, \lambda, \mu)$, with:

$$v = K \left(1 + \frac{(K-1)(R-1)}{T} \right), \quad k = R(K-1),$$

$$\lambda = (K-2) + (R-1)(T-1), \quad \mu = RT,$$

$$r = K-1-T, \quad s = -R.$$

If a strongly regular graph has parameters such that it could be the point graph of some partial geometry, then the graph is called *pseudo-geometric*, and it is called *geometric* if it is indeed the point graph of a partial geometry. The idea of introducing grand cliques and then showing that the grand cliques and the points form a design, as used above, was used by Bose to prove the following theorem.

Theorem 21.6. *If a strongly regular graph is pseudo-geometric, corresponding to $pg(K, R, T)$, and if $2K > R(R-1) + T(R+1)(R^2 - 2R + 2)$, then the graph is geometric.*

We do not give a proof here. The ideas of this proof were extended by A. Neumaier (1979), and, after an improvement by A. E. Brouwer, his result obtained the following form (known as the *claw bound*).

Theorem 21.7. *If, for a strongly regular graph with the usual parameters, $\mu \neq s^2$ and $\mu \neq s(s+1)$, then $2(r+1) \leq s(s+1)(\mu+1)$.*

The idea of the proof is to show that if r is large, then the graph is the point graph of a partial geometry; this is done by counting arguments. Then the absolute bound and Krein conditions are applied to the point graph of the dual partial geometry. These show the inequality stating that r cannot be too large.

The parameters (2058, 242, 91, 20) are feasible and satisfy all the other necessary conditions stated in this chapter, except the claw bound. So a graph with these parameters does not exist.

Problem 21I. Consider an $srg(v, k, \lambda, 1)$. Show that the induced subgraph on $\Gamma(x)$ is a union of cliques. Count the number of $(\lambda+2)$ -cliques in the graph. Thus show that both $k/(\lambda+1)$ and $vk/\{(\lambda+1)(\lambda+2)\}$ are integers. Apply to the set (209, 16, 3, 1).

The partial geometries can be divided into four classes:

- (1) A partial geometry with $T = K$ is a 2 -($v, K, 1$) design.
- (2) A partial geometry with $T = R - 1$ is called a *net*; dually, if $T = K - 1$ we speak of a *transversal design*.
- (3) A partial geometry with $T = 1$ is called a *generalized quadrangle*; the notation $GQ(K - 1, R - 1)$ is commonly used for a $pg(K, R, 1)$.
- (4) If $1 < T < \min\{K - 1, R - 1\}$, then we call the partial geometry *proper*.

Example 21.6. Consider the affine plane $AG_2(n)$. From Problem 19K we know that the lines can be divided into equivalence classes of parallel lines, each containing n lines. Consider all the points of the plane and take the lines of m parallel classes. Then it is clear that these form a $pg(n, m, m - 1)$, i.e. a net.

Example 21.7. Consider a Latin square of order n . Let the n^2 cells be the vertices of a graph; two vertices are joined by an edge if and only if they are in the same row or in the same column, or if they have the same entry. The graph is regular, with degree $3(n - 1)$. If two vertices are joined, we may assume without loss of generality that they are in the same row (think of the Latin square as an $OA(n, 3)$). Then they have $n - 2$ mutual neighbors.

If two vertices are not joined, then they clearly have six common neighbors. So this is an $sg(n^2, 3(n-1), n-2, 6)$. This is called a *Latin square graph* and the notation is $L_3(n)$, in accordance with the notation of Example 21.2. Generalizations will occur in a later chapter. The graph $L_3(n)$ is geometric, corresponding to a partial geometry $pg(n, 3, 2)$, i.e. a net. Of course lines correspond to rows, columns, and symbols of the square. We shall see in Chapter 22 that in fact nets and orthogonal arrays are equivalent concepts.

Example 21.8. A quadrangle satisfies the conditions for a partial geometry. It is a $pg(2, 2, 1)$ which accounts for the name generalized quadrangle.

Consider a hyperoval O in $PG_2(4)$. We take as point set the 15 points of the plane that are not on O . Lines will be the secants of O . Then every line has 3 points, and every point is on 3 lines. In fact this is a $pg(3, 3, 1)$, i.e. $GQ(2, 2)$.

Note that the same construction applied to $PG_2(q)$ for q even yields a $pg(q-1, \frac{1}{2}(q+2), \frac{1}{2}(q-2))$.

Example 21.9. Consider $PG_2(q)$ where q is even. As in Example 19.7, this is an incidence structure whose objects are the 1-dimensional subspaces and 2-dimensional subspaces of \mathbb{F}_q^3 . Again, let O be a hyperoval in the projective plane. Let all 1-dimensional subspaces that are in O and their cosets in \mathbb{F}_q^3 be lines; points are the points of the vector space. Every line has q points; every point is on $q+2$ lines. The fact that O is a hyperoval implies that for any point p not on line L , there is a unique line through p that meets L . So we have defined a $GQ(q-1, q+1)$.

Example 21.10. Consider the subgroup G of \mathbb{Z}_3^6 generated by the element $(1, 1, 1, 1, 1, 1)$. For each coset $\mathbf{a} + G$, the sum of the coordinates of the points is a constant i . We say that the coset is of type i . Let \mathcal{A}_i be the set of cosets of G of type i . We define a tripartite graph Γ by joining the coset $\mathbf{a} + G$ to the coset $\mathbf{a} + \mathbf{b} + G$ for each \mathbf{b} that has only one nonzero coordinate. Clearly, any element of \mathcal{A}_i has six neighbors in \mathcal{A}_{i+1} and six in \mathcal{A}_{i+2} . We construct a partial geometry by taking some \mathcal{A}_i as point set and one of the other two classes \mathcal{A}_j as line set. Incidence corresponds to adjacency. That $K = R = 6$ is clear. It is an easy exercise to show that $T = 2$.

This defines a $pg(6, 6, 2)$.

We now give a nice application of Theorem 21.5. We shall prove the theorem, mentioned in Chapter 19 without proof, which states that a quasiresidual design with $\lambda = 2$ is a residual design. Since the cases $k \leq 6$ require separate treatment, we restrict ourselves to blocksize > 6 .

Theorem 21.8. *Let \mathcal{D} be a $2-(v, k, 2)$ design with $k > 6$ and $v = \frac{1}{2}k(k+1)$ (so \mathcal{D} is quasiresidual). Then \mathcal{D} is a residual of a symmetric 2-design.*

PROOF: Let B be a block and let a_i denote the number of blocks ($\neq B$) that meet B in i points. Just as in Theorem 19.9 we find

$$\sum a_i = \frac{1}{2}k(k+3), \quad \sum ia_i = k(k+1), \quad \sum i(i-1)a_i = k(k-1).$$

This implies that $\sum (i-1)(i-2)a_i = 0$. Therefore any two distinct blocks meet in 1 or in 2 points, i.e. the design \mathcal{D} is quasisymmetric. From Theorem 21.2 we find that the block graph G of \mathcal{D} is strongly regular. Calculation of the parameters shows that G has the same parameters as $T(k+2)$. So by Theorem 21.5, G is isomorphic to $T(k+2)$. This means that we can label the blocks of \mathcal{D} with 2-subsets of $S := \{1, 2, \dots, k+2\}$ in such a way that two blocks meet in i points whenever their labels meet in $2-i$ points ($i = 1, 2$). We adjoin the set S to the point set of \mathcal{D} , and we adjoin to each block its label, a 2-subset of S . Finally, we consider S as a new block. This produces the required symmetric design with $\lambda = 2$ that has \mathcal{D} as residual with respect to the block S . \square

We list below a table of feasible parameter sets with $v < 30$ and what we have learned about them in this chapter. The only one left as a challenge for the reader is no. 14, i.e. $GQ(2, 4)$ for which no construction was given. The corresponding graph is known as the *Schlaefli graph*.

No.	v	k	λ	μ	Example
1	5	2	0	1	$P(5)$
2	9	4	1	2	$L_2(3)$
3	10	3	0	1	Petersen, $\overline{T(5)}$
4	13	6	2	3	$P(13)$
5	15	6	1	3	$GQ(2, 2)$
6	16	5	0	2	Clebsch
7	16	6	2	2	$L_2(4)$
8	17	8	3	4	$P(17)$
9	21	10	3	6	$T(7)$
10	21	10	4	5	does not exist, conference
11	25	8	3	2	$L_2(5)$
12	25	12	5	6	$L_3(5)$
13	26	10	3	4	$STS(13)$, Theorem 21.2
14	27	10	1	5	$GQ(2, 4)$
15	28	9	0	4	does not exist, Thms. 21.3, 21.4
16	28	12	6	4	$T(8)$
17	29	14	6	7	$P(29)$

We give some remarks on directed strongly regular graphs and a few problems.

The condition on paths of length 2 in the definition of strongly regular graphs is best seen by writing (21.5) as follows

$$(21.5') \quad AJ = kJ, \quad A^2 = kI + \lambda A + \mu(J - I - A).$$

The definition was generalized to directed graphs by A. Duval (1988). We consider a directed graph G without loops or multiple edges. If there is an edge from a to b , we write $a \rightarrow b$. We allow edges in both directions, indicated by $a \leftrightarrow b$. In that case we call (a, b) an undirected edge. The generalization of (21.5') will be the same with respect to paths of length 2, but we now require that each vertex has indegree k , outdegree k and that among these edges there are t undirected edges (producing paths of length 2 from a vertex to itself). So, G is called a *directed strongly regular graph* if its adjacency matrix A satisfies

$$(21.8) \quad AJ = JA = kJ, \quad A^2 = tI + \lambda A + \mu(J - I - A).$$

For such a graph on v vertices, the notation $dsrg(v; k, t; \lambda, \mu)$ will be used.

Example 21.11. Let G be a graph on six vertices consisting of a directed triangle $1 \rightarrow 2 \rightarrow 3 \rightarrow 1$, a directed triangle $1' \rightarrow 3' \rightarrow 2' \rightarrow 1'$, and undirected edges (i, i') , $i = 1, 2, 3$. If C is the 3×3 circulant matrix with $c_{ij} = 1$ for $(i, j) = (1, 2), (2, 3), (3, 1)$ and 0 otherwise, then the adjacency matrix A of G is

$$A = \begin{pmatrix} C & I \\ I & C^2 \end{pmatrix}.$$

One easily checks that A satisfies (21.8) with $k = 2$, $t = 1$, $\lambda = 0$, and $\mu = 1$. So G is a $dsrg(6; 2, 1; 0, 1)$.

Problem 21J. State and prove an analog of Theorem 21.1 for directed strongly regular graphs.

Problem 21K. Exclude strongly regular graphs and graphs with adjacency matrix $J - A$. Show that the eigenvalues calculated in Problem 21J lead to an analog of the “half-case” if $(\mu - \lambda)^2 + 4(t - \mu)$ is not the square of an integer. Prove that in this case, the adjacency matrix A of the $dsrg$ is of the type of Q in (18.5).

Problem 21L. Consider the case $\mu = 1$, $\lambda = 0$, $t = k - 1$. Prove that only three values of v are possible. Show that in the second case, an example can be obtained from $K_{3,3}$ by replacing vertices by directed triangles, and edges by copies of the graph of Example 21.11 in a suitable way.

We now give some comments and problems on neighborhood regular graphs.

In a strongly regular graph G the neighborhoods $\Gamma(x)$ and $\Delta(x)$ of x in G , respectively in the complement \overline{G} , are regular graphs. C. D. Godsil and B. D. McKay (1979) called any graph that has this property a *neighborhood regular graph*. It is not difficult to show that a neighborhood regular graph that is also regular is in fact a strongly regular graph. If G or \overline{G} is not connected, trivial situations arise. In the following problems, we assume that G is neighborhood regular, not regular, and that G and \overline{G} are connected.

Problem 21M.

(i) Show that the degree of $\Gamma(x)$ does not depend on x . Call this number a .

(ii) Show that there is a number \bar{a} such that for each x , the degree of $\overline{\Delta(x)}$ is \bar{a} .

Problem 21N. If X and Y are subsets of the vertex set of G , we denote by $|XY|$ the number of edges (x, y) in G with $x \in X$ and $y \in Y$. Let x_1 and x_2 be two non-adjacent edges in G with degree k_1 , respectively k_2 , $k_1 \neq k_2$. Let $d_i := \deg \Delta(x_i)$, $i = 1, 2$. Note that $d_1 \neq d_2$. Now consider the following subsets of the vertex set of G : $A := \Gamma(x_1) \cap \Delta(x_2)$, $B := \Gamma(x_2) \cap \Delta(x_1)$, $C := \Gamma(x_1) \cap \Gamma(x_2)$, and $D := \Delta(x_1) \cap \Delta(x_2)$.

(i) Find relations between the numbers $|XY|$ and $|X|$, where X and Y are among B, C, D .

(ii) Deduce that

$$|DD| = (a + \bar{a} + 1)d_1 - d_1^2 - a|C| + |CC|.$$

(iii) Prove that $d_1 + d_2 = a + \bar{a} + 1$.

(iv) Show that *all* the vertices in G have degree k_1 or k_2 .

Example 21.12. Let G be the octagon on vertices 1 to 8 with the two diagonals (15) and (26). This is a neighborhood regular graph with $k_1 = 2$, $k_2 = 3$, $a = 0$, $\bar{a} = 2$, $d_1 = 1$, and $d_2 = 2$.

Problem 21O. Given a Steiner triple system \mathcal{S} on n points, define a graph G whose vertices are the triples \mathcal{A} of the system and where $A, B \in \mathcal{A}$ are adjacent when $|A \cap B| = 1$.

(i) Show by elementary means (i.e. do not use Theorem 21.2 or matrix methods) that G is strongly regular and calculate its parameters.

(ii) Show that if C is a clique in G and $|C| > 7$, then C is a subset of the triples that contain a fixed point x for some point x of \mathcal{S} .

(iii) Use this to show that if the graphs G_1 and G_2 arising from two Steiner triple systems on $n > 15$ points are isomorphic, then the two systems are also isomorphic. (We remark that there are more than 163929929318400 nonisomorphic Steiner triple systems

on 25 points—see R. M. Wilson (1973/74)—so we have at least that many nonisomorphic strongly regular graphs on 100 vertices.)

Problem 21P. Show that equality in Problem 4H cannot occur unless $n = 3$.

Problem 21Q. Prove the so-called *Friendship Theorem*: At a party with n people ($n > 3$) every two persons have exactly one mutual friend. Then there is a unique person at the party who is a friend of all the others. Use problem 1J.

Notes.

Strongly regular graphs and partial geometries were introduced by R. C. Bose in 1963. A much more general concept, namely that of an *association scheme*, had been introduced by Bose and Shimamoto in 1952; see Chapter 30 here and Cameron and Van Lint (1991), Ch. 17.

For a survey of construction methods for strongly regular graphs, see Hubaut (1975) and Brouwer and Van Lint (1982).

The Clebsch graph may be defined by the 16 lines in the Clebsch quartic surface, a pair of lines being adjacent if and only if they are skew. Alfred Clebsch (1833–1872) was a mathematician and physicist who worked in Karlsruhe, Giessen, and Göttingen. He was one of the founders of the famous journal *Mathematische Annalen*.

The algebra \mathfrak{A} was introduced by R. C. Bose and D. M. Mesner in 1959.

The reference Goethals and Seidel (1970) contains, besides Theorem 21.2, many interesting connections between strongly regular graphs and other combinatorial designs. Hadamard matrices, Steiner systems and the Golay code all contribute to the theory. For these connections, again see Cameron and Van Lint (1991).

The Higman-Sims graph is connected to their famous finite simple group (see Higman and Sims (1968)).

Theorem 21.3 became known as the Krein condition because a special case of this theorem was proved by L. L. Scott by applying a result of M. G. Krein concerning topological groups to a problem on finite groups. The simple proof given in this chapter is due to D. G. Higman (1975) and P. Delsarte (1973). The case of equality in

the Krein conditions was treated by Delsarte, Goethals and Seidel (1977) and Cameron, Goethals and Seidel (1978).

The idea of the proof of Theorem 21.4 is due to T. H. Koornwinder (1976).

Theorem 21.5 was proved several times: see for example, L. C. Chang (1959), W. S. Connor (1958), A. J. Hoffman (1960). The three exceptional graphs for $n = 8$ are known as the *Chang graphs*.

For surveys on partial geometries, see Van Lint (1983), De Clerck and Van Maldeghem (1995), and De Clerck (2000).

Nets were introduced by R. H. Bruck in 1951. Bose's result on pseudo-geometric graphs was inspired by Bruck's work (e.g. the idea of grand cliques).

For all that one would like to know about generalized quadrangles (and more) we refer to the book *Finite Generalized Quadrangles* by S. E. Payne and J. A. Thas (1984).

Only three proper partial geometries with $T = 2$ are known. The geometry $pg(6, 6, 2)$ of Example 21.9 was first constructed by Van Lint and Schrijver (1981); the construction that we described is due to Cameron and Van Lint (1982). The other known examples are a $pg(5, 18, 2)$ due to Haemers and a $pg(8, 20, 2)$ found by Mathon (with the aid of a computer).

A big step in the direction of the proof of the nonexistence of a projective plane of order 10, mentioned in Chapter 19, was the proof of the nonexistence of $pg(6, 9, 4)$. This implied (see Example 21.8) that, if the plane existed, it would not have any hyperovals.

References.

- R. C. Bose (1963), Strongly regular graphs, partial geometries, and partially balanced designs, *Pacific J. Math.* **13**, 389–419.
- R. C. Bose and D. M. Mesner (1959), On linear associative algebras corresponding to association schemes of partially balanced designs, *Ann. Math. Stat.* **30**, 21–38.
- A. E. Brouwer and J. H. van Lint (1982), Strongly regular graphs and partial geometries, in: *Enumeration and Design* (D. M. Jackson and S. A. Vanstone, eds.), Academic Press.
- R. H. Bruck (1951), Finite nets I, *Canad. J. Math.* **3**, 94–107.
- R. H. Bruck (1963), Finite nets II, *Pacific J. Math.* **13**, 421–457.

- P. J. Cameron (1978), Strongly regular graphs, in: *Selected Topics in Graph Theory* (L. W. Beineke and R. J. Wilson, eds.), Academic Press.
- P. J. Cameron, J.-M. Goethals, and J. J. Seidel (1978), The Krein condition, spherical designs, Norton algebras and permutation groups, *Proc. Kon. Ned. Akad. v. Wetensch.* **81**, 196–206.
- P. J. Cameron and J. H. van Lint (1991), *Designs, Graphs, Codes and their links*, London Math. Soc. Student Texts **22**, Cambridge University Press.
- P. J. Cameron and J. H. van Lint (1982), On the partial geometry $pg(6, 6, 2)$, *J. Combinatorial Theory (A)* **32**, 252–255.
- L. C. Chang (1959), The uniqueness and nonuniqueness of triangular association schemes, *Sci. Record Peking Math.* **3**, 604–613.
- F. De Clerck and H. Van Maldeghem (1995), Some classes of rank 2 geometries. In F. Buekenhout (editor) *Handbook of Incidence geometry, Buildings and Foundations*, North-Holland.
- F. De Clerck (2000), Partial and semipartial geometries: an update, *Combinatorics 2000* (Gaeta, Italy).
- W. S. Connor (1958), The uniqueness of the triangular association scheme, *Ann. Math. Stat.* **29**, 262–266.
- P. Delsarte (1973), An algebraic approach to the association schemes of coding theory, *Philips Res. Repts. Suppl.* **10**.
- P. Delsarte, J.-M. Goethals and J. J. Seidel (1977), Spherical codes and designs, *Geometriae Dedicata* **6**, 363–388.
- A. M. Duval (1988), A Directed Graph Version of Strongly Regular Graphs, *J. Combinatorial Theory (A)* **47**, 71–100.
- A. Gewirtz (1969), The uniqueness of $g(2, 2, 10, 56)$, *Trans. New York Acad. Sci.* **31**, 656–675.
- C. D. Godsil and B. D. McKay (1979), Graphs with Regular Neighborhoods, *Combinatorial Mathematics VII*, 127–140, Springer.
- J.-M. Goethals and J. J. Seidel (1970), Strongly regular graphs derived from combinatorial designs, *Canad. J. Math.* **22**, 597–614.
- D. G. Higman (1975), Invariant relations, coherent configurations and generalized polygons, in: *Combinatorics* (M. Hall, Jr. and J. H. van Lint, eds.), D. Reidel.
- D. G. Higman and C. C. Sims (1968), A simple group of order

- 44,352,000, *Math. Z.* **105**, 110–113.
- A. J. Hoffman (1960), On the uniqueness of the triangular association scheme, *Ann. Math. Stat.* **31**, 492–497.
- X. Hubaut (1975), Strongly regular graphs, *Discrete Math.* **13**, 357–381.
- T. H. Koornwinder (1976), A note on the absolute bound for systems of lines, *Proc. Kon. Ned. Akad. v. Wetensch.* **79**, 152–153.
- J. H. van Lint (1983), Partial geometries, *Proc. Int. Congress of Math.*, Warsaw.
- J. H. van Lint and A. Schrijver (1981), Construction of strongly regular graphs, two-weight codes and partial geometries by finite fields, *Combinatorica* **1**, 63–73.
- J. H. van Lint and J. J. Seidel (1969), Equilateral point sets in elliptic geometry, *Proc. Kon. Ned. Akad. v. Wetensch.* **69**, 335–348.
- A. Neumaier (1979), Strongly regular graphs with smallest eigenvalue $-m$, *Archiv der Mathematik* **33**, 392–400.
- A. Neumaier (1980), New inequalities for the parameters of an association scheme, in: *Combinatorics and Graph Theory*, Lecture Notes in Math. **885**, Springer-Verlag.
- S. E. Payne and J. A. Thas (1984), *Finite Generalized Quadrangles*, Pitman.
- R. M. Wilson (1973/74), Nonisomorphic Steiner triple systems, *Math. Z.* **135**, 303–313.

22

Orthogonal Latin squares

Two Latin squares $L_1 : R \times C \rightarrow S$ and $L_2 : R \times C \rightarrow T$ (with the same row and column sets) are said to be *orthogonal* when for each ordered pair $(s, t) \in S \times T$, there is a unique cell $(x, y) \in R \times C$ so that

$$L_1(x, y) = s \quad \text{and} \quad L_2(x, y) = t.$$

The use of the word ‘orthogonal’ is perhaps unfortunate since it has other meanings in mathematics, but it has become far too commonplace to try to change now.

For example, let

$$A := \begin{bmatrix} A & K & Q & J \\ Q & J & A & K \\ J & Q & K & A \\ K & A & J & Q \end{bmatrix}, \quad B := \begin{bmatrix} \spadesuit & \heartsuit & \diamondsuit & \clubsuit \\ \clubsuit & \diamondsuit & \heartsuit & \spadesuit \\ \heartsuit & \spadesuit & \clubsuit & \diamondsuit \\ \diamondsuit & \clubsuit & \spadesuit & \heartsuit \end{bmatrix}$$

Figure 22.1

where $R = C = \{1, 2, 3, 4\}$, $S = \{A, K, Q, J\}$, $T = \{\spadesuit, \heartsuit, \diamondsuit, \clubsuit\}$. The orthogonality of A and B is evident when the two squares are superposed and we see that each element of $S \times T$ appears exactly once.

$$\begin{bmatrix} A\spadesuit & K\heartsuit & Q\diamondsuit & J\clubsuit \\ Q\clubsuit & J\diamondsuit & A\heartsuit & K\spadesuit \\ J\heartsuit & Q\spadesuit & K\clubsuit & A\diamondsuit \\ K\diamondsuit & A\clubsuit & J\spadesuit & Q\heartsuit \end{bmatrix}$$

Orthogonality does not depend on the particular symbol set used. We could replace the playing card suits in our example by any four symbols in any order, and the resulting square would still be

orthogonal to A . We have used Latin letters for the symbols of A ; if we had used Greek letters for B , it would have been clear why the superposition of two orthogonal Latin squares is often called a *Græco-Latin square*.

The example we have given with playing cards is similar to what is known as *Euler's 36 officers problem*. According to folklore, Euler was asked by Catherine the Great (at whose court he was in residence) to arrange 36 officers from six different regiments and of six different ranks (one officer of each rank from each regiment) in a 6 by 6 array so that each row and each column contained one officer of each rank and one officer of each regiment. A solution requires a pair of orthogonal Latin squares of order 6.

Surprisingly, there is no solution. Whether he was asked by Catherine or not, Euler did consider the problem in 1779 and convinced himself that it was impossible. Euler was capable of monumental calculation, but it is not clear that he had really examined all cases. This was systematically done in 1900 by G. Tarry. Today a computer can do this easily. A short proof (still involving several cases to be analyzed) was given by D. R. Stinson (1984).

Euler knew that a pair of orthogonal Latin squares of order n existed for all odd values of n , and all $n \equiv 0 \pmod{4}$; see Theorem 22.3 below. For examples of orthogonal Latin squares of odd orders n , let G be any group of order n and define squares L_1 and L_2 with row, column, and symbol sets G by

$$L_1(x, y) := xy, \quad L_2(x, y) := x^{-1}y.$$

For completely trivial reasons, there is no pair of orthogonal Latin squares of order 2. Euler asserted that he was of the opinion that this impossibility for $n = 2, 6$ extended as well to $n = 10, 14, 18, \dots$, i.e. to orders $n \equiv 2 \pmod{4}$. This statement was known as 'Euler's conjecture' for 177 years until it was suddenly and completely disproved by Bose, Parker, and Shrikhande. We will prove later their theorem that pairs of orthogonal Latin squares of orders n exist for *all* n except $n = 2, 6$.

At various times, a more general question has been raised: can one find sets of many Latin squares, any two of which are orthogonal? We will denote by $N(n)$ the largest integer k for which there

exist k Latin squares of order n that are pairwise orthogonal. For example, we may add

$$C := \begin{bmatrix} 0 & \alpha & \beta & \gamma \\ \alpha & 0 & \gamma & \beta \\ \beta & \gamma & 0 & \alpha \\ \gamma & \beta & \alpha & 0 \end{bmatrix}$$

(the addition table of the Klein four-group) to the squares in Fig. 22.1 to obtain three pairwise orthogonal Latin squares of order 4; thus $N(4) \geq 3$. We remark that the definition of orthogonality is trivial or vacuous for $n = 1$ or 0 , and so $N(1) = N(0) = \infty$.

Here is a construction that proves $N(q) \geq q - 1$ for a prime power q . All row, column, and symbol sets are to be the elements of the field \mathbb{F}_q . For each nonzero element a in \mathbb{F}_q , define $L_a(x, y) := ax + y$; these $q - 1$ squares are pairwise orthogonal. As we all know, the systems

$$\begin{aligned} ax + by &= s \\ cx + dy &= t \end{aligned}$$

have unique solutions (x, y) when $ad - bc \neq 0$, so it is easy to tell when two squares defined by linear equations are orthogonal. Here are the squares for $q = 5$:

$$\begin{bmatrix} 0 & 1 & 2 & 3 & 4 \\ 1 & 2 & 3 & 4 & 0 \\ 2 & 3 & 4 & 0 & 1 \\ 3 & 4 & 0 & 1 & 2 \\ 4 & 0 & 1 & 2 & 3 \end{bmatrix}, \quad \begin{bmatrix} 0 & 1 & 2 & 3 & 4 \\ 2 & 3 & 4 & 0 & 1 \\ 4 & 0 & 1 & 2 & 3 \\ 1 & 2 & 3 & 4 & 0 \\ 3 & 4 & 0 & 1 & 2 \end{bmatrix},$$

$$\begin{bmatrix} 0 & 1 & 2 & 3 & 4 \\ 3 & 4 & 0 & 1 & 2 \\ 1 & 2 & 3 & 4 & 0 \\ 4 & 0 & 1 & 2 & 3 \\ 2 & 3 & 4 & 0 & 1 \end{bmatrix}, \quad \begin{bmatrix} 0 & 1 & 2 & 3 & 4 \\ 4 & 0 & 1 & 2 & 3 \\ 3 & 4 & 0 & 1 & 2 \\ 2 & 3 & 4 & 0 & 1 \\ 1 & 2 & 3 & 4 & 0 \end{bmatrix}.$$

Theorem 22.1. For $n \geq 2$, we have $1 \leq N(n) \leq n - 1$.

PROOF: We may change all row, column, and symbol sets in a set of k pairwise orthogonal Latin squares $\{L_i\}_{i=1}^k$ to $\{1, 2, \dots, n\}$ (for

notational convenience), and we might as well rename the symbols if necessary so that the first row of each square is $1, 2, \dots, n$ in that order. Now we consider the elements

$$L_1(2, 1), L_2(2, 1), \dots, L_k(2, 1)$$

in the second row, first column. None of these is 1, since 1 occurs already in the first column. They are distinct because if $L_i(2, 1) = L_j(2, 1) = s$, say, then the fact that also $L_i(1, s) = L_j(1, s) = s$ would contradict the orthogonality of L_i and L_j . The upper bound follows. \square

In view of our construction from finite fields and the simple theorem above, we have

$$(22.1) \quad N(q) = q - 1 \quad \text{if } q \text{ is a prime power.}$$

At this point, we want to show that the concept of pairwise orthogonal Latin squares is equivalent to something the reader has already seen in the previous chapter! The assertion of the theorem will be more immediately apparent if we first notice that the property of being a Latin square can itself be described in terms of orthogonality. For example, a square of order 5 is Latin if and only if it is orthogonal to the two squares

$$\begin{bmatrix} 0 & 0 & 0 & 0 & 0 \\ 1 & 1 & 1 & 1 & 1 \\ 2 & 2 & 2 & 2 & 2 \\ 3 & 3 & 3 & 3 & 3 \\ 4 & 4 & 4 & 4 & 4 \end{bmatrix} \quad \text{and} \quad \begin{bmatrix} 0 & 1 & 2 & 3 & 4 \\ 0 & 1 & 2 & 3 & 4 \\ 0 & 1 & 2 & 3 & 4 \\ 0 & 1 & 2 & 3 & 4 \\ 0 & 1 & 2 & 3 & 4 \end{bmatrix}.$$

Theorem 22.2. *A set of k pairwise orthogonal Latin squares of order n exists if and only if an $(n, k + 2)$ -net exists.*

PROOF: Suppose $L_i : R \times C \rightarrow S_i$, $1 \leq i \leq k$, are pairwise orthogonal Latin squares. Let $\mathcal{P} = R \times C$, the set of n^2 cells. Roughly speaking, we take as lines the rows, the columns, and the ‘isymbol’ lines in each square. More formally, let

$$\mathcal{A}_1 = \{ \{ (x, b) : b \in C \} : x \in R \},$$

$$\mathcal{A}_2 = \{(a, y) : a \in R\} : y \in C\},$$

$$\mathcal{A}_{i+2} = \{(x, y) : L_i(x, y) = c\} : c \in S_i\}, \quad 1 \leq i \leq k,$$

and let $\mathcal{B} = \cup_{i=1}^{k+2} \mathcal{A}_i$. That $(\mathcal{P}, \mathcal{B})$ is an $(n, k+2)$ -net follows from the definitions of Latin and orthogonal.

Given an $(n, k+2)$ -net $(\mathcal{P}, \mathcal{B})$, where $\mathcal{B} = \cup_{i=1}^{k+2} \mathcal{A}_i$ is the partition into parallel classes, define $L_i : \mathcal{A}_1 \times \mathcal{A}_2 \rightarrow \mathcal{A}_{i+2}$ by declaring that $L_i(A, B)$ is to be the unique line in \mathcal{A}_{i+2} containing the point of intersection of A and B . As usual we leave to the reader the details of checking the Latin and orthogonal properties of these squares. \square

Corollary. $N(n) = n - 1$ if and only if there exists a projective (or affine) plane of order n .

The value of $N(n)$ tells us, in some very imprecise sense, how close to the existence of a projective plane of order n we may get. But we know terribly little about this function. The only value of n other than prime powers for which $N(n)$ is known is $n = 6$.

Problem 22A. (i) Consider the complement of the graph of an (n, n) -net and prove that $N(n) \geq n - 2$ implies that $N(n) = n - 1$.

(ii) Use the result of Problem 21F to prove that if $n > 4$, then $N(n) \geq n - 3$ implies that $N(n) = n - 1$.

Theorem 22.3.

(i) $N(nm) \geq \min\{N(n), N(m)\}$.

(ii) If $n = p_1^{e_1} p_2^{e_2} \cdots p_r^{e_r}$ is the factorization of n into powers of primes, then

$$N(n) \geq \min_{1 \leq i \leq r} (p_i^{e_i} - 1).$$

PROOF: Part (ii) follows from part (i) and (22.1), used inductively.

To prove part (i), we first define a Kronecker-like product for squares in the natural way: Given $L_i : R_i \times C_i \rightarrow S_i$, $i = 1, 2$, define

$$L_1 \otimes L_2 : (R_1 \times R_2) \times (C_1 \times C_2) \rightarrow (S_1 \times S_2)$$

by

$$(L_1 \otimes L_2)((x_1, x_2), (y_1, y_2)) := (L_1(x_1, y_1), L_2(x_2, y_2)).$$

It is straightforward to verify that if $\{A_i\}_{i=1}^k$ are pairwise orthogonal Latin squares of order n and $\{B_i\}_{i=1}^k$ are pairwise orthogonal Latin squares of order m , then $\{A_i \otimes B_i\}_{i=1}^k$ are pairwise orthogonal Latin squares of order nm . We leave this task to the reader, but advise you just to read on and not bother. \square

Theorem 22.3 is known as MacNeish's theorem. MacNeish conjectured in 1922 that equality held in Theorem 22.3(ii). This would imply Euler's conjecture. But combinatorial problems of this type rarely have such simple answers.

The MacNeish conjecture was disproved first for $n = 21$ when three Latin squares of order 21 were constructed with the aid of the 21 point projective plane of order 4; see Example 22.1 below. This was an example of *composition methods*, which also provided the first counterexample to Euler's conjecture ($n = 22$). The first pair of orthogonal Latin squares of order 10 was found by Parker by what might be called *difference methods*. We discuss composition methods first; they have proved more powerful for large values of n .

Bose, Parker and Shrikhande gave many constructions for sets of orthogonal Latin squares. We choose to describe two basic and elegant ones in terms of quasigroups. Recall that a *quasigroup* is a Latin square whose row, column, and symbol sets are the same set X . A quasigroup L is *idempotent* when $L(x, x) = x$ for all $x \in X$. For example, if X is the finite field \mathbb{F}_q of order q , then

$$L_a(x, y) := ax + (1 - a)y$$

defines an idempotent quasigroup L_a if $a \neq 0, 1$. Any two squares of this form are orthogonal.

Problem 22B. For a prime power $q \geq 4$, construct two Latin squares A, S of order q with row and column sets equal to \mathbb{F}_q so that A is orthogonal to its transpose, and to S , which is to be symmetric. In addition, ensure that S is idempotent if q is odd and 'unipotent', i.e. has constant diagonal, if q is even.

Suppose we have a linear space, cf. Chapter 19, on a point set X with line set \mathcal{A} . Further suppose that for each line A in \mathcal{A} , we have k pairwise orthogonal idempotent quasigroups $L_1^A, L_2^A, \dots, L_k^A$ on the

set A . Then we can construct k pairwise orthogonal idempotent quasigroups L_1, L_2, \dots, L_k on the entire set X by declaring, for each $i = 1, 2, \dots, k$, that $L_i(x, x) := x$ for $x \in X$, and for distinct $x, y \in X$, $L_i(x, y) := L_i^A(x, y)$, where A is the unique line in \mathcal{A} which contains both x and y . It is a simple matter to check that L_1, L_2, \dots, L_k are Latin squares and that they are orthogonal; for example, given i, j, s and t , $s \neq t$, a cell (x, y) for which

$$L_i(x, y) = s \quad \text{and} \quad L_j(x, y) = t$$

exists, and x, y may be found in that line B which contains s and t , because of the orthogonality of L_i^B and L_j^B .

Theorem 22.4. *For every linear space with line set \mathcal{A} on an n -set X , we have*

$$N(n) \geq \min_{A \in \mathcal{A}} \{N(|A|) - 1\}.$$

PROOF: Let k be the indicated minimum. This means we have at least $k + 1$ pairwise orthogonal quasigroups on each $A \in \mathcal{A}$. We will describe how to obtain k pairwise orthogonal *idempotent* quasigroups on each A . Then $N(n) \geq k$ follows from the construction above.

In general, let H_1, H_2, \dots, H_{k+1} be pairwise orthogonal quasigroups on an m -set B . Pick any $b \in B$. There will be m cells (x, y) for which $H_{k+1}(x, y) = b$, one in each row and one in each column. Simultaneously permute the columns, say, of all squares so that these cells are on the diagonal of the $(k + 1)$ -th square. Orthogonality implies that for each $i \leq k$, all m symbols occur on the diagonal of the i -th square. Finally, we permute the symbols independently in each of the first k squares so that the resulting squares are idempotent. \square

Theorem 22.5. *If \mathcal{A} is the set of lines of a linear space on an n -set X and $\mathcal{B} \subseteq \mathcal{A}$ is a set of pairwise disjoint lines, then*

$$N(n) \geq \min (\{N(|A|) - 1 : A \in \mathcal{A} \setminus \mathcal{B}\} \cup \{N(|B|) : B \in \mathcal{B}\}).$$

PROOF: Let k be the indicated minimum. As we saw in the proof of the preceding theorem, there exist k pairwise orthogonal idempotent quasigroups L_i^A on each A in $\mathcal{A} \setminus \mathcal{B}$. If necessary, we add

singleton sets to \mathcal{B} so that \mathcal{B} becomes a partition of X . We have k pairwise orthogonal quasigroups L_i^B (not necessarily idempotent) on each $B \in \mathcal{B}$. We define L_1, L_2, \dots, L_k on the entire set X by declaring, for each $i = 1, 2, \dots, k$, that $L_i(x, x) := L_i^B(x, x)$ where B is the unique member of \mathcal{B} that contains x , and for distinct x, y , $L_i(x, y) := L_i^A(x, y)$, where A is the unique line in \mathcal{A} (whether or not in \mathcal{B}) that contains both x and y . The quasigroups L_i are orthogonal (the easy details are left to the reader) and thus $N(n) \geq k$. \square

Example 22.1. Let $n = 21$ and consider the projective plane of order 4 with 21 lines of size 5. Theorem 22.4 implies that $N(21) \geq 3$ and this disproves MacNeish's conjecture. Delete three noncollinear points. We have a linear space with 18 points, and lines of sizes 5, 4, and 3; the three lines of size 3 are pairwise disjoint. Theorem 22.5 implies that $N(18) \geq 2$ and this disproves Euler's conjecture.

Example 22.2. To see how far wrong Euler was, we consider two more values of $n \equiv 2 \pmod{4}$. Delete three noncollinear points from a projective plane of order 8 to obtain a linear space on 70 points with lines of sizes 9, 8, and (pairwise disjoint lines of size) 7. Theorem 22.5 shows $N(70) \geq 6$. It is possible to find seven points in the plane constructed from \mathbb{F}_8 such that no three are collinear (even 10, see Problem 19I), and deleting these produces a linear space which can be used in Theorem 22.4 to give us $N(66) \geq 5$.

The next construction would be difficult to describe without the use of *transversal designs*. Transversal designs provide a compact and conceptually convenient language with which to manipulate sets of pairwise orthogonal Latin squares. (They also provide a large family of linear spaces useful for the construction of other combinatorial designs or even more orthogonal Latin squares.) A $\text{TD}(n, k)$ can be defined as the dual incidence structure of an (n, k) -net, i.e. as an $(n, k, k - 1)$ -partial geometry. So there are nk points and n^2 blocks (we will use 'blocks' rather than 'lines' when discussing transversal designs). Each point is in n blocks; each block contains k points. The points fall into k equivalence classes (called, confusingly, *groups*) of size n so that two points in the same group are not contained in a block while two points in different groups

belong to exactly one block. In particular, each block contains exactly one point from each group. We need to refer to the groups so often that we incorporate them into the notation and speak of a transversal design $(X, \mathcal{G}, \mathcal{A})$ where the three coordinates are the sets of points, groups, and blocks, respectively. $(X, \mathcal{G} \cup \mathcal{A})$ is a linear space with block-sizes k and n .

Example 22.3. Here is a $\text{TD}(2,3)$:

Groups: $\{a_1, a_2\}, \{b_1, b_2\}, \{c_1, c_2\}$

Blocks: $\{a_1, b_1, c_1\}, \{a_1, b_2, c_2\}, \{a_2, b_1, c_2\}, \{a_2, b_2, c_1\}$.

In view of Theorem 22.2, the existence of a $\text{TD}(n, k+2)$ is equivalent to the existence of k pairwise orthogonal Latin squares. At the risk of boring some readers, we review the connection by quickly describing how to get the squares from a $\text{TD}(n, k+2)$: number the groups $\{G_1, G_2, \dots, G_{k+2}\}$ and define $L_i : G_1 \times G_2 \rightarrow G_{i+2}$ by declaring $L_i(x, y)$ to be the point of intersection of G_{i+2} and the block which contains x and y .

A $\text{TD}(n, k)$ is said to be *resolvable* when the set \mathcal{A} of blocks can be partitioned into n parallel classes $\mathcal{A}_1, \mathcal{A}_2, \dots, \mathcal{A}_n$, i.e. each \mathcal{A}_i is a set of n blocks of size k which partition the point set X . From a $\text{TD}(n, k)$ $(X, \mathcal{G}, \mathcal{A})$, we can always construct a resolvable $\text{TD}(n, k-1)$ by deleting the n points of one of the groups $G_0 = \{x_1, x_1, \dots, x_n\}$, which removes exactly one point from each block; for each i , the blocks which have had x_i removed form a parallel class on the point set $X \setminus G_0$ of the $\text{TD}(n, k-1)$. (Conversely, a resolvable $\text{TD}(n, k-1)$ can be extended to a $\text{TD}(n, k)$.)

Theorem 22.6. *If $0 \leq u \leq t$, then*

$$N(mt + u) \geq \min\{N(m), N(m+1), N(t) - 1, N(u)\}.$$

PROOF: Let k be the right-hand side above, plus 2. This means that transversal designs $\text{TD}(m, k)$, $\text{TD}(m+1, k)$, $\text{TD}(t, k+1)$, and $\text{TD}(u, k)$ exist; and to prove the theorem, we must construct a $\text{TD}(mt + u, k)$.

As the construction is rather technical, we warm up by first describing the construction of a $\text{TD}(mt, k)$ from a $\text{TD}(t, k)$ and various $\text{TD}(m, k)$'s. This is the degenerate case $u = 0$ in the theorem.

The construction does not require a $\text{TD}(m+1, k)$ or a $\text{TD}(t, k+1)$ and thus it reproves Theorem 22.3(i).

Let $(X, \mathcal{G}, \mathcal{A})$ be a $\text{TD}(t, k)$. To each $x \in X$, associate a set M_x of m new elements so that any two sets M_x are disjoint. For $S \subseteq X$, let $M_S := \cup_{x \in S} M_x$.

We construct a $\text{TD}(mt, k)$ on the point set M_X of size kmt with groups $\{M_G : G \in \mathcal{G}\}$ each of size mt ; the blocks \mathcal{B} are obtained as follows. For each $A \in \mathcal{A}$, choose blocks \mathcal{B}_A so that

$$(M_A, \{M_x : x \in A\}, \mathcal{B}_A)$$

is a $\text{TD}(m, k)$, and let $\mathcal{B} = \cup_{A \in \mathcal{A}} \mathcal{B}_A$. The verification is straightforward.

To return to the general case, recall that the existence of a $\text{TD}(t, k+1)$ implies the existence of a resolvable $\text{TD}(t, k)$. So we have a $\text{TD}(t, k)$ $(X, \mathcal{G}, \mathcal{A})$ where \mathcal{A} admits a partition into parallel classes $\mathcal{A}_1, \mathcal{A}_2, \dots, \mathcal{A}_t$. We treat the blocks of the first u parallel classes in one way, and the blocks in $\mathcal{B} := \cup_{i=u+1}^t \mathcal{A}_i$ in another way.

Let $(U, \mathcal{H}, \mathcal{C})$ be a $\text{TD}(u, k)$. We also require a partition of U into u k -subsets $\{K_1, K_2, \dots, K_u\}$; each is to consist of exactly one point from each set $H \in \mathcal{H}$, but these k -subsets are not required to be blocks in \mathcal{C} .

Let $\mathcal{G} = \{G_1, G_2, \dots, G_k\}$ and $\mathcal{H} = \{H_1, H_2, \dots, H_k\}$ be numberings of the groups. We construct a $\text{TD}(mt+u, k)$ with point set $Y := M_X \cup U$ and groups

$$\mathcal{J} := \{M_{G_1} \cup H_1, M_{G_2} \cup H_2, \dots, M_{G_k} \cup H_k\}.$$

The blocks are obtained as follows. For each block $B \in \mathcal{B}$ as before, let

$$(M_B, \{M_x : x \in B\}, \mathcal{D}_B)$$

be a $\text{TD}(m, k)$. For each block $A \in \text{Cal} \mathcal{A}_i$, let

$$(M_A \cup K_i, \{(M_A \cap M_{G_j}) \cup (K_i \cap H_j) : j = 1, 2, \dots, k\}, \mathcal{D}_A)$$

be a $\text{TD}(m+1, k)$ in which K_i occurs as a block, and let \mathcal{D}'_A denote the remaining $(m+1)^2 - 1$ blocks. Then we claim that $(Y, \mathcal{J}, \mathcal{E})$ is the required $\text{TD}(mt+u, k)$, where

$$\mathcal{E} := \mathcal{C} \cup \left(\bigcup_{B \in \mathcal{B}} \mathcal{D}_B \right) \cup \left(\bigcup_{A \in \mathcal{A}_1 \cup \dots \cup \mathcal{A}_u} \mathcal{D}'_A \right).$$

Verification requires consideration of several cases. □

Example 22.4. With $m = 3$ in Theorem 22.6, we see that

(22.2)

$N(3t + u) \geq 2$ whenever $0 \leq u \leq t$, $N(t) \geq 3$, and $N(u) \geq 2$.

We may take $(t, u) = (5, 3), (7, 1), (7, 5)$, and $(9, 3)$ to find that $N(n) \geq 2$ for $n = 18, 22, 26$, and 30 .

Theorem 22.7. $N(n) \geq 2$ for all $n \neq 2, 6$.

PROOF: We need only consider $n \equiv 2 \pmod{4}$. For $n = 10, 14$, see Examples 22.6 and 22.7 below. For $n = 18, 22, 26$, and 30 , see Example 22.4 above. We now assume $n \geq 34$. One of

$$n - 1, n - 3, n - 5, n - 7, n - 9, n - 11$$

is divisible by 3 but not by 9, so we can write $n = 3t + u$ where $u = 1, 3, 5, 7, 9$, or 11 , and t is not divisible by 3. Since n is even, t is also odd, so $N(t) \geq 4$ by Theorem 22.3(ii). A consequence of $n \geq 34$ is $t \geq 11$, so $0 \leq u \leq t$, and then $N(n) \geq 2$ by (22.2). □

Theorem 22.8. $N(n) \rightarrow \infty$ as $n \rightarrow \infty$.

PROOF: Let x be a positive integer. We claim that $N(n) \geq x - 1$ whenever

$$(22.3) \quad n \geq 2 \left(\prod_{p \leq x} p \right)^{2x+1},$$

where the product is extended over all primes $p \leq x$.

Given n satisfying (22.3), let m be chosen (Chinese remainder theorem) so that $0 \leq m \leq (\prod_{p \leq x} p)^x$ and such that for all primes $p \leq x$,

$$m \equiv \begin{cases} -1 \pmod{p^x} & \text{if } p \text{ divides } n, \\ 0 \pmod{p^x} & \text{if } p \text{ does not divide } n. \end{cases}$$

Then choose an integer $t \equiv 1 \pmod{\prod_{p \leq x} p}$ so that

$$0 \leq u := n - mt < \left(\prod_{p \leq x} p \right)^{x+1}.$$

The remainder of the proof is provided by Problem 22C below. □

Problem 22C. With m , t , and u chosen as above, show that $u \leq t$ and that Theorem 22.3(ii) implies that $N(mt + u) \geq x - 1$.

* * *

We have seen constructions by so-called difference methods in Chapter 19. We use this idea to construct Latin squares here. It is convenient to describe our constructions in terms of *orthogonal arrays*. An $OA(n, k)$ is a $k \times n^2$ array (or we prefer here to think of a set of n^2 column vectors of height k since the order of the columns is immaterial) whose entries are taken from a set S of n symbols, so that for any distinct i, j , $1 \leq i, j \leq k$, and any two symbols s, t from S , there is a unique column whose i -th coordinate is s and whose j -th coordinate is t . This generalizes the $OA(n, 3)$'s introduced in Chapter 17.

This is yet another equivalent formulation of orthogonality; the existence of an $OA(n, k + 2)$ is equivalent to the existence of k pairwise orthogonal Latin squares. For example, to get the array from squares L_1, L_2, \dots, L_k , assume without loss of generality that all row, column, and symbol sets are the same set S and take all columns

$$[i, j, L_1(i, j), L_2(i, j), \dots, L_k(i, j)]^\top, \quad i, j \in S.$$

Readers should immediately be able to write out two orthogonal squares from the $OA(3, 4)$ in Fig. 22.2 (of course, *any* two rows may be used to 'coordinate' the squares).

$$\begin{bmatrix} x & x & x & y & y & y & z & z & z \\ x & y & z & x & y & z & x & y & z \\ x & y & z & z & x & y & y & z & x \\ x & y & z & y & z & x & z & x & y \end{bmatrix}$$

Figure 22.2

Example 22.5. The following matrix of elements of \mathbb{Z}_{15} was found with the aid of a computer by Schellenberg, Van Rees, and Vanstone

(1978):

$$\begin{bmatrix} 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0 \\ 0 & 1 & 2 & 3 & 4 & 5 & 6 & 7 & 8 & 9 & 10 & 11 & 12 & 13 & 14 \\ 0 & 2 & 5 & 7 & 9 & 12 & 4 & 1 & 14 & 11 & 3 & 6 & 8 & 10 & 13 \\ 0 & 6 & 3 & 14 & 10 & 7 & 13 & 4 & 11 & 2 & 8 & 5 & 1 & 12 & 9 \\ 0 & 10 & 6 & 1 & 11 & 2 & 7 & 12 & 3 & 8 & 13 & 4 & 14 & 9 & 5 \end{bmatrix}$$

It has the property that for any two rows, the differences between the coordinates of those two rows comprise all elements of \mathbb{Z}_{15} , each with multiplicity one. It follows that we obtain an $OA(15, 5)$ by taking all *translates* of these columns by elements of \mathbb{Z}_{15} . Thus three pairwise orthogonal Latin squares of order 15 can be constructed. But the $OA(15, 5)$ is resolvable: the 15 translates of any column have the property that in each coordinate, all symbols occur once. As with transversal designs, we can add a new row to obtain an $OA(15, 6)$ and hence four pairwise orthogonal Latin squares of order 15. It is not known whether $N(15) \geq 5$.

The last three rows of the above matrix are what we call below pairwise orthogonal orthomorphisms of \mathbb{Z}_{15} .

In 1960, Johnson, Dulmage, Mendelsohn and a computer proved by this method that $N(12) \geq 5$, using the group $\mathbb{Z}_2 \oplus \mathbb{Z}_2 \oplus \mathbb{Z}_3$. The cyclic group of order 12 is of no use; see Theorem 22.9 below.

Example 22.6. We will describe a construction that proves

$$N(m) \geq 2 \Rightarrow N(3m + 1) \geq 2.$$

Let G be an abelian group of order $2m + 1$ and let M be a system of representatives for the pairs $\{i, -i\}$ ($i \neq 0$) in G . That is $|M| = m$ and $G = \{0\} \cup M \cup -M$. For each $i \in M$, introduce a new symbol ∞_i and take $S := G \cup \{\infty_i : i \in M\}$ as the symbols set for an $OA(3m + 1, 4)$.

Consider the set of all column vectors obtained from

$$\left\{ \begin{bmatrix} 0 \\ 0 \\ 0 \\ 0 \end{bmatrix} \right\} \cup \left\{ \begin{bmatrix} \infty_i \\ 0 \\ i \\ -i \end{bmatrix}, \begin{bmatrix} 0 \\ \infty_i \\ -i \\ i \end{bmatrix}, \begin{bmatrix} i \\ -i \\ \infty_i \\ 0 \end{bmatrix}, \begin{bmatrix} -i \\ i \\ 0 \\ \infty_i \end{bmatrix} : i \in M \right\}$$

by translating them by the elements of G with the understanding that the ∞ 's are fixed, i.e. $\infty_i + g = \infty_i$. This gives us

$(4m + 1)(2m + 1)$ columns. Add to these the m^2 columns of an $OA(m, 4)$ to obtain an $OA(3m + 1, 4)$.

To be more explicit in the case $m = 3$, let us use symbols $\mathbb{Z}_7 \cup \{x, y, z\}$ and $M = \{1, 2, 3\}$. We take the seven translates of the following 13 columns, and adjoin the $OA(3, 4)$ from Fig. 22.2:

$$\begin{bmatrix} 0 & x & 0 & 1 & 6 & y & 0 & 2 & 5 & z & 0 & 3 & 4 \\ 0 & 0 & x & 6 & 1 & 0 & y & 5 & 2 & 0 & z & 4 & 3 \\ 0 & 1 & 6 & x & 0 & 2 & 5 & y & 0 & 3 & 4 & z & 0 \\ 0 & 6 & 1 & 0 & x & 5 & 2 & 0 & y & 4 & 3 & 0 & z \end{bmatrix}$$

Verification of the construction requires special consideration of the symbols x, y, z (which we have used rather than the ∞ 's), and the observation that the differences between any two of the above rows (when both coordinates are in \mathbb{Z}_7) comprise all the elements of \mathbb{Z}_7 , each with multiplicity one. The resulting squares are shown below.

$$\begin{bmatrix} 0 & z & 1 & y & 2 & x & 3 & 6 & 5 & 4 \\ 4 & 1 & z & 2 & y & 3 & x & 0 & 6 & 5 \\ x & 5 & 2 & z & 3 & y & 4 & 1 & 0 & 6 \\ 5 & x & 6 & 3 & z & 4 & y & 2 & 1 & 0 \\ y & 6 & x & 0 & 4 & z & 5 & 3 & 2 & 1 \\ 6 & y & 0 & x & 1 & 5 & z & 4 & 3 & 2 \\ z & 0 & y & 1 & x & 2 & 6 & 5 & 4 & 3 \\ 1 & 2 & 3 & 4 & 5 & 6 & 0 & x & y & z \\ 2 & 3 & 4 & 5 & 6 & 0 & 1 & z & x & y \\ 3 & 4 & 5 & 6 & 0 & 1 & 2 & y & z & x \end{bmatrix} \quad \begin{bmatrix} 0 & 4 & x & 5 & y & 6 & z & 1 & 2 & 3 \\ z & 1 & 5 & x & 6 & y & 0 & 2 & 3 & 4 \\ 1 & z & 2 & 6 & x & 0 & y & 3 & 4 & 5 \\ y & 2 & z & 3 & 0 & x & 1 & 4 & 5 & 6 \\ 2 & y & 3 & z & 4 & 1 & x & 5 & 6 & 0 \\ x & 3 & y & 4 & z & 5 & 2 & 6 & 0 & 1 \\ 3 & x & 4 & y & 5 & z & 6 & 0 & 1 & 2 \\ 6 & 0 & 1 & 2 & 3 & 4 & 5 & x & y & z \\ 5 & 6 & 0 & 1 & 2 & 3 & 4 & y & z & x \\ 4 & 5 & 6 & 0 & 1 & 2 & 3 & z & x & y \end{bmatrix}$$

Example 22.7. We will describe an $OA(14, 4)$ on the symbols $\mathbb{Z}_{11} \cup \{x, y, z\}$. We take the 11 translates by elements of \mathbb{Z}_{11} of the following 17 columns, and adjoin the $OA(3, 4)$ from Fig. 22.2:

$$\begin{bmatrix} 0 & 0 & 6 & 4 & 1 & x & 1 & 4 & 0 & y & 2 & 6 & 0 & z & 8 & 9 & 0 \\ 0 & 1 & 0 & 6 & 4 & 0 & x & 1 & 4 & 0 & y & 2 & 6 & 0 & z & 8 & 9 \\ 0 & 4 & 1 & 0 & 6 & 4 & 0 & x & 1 & 6 & 0 & y & 2 & 9 & 0 & z & 8 \\ 0 & 6 & 4 & 1 & 0 & 1 & 4 & 0 & x & 2 & 6 & 0 & y & 8 & 9 & 0 & z \end{bmatrix}$$

Once again, verification of the construction requires special consideration of the symbols x, y, z (which we have used rather than the ∞ 's), and the observation that the differences between any two of

the above rows (when both coordinates are in \mathbb{Z}_{11}) comprise all the elements of \mathbb{Z}_{11} , each with multiplicity one.

Problem 22D. Show that the existence of k pairwise orthogonal idempotent quasigroups is equivalent to the existence of a TD($n, k+2$) in which there may be found a parallel class of blocks.

An *orthomorphism* of an abelian group G is a permutation σ of the elements of G such that

$$x \mapsto \sigma(x) - x$$

is also a permutation of G . The reader can check that the square $L(x, y) := \sigma(x) + y$ is Latin if and only if σ is a permutation, and is orthogonal to the addition table $A(x, y) := x + y$ of G if and only if σ is an orthomorphism.

We remark that if there is *any* orthogonal mate to A , then there is an orthomorphism: the cells in the positions where an orthogonal mate contains a given symbol have the property that there is exactly one in each row and column, and so are of the form $(x, \tau(x))$, $x \in G$, for some permutation τ . Since these cells must contain different symbols in A , the mapping σ defined by $\sigma(x) := x + \tau(x)$ is a permutation. In view of this remark, the following theorem proves that cyclic squares of even order have no orthogonal mates, i.e. there are no Latin squares orthogonal to it.

Theorem 22.9. *If an abelian group G admits an orthomorphism, then its order is odd or its Sylow 2-subgroup is not cyclic.*

PROOF: If the Sylow 2-subgroup is cyclic and nontrivial, then there is exactly one element z of G with order 2. When we add all elements of G , each element pairs with its additive inverse except z and 0; so the sum of all elements of G is z . But if σ were an orthomorphism, then

$$z = \sum_{x \in G} (\sigma(x) - x) = \sum_{x \in G} \sigma(x) - \sum_{x \in G} x = z - z = 0,$$

a contradiction to our choice of z . □

Remarks. If G is abelian and has odd order, then it has automorphisms fixing only the identity (this is true for some abelian groups of even order also), and these are orthomorphisms. Even if G is not abelian, one can define orthomorphisms (also called *complete mappings*) and it remains true that these do not exist if the Sylow 2-subgroup is cyclic and nontrivial—see Hall and Paige (1955), where complete mappings are also shown to exist for solvable groups with trivial or noncyclic Sylow 2-subgroups.

* * *

H. B. Mann (1950) observed that a Latin square of order $4t + 1$ with a subsquare of order $2t$ has no orthogonal mates. Similarly, a Latin square of order $4t + 2$ with a subsquare of order $2t + 1$ has no orthogonal mates. Both these results are corollaries of part (ii) of the following theorem, which also proves that none of the pairs of orthogonal squares of orders $12t + 10$ we constructed in Example 22.6 can be extended to a set of three or more pairwise orthogonal Latin squares. We leave it to the reader to convince himself that subsquares correspond to subtransversal designs.

Theorem 22.10. *Let $(X, \mathcal{G}, \mathcal{A})$ be a $TD(n, k)$ which contains a sub- $TD(m, k)$ $(Y, \mathcal{H}, \mathcal{B})$ with $m < n$. (This means $Y \subseteq X$, $\mathcal{H} = \{G \cap Y : G \in \mathcal{G}\}$, and $\mathcal{B} \subseteq \mathcal{A}$.) Then*

- (i) $m(k - 1) \leq n$;
- (ii) if $(X, \mathcal{G}, \mathcal{A})$ is resolvable, then

$$m^2 \geq n \left\lceil \frac{mk - n}{k - 1} \right\rceil.$$

PROOF: Pick a point $x_0 \in X \setminus Y$. Say x_0 belongs to $G_0 \in \mathcal{G}$. For each of the $m(k - 1)$ points $y \in Y \setminus G_0$, there is a unique block $A_y \in \mathcal{A}$ with $\{x_0, y\} \subseteq A_y$. A block containing two points of Y must belong to \mathcal{B} (and could not contain x_0), so these $m(k - 1)$ blocks are distinct. This number cannot exceed the total number of blocks on x_0 , which is n .

Suppose that $(X, \mathcal{G}, \mathcal{A})$ is resolvable and that $\{\mathcal{A}_1, \mathcal{A}_2, \dots, \mathcal{A}_n\}$ is a partition of \mathcal{A} into parallel classes. Let s_i denote the number of

blocks of \mathcal{A}_i which are contained in Y and let t_i denote the number of blocks of \mathcal{A}_i which meet Y in exactly one point. Then

$$ks_i + t_i = |Y| = mk \quad \text{and} \quad s_i + t_i \leq n,$$

from which it follows that $(k-1)s_i \geq mk - n$, or equivalently,

$$s_i \geq \left\lceil \frac{mk - n}{k - 1} \right\rceil.$$

Part (ii) now follows from $m^2 = |\mathcal{B}| = \sum_{i=1}^n s_i$. □

Problem 22E. Prove that $N(24) \geq 3$ and $N(33) \geq 3$.

Problem 22F. Suppose we have $c-1$ mutually orthogonal Latin squares of order k . Then we have an $OA(k, c+1)$ which we represent as follows:

$$\left(\begin{array}{cccccccccccc} 1 & 1 & \dots & 1 & 2 & 2 & \dots & 2 & \dots & k & k & \dots & k \\ 1 & 2 & \dots & k & & & & & & & & & \\ \vdots & & & & & & & & & & & & \\ 1 & 2 & \dots & k & & & A_1 & & & & & & A_{k-1} \end{array} \right),$$

where every row of each matrix A_i is a permutation of $1, 2, \dots, k$. Let A be the $c \times k(k-1)$ matrix formed by the matrices A_i . Use this matrix and the matrix S of Problem 19U to prove the following theorem.

Theorem. *If there exists a symmetric $(v, k, 1)$ -design, then $N(v) \geq N(k)$.*

Problem 22G. Generalize Theorem 22.6 to the following.

Theorem. *If $0 \leq u \leq t$, $0 \leq v \leq t$, then*

$$N(mt + u + v) \geq \min\{N(m), N(m+1), N(m+2), N(t) - 2, N(u), N(v)\}.$$

Problem 22H. Show that $N(21) \geq 4$.

Problem 22I. Show that $N(51) \geq 4$.

Problem 22J. Suppose that by giving examples one has shown that $N(n) \geq 3$ for $a \leq n \leq 7a + 3$. Show that $N(n) \geq 3$ for $7a \leq n \leq 7^2a$ and conclude that $N(n) \geq 3$ for $n \geq a$.

Notes.

The term ‘*mutually* orthogonal Latin squares’ rather than ‘pairwise orthogonal Latin squares’ and its acronym ‘MOLS’ are in common usage.

We have already mentioned Euler in the notes to Chapter 1. Euler’s paper of 1782 was titled ‘A new type of magic square’, because Euler had noticed that special magic squares arise from a pair of orthogonal Latin squares. As an example, change the symbol sets of A and B in Fig. 22.1 to $\{4, 3, 2, 1\}$ and $\{12, 8, 4, 0\}$, respectively, and *add*, rather than *superpose*, to obtain

$$\begin{pmatrix} 16 & 11 & 6 & 1 \\ 2 & 5 & 12 & 15 \\ 9 & 14 & 3 & 8 \\ 7 & 4 & 13 & 10 \end{pmatrix}.$$

Each line of this matrix sums to 34. (The Latin property does not in general imply that the diagonals sum to the ‘magic number’, but our example is a particularly nice square: the diagonals, the four corners, and many other sets of four entries sum to 34.)

The authors are aware that ‘ A ’ is used in Fig. 22.1 both as the name of a matrix and an entry in that same matrix. We are just checking whether readers are on their toes.

Orthogonal Latin squares, often in the form of orthogonal arrays, are of great importance in the statistical theory of design of experiments.

MacNeish’s paper of 1922 actually includes a false proof of Euler’s conjecture.

The connection between orthogonal Latin squares and finite projective planes was observed by R. C. Bose (1938).

Many results on orthogonal Latin squares were anticipated by E. H. Moore (1896), as has been pointed out to the authors by R. D. Baker. Unfortunately, the term Latin square is nowhere to be found in Moore’s paper, so no one noticed his results for a long

time. The results in his paper include special cases of Theorem 22.3 and Theorem 22.4 (albeit in entirely different forms) as well as descriptions of projective planes of prime power order, so he could have disproved the MacNeish conjecture had he known of it.

Theorem 22.6 is a special case of a construction of Wilson (1974) which in turn has been generalized in several ways. See T. Beth, D. Jungnickel, and H. Lenz (1986).

Using methods similar to Problem 22J, the second of the present authors proved that $N(n) \geq 3$ for $n \geq 47$. Presently it is known that $N(n) \geq 3$ for $n > 10$. See Colbourn and Dinitz (1996) for recent lower bounds on $N(n)$ for various n .

Theorem 22.8 is due to Chowla, Erdős, and Straus (1960). They proved more: $N(n) \geq n^{1/91}$ for sufficiently large n . Their work is number-theoretical and is based on the Bose–Parker–Shrikhande constructions. Their result has been improved several times, but the best result to date is that of T. Beth (1983). This seems far from the real truth. It is quite possible that $N(n) \geq n/10$, say, for all, or for all but finitely many, values of n , but at the present time this appears to be incredibly hard to prove.

References.

- T. Beth (1983), Eine Bemerkung zur Abschätzung der Anzahl orthogonaler lateinischer Quadrate mittels Siebverfahren, *Abh. Math. Sem. Hamburg* **53**, 284–288.
- T. Beth, D. Jungnickel, and H. Lenz (1986), *Design Theory*, Bibliographisches Institut.
- R. C. Bose (1938), On the application of the properties of Galois fields to the problem of construction of hyper-Graeco-Latin squares, *Sanhkya* **3**, 323–338.
- R. C. Bose, S. S. Shrikhande, and E. T. Parker (1960), Further results in the construction of mutually orthogonal Latin squares and the falsity of a conjecture of Euler, *Canad. J. Math.* **12**, 189–203.
- S. Chowla, P. Erdős, and E. G. Straus (1960), On the maximal number of pairwise orthogonal Latin squares of a given order, *Canad. J. Math.* **12**, 204–208.
- C. J. Colbourn and J. H. Dinitz, editors (1996), *The CRC Handbook of Combinatorial Designs*, CRC Press.

- A. L. Dulmage, D. Johnson, and N. S. Mendelsohn (1961), Orthomorphisms of groups and orthogonal Latin squares, *Canadian J. Math.* **13**, 356–372.
- M. Hall and L. J. Paige (1955), Complete mappings of finite groups, *Pacific J. Math.* **5**, 541–549.
- H. F. MacNeish (1922), Euler squares, *Ann. Math.* **23**, 221–227.
- H. B. Mann (1950), On orthogonal Latin squares, *Bull. Amer. Math. Soc.* **50**, 249–257.
- E. H. Moore (1896), Tactical memoranda I–III, *Amer. J. Math.* **18**, 264–303.
- P. J. Schellenberg, G. M. J. Van Rees, and S. A. Vanstone (1978), Four pairwise orthogonal Latin squares of order 15, *Ars Comb.* **6**, 141–150.
- D. R. Stinson (1984), Nonexistence of a Pair of Orthogonal Latin Squares of Order Six, *J. Combinatorial Theory (A)* **36**, 373–376.
- R. M. Wilson (1974), Concerning the number of mutually orthogonal Latin squares, *Discrete Math.* **9**, 181–198.

23

Projective and combinatorial geometries

A *combinatorial geometry* is a pair (X, \mathcal{F}) where X is a set of *points* and where \mathcal{F} is a family of subsets of X called *flats* such that

- (1) \mathcal{F} is closed under (pairwise) intersection,
- (2) there are no infinite chains in the poset \mathcal{F} ,
- (3) \mathcal{F} contains the empty set, all singletons $\{x\}$, $x \in X$, and the set X itself,
- (4) for every flat $E \in \mathcal{F}$, $E \neq X$, the flats that cover E in \mathcal{F} partition the remaining points.

Here, F *covers* E in \mathcal{F} means that $E, F \in \mathcal{F}$, $E \subsetneq F$, but that $E \subsetneq G \subsetneq F$ does not hold for any $G \in \mathcal{F}$. This latter property should be familiar to the reader from geometry: the lines that contain a given point partition the remaining points; the planes that contain a given line partition the remaining points.

A trivial example of a geometry consists of a finite set X and *all* subsets of X as the flats. This is the *Boolean algebra* on X .

We remark that (1) and (2) imply that \mathcal{F} is closed under arbitrary intersection.

Example 23.1. Every linear space (as introduced in Chapter 19) gives us a combinatorial geometry on its point set X when we take as flats \emptyset , all singletons $\{\{x\} : x \in X\}$, all lines, and X itself. The fact that the lines on a given point partition the remaining points is another way of saying that two points determine a unique line.

Example 23.2. Every Steiner system $S(t, k, v)$ gives us a combinatorial geometry on its point set X when we take as flats all subsets of cardinality $< t$, all blocks, and X . To get a geometry by

this construction, it is not necessary that all blocks have the same size, but only that each t -subset is contained in a unique block (cf. Problem 19R, where we have called these Generalized Steiner Systems).

Example 23.3. Let V be an n -dimensional vector space over a field \mathbb{F} . By an *affine subspace* of V , we mean either the empty set or a coset (or *translate*) of an (ordinary, i.e. linear) subspace of V in the additive group. For example, for $a, b \in \mathbb{F}$, the subset $\{(x, y) : y = ax + b\}$ is an affine subspace of \mathbb{F}^2 . The set V together with all affine subspaces forms a combinatorial geometry called the *affine geometry* $AG_n(\mathbb{F})$. We write $AG_n(q)$ for $AG_n(\mathbb{F}_q)$; the case $n = 2$ was introduced in Chapter 19.

Example 23.4. The *projective geometry* $PG_n(\mathbb{F})$, while more fundamental than $AG_n(\mathbb{F})$, can be a little more awkward to define. Let V be an $(n + 1)$ -dimensional vector space V over a field \mathbb{F} . The point set X of $PG_n(\mathbb{F})$ is to consist of all the 1-dimensional (linear) subspaces of V . For example, if \mathbb{F} is the field \mathbb{F}_q of q elements, then the number of projective points of $PG_n(\mathbb{F}_q)$ is

$$\frac{q^{n+1} - 1}{q - 1} = q^n + \cdots + q^2 + q + 1.$$

To each linear subspace W of V , we associate a flat F_W consisting of all the 1-dimensional subspaces of V that are contained in W , and take \mathcal{F} to be the set of all such flats F_W . We write $PG_n(q)$ for $PG_n(\mathbb{F}_q)$; the case $n = 2$ was introduced in Chapter 19.

Projective geometries $PG_n(\mathbb{F})$ can be defined also for \mathbb{F} a *division ring* (lacking commutativity of multiplication); see Crawley and Dilworth (1973).

Let Y be any subset of the elements X of a combinatorial geometry (X, \mathcal{F}) and let

$$\mathcal{E} := \{F \cap Y : F \in \mathcal{F}\}.$$

Then (Y, \mathcal{E}) is also a combinatorial geometry, the *subgeometry* on Y . For example, $AG_n(\mathbb{F})$ is a subgeometry of $PG_n(\mathbb{F})$. There is a standard embedding of the point set of $AG_n(\mathbb{F})$ into the point

set of $PG_n(\mathbb{F})$: to each vector \mathbf{x} in an n -dimensional vector space V , associate the 1-dimensional subspace that is the span of $(\mathbf{x}, 1)$ in the $(n + 1)$ -dimensional space $V \times \mathbb{F}$. The image consists of all projective points not contained in the hyperplane $V \times \mathbf{0}$.

The set of flats \mathcal{F} of a combinatorial geometry, when ordered by inclusion, has several important properties.

A *lattice* L is a partially ordered set with the property that any finite subset $S \subseteq L$ has a *meet* (or *greatest lower bound*), that is an element b in L so that

$$\forall_{a \in S}[b \leq a] \quad \text{and} \quad \forall_{a \in S}[c \leq a] \Rightarrow c \leq b,$$

as well as a *join* (or *least upper bound*), that is an element b in L so that

$$\forall_{a \in S}[b \geq a] \quad \text{and} \quad \forall_{a \in S}[c \geq a] \Rightarrow c \geq b.$$

The meet and join of a two-element set $S = \{x, y\}$ are denoted, respectively, by $x \wedge y$ and $x \vee y$. It is easily seen that \wedge and \vee are commutative, associative, idempotent binary operations; moreover, if all two-element subsets have meets and joins, then any finite subset has a meet and a join.

The lattices we will consider have the property that there are no infinite chains. Such a lattice has a (unique) least element (that we denote by 0_L) because the condition that no infinite chains exist allows us to find a minimal element m , and any minimal element is minimum since if $m \not\leq a$, then $m \wedge a$ would be less than m . Similarly, there is a unique largest element 1_L .

For elements a and b of a poset, we say that a *covers* b and write $a \succ b$ when $a > b$ but there are no elements c so that $a > c > b$. For example when U and W are linear subspaces of a vector space, $U \succ W$ when $U \supseteq W$ and $\dim(U) = \dim(W) + 1$. Recall that a *chain* in a partially ordered set P is a totally ordered subset of P . So a finite chain can be thought of as a sequence $a_0 < a_1 < \cdots < a_n$. A *point* of a lattice L with minimum element 0_L is an element that covers 0_L .

A *geometric lattice* is a lattice L that has no infinite chains, and such that

- (1) L is *atomic*, that is, each element of L is the join of points of L , and

- (2) L is *semimodular*, that is, if a and b are distinct and both cover c in L , then $a \vee b$ covers both a and b .

Theorem 23.1. *The set of flats of a combinatorial geometry, ordered by inclusion, is a geometric lattice. Conversely, given a geometric lattice L with points X , then $(X, \{F_y : y \in L\})$ is a combinatorial geometry, where*

$$F_y := \{x \in X : x \leq y\}.$$

PROOF: Since the set \mathcal{F} of flats of a combinatorial geometry is closed under intersection, the poset of flats is an atomic lattice (the meet of two flats is their intersection; the join of two flats is the intersection of all flats containing both). Suppose that flats F_1 and F_2 cover a flat E in a combinatorial geometry. Let x be a point in $F_1 \setminus F_2$. There is a flat G_2 that covers F_2 in \mathcal{F} and contains the point x . G_2 contains F_1 since otherwise $E \subsetneq F_1 \cap G_2 \subsetneq F_1$. But by a symmetric argument, there is a flat G_1 that covers F_1 and also contains F_1 and F_2 . The join $F_1 \vee F_2$ must be contained in both G_1 and G_2 . Since G_i covers F_i , $F_1 \vee F_2 = G_1 = G_2$.

Let L be a geometric lattice and define the flats F_y as subsets of the point set X of L as in the statement of the theorem. It is clear that the empty set, any singleton, and X are flats (when y is taken to be 0_L , a point of L , or 1_L , respectively). Since $x \leq y$ and $x \leq z$ if and only if $x \leq y \wedge z$, we have $F_y \cap F_z = F_{y \wedge z}$; thus $\mathcal{F} := \{F_y : y \in L\}$ is closed under intersection. No point x not in a given flat F_y can be in two flats that cover F_y , so it remains only to show that some flat that covers F_y contains x . We show that $F_{x \vee y}$ covers F_y to complete the proof.

This is equivalent to showing that $x \vee y \succ y$ in L whenever $x \not\leq y$ in L and x is a point of L . Choose a maximal chain

$$0_L \triangleleft y_1 \triangleleft y_2 \triangleleft \cdots \triangleleft y_k = y.$$

Since x and y_1 cover 0_L , $x \vee y_1$ covers y_1 . Since $x \vee y_1$ and y_2 cover y_1 , $x \vee y_2$ covers y_2 (clearly $x \vee y_1 \vee y_2 = x \vee y_2$). Inductively, we find that $x \vee y_k$ covers y_k . \square

In some sense, the difference between geometric lattices and combinatorial geometries is the same as that between incidence structures on the one hand and families of subsets of a set on the other.

Incidence structures and lattices are more abstract and must be used to avoid confusion in certain cases (e.g. when discussing duality or intervals), but we prefer the language and notation of sets and subsets for many arguments.

For example, for elements a and b of a partially ordered set, the *interval* $[a, b]$ is defined as $[a, b] := \{x : a \leq x \leq b\}$. Any interval in a lattice is again a lattice. The reader should check that any interval of a geometric lattice is again a geometric lattice. It would be awkward to state the corresponding fact in terms of combinatorial geometries.

In view of Theorem 23.1 (more precisely, the simple correspondences described in the proof), it is often convenient (though sometimes confusing) to mix the notation and language of combinatorial geometries and geometric lattices. For example, we can use the same symbol $PG_n(\mathbb{F})$ to denote the combinatorial geometry and the corresponding lattice of subspaces of a vector space.

Problem 23A. (i) Any interval of $PG_n(\mathbb{F})$ is isomorphic as a poset to $PG_m(\mathbb{F})$ for some $m \leq n$. (ii) $PG_n(\mathbb{F})$ is isomorphic to its dual poset (where order is reversed).

Example 23.5. The partition lattices Π_n , whose elements are all partitions of an n -set X , provide another family of geometric lattices, and hence give us combinatorial geometries. The partitions are ordered by *refinement*; \mathcal{A} is a refinement of \mathcal{B} if each block of \mathcal{B} is the union of blocks of \mathcal{A} . So the least element (the finest partition) is all singletons $\{\{x\} : x \in X\}$ and the greatest element is $\{X\}$, consisting of a single block. A moment's thought shows that one partition covers another if the former is obtained by coalescing two blocks of the latter into one. The points are the partitions that consist of a single block of size 2 and $n - 2$ singletons.

For example, Π_4 has 15 elements:

$$\begin{aligned} & \{1234\} \\ & \{123, 4\}, \{124, 3\}, \{134, 2\}, \{234, 1\}, \{12, 34\}, \{13, 24\}, \{14, 23\} \\ & \{12, 3, 4\}, \{13, 2, 4\}, \{14, 2, 3\}, \{23, 1, 4\}, \{24, 1, 3\}, \{34, 1, 2\} \\ & \{1, 2, 3, 4\} \end{aligned}$$

To simplify the notation, we have written $\{123, 4\}$, for example, for what should be $\{\{1, 2, 3\}, \{4\}\}$.

Example 23.6. The points of Π_n are in one-to-one correspondence with the edges of K_n . Given any simple graph G on n vertices, we obtain a geometric lattice $L(G)$ whose points correspond to the edge set $E(G)$ of G as follows. The elements of L are to be all those partitions \mathcal{A} of $V(G)$ such that the subgraph of G induced by each block of \mathcal{A} is connected. The partitions with this property are exactly those that are the join (in Π_n) of points (in Π_n) corresponding to some subset of the edges of G . The lattices $L(G)$ are sometimes called the lattices of *contractions* of G (see Chapter 33).

Fig. 23.1 is an attempt to illustrate the combinatorial geometries $L(K_4)$ and $L(K_5)$. $L(K_5)$, for example, has ten points; the dot in the figure labeled 12 represents the point (partition) $\{12, 3, 4, 5\}$. The partitions of the type $\{123, 4, 5\}$, for example, contain three points and are represented by line segments; lines with two points are not shown. (We note that the six point/seven line $L(K_4)$ is the geometry that arises from deleting a point from the Fano configuration.)




Figure 23.1

For a subset S of the points of a combinatorial geometry, the *closure* \overline{S} is the intersection of all flats containing S . For example, in a linear space, the closure of a two point set is the line containing the points. Exercise: show that $S \subseteq \overline{S}$, $A \subseteq B \Rightarrow \overline{A} \subseteq \overline{B}$, and $\overline{\overline{S}} = \overline{S}$. It will be occasionally convenient to use the symbol for join in the lattice of flats; note that

$$E \vee F := \overline{E \cup F}.$$

A subset $S \subseteq X$ is *independent* when for each $x \in S$, $x \notin \overline{S \setminus \{x\}}$. In Example 23.1, three points in a linear space are independent if and only if they are not contained in a line; no four points are independent. A set of points in $PG_n(\mathbb{F})$ is independent if and only if representative vectors are linearly independent. A set of points in $AG_n(\mathbb{F})$ is independent if and only if the vectors are affinely independent. One viewpoint of combinatorial geometries is that they represent the study of ‘abstract independence’.

By the *rank* of a combinatorial geometry with point set X , we mean the maximum size of an independent subset of X . $PG_n(\mathbb{F})$ and $AG_n(\mathbb{F})$ both have rank $n + 1$. We will avoid the word *dimension*, but if we forget and use it, it will mean the rank *minus one*. The maximum size of an independent subset of a flat F is the *rank* of that flat. The flats of rank 1 are called *points*, the flats of rank 2 are called *lines*, the flats of rank 3 are called *planes*. The flats of rank 1 less than $\text{rank}(X)$ are called *hyperplanes* or *copoints*. Occasionally, we need to use the term *coline* for a flat for which the rank equals $\text{rank}(X) - 2$.

From any combinatorial geometry (X, \mathcal{F}) , we obtain a linear space (X, \mathcal{L}) where \mathcal{L} is the set of all lines (flats of rank 2).

In Fig. 23.1, any two points determine a line that may have two or three points; only the latter are drawn in the figure. The planes in $L(K_5)$ have either four or six points; the latter contain four three-point lines.

We collect some simple facts:

Lemma 23.2.

- (1) If $x \notin \overline{A}$ but $x \in \overline{A \cup \{y\}}$, then $y \in \overline{A \cup \{x\}}$ (the *exchange axiom*).
- (2) If S is an independent set of points in a geometry and $x \notin \overline{S}$, then $\{x\} \cup S$ is independent.
- (3) If $F = \overline{S}$, then $F = \overline{A}$ for any maximal independent subset A of S .

PROOF: $F_1 := \overline{A \cup \{x\}}$ is the flat that covers $E := \overline{A}$ and contains x ; $F_2 := \overline{A \cup \{y\}}$ is the flat that covers E and contains y . If $x \in F_2$, it must be that $F_1 = F_2$. This proves (1).

If $\{x\} \cup S$ is not independent, there is some $y \in S$ such that

$y \in \overline{(S \cup \{x\}) \setminus \{y\}}$. Let $A := S \setminus \{y\}$. Since S is independent, $y \notin \overline{A}$. But (1) then implies that $x \in \overline{A \cup \{y\}}$, i.e. $x \in \overline{S}$. This proves (2).

Suppose $F = \overline{S}$ and that A is an independent subset of S that is maximal with respect to that property. If $S \not\subseteq \overline{A}$, we could find a larger independent subset of S by (2). So $S \subseteq \overline{A}$ and since F is the smallest flat containing S , $F \subseteq \overline{A}$. This proves (3). \square

A *basis* for a flat F is an independent subset $B \subseteq F$ so that $\overline{B} = F$, i.e. any maximal independent subset of F . As an exercise, the reader should check that we could also have defined a basis of F as a minimal *spanning* set, i.e. a subset B of F so that $\overline{B} = F$ and that is minimal with respect to this property.

Problem 23B. Let G be a connected simple graph. Show that the bases of the combinatorial geometry $L(G)$ are exactly the edge sets of spanning trees in G .

Theorem 23.3. *All bases of a flat F in a combinatorial geometry have the same finite cardinality (called the rank of F). For flats E and F ,*

$$(23.1) \quad \text{rank}(E) + \text{rank}(F) \geq \text{rank}(E \cap F) + \text{rank}(E \vee F).$$

PROOF: It should be clear that the condition that there are no infinite chains of flats forces all independent sets to be finite.

If it is not true that all bases of F have the same cardinality, choose an ordered pair (B_1, B_2) of bases with $|B_1| > |B_2|$ but so that $|B_2 \setminus B_1|$ is as small as possible subject to this constraint. Pick $x \in B_1 \setminus B_2$. Then $B_1 \setminus \{x\}$ is independent and has a closure which does not contain F and hence does not contain B_2 . Pick $y \in B_2 \setminus B_1$ such that $y \notin \overline{B_1 \setminus \{x\}}$. Then $(B_1 \setminus \{x\}) \cup \{y\}$ is independent by Lemma 23.2 and is contained in a basis B_3 for F . Now we have an ordered pair (B_3, B_1) of bases with $|B_3| > |B_1|$, but $B_2 \setminus B_3$ is a proper subset of $B_2 \setminus B_1$, a contradiction.

To prove the second part of the theorem, first note that Lemma 23.2(2) implies that a basis for a flat E can be extended to a basis for any flat E' containing E .

Now let B be a basis for $E \cap F$. Extend B to bases B_1 and B_2 for E and F , respectively. Then any flat containing $B_1 \cup B_2$ contains E

and F and hence $\overline{E \cup F}$; that is, $\overline{B_1 \cup B_2} = \overline{E \cup F}$ and so $B_1 \cup B_2$ contains a basis for $\overline{E \cup F}$. Then

$$\begin{aligned} \text{rank}(\overline{E \cup F}) &\leq |B_1 \cup B_2| = |B_1| + |B_2| - |B_1 \cap B_2| \\ &= \text{rank}(E) + \text{rank}(F) - \text{rank}(E \cap F). \end{aligned}$$

□

The inequality (23.1) is called *the semimodular law*.

We remark that the proof of Theorem 23.3 shows that all maximal independent subsets of any subset S , not necessarily a flat, have the same cardinality. This is a corollary of the statement for flats, however, because we can apply Theorem 23.4 to the subgeometry on S .

As an exercise, make sure that you understand the following: Let E and F be flats in a geometry with $E \subseteq F$. If $\text{rank}(E) = \text{rank}(F)$, then $E = F$; F covers E if and only if $\text{rank}(F) = \text{rank}(E) + 1$.

For the affine geometries $AG_n(q)$, the number of points on a flat of rank r is q^r . For the projective geometries $PG_n(q)$, the number of points on a flat of rank r is

$$(23.2) \quad \frac{q^{r+1} - 1}{q - 1} = q^r + \cdots + q^2 + q + 1.$$

Theorem 23.4. *Suppose that every flat of rank i in a combinatorial geometry on v points has exactly k_i points, $i = 0, 1, \dots, n$. Then the total number of flats of rank r is*

$$(23.3) \quad \prod_{i=0}^{r-1} \frac{(v - k_i)}{(k_r - k_i)}.$$

Furthermore, the set of points together with the family of rank r flats is a 2-design.

PROOF: Since the flats of rank $r + 1$ that contain a flat of rank r partition the remaining $v - k_r$ points into sets of size $k_{r+1} - k_r$, there must be exactly $(v - k_r)/(k_{r+1} - k_r)$ such flats. The formula (23.3) now follows by induction on r when we count the ordered pairs (E, F) of rank r and rank $r + 1$ flats with $E \subseteq F$. Note that $k_0 = 0$ and $k_1 = 1$, so that (23.3) is valid for $r = 1$.

Any two points are contained in a unique rank 2 flat. The above argument implies that any rank 2 flat is contained in the same number of rank r flats. Hence the rank r flats give a 2-design. \square

The numbers of rank r flats of $PG_n(q)$ are called *Gaussian numbers*; see Chapter 24. Equations (23.2) and (23.3) imply that the numbers of points and hyperplanes of $PG_n(q)$ are equal (there are other ways of seeing this) and so we have the following corollary.

Corollary. *The points and hyperplanes of the projective geometry $PG_n(q)$ form a (v, k, λ) -symmetric design with*

$$\begin{aligned} v &= (q^{n+1} - 1)/(q - 1), \\ k &= (q^n - 1)/(q - 1), \\ \lambda &= (q^{n-1} - 1)/(q - 1). \end{aligned}$$

Problem 23C. Show that the incidence structure whose points are the points of $AG_r(2)$ and whose blocks are the planes of $AG_r(2)$ is a Steiner system $S(3, 4, 2^r)$.

The following theorem is due to C. Greene (1970).

Theorem 23.5. *The number of hyperplanes in a finite combinatorial geometry is at least the number of points.*

PROOF: The proof will be similar to that of Theorem 19.1. First, we shall show that if a point x is not on a hyperplane H , then the number r_x of hyperplanes on x is at least the number k_H of points on H by induction on the rank. The assertion is trivial for geometries of rank ≤ 2 . By the induction hypothesis, we know that the number of hyperplanes of the subgeometry on H (i.e. the number of colines C contained in H) is at least k_H . But for each such coline C , we get a hyperplane (the join of C and x) on x .

Now we repeat from the proof of Theorem 19.1: Let \mathcal{H} denote the set of hyperplanes, $v := |X|$, $b := |\mathcal{H}|$. Suppose $b \leq v$. Then

$$1 = \sum_{x \in X} \sum_{H \not\ni x} \frac{1}{v(b - r_x)} \geq \sum_{H \in \mathcal{H}} \sum_{x \notin H} \frac{1}{b(v - k_H)} = 1,$$

and this implies that in all the inequalities, equality must hold. Therefore $v = b$. \square

See the remark following Lemma 23.8 below concerning the case of equality in Theorem 23.5.

In studying $PG_n(\mathbb{F})$, the dimension formula

$$\dim(U \cap W) + \dim(U + W) = \dim(U) + \dim(W)$$

for linear subspaces of a vector space plays a crucial role. Equivalently,

$$(23.4) \quad \text{rank}(E \cap F) + \text{rank}(E \vee F) = \text{rank}(E) + \text{rank}(F)$$

for flats E and F of $PG_n(\mathbb{F})$. This is a stronger version of the semimodular law. Indeed, a combinatorial geometry in which (23.4) holds is said to be *modular*. In a modular combinatorial geometry, for example, (23.4) implies that any two lines contained in a plane must meet nontrivially (cf. Theorem 19.1).

Problem 23D. Let (X, \mathcal{B}) be the linear space consisting of the points and lines of a finite modular combinatorial geometry of rank 3. Show that (X, \mathcal{B}) is either a nearpencil as defined following Theorem 19.1 or else is a projective plane as defined in Chapter 19—that is, show that any two lines have the same cardinality $n + 1$ and that there are exactly $n^2 + n + 1$ points for some integer $n \geq 2$.

We have introduced the projective geometries $PG_n(\mathbb{F})$ and have defined projective planes in Chapter 19. Here is the general definition: A *projective geometry* is a modular combinatorial geometry that is *connected* in the sense that the point set cannot be expressed as the union of two proper flats.

We do not have the space or the time to prove here the following fundamental result. See Veblen and Young (1907) or Crawley and Dilworth (1973) for a proof.

Theorem 23.6. *Every projective geometry of rank $n \geq 4$ is isomorphic to $PG_n(\mathbb{F})$ for some division ring \mathbb{F} .*

Combinatorial geometries of rank ≤ 2 are without great interest, but all are modular and, except for the two point line, are projective geometries. The rank 3 projective geometries are, by Problem 23D,

equivalent to projective planes as introduced in Chapter 19 (the nearpencils are not connected).

Every modular combinatorial geometry can be put together from projective geometries. This is the content of the following problem.

Problem 23E.

(i) Let (X_1, \mathcal{F}_1) and (X_2, \mathcal{F}_2) be modular combinatorial geometries; $X_1 \cap X_2 = \emptyset$. Show that $(X_1 \cup X_2, \{F_1 \cup F_2 : F_1 \in \mathcal{F}_1, F_2 \in \mathcal{F}_2\})$ is a modular combinatorial geometry.

(ii) Let (X, \mathcal{F}) be a modular combinatorial geometry such that X is the union of two flats X_1 and X_2 where $X_1 \cap X_2 = \emptyset$. Let $\mathcal{F}_i := \{F \cap X_i : F \in \mathcal{F}\}$, $i = 1, 2$. Show that (X_i, \mathcal{F}_i) , $i = 1, 2$, is a modular combinatorial geometry and that $\mathcal{F} = \{F_1 \cup F_2 : F_1 \in \mathcal{F}_1, F_2 \in \mathcal{F}_2\}$.

Problem 23F. Prove that every flat F of a combinatorial geometry (X, \mathcal{F}) has a *modular complement*, i.e. there exists a flat E such that $E \cap F = \emptyset$, $E \vee F = X$, and $\text{rank}(E) + \text{rank}(F) = \text{rank}(X)$.

The linear spaces consisting of the points and lines of modular combinatorial geometries satisfy the following condition known as the *Pasch axiom*. A line that meets two sides of a triangle also meets the third. More precisely, suppose A, B, C are distinct lines and a, b, c distinct points with incidence as in Fig. 23.2. We require that any line L that contains a point other than a or b from the line C and a point other than a or c from the line B also contains a point other than b or c from the line A . See Fig. 23.2. To see that this holds in a modular geometry, notice that L and A must both be contained in the plane $P = \overline{\{a, b, c\}}$, and the modular equation implies that two lines in a plane must meet nontrivially.




Figure 23.2

Problem 23G. Consider the incidence structure whose points are the k -dimensional subspaces of a vector space V and whose lines are the $(k + 1)$ -dimensional subspaces of V , with incidence being containment. Show that this incidence structure satisfies the Pasch axiom.

Theorem 23.7. *A finite linear space (X, \mathcal{A}) for which the Pasch axiom holds, consists of the points and lines of some modular combinatorial geometry on X .*

PROOF: Suppose the Pasch axiom holds. We must construct the flats of a combinatorial geometry, which we do as follows. We say that a subset $S \subseteq X$ is a *flat* when, for any line L ,

$$|L \cap S| \geq 2 \quad \text{implies} \quad L \subseteq S.$$

Let \mathcal{F} denote the set of all such flats; this includes the empty set, all singletons, and X , as well as all lines in \mathcal{A} . Check that the definition implies that the intersection of any number of flats is again a flat.

Let x be a point not in a flat S . Let T be the union of all lines joining x to the points $s \in S$. We claim that this simple construction produces a flat T , and that T covers S .

To this end, let L be a line containing two points t_1, t_2 of T . We want to show $L \subseteq T$. If t_1, t_2 both belong to one of the lines on x , then L is that line and so $L \subseteq T$. Otherwise both t_1 and t_2 are in S ; then $L \subseteq T$, so assume $t_1 \notin S$. Then t_1 and t_2 belong to distinct lines M_1 and M_2 on x . Say M_i meets S in s_i , $i = 1, 2$, and let N be the line joining s_1 and s_2 . We have $N \subseteq S$. The Pasch axiom guarantees that L meets N in some point z of S .

Consider any other point $t_3 \in L$. Let M_3 be the line joining x and t_3 . Since M_3 meets two sides of the triangle with sides M_1 , L , and N (with vertices z , t_1 , and s_1), it must meet the third side N in some point s_3 of S . Then M_3 is one of the lines joining x to points of S , so $t_3 \in T$. We have now proved that T is a flat.

That T covers S is easy to see: If U is a flat, $S \subsetneq U \subseteq T$, pick $y \in U \setminus S$. By construction, the line joining x and y is one of the lines on x that meets S ; that line contains two points of U and hence is contained in U . This means $x \in U$, whence $T \subseteq U$.

Since any point lies in a flat that covers a flat S , (X, \mathcal{F}) is a combinatorial geometry. (The hypothesis that X is finite is only used here to ensure that there are no infinite chains of flats.)

Let x be a point on a line L and let H be any hyperplane. Since (if x is not already in H) the join of H and x must be X , L must be one of the lines on x that meet H . That is, any line L and any hyperplane H meet nontrivially. This implies modularity by Lemma 23.8 below. \square

Lemma 23.8. *A combinatorial geometry is modular if and only if any line and any hyperplane meet nontrivially.*

PROOF: The modular law (23.4) shows that any rank 2 flat and any rank $n - 1$ flat in a rank n geometry meet in a flat of rank ≥ 1 .

For the converse, we use induction on the rank. Assume that all lines and hyperplanes in a rank n combinatorial geometry meet nontrivially. Suppose H is a hyperplane and that there exists a line $L \subseteq H$ and a rank $n - 2$ flat $C \subseteq H$ that are disjoint. But then for any point $x \notin H$, the hyperplane $C \vee \{x\}$ would be disjoint from the line L . So by induction, the subgeometry on any hyperplane H is modular.

Thus if there is a pair of flats E and F that provide a counterexample to the modular law (23.4), then $E \vee F$ is equal to the entire point set X . Let H be a hyperplane containing E and let $F' := H \cap F$. Then $E \vee F' \subseteq H$. But $\text{rank}(F') \geq \text{rank}(F) - 1$ since otherwise a modular complement of F' in F would have rank ≥ 2 and so would contain a line, one that would be disjoint from H . We see that E and F' provide a counterexample to (23.4) contained in H , contradicting the modularity of the subgeometry H . \square

Remark. Suppose the number of hyperplanes of a finite combinatorial geometry (X, \mathcal{F}) is equal to the number of points. Then, reviewing the proof of Theorem 23.5, $r_x = k_H$ whenever $x \notin H$. If we apply Theorem 23.5 to the interval $[\{x\}, X]$ in any combinatorial geometry, we find that $r_x \geq l_x$, where l_x denotes the number of lines containing x (since these lines are the points of the geometric lattice $[\{x\}, X]$). For $x \notin H$ we obviously have $l_x \geq k_H$ since the lines $\{x\} \vee \{y\}$, $y \in H$, are distinct. In summary, equality in Theorem 23.5 implies that $l_x = k_H$ when $x \notin H$. This means that

every line meets every hyperplane and hence (X, \mathcal{F}) is modular by Lemma 23.8.

Two triangles $\{a_1, b_1, c_1\}$ and $\{a_2, b_2, c_2\}$ are said to be *perspective from a point* if there exists a point p (the *point of perspectivity*) such that $\{p, a_1, a_2\}$ are collinear, $\{p, b_1, b_2\}$ are collinear, and $\{p, c_1, c_2\}$ are collinear. Two triangles $\{a_1, b_1, c_1\}$ and $\{a_2, b_2, c_2\}$ are said to be *perspective from a line* if there exists a line L (the *line or axis of perspectivity*) such that $\{L, A_1, A_2\}$ are concurrent, $\{L, B_1, B_2\}$ are concurrent, and $\{L, C_1, C_2\}$ are concurrent. Here we are using ‘triangle’ to mean three noncollinear points, and $A_i, B_i,$ and C_i to denote the ‘sides’ of the triangle opposite $a_i, b_i,$ and $c_i,$ respectively. That is, $A_i := \overline{b_i, c_i}, i = 1, 2,$ etc.




Figure 23.3

In Fig. 23.3, the triangles are perspective from the point p and also perspective from the line L . The incidence structure so illustrated, with ten points and ten lines, each line on three points and each point on three lines, is called the *Desargues configuration*. The triangles need not lie in a plane. The right diagram in Fig. 23.1 is isomorphic (!) to that in Fig. 23.3 as an incidence structure; the former is easier to imagine as 3-dimensional. It can be viewed in many ways, e.g. as showing that the triangles $\{25, 35, 45\}$ and $\{12, 13, 14\}$ are perspective from the point 15 and also perspective from the line $\{23, 24, 34\}$.

If we choose a basis for the $(n+1)$ -dimensional vector space whose subspaces comprise $PG_n(\mathbb{F})$, we can describe projective points by so-called *homogeneous coordinates*. By $\langle x_0, x_1, \dots, x_n \rangle$, we mean the 1-dimensional subspace spanned by the vector (x_0, x_1, \dots, x_n) .

The projective point $\langle x_0, x_1, \dots, x_n \rangle$ is the same as $\langle y_0, y_1, \dots, y_n \rangle$ if and only if the vector (y_0, y_1, \dots, y_n) is a nonzero scalar multiple of (x_0, x_1, \dots, x_n) . The hyperplanes may also be described by homogeneous $(n+1)$ -tuples: $[c_0, c_1, \dots, c_n]$ will denote the hyperplane consisting of points with homogeneous coordinates $\langle x_0, x_1, \dots, x_n \rangle$ so that $c_0x_0 + x_1c_1 + \dots + x_nc_n = 0$.

Theorem 23.9 (Desargues' theorem). *In $PG_n(\mathbb{F})$, if two triangles are perspective from a point, then they are perspective from a line.*

PROOF: Let triangles $\{a_1, b_1, c_1\}$ and $\{a_2, b_2, c_2\}$ be perspective from a point p . We are going to assume that no three of p, a_1, b_1 and c_1 are collinear so that we do not spend too much time on details. We will also assume that all points lie in a plane, i.e. we prove the theorem for $PG_2(\mathbb{F})$. The other cases are left for the reader.

We choose a basis for a 3-dimensional vector space so that the basis vectors $\mathbf{x}, \mathbf{y}, \mathbf{z}$ span the 1-dimensional subspaces a_1, b_1 , and c_1 , respectively. Then the homogeneous coordinates for a_1, b_1 , and c_1 are $\langle 1, 0, 0 \rangle$, $\langle 0, 1, 0 \rangle$, and $\langle 0, 0, 1 \rangle$, respectively. Then p has homogeneous coordinates $\langle \alpha, \beta, \gamma \rangle$ where all coordinates are nonzero. We replace the original basis vectors by $\alpha\mathbf{x}, \beta\mathbf{y}$ and $\gamma\mathbf{z}$; then a_1, b_1 , and c_1 are still represented by $\langle 1, 0, 0 \rangle$, $\langle 0, 1, 0 \rangle$, and $\langle 0, 0, 1 \rangle$, respectively, while p now has homogeneous coordinates $\langle 1, 1, 1 \rangle$. This will simplify our computations.

It follows that $a_2 = \langle \alpha, 1, 1 \rangle$, $b_2 = \langle 1, \beta, 1 \rangle$, $c_2 = \langle 1, 1, \gamma \rangle$, for some $\alpha, \beta, \gamma \in \mathbb{F}$. The line joining a_1 and b_1 is $[0, 0, 1]$; the line joining a_2 and b_2 is $[1 - \beta, 1 - \alpha, \alpha\beta - 1]$ (check that both a_2 and b_2 are on this line). The point on both lines is $\langle 1 - \beta, \alpha - 1, 0 \rangle$. Similarly, the point of intersection of the lines joining b_1 and c_1 with the line joining b_2 and c_2 is found to be $\langle 0, 1 - \alpha, \gamma - 1 \rangle$, and the point of intersection of the lines joining c_1 and a_1 with the line joining c_2 and a_2 is found to be $\langle \beta - 1, 0, 1 - \gamma \rangle$. The three points of intersection are collinear since their coordinates are linearly dependent.

(If we are careful, the proof should go through also for division rings \mathbb{F} .) □

Problem 23H. Prove that the linear space of $PG_n(\mathbb{F})$ also satisfies *Pappus' theorem* when \mathbb{F} is a (commutative) field, which is as

follows. Let $a_i, b_i,$ and c_i be collinear points, say on a line L_i , for $i = 1, 2$. Suppose L_1 and L_2 meet in a point (not one of the six named points). Then the lines $\overline{\{a_1, b_2\}}$ and $\overline{\{a_2, b_1\}}$ meet in a point c , the lines $\overline{\{b_1, c_2\}}$ and $\overline{\{b_2, c_1\}}$ meet in a point a , and the lines $\overline{\{a_1, c_2\}}$ and $\overline{\{a_2, c_1\}}$ meet in a point b ; and the three points a, b, c are collinear.




Figure 23.4

Projective planes in which the statement of Theorem 23.9 is valid (if two triangles are perspective from a point, then they are perspective from a line) are called *Desarguesian planes*. Projective planes in which the conclusion of Problem 23H holds are called *Pappian planes*. We do not have the space or time to prove the further following fundamental result. See Crawley and Dilworth (1973).

Theorem 23.10.

- (1) A projective geometry of rank 3 is isomorphic to $PG_2(\mathbb{E})$ for some division ring \mathbb{E} if and only if it is a Desarguesian plane.
- (2) A projective geometry of rank 3 is isomorphic to $PG_2(\mathbb{F})$ for some field \mathbb{F} if and only if it is a Pappian plane.

A corollary of Theorem 23.10 is that every Pappian plane is Desarguesian. For a synthetic (i.e. coordinate-free) proof that Pappus' theorem implies Desargues' theorem, see D. Pedoe (1963). We remark that every finite division ring is a field (Wedderburn's theorem), so that every finite Desarguesian plane is Pappian; see M. Hall, Jr. (1972).

We describe one method of obtaining finite projective planes that are not Desarguesian.

Let G be an abelian group of order n^2 , and suppose that there exist subgroups H_0, H_1, \dots, H_n of order n that partition the nonzero elements of G , that is such that $H_i \cap H_j = \{0\}$ for $i \neq j$ and, therefore,

$$\bigcup_{i=0}^n H_i \setminus \{0\} = G \setminus \{0\}.$$

Then, we claim, the incidence structure whose points are the elements of G and whose lines are all cosets (translates) of all the subgroups H_i is an affine plane. In general, the intersection of cosets of two subgroups H and K is either empty or a coset of $H \cap K$, so lines meet in at most one point. We could now count covered pairs to show that every two distinct points are contained in a line, but it is just as simple to note that given points $x, y \in G$, the coset $H_\ell + y$ contains both points where H_ℓ is the subgroup containing the difference $x - y$. An affine plane obtained from a group G and $n + 1$ subgroups in this way is called an *affine translation plane*. It is known that G must be elementary abelian for such subgroups to exist; see J. André (1954). The affine plane may be completed to a projective plane as in Problem 19K; any projective plane obtained in this way is a *translation plane*.

Example 23.7. Here is a partition of the nonzero elements of \mathbb{F}_3^4 into ten subgroups H_0, H_1, \dots, H_9 . (We have denoted the elements as strings, dropping commas and parentheses.)

$$\begin{aligned} &\{0000, 1000, 2000, 0100, 0200, 1100, 2200, 2100, 1200\} \\ &\{0000, 0010, 0020, 0001, 0002, 0011, 0022, 0021, 0012\} \\ &\{0000, 1010, 2020, 0101, 0202, 1111, 2222, 2121, 1212\} \\ &\{0000, 2010, 1020, 0201, 0102, 2211, 1122, 1221, 2112\} \\ &\{0000, 0110, 0220, 2001, 1002, 2111, 1222, 2221, 1112\} \\ &\{0000, 0210, 0120, 1001, 2002, 1211, 2122, 1121, 2212\} \\ &\{0000, 1110, 2220, 2101, 1202, 0211, 0122, 1021, 2012\} \\ &\{0000, 2210, 1120, 1201, 2102, 0111, 0222, 2021, 1012\} \\ &\{0000, 2110, 1220, 2201, 1102, 1011, 2022, 0121, 0212\} \\ &\{0000, 1210, 2120, 1101, 2202, 2011, 1022, 0221, 0112\} \end{aligned}$$

The affine plane corresponding to this ‘spread’ of subgroups is the Desarguesian plane.

But note that the elements of the first four subgroups, for example, can be partitioned into subgroups in *another* way, as indicated by the columns below.

{0000,	{0000,	{0000,	{0000,
1000, 2000,	0100, 0200,	1100, 2200,	2100, 1200,
0010, 0020,	0001, 0002,	0011, 0022,	0021, 0012,
1010, 2020,	0101, 0202,	1111, 2222,	2121, 1212,
2010, 1020}	0201, 0102}	2211, 1122}	1221, 2112}

The above example is the special case $q = 3$ of a construction we now describe. Let V be a 2-dimensional vector space over \mathbb{F}_{q^2} and let H_0, H_1, \dots, H_{q^2} be the 1-dimensional subspaces over \mathbb{F}_{q^2} . If we consider V as a 4-dimensional vector space over \mathbb{F}_q , the subspaces H_i are 2-dimensional over \mathbb{F}_q (they form a *spread* of lines in $PG_3(q)$; see Theorem 24.3). Let U be any 2-dimensional subspace over \mathbb{F}_q other than one of the H_i 's. Then U meets any H_i in $\{0\}$ or in a 1-dimensional subspace over \mathbb{F}_q . Say U meets H_0, H_1, \dots, H_q in q points each and $H_{q+1}, H_{q+2}, \dots, H_{q^2}$ in the zero vector only. Consider the \mathbb{F}_q -subspaces αU as α ranges over the nonzero elements of \mathbb{F}_{q^2} ; since multiplying by the nonzero elements of \mathbb{F}_q fixes U , there are only $(q^2 - 1)/(q - 1)$ distinct such subspaces, say U_0, U_1, \dots, U_q . These $q + 1$ subspaces U_i meet pairwise only in the zero vector and their union is $H_0 \cup H_1 \cup \dots \cup H_q$. Thus

$$U_0, U_1, \dots, U_q, H_{q+1}, H_{q+2}, \dots, H_{q^2}$$

is another partition of V into subgroups of order q^2 .

We shall not prove here that the projective planes resulting from this construction are not Desarguesian (for $q > 2$). See Theorem 10.9 in D. R. Hughes and F. C. Piper (1973). The reader can find counterexamples to Desargues' theorem in Example 23.7 by hand.

We conclude the chapter with proof of an important step in the difficult proof of Theorem 23.6. We need a preliminary observation.

Proposition 23.11. *The subgeometry on any flat of a projective geometry is again a projective geometry.*

PROOF: That the modular law holds in the subgeometry on a flat of a modular projective geometry is immediate. We must show that

these subgeometries are connected. To this end, it will suffice to show that if H is a hyperplane in a projective geometry with point set X , then the subgeometry on H is connected.

If not, $H = E \cup F$ where E and F are flats. By (23.4), $\text{rank}(E) + \text{rank}(F) = n - 1$ where $n := \text{rank}(X)$. Let E_1, \dots, E_s and F_1, \dots, F_t be the flats that cover E and F , respectively, that contain points outside of H ; each family partitions the points outside of H . Suppose that both $s, t \geq 2$. By (23.4), there exists $x_i \in E_i \cap F_i$, $i = 1, 2$. The line $\overline{\{x_1, x_2\}}$, again by (23.4), meets H in some point $e \in E$. But then x_2 , being on the line joining e and x_1 , must be contained in E_1 , a contradiction. Thus one of s or t must be 1, say $s = 1$, and then X is the union of the disjoint flats F and E_1 , contradicting the connectivity of the original projective geometry. \square

A corollary of Proposition 23.11 is that every line of a projective geometry has at least three points (since a two-point line is not connected). This is used at a critical point in the proof below. We remark that with the aid of Problem 23D, it is easy to see that all lines in a finite projective geometry have the same size $n + 1$.

Theorem 23.12. *Desargues' theorem holds in any projective geometry of rank ≥ 4 .*

PROOF: Consider two triangles $\{a_1, b_1, c_1\}$ and $\{a_2, b_2, c_2\}$ that are perspective from a point x .

We first assume that the planes P_1 and P_2 spanned by $\{a_1, b_1, c_1\}$ and $\{a_2, b_2, c_2\}$, respectively, are distinct. Let $T := \overline{\{x, a_1, b_1, c_1\}}$. The lines $\overline{\{x, a_1\}}$, $\overline{\{x, b_1\}}$, and $\overline{\{x, c_1\}}$ contain, respectively, the points a_2 , b_2 , and c_2 , so P_1 and P_2 are contained in T , that evidently has rank 4. So by the modular law, P_1 and P_2 must meet in a line L . We claim that the two original triangles are perspective from the line L .

The plane $Q := \overline{\{p, a_1, b_1\}}$ contains a_2 and b_2 and hence contains both the lines $\overline{\{a_1, b_1\}}$ and $\overline{\{a_2, b_2\}}$ that therefore intersect in a point q , say. The point q belongs to both P_1 and P_2 , and hence $q \in L$. Similarly, the lines $\overline{\{b_i, c_i\}}$, $i = 1, 2$, meet in a point on L ; and the lines $\overline{\{a_i, c_i\}}$, $i = 1, 2$, meet in a point on L . The two triangles are thus perspective from L .

Now assume that the two original triangles lie in a plane P .

Let x_1 be any point not in P and x_2 any other point on the line containing x_1 and p . The lines $\overline{\{x_1, a_1\}}$ and $\overline{\{x_2, a_2\}}$ are contained in the plane $\overline{\{p, x_1, a_1\}}$ and so meet in a point a^* . Similarly, the lines $\overline{\{x_1, b_1\}}$ and $\overline{\{x_2, b_2\}}$ meet in a point b^* and the lines $\overline{\{x_1, c_1\}}$ and $\overline{\{x_2, c_2\}}$ meet in a point c^* . The plane $P^* := \overline{\{a^*, b^*, c^*\}}$ and P are contained in a rank 4 flat and so meet in a line $L := P \cap P^*$.

The triangles $\{a_1, b_1, c_1\}$ and $\{a^*, b^*, c^*\}$ are perspective from the point x_1 and lie in different planes, and so are perspective from the line L . Similarly, the triangles $\{a_2, b_2, c_2\}$ and $\{a^*, b^*, c^*\}$ are perspective from x_2 , and so are perspective from L . The line $\overline{\{a_1, b_1\}}$ meets L in the same point as the line $\overline{\{a^*, b^*\}}$; the line $\overline{\{a_2, b_2\}}$ meets L in the same point as the line $\overline{\{a^*, b^*\}}$; hence the lines $\overline{\{a_1, b_1\}}$ and $\overline{\{a_2, b_2\}}$ meet in a point of L . Similarly, the other corresponding ‘sides’ of the two original triangles meet in points of L . In summary, the original triangles are perspective from the line L . \square

Problem 23I. Determine the number of flats of rank $n - k$ in the partition lattice Π_n .

Problem 23J. For an arbitrary block design (with parameters v, k, λ, b, r) we define a *line* to be the intersection of all blocks containing a pair of points x, y . Prove:

- (i) Any two points are on a unique line;
- (ii) If L is a line, then $2 \leq |L| \leq \frac{b-\lambda}{r-\lambda}$;
- (iii) If a line meets a block in two points, it is contained in the block.

Notes.

Girard Desargues (1593–1662) was an architect and military engineer who introduced the term *involution* in his work on perspective. He worked in Lyons and Paris. The work of Pappus of Alexandria (fl. 320), the last significant Greek geometer, was considerably earlier. The mathematical discipline of projective geometry did not develop until the 19th century.

Moritz Pasch was originally an algebraist but then became interested in non-euclidean geometry. He came to Giessen at the age of 27 as Privatdozent and stayed there until his death (60 years later). He was Rektor of the university 1893–1894.

An interesting family of combinatorial geometries called transversal geometries arises from bipartite graphs; see Crapo and Rota (1970). The independent sets of these geometries are those subsets of one part X of a bipartition (X, Y) with the property that they can be matched into Y .

We have seen that the concept of combinatorial geometries and geometric lattices are ‘cryptomorphic’, i.e. they are essentially different axiom systems for the same structures. Crapo and Rota (1970) give further cryptomorphic versions. For example, ‘matroids’ are more-or-less the same thing as combinatorial geometries, though the emphasis of the theory of matroids is different.

Some characterizations of the symmetric design consisting of the points and hyperplanes of a finite projective space may be found in Section 2.1 of P. Dembowski (1968).

References.

- J. André (1954), Über nicht-Desarguessche Ebenen mit transitiver Translationengruppe, *Math. Zeitschr.* **60**, 156–186.
- L. M. Batten (1986), *Combinatorics of Finite Geometries*, Cambridge University Press.
- H. Crapo and G.-C. Rota (1970), *Combinatorial Geometries*, MIT Press.
- P. Crawley and R. P. Dilworth (1973), *Algebraic Theory of Lattices*, Prentice-Hall.
- P. Dembowski (1968), *Finite Geometries*, Springer-Verlag.
- C. Greene (1970), A rank inequality for finite geometric lattices, *J. Combinatorial Theory* **9**, 357–364.
- M. Hall, Jr. (1972), *The Theory of Groups*, 2nd edn., Chelsea.
- D. R. Hughes and F. C. Piper (1973), *Projective Planes*, Springer-Verlag.
- D. Pedoe (1963), *An Introduction to Projective Geometry*, Macmillan.
- O. Veblen and J. W. Young (1907), *Projective Geometries* (2 vols.), Ginn Co.

24

Gaussian numbers and q -analogues

There exist many analogies between the partially ordered set of all subsets of a finite set and the partially ordered set of all subspaces of a finite vector space. This is primarily because they are both examples of ‘matroid designs’ as defined in the previous chapter. Let $V_n(q)$ denote an n -dimensional vector space over the field \mathbb{F}_q of q elements. We use the term k -subspace as a short form of k -dimensional subspace.

We begin with some counting. To obtain a maximal chain (i.e. a chain of size $n + 1$ containing one subspace of each possible dimension) in the partially ordered set of all subspaces of $V_n(q)$, we start with the 0-subspace. After we have chosen an i -subspace U_i , $0 \leq i < n$, we can choose an $(i + 1)$ -subspace U_{i+1} that contains U_i in $(q^n - q^i)/(q^{i+1} - q^i)$ ways since we can take the span of U_i and any of the $(q^n - q^i)$ vectors *not* in U_i —but any $(i + 1)$ -subspace will arise exactly $(q^{i+1} - q^i)$ times in this manner. In summary, the number of maximal chains of subspaces in $V_n(q)$ is

$$M(n, q) = \frac{(q^n - 1)(q^{n-1} - 1)(q^{n-2} - 1) \cdots (q^2 - 1)(q - 1)}{(q - 1)^n}.$$

We may consider $M(n, q)$ as a polynomial in q for each integer n . When the indeterminate q is replaced by a prime power, we have the number of maximal chains in the poset $PG_n(q)$. When q is replaced by 1, we have $M(n, 1) = n!$, which is the number of maximal chains in the poset of subsets of an n -set.

The *Gaussian number* $\begin{bmatrix} n \\ k \end{bmatrix}_q$ can be defined as the number of k -subspaces of $V_n(q)$. These are called *Gaussian coefficients* by some

authors to emphasize the analogy with binomial coefficients. To find an expression for $\begin{bmatrix} n \\ k \end{bmatrix}_q$, we count the number N of pairs (U, \mathcal{C}) where U is a k -subspace and \mathcal{C} is a maximal chain that contains U . Of course, every maximal chain contains exactly one subspace of dimension k , so $N = M(n, q)$. On the other hand, we get each such maximal chain uniquely by appending to a maximal chain in the partially ordered set of all subspaces of U , of which there are $M(k, q)$, a maximal chain in the partially ordered set of all subspaces of $V_n(q)$ that contain U ; there are $M(n - k, q)$ of these, since the partially ordered set $\{W : U \subseteq W \subseteq V\}$ is isomorphic to the partially ordered set of subspaces of the factor space V/U that has dimension $n - k$. Thus

$$\begin{bmatrix} n \\ k \end{bmatrix}_q = \frac{M(n, q)}{M(k, q)M(n - k, q)} = \frac{(q^n - 1)(q^{n-1} - 1) \cdots (q^{n-k+1} - 1)}{(q^k - 1)(q^{k-1} - 1) \cdots (q - 1)}.$$

For some purposes, it is better to think of $\begin{bmatrix} n \\ k \end{bmatrix}_q$ as a *polynomial* in an indeterminate q rather than as a function of a prime power q . That the rational function above is in fact a polynomial can be seen in several ways. For example, it is an easy exercise to see that a rational function in x which is integral for infinitely many integral values of x must be a polynomial in x . Perhaps *Gaussian polynomial* is a better term than *Gaussian number* or *coefficient*. As an example,

$$\begin{bmatrix} 6 \\ 3 \end{bmatrix}_q = q^9 + q^8 + 2q^7 + 3q^6 + 3q^5 + 3q^4 + 3q^3 + 2q^2 + q + 1.$$

When the indeterminate q is replaced by 1 in $\begin{bmatrix} n \\ k \end{bmatrix}_q$, we obtain $\binom{n}{k}$. This explains a small part of a tendency for results concerning finite vector spaces to reduce to the corresponding results for sets when q is replaced by 1. It is also possible to have so-called *q-analogues* of results on sets where we try to replace ‘ k -subset’ by ‘ k -subspace’. Sometimes these statements are true and have proofs that are similar to the results on sets.

The following is the q -analogue of Sperner’s theorem, Theorem 6.3.

Theorem 24.1. *If \mathcal{A} is an antichain in the partially ordered set of all subspaces of $V_n(q)$, then*

$$|\mathcal{A}| \leq \left[\begin{matrix} n \\ \lfloor n/2 \rfloor \end{matrix} \right]_q.$$

PROOF: Let \mathcal{A} be an antichain and count the number N of pairs (U, \mathcal{C}) where $U \in \mathcal{A}$ and \mathcal{C} is a maximal chain that contains U . Every maximal chain contains at most one subspace in \mathcal{A} , so $N \leq M(n, q)$. On the other hand, each k -subspace in \mathcal{A} lies in exactly $M(k, q)M(n - k, q)$ maximal chains \mathcal{C} . Thus

$$M(n, q) \geq N = \sum_{k=0}^n c_k M(k, q) M(n - k, q),$$

where c_k is the number of k -dimensional subspaces belonging to \mathcal{A} . The proof is completed in a manner analogous to the proof of Theorem 6.3 if we believe that $\left[\begin{matrix} n \\ k \end{matrix} \right]_q \leq \left[\begin{matrix} n \\ \lfloor n/2 \rfloor \end{matrix} \right]_q$ for all k , and this is left to the reader to verify. \square

The following theorem gives a combinatorial interpretation of the coefficients of the $\left[\begin{matrix} n \\ k \end{matrix} \right]_q$ as a polynomial in q , and thus proves they are all positive integers.

Theorem 24.2. *Let*

$$\left[\begin{matrix} n \\ k \end{matrix} \right]_q = \sum_{\ell=0}^{k(n-k)} a_\ell q^\ell.$$

Then the coefficient a_ℓ is the number of partitions of ℓ whose Ferrers diagrams fit in a box of size $k \times n - k$.

PROOF: We can work with the vector space \mathbb{F}_q^n of n -tuples over \mathbb{F}_q . It is well known that every k -subspace of \mathbb{F}_q^n arises uniquely as the row space of a $k \times n$ matrix over \mathbb{F}_q that (i) has rank k and (ii) is a so-called *row-reduced echelon form*. This means that the first nonzero entry in each row is a 1, the entries above a leading 1 are 0's, and the leading 1 in row i is further to the right than the leading 1 in row $i - 1$, $i = 2, 3, \dots, k$.

Suppose the leading 1 in row i occurs in column c_i , $i = 1, 2, \dots, k$. Then $(n - k + 1 - c_1, n - k + 2 - c_2, \dots, n - 1 - c_{k-1}, n - c_k)$ is a non-increasing sequence of nonnegative numbers and so, when terminal zeros are dropped, corresponds to a partition of some number into at most k parts of size at most $n - k$. Conversely, such a partition gives us the positions of leading ones in a *class* of echelon forms.

For example, there are 20 classes of echelon forms in the case $n = 6$, $k = 3$; see Fig. 24.1.




Figure 24.1

In each matrix of Fig. 24.1, the positions of the dots, when the intervening columns are deleted and we reflect through a vertical axis, describe the Ferrers diagram of a partition (of some number ≤ 9) that fits in a 3 by 3 box. The class represented by the last matrix in the first row, for example, contains q^7 echelon forms.

In general, the class of echelon forms where the leading 1 in row i occurs in column c_i , $i = 1, 2, \dots, k$, contains q^ℓ matrices for some ℓ since the positions not containing 1's or required to be 0's may be filled arbitrarily with elements of \mathbb{F}_q . To be precise,

$$\ell = (n - k + 1 - c_1) + \dots + (n - 1 - c_{k-1}) + (n - c_k)$$

because for each $i = 1, 2, \dots, k$, there are $n - (k - i) - c_i$ positions in the i -th row that may be arbitrarily filled. That is, the class consists of q^ℓ matrices where the partition into at most k parts of

size at most $n - k$ that corresponds to the class is in fact a partition of the number ℓ .

Thus when a_ℓ is defined as the number of partitions of ℓ whose Ferrers diagrams fit in a box of size $k \times n - k$, we have a polynomial $\sum_{\ell=0}^{k(n-k)} a_\ell q^\ell$ that agrees with the polynomial $\begin{bmatrix} n \\ k \end{bmatrix}_q$ when evaluated at any prime power q ; hence the two polynomials are equal. \square

We remark that when we set $q = 1$ in the statement of Theorem 24.2, we obtain as a corollary the result that the total number of partitions whose Ferrers diagram fits in a box of size $k \times n - k$ is $\binom{n}{k}$.

Problem 24A. Show this directly.

Next, we derive a recursion (24.1) for the Gaussian numbers. This provides another way to see that they are polynomials in q (by induction on n , say). Pick a hyperplane H , i.e. an $(n - 1)$ -subspace, of $V_n(q)$. Some k -subspaces are contained in H (their number is $\begin{bmatrix} n-1 \\ k \end{bmatrix}_q$) and the rest meet H in a $(k - 1)$ -subspace. Each of the $\begin{bmatrix} n-1 \\ k-1 \end{bmatrix}_q$ $(k - 1)$ -subspaces in H is contained in

$$\begin{bmatrix} n - k + 1 \\ 1 \end{bmatrix}_q = \frac{q^{n-k+1} - 1}{q - 1}$$

k -subspaces of V , of which

$$\begin{bmatrix} n - k \\ 1 \end{bmatrix}_q = \frac{q^{n-k} - 1}{q - 1}$$

are contained in H ; this leaves q^{n-k} that are not contained in H . Thus

$$(24.1) \quad \begin{bmatrix} n \\ k \end{bmatrix}_q = \begin{bmatrix} n - 1 \\ k \end{bmatrix}_q + q^{n-k} \begin{bmatrix} n - 1 \\ k - 1 \end{bmatrix}_q.$$

Problem 24B. Determine the exponents e_i (they may be functions of m , n , and k as well as i) so that the following identity is valid:

$$\begin{bmatrix} n + m \\ k \end{bmatrix}_q = \sum_{i=0}^k q^{e_i} \begin{bmatrix} n \\ i \end{bmatrix}_q \begin{bmatrix} m \\ k - i \end{bmatrix}_q.$$

(One way to solve this involves echelon forms; another uses (24.1).)

The equation of Problem 24B is a q -analogue of the equation

$$\binom{n+m}{k} = \sum_{i=0}^k \binom{n}{i} \binom{m}{k-i}$$

for binomial coefficients. The q -analogue of inclusion-exclusion appears in the next chapter; see Theorem 25.2 for an application.

What is the q -analogue of (simple) t -designs? This would be a family \mathcal{B} of k -subspaces of $V_v(q)$ such that each t -subspace is contained in exactly λ members of \mathcal{B} . No nontrivial examples of such ' q - $S_\lambda(t, k, v)$'s were known with $t \geq 2$ until 1986 when S. Thomas described a family with

$$q = 2, \quad \lambda = 7, \quad t = 2, \quad k = 3, \quad v \equiv \pm 1 \pmod{6}.$$

The case $t = \lambda = 1$ is already nontrivial for vector spaces. For sets, an $S(1, k, v)$ is a partition of a v -set into k -subsets, and this exists if and only if k divides v .

Theorem 24.3. *There exists a family of k -subspaces of $V_v(q)$ such that every 1-subspace is contained in exactly one member of the family (a so-called spread of k -subspaces) if and only if k divides v .*

PROOF: In other words, we are interested in families of k -subspaces such that any two of them intersect in the 0-subspace but such that their union is the entire v -dimensional vector space.

The number of k -subspaces that we require is the total number of nonzero vectors divided by the number of nonzero vectors in a k -subspace, and this is $(q^v - 1)/(q^k - 1)$. This is an integer if and only if k divides v .

Suppose $v = km$ where m is an integer. As a v -dimensional vector space over \mathbb{F}_q , we take an m -dimensional vector space V over \mathbb{F}_{q^k} . Let \mathcal{B} be the family of 1-subspaces of V as a vector space over \mathbb{F}_{q^k} . (So there are $q^{k(m-1)} + q^{k(m-2)} + \dots + q^k + 1$ of these and each contains q^k vectors.) Now think of V as a vector space over \mathbb{F}_q , a subfield of \mathbb{F}_{q^k} ; the members of \mathcal{B} are k -dimensional subspaces over \mathbb{F}_q and provide the required partition. \square

Problem 24C. Let \mathcal{B} be a spread of k -subspaces in $V_v(q)$. Let \mathcal{A} consist of all cosets of all members of \mathcal{B} . Show that \mathcal{A} is the block set of an $S(2, q^k, q^v)$ on the set of points $V_v(q)$. (The case $v = 2k$ is particularly interesting because we obtain affine planes of order q^k . Planes obtained from spreads are called *translation planes*.)

Problem 24D. Prove that

$$\sum_{k=0}^n (q^n - 1) \dots (q^{n-k+1} - 1) q^{\binom{k}{2}} \begin{bmatrix} n \\ k \end{bmatrix}_q = q^{n^2}.$$

The Erdős-Ko-Rado Theorem (see Theorem 6.4) can be formulated in two (equivalent) ways. In one formulation, the bound for m is $\binom{n-1}{k-1}$ and in the other it is $\frac{k}{n} \cdot \binom{n}{k}$, where $\binom{n}{k}$ counts the total number of k -subsets of the n -set.

Now consider a possible q -analogue. Start with a collection $\mathcal{A} := \{A_1, A_2, \dots, A_m\}$ of m distinct k -dimensional subspaces of the n -dimensional vectorspace $V(n, q)$ over \mathbb{F}_q such that any two of the A_i intersect in a subspace of dimension ≥ 1 . Then one can either conjecture that if $k \leq \frac{1}{2}n$

$$m \leq \begin{bmatrix} n-1 \\ k-1 \end{bmatrix}_q \quad \text{or} \quad m \leq \frac{k}{n} \cdot \begin{bmatrix} n \\ k \end{bmatrix}_q.$$

In this case, the bounds differ. The first one is stronger than the second one. For a proof of the first bound see W. N. Hsieh (1975). This result was strengthened by P. Frankl and R. M. Wilson (1986). The second bound can be proved by generalizing the proof of Theorem 6.4 which is the next problem.

Problem 24E. Consider the situation described above. Let $\pi := (\mathbf{x}_1, \mathbf{x}_2, \dots, \mathbf{x}_n)$ run through the set B_n of *all* ordered bases of $V(n, q)$. We place π on a circle. If a sequence of k consecutive vectors \mathbf{x}_i (on the circle) is a basis for A_j , we say $A_j \in \pi$.

(i) Show that for a fixed π , we have $|\mathcal{A} \cap \pi| \leq k$.

(ii) For a fixed A_j , count the number of bases $\pi \in B_n$ such that $A_j \in \pi$.

(iii) Prove that

$$m \leq \frac{k}{n} \cdot \begin{bmatrix} n \\ k \end{bmatrix}_q.$$

Notes.

It has been suggested that one should use the notation n^q for $M(n, q)$ (which is to be pronounced ‘ n q -torial’). Then we have

$$\left[\begin{matrix} n \\ k \end{matrix} \right]_q = \frac{n^q}{k^q (n-k)^q}.$$

Also note

$$\lim_{q \rightarrow 1} n^q = n! \quad (\text{that is, } n!).$$

We do not know who first proposed this.

The q -analogue of Ramsey’s theorem was a long outstanding problem until it was solved by R. L. Graham, K. Leeb, and B. L. Rothschild in 1972.

Carl Friedrich Gauss (1777–1855) was possibly the greatest mathematician (scientist) of all time. He made extremely important contributions to number theory. He was the first to study properties of the expressions that are now called Gaussian polynomials or Gaussian numbers.

References.

- P. Frankl and R. M. Wilson (1986), The Erdős-Ko-Rado theorem for vector spaces, *J. Combinatorial Theory (A)* **43**, 228–236.
- R. L. Graham, K. Leeb, B. L. Rothschild (1972), Ramsey’s theorem for a class of categories, *Adv. Math.* **8**, 417–433.
- R. L. Graham, B. L. Rothschild, and J. Spencer (1980), *Ramsey Theory*, Wiley.
- W. N. Hsieh (1975), Intersection theorems for systems of finite vector spaces, *Discrete Math.* **12**, 1–16.
- S. Thomas (1986), Designs over finite fields, *Geometriae Dedicata* **24**, 237–242.

25

Lattices and Möbius inversion

One of the techniques belonging to the foundations of combinatorics is the principle of Möbius inversion over partially ordered sets. This can be thought of as a generalization of inclusion-exclusion as well as an extension of the inversion with the classical Möbius function of number theory, which was discussed in Chapter 10.

Let P be a finite partially ordered set. We will consider matrices α whose rows and columns are indexed by the elements of P , that is mappings from $P \times P$ to the rationals or complex numbers. The *incidence algebra* $\mathbb{A}(P)$ consists of all matrices α such that $\alpha(x, y) = 0$ unless $x \leq y$ in P . By the definition of matrix multiplication,

$$(\alpha\beta)(x, y) = \sum_{z \in P} \alpha(x, z)\beta(z, y).$$

If $\alpha, \beta \in \mathbb{A}(P)$, then the above sum need be extended over only those z in the interval $[x, y] := \{x \leq z \leq y\}$. It is easily seen that $\mathbb{A}(P)$ is closed under multiplication, as well as addition and scalar multiplication.

An element of $\mathbb{A}(P)$ that will play an important role in the following theory is ζ (the *zeta function* of P) which is defined by

$$\zeta(x, y) = \begin{cases} 1 & \text{if } x \leq y \text{ in } P, \\ 0 & \text{otherwise.} \end{cases}$$

We claim that ζ is invertible and that its inverse, which is called the *Möbius function* of P and is denoted by μ , is integral and lies in $\mathbb{A}(P)$.

This is simple to verify. The equation $\mu\zeta = I$ (the identity)

requires that

$$(25.1) \quad \sum_{x \leq z \leq y} \mu(x, z) = \begin{cases} 1 & \text{if } x = y, \\ 0 & \text{otherwise,} \end{cases}$$

and this can be ensured by simply *defining* μ inductively, by declaring $\mu(x, x) := 1$, $\mu(x, y) := 0$ if $x \not\leq y$, and

$$(25.2) \quad \mu(x, y) := - \sum_{x \leq z < y} \mu(x, z) \quad \text{for } x < y \text{ in } P.$$

For example, when $P = \{1, 2, 3, 4, 6, 12\}$, the lattice of all (positive) divisors of the integer 12,

$$\zeta = \begin{pmatrix} 1 & 1 & 1 & 1 & 1 & 1 \\ 0 & 1 & 0 & 1 & 1 & 1 \\ 0 & 0 & 1 & 0 & 1 & 1 \\ 0 & 0 & 0 & 1 & 0 & 1 \\ 0 & 0 & 0 & 0 & 1 & 1 \\ 0 & 0 & 0 & 0 & 0 & 1 \end{pmatrix}, \quad \mu = \begin{pmatrix} 1 & -1 & -1 & 0 & 1 & 0 \\ 0 & 1 & 0 & -1 & -1 & 1 \\ 0 & 0 & 1 & 0 & -1 & 0 \\ 0 & 0 & 0 & 1 & 0 & -1 \\ 0 & 0 & 0 & 0 & 1 & -1 \\ 0 & 0 & 0 & 0 & 0 & 1 \end{pmatrix}.$$

The top row of μ was computed as follows:

$$\mu(1, 1) = +1,$$

$$\mu(1, 2) = -\mu(1, 1) = -1,$$

$$\mu(1, 3) = -\mu(1, 1) = -1,$$

$$\mu(1, 4) = -\mu(1, 1) - \mu(1, 2) = 0,$$

$$\mu(1, 6) = -\mu(1, 1) - \mu(1, 2) - \mu(1, 3) = +1,$$

$$\mu(1, 12) = -\mu(1, 1) - \mu(1, 2) - \mu(1, 3) - \mu(1, 4) - \mu(1, 6) = 0.$$

We remark that a somewhat different equation concerning μ results if we consider instead the relation $\zeta\mu = I$:

$$(25.3) \quad \sum_{x \leq z \leq y} \mu(z, y) = \begin{cases} 1 & \text{if } x = y, \\ 0 & \text{otherwise.} \end{cases}$$

Another much more complicated way of looking at the matter of the invertibility of ζ is as follows. We first remark that a finite

partial order can always be ‘dominated’ by a total order; that is, there exists an indexing $P = \{x_1, x_2, \dots, x_n\}$ such that $x_i \leq x_j$ in P implies that $i \leq j$. (Proof: Let x be any maximal element of P , index $P \setminus \{x\}$ by induction, and put x at the end.) With respect to such an indexing of P , the matrices in $\mathbb{A}(P)$ are upper triangular. The zeta function has 1’s on the diagonal and so has determinant 1 and hence an integral inverse by Cramer’s formula. Then $\zeta^{-1} = \mu$ lies in $\mathbb{A}(P)$ because the inverse of any matrix (or element of a finite-dimensional commutative algebra) is a polynomial in that matrix (or element).

The equation (25.2) implies that $\mu(x, y) = -1$ if $x < y$. Also note that $\mu(x, y) = k - 1$ if the interval $[x, y]$ is a k -point line, i.e. the interval consists of x , y , and k pairwise noncomparable elements z_1, \dots, z_k , each with $x < z_i < y$.

In the following theorem, we list the values of the Möbius function of some common partially ordered sets. The proof of Theorem 25.1 will not be given until the end of the chapter because we wish to talk about the implications of Möbius inversion first. Clever and/or industrious readers will be able to prove some parts of Theorem 25.1 with the recursion (25.2) and simple induction arguments, but we prefer to wait until we have Weisner’s theorem, Theorem 25.3, available. We do not prove part (v) here—see the notes.

Theorem 25.1. (i) For the lattice of all subsets of an n -set X ,

$$\mu(A, B) = \begin{cases} (-1)^{|B|-|A|} & \text{if } A \subseteq B, \\ 0 & \text{otherwise.} \end{cases}$$

(ii) For the lattice of all (positive) divisors of an integer n ,

$$\mu(a, b) = \begin{cases} (-1)^r & \text{if } \frac{b}{a} \text{ is the product of } r \text{ distinct primes,} \\ 0 & \text{otherwise, i.e. if } a \nmid b \text{ or } \frac{b}{a} \text{ is not squarefree.} \end{cases}$$

(That is, $\mu(a, b) = \mu(\frac{b}{a})$ where the latter μ is the classical function of a single variable in (10.8).)

(iii) For the lattice of all subspaces of a finite-dimensional vector space V over the field \mathbb{F}_q of q elements,

$$\mu(U, W) = \begin{cases} (-1)^k q^{\binom{k}{2}} & \text{if } U \subseteq W \text{ and } \dim(W) - \dim(U) = k, \\ 0 & \text{if } U \not\subseteq W. \end{cases}$$

(iv) For the lattice Π_n of all partitions of an n -set X ,

$$\mu(\mathcal{A}, \mathcal{B}) = (-1)^{|\mathcal{A}|-|\mathcal{B}|} \prod_{B \in \mathcal{B}} (n_B - 1)!$$

for elements \mathcal{A} and \mathcal{B} of Π_n with $\mathcal{A} \preceq \mathcal{B}$, where n_B denotes the number of blocks of \mathcal{A} that are contained in a block B of \mathcal{B} .

(v) For the lattice of faces of a convex polytope,

$$\mu(A, B) = \begin{cases} (-1)^{\dim(B)-\dim(A)} & \text{if } A \subseteq B, \\ 0 & \text{otherwise.} \end{cases}$$

We now state the principle of *Möbius inversion*. Let P be a finite partially ordered set and μ its Möbius function. Let $f, g, h : P \rightarrow \mathbb{R}$ (or into any additive group) be functions such that the relations

$$g(x) = \sum_{a:a \leq x} f(a) \quad \text{and} \quad h(x) = \sum_{b:b \geq x} f(b)$$

hold for all $x \in P$. Then, for all $x \in P$,

$$(25.4) \quad f(x) = \sum_{a:a \leq x} \mu(a, x)g(a),$$

and

$$(25.5) \quad f(x) = \sum_{b:b \geq x} \mu(x, b)h(b).$$

These are readily verified by direct substitution. For example, the right-hand side of (25.4) is

$$\sum_{a:a \leq x} \mu(a, x) \left(\sum_{b:b \leq a} f(b) \right) = \sum_{b:b \leq x} f(b) \left(\sum_{a:b \leq a \leq x} \mu(a, x) \right).$$

But the inner sum on the right is zero by (25.3) unless $b = x$, so only the term $f(x)$ survives. Or, in matrix notation (when we regard

f , g , and h as row or column vectors—whichever is appropriate—whose coordinates are indexed by P), the relations assumed for g and h are equivalent to $g = \zeta f$, so $f = \mu g$, and $h = f\zeta$, so $f = h\mu$.

When the principle of Möbius inversion is applied to the lattice of subsets of a set X , we recover inclusion-exclusion. Let $(A_i : i \in I)$ be a finite family of subsets of a finite set X . For $J \subseteq I$, let $f(J)$ equal the number of elements of X that belong to *exactly* the sets A_j with $j \in J$ and to no others. (Think of the size of one of the regions in a Venn diagram of the sets.) Let $g(J)$ equal the number of elements in $\bigcap_{j \in J} A_j$. Then $g(J) = \sum_{K: J \subseteq K} f(K)$, so Möbius inversion gives

$$f(J) = \sum_{K: J \subseteq K} (-1)^{|K \setminus J|} g(K).$$

In the case $J = \emptyset$, the above can be written

$$|X - \bigcup_{i \in I} A_i| = \sum_{K \subseteq I} (-1)^{|K|} \left| \bigcap_{j \in K} A_j \right|,$$

which is a cryptic way of stating inclusion-exclusion.

When the principle of Möbius inversion is applied to the lattice of (positive) divisors of an integer n , we recover the classical number-theoretic Möbius inversion. If f and g satisfy

$$g(m) = \sum_{k|m} f(k) \quad \text{for all } m \text{ dividing } n,$$

then Möbius inversion gives

$$f(m) = \sum_{k|m} \mu(k, m) g(k) \quad \text{for all } m \text{ dividing } n,$$

and this, in view of Theorem 25.1(ii), is equivalent to Theorem 10.4.

We give a q -analogue of Example 10.2, where we used inclusion-exclusion to find the expression $\sum_{k=0}^m (-1)^{m-k} \binom{m}{k} k^n$ for the number of surjections from an n -set to an m -set.

Theorem 25.2. *The number of surjective linear transformations from an n -dimensional vector space to an m -dimensional vector space V over \mathbb{F}_q is*

$$\sum_{k=0}^m (-1)^{m-k} \begin{bmatrix} m \\ k \end{bmatrix}_q q^{nk + \binom{m-k}{2}}.$$

PROOF: For a subspace $U \subseteq V$, let $f(U)$ denote the number of linear transformations whose image is U . Let $g(U)$ denote the number of linear transformations whose image is contained in U . Clearly,

$$g(U) = \sum_{W:W \subseteq U} f(W)$$

and $g(U)$ is q^{nr} if $\dim(U) = r$. By Möbius inversion on the lattice of subspaces of V ,

$$f(U) = \sum_{W:W \subseteq U} \mu(W, U) q^{n \dim(W)}.$$

Take $U = V$ and use Theorem 25.1(iii) to produce the stated result. \square

Corollary. *The number of $n \times m$ matrices over the field \mathbb{F}_q that have rank r is*

$$\begin{bmatrix} m \\ r \end{bmatrix}_q \sum_{k=0}^r (-1)^{r-k} \begin{bmatrix} r \\ k \end{bmatrix}_q q^{nk + \binom{r-k}{2}}.$$

We note that the number of injective linear transformations has a relatively simple form. If we fix a basis for an n -dimensional vector space and consider injections into an m -dimensional vector space, the image of the i -th basis vector must be chosen as one of the $(q^m - q^{i-1})$ vectors not in the span of the images of the previous basis vectors. In summary, there are $(q^m - 1)(q^m - q) \cdots (q^m - q^{n-1})$ injective linear transformations. Since Theorem 25.2 with $m = n$ also gives an expression for this number, we have proved an identity.

Problem 25A. (i) Use Möbius inversion to derive an expression for the number of k -subspaces that meet trivially a given r -subspace of an n -dimensional vector space over \mathbb{F}_q . This should give a q -analogue to Eq. (10.5). (ii) For the special case when $r + k = n$, show, from another point of view, that there are exactly q^{rk} such subspaces by consideration of $r \times n$ matrices over \mathbb{F}_q of the form $(I M)$, where I is an identity of order r .

Problem 25B. Use Möbius inversion to derive an expression for the number of nonsingular linear mappings of an n -dimensional vector space over \mathbb{F}_q to itself that fix no vectors other than $\mathbf{0}$, i.e. that do not have 1 as an eigenvalue. (These will be orthomorphisms of the additive group; see the Remarks following Theorem 22.9.)

* * *

The partially ordered sets mentioned in the statement of Theorem 25.1 are all lattices. The following useful theorem was found by L. Weisner (1935).

Theorem 25.3. *Let μ be the Möbius function of a finite lattice L and let $a \in L$ with $a > 0_L$. Then*

$$\sum_{x: x \vee a = 1_L} \mu(0_L, x) = 0.$$

PROOF: Fix a and consider

$$S := \sum_{x, y \in L} \mu(0, x) \zeta(x, y) \zeta(a, y) \mu(y, 1) = \sum_{x \in L} \sum_{\substack{y \geq x, \\ y \geq a}} \mu(0, x) \mu(y, 1).$$

Now on the one hand,

$$S = \sum_x \mu(0, x) \sum_{\substack{y \geq x \\ y \geq a}} \mu(y, 1);$$

but $y \geq a$ and $y \geq x$ if and only if $y \geq x \vee a$, and the inner sum is

$$\sum_{y \geq x \vee a} \mu(y, 1) = \begin{cases} 1 & \text{if } x \vee a = 1, \\ 0 & \text{if } x \vee a < 1. \end{cases}$$

Thus S is the sum in the statement of the theorem. On the other hand,

$$S = \sum_{y \geq a} \mu(y, 1) \sum_{0 \leq x \leq y} \mu(0, x),$$

and the inner sum is always 0 since $y > 0$. □

Corollary. For elements x, y of a geometric lattice L with $x \leq y$, $\mu(x, y)$ has sign $(-1)^{\text{rank}(y) - \text{rank}(x)}$ and, in particular, is never 0.

PROOF: We show that $\mu(0_L, 1_L)$ has sign $(-1)^{\text{rank}(L)}$ by induction on the rank of L . Pick a point $p \in L$. By semimodularity, $a \vee p = 1_L$ if and only if $a = 1_L$ or a is a copoint not on p ; so Weisner's theorem, Theorem 25.3, gives

$$(25.6) \quad \mu(0_L, 1_L) = - \sum_{h: h < 1_L, h \not\geq p} \mu(0_L, h).$$

Since all terms on the right-hand side have sign $(-1)^{\text{rank}(L)-1}$ by the induction hypothesis, the proof is complete. □

The number of proper colorings $\chi_G(x)$ of a graph G with x colors can be found by Möbius inversion on the lattice $L(G)$ introduced in Chapter 23, although this is not necessarily a very practical method. Recall that the elements of $L(G)$ are the partitions \mathcal{A} of the vertex set of G , all of whose blocks induce connected subgraphs of G . For \mathcal{A} in $L(G)$, let $g(\mathcal{A})$ denote the number of mappings from the vertex set of G into a set of x colors (i.e. colorings) so that all vertices in each block of \mathcal{A} receive the same color. Clearly, $g(\mathcal{A}) = x^{|\mathcal{A}|}$. Let $f(\mathcal{A})$ denote the number of mappings that are constant on each block of \mathcal{A} , but such that the endpoints of edges joining distinct blocks of \mathcal{A} receive different colors. Given a coloring 'counted by' $g(\mathcal{A})$, a moment's thought shows that there is a unique coarser partition \mathcal{B} so that the coloring is 'counted by' $f(\mathcal{B})$ (one must coalesce two blocks of \mathcal{A} of the same color if an edge joins them). Thus, $g(\mathcal{A}) = \sum_{\mathcal{B} \succeq \mathcal{A}} f(\mathcal{B})$, so Möbius inversion gives

$$f(\mathcal{A}) = \sum_{\mathcal{B} \succeq \mathcal{A}} \mu(\mathcal{A}, \mathcal{B}) g(\mathcal{B}).$$

The number of proper colorings is f evaluated on $0_{L(G)}$ (the partition into singletons), and this is

$$\chi_G(x) = \sum_{\mathcal{B}} \mu(0_{L(G)}, \mathcal{B}) x^{|\mathcal{B}|} = \sum_{k=1}^n \left(\sum_{|\mathcal{B}|=k} \mu(0_{L(G)}, \mathcal{B}) \right) x^k.$$

The polynomial $\chi_G(x)$ is called the *chromatic polynomial* of the graph. The corollary above leads directly to the following statement.

Theorem 25.4. *The number of proper colorings of a graph G on n vertices in x colors is given by a monic polynomial $\chi_G(x)$ of degree n whose coefficients alternate in sign.*

Problem 25C. Let G be a simple graph with n vertices and m edges. Show that the coefficient of x^{n-1} in $\chi_G(x)$ is $-m$, and that the coefficient of x^{n-2} is $m(m-1)/2$ minus the number of triangles in G .

T. Dowling and R. M. Wilson (1975) proved the following theorem and its corollary, the latter being a generalization of the inequality of Theorem 19.1 on linear spaces.

Theorem 25.5. *If L is a finite lattice so that $\mu(x, 1_L) \neq 0$ for all $x \in L$, then there exists a permutation π of the elements of L so that $x \vee \pi(x) = 1_L$ for all $x \in L$.*

PROOF: Before we begin the proof, we remark that an example of a lattice that does not satisfy our hypothesis is a chain with more than two elements. And, of course, there is no permutation π with the property stated above. On the other hand, the lattice of all subsets of an n -set admits a unique permutation with the property above, namely the permutation that takes each subset to its complement.

All matrices here will have rows and columns indexed by L . Let

$$\eta(x, y) := \begin{cases} 1 & \text{if } x \vee y = 1_L, \\ 0 & \text{otherwise.} \end{cases}$$

Let δ_1 be the diagonal matrix with $\delta_1(x, x) := \mu(x, 1_L)$. Then $\zeta\delta_1\zeta^\top = \eta$ because

$$\begin{aligned}\zeta\delta_1\zeta^\top(x, y) &= \sum_{a,b} \zeta(x, a)\delta_1(a, b)\zeta(y, b) \\ &= \sum_{a:a \geq x \text{ and } a \geq y} \delta_1(a, a) \\ &= \sum_{a:a \geq x \vee y} \mu(a, 1_L)\end{aligned}$$

and the last sum is, by (25.1), 1 if $x \vee y = 1_L$, and 0 otherwise.

Under our hypothesis that $\mu(x, 1_L) \neq 0$, the matrix δ_1 is nonsingular. Since ζ is nonsingular too, we conclude that η is also. Hence some term in its determinant expansion does not vanish, and this implies the conclusion of the theorem. \square

Corollary. *In a finite geometric lattice of rank n , the number of elements of rank $\geq n - k$ is at least the number of elements of rank $\leq k$, $0 \leq k \leq n$.*

PROOF: Consider a permutation π as in Theorem 25.5 (which applies because of the Corollary to Theorem 25.3). The semimodular law

$$\text{rank}(x) + \text{rank}(\pi(x)) \geq \text{rank}(x \vee \pi(x)) + \text{rank}(x \wedge \pi(x)) \geq n$$

implies that the image of an element of rank $\leq k$ is one of rank $\geq n - k$. \square

We give a similar matrix proof of a theorem of T. Dowling (1977) on *complementing permutations* below.

Theorem 25.6. *If L is a finite lattice such that $\mu(x, 1_L) \neq 0$ and $\mu(0_L, x) \neq 0$ for all $x \in L$, then there exists a permutation π of the elements of L so that*

$$x \vee \pi(x) = 1_L \quad \text{and} \quad x \wedge \pi(x) = 0_L$$

for all $x \in L$.

PROOF: Let δ_1 be as in the proof of the previous theorem and let δ_0 be the diagonal matrix with $\delta_0(x, x) := \mu(0_L, x)$. Now consider

$\kappa := \zeta \delta_1 \zeta^\top \delta_0 \zeta$. Our hypotheses imply that κ is nonsingular. We claim that $\kappa(x, y) = 0$ unless x and y are complements. Then any permutation corresponding to a nonvanishing term in the determinant expansion of κ will be a complementing permutation.

To establish our claim, first note that $\kappa = \eta \delta_0 \zeta$, so

$$\kappa(x, y) = \sum_{z: z \vee x = 1_L, z \leq y} \mu(0_L, z).$$

If this sum is not zero, then there exists some z with $z \vee x = 1_L$ and $z \leq y$, which implies that $y \vee x = 1_L$. By duality, $\eta' = \zeta^\top \delta_0 \zeta$, where

$$\eta'(x, y) := \begin{cases} 1 & \text{if } x \wedge y = 0_L, \\ 0 & \text{otherwise.} \end{cases}$$

Now note that $\kappa = \zeta \delta_1 \eta'$ and, similarly, $\kappa(x, y) \neq 0$ will imply that $x \wedge y = 0_L$. \square

Finally, we give the proof we promised at the beginning of the chapter.

PROOF OF THEOREM 25.1: (i) Since the interval $[A, B]$ is isomorphic to the lattice of subsets of $B \setminus A$, it suffices to show $\mu(\emptyset, C) = (-1)^{|C|}$. We use the equation (25.6) and proceed by induction on $|C|$. Let p be a point of C . There is only one copoint not on p , namely the complement of $\{p\}$. So (25.6) implies that

$$\mu(\emptyset, C) = -\mu(\emptyset, C \setminus \{p\}) = -(-1)^{(|C|-1)} = (-1)^{|C|}.$$

(ii) Again, it will suffice to calculate $\mu(1, m)$, and we use induction on m . Let p be a prime divisor of m . Weisner's theorem asserts

$$\mu(1, m) = - \sum_{\text{lcm}(a,p)=m, a < m} \mu(0, a).$$

If p^2 divides m , then the sum on the right is empty, and thus $\mu(1, m) = 0$. If p^2 does not divide m , then there is one term, namely when $a = m/p$.

(iii) It will suffice to show that $\mu(0, V) = (-1)^k q^{\binom{k}{2}}$ for V of dimension k . We proceed by induction on k . Let P be a 1-dimensional subspace of V . By Weisner's theorem,

$$\mu(0, V) = - \sum_{U: U \vee P = V, U \neq V} \mu(0, U).$$

By the induction hypothesis, each term $\mu(0, U)$ in the above sum is equal to $(-1)^{k-1} q^{\binom{k-1}{2}}$. The only subspaces U other than V such that $U \vee P = V$ are those U of dimension $k-1$ that do not contain P ; their number is

$$\begin{bmatrix} k \\ 1 \end{bmatrix}_q - \begin{bmatrix} k-1 \\ 1 \end{bmatrix}_q = q^{k-1}.$$

This completes the proof of part (iii).

(iv) Consider two partitions \mathcal{A} and \mathcal{B} with $\mathcal{A} \preceq \mathcal{B}$. Say \mathcal{B} has k blocks that, when numbered, are the unions of n_1, n_2, \dots, n_k blocks of \mathcal{A} , respectively. Then the interval $[\mathcal{A}, \mathcal{B}]$ is isomorphic to the direct product of partition lattices

$$\Pi_{n_1} \times \Pi_{n_2} \times \cdots \times \Pi_{n_k},$$

since a partition \mathcal{C} with $\mathcal{A} \preceq \mathcal{C} \preceq \mathcal{B}$ is specified by a partition of the n_i blocks of \mathcal{A} that lie in the i -th block of \mathcal{B} , for each $i = 1, 2, \dots, k$.

We now mention the fact that the Möbius function $\mu_{P \times Q}$ of the direct product $P \times Q$ of two partially ordered sets is the (Kronecker or tensor) product of the Möbius functions μ_P and μ_Q of P and Q ; that is,

$$\mu_{P \times Q}((a_1, b_1), (a_2, b_2)) = \mu_P(a_1, a_2) \mu_Q(b_1, b_2).$$

(We leave the reader to think about this; just check that defining $\mu_{P \times Q}$ as above produces an inverse of $\zeta_{P \times Q}$.) Thus $\mu(\mathcal{A}, \mathcal{B})$ is the product of $\mu(0_{\Pi_{n_i}}, 1_{\Pi_{n_i}})$ for $i = 1, 2, \dots, k$.

We now show that $\mu(0_{\Pi_n}, 1_{\Pi_n}) = (-1)^{n-1} (n-1)!$ by induction on n . Let \mathcal{P} be a point of Π_n , i.e. a partition of an n -set into a 2-set

$\{x, y\}$ and $n - 2$ singletons. The partitions \mathcal{A} so that $\mathcal{P} \vee \mathcal{A} = 1_{\Pi_n}$ are the 2^{n-2} partitions with two blocks that separate x and y ; there are $\binom{n-2}{i}$ such partitions where the block containing x has size $i + 1$ and the block containing y has size $n - 1 - i$. From (25.6) and the induction hypothesis,

$$\begin{aligned} \mu(0_{\Pi_n}, 1_{\Pi_n}) &= - \sum_{i=0}^{n-2} \binom{n-2}{i} (-1)^i (i)! (-1)^{n-2-i} (n-2-i)! \\ &= (-1)^{n-1} (n-1)!. \end{aligned}$$

□

Problem 25D. The *dual* of Weisner's theorem (derived by applying Theorem 25.3 to the dual lattice) asserts

$$\sum_{x: x \wedge a = 0_L} \mu(x, 1_L) = 0 \quad \text{for all } a \in L \text{ with } a < 1_L.$$

Take a to be a partition with one block of size $n - 1$ and one of size 1 (in the partition lattice) and use the above to give a somewhat different proof of $\mu(0_{\Pi_n}, 1_{\Pi_n}) = (-1)^{n-1} (n - 1)!$.

We use Möbius inversion over the lattice of partitions to get an expression for the number of connected labeled simple graphs on n vertices. Let X be an n -set. To each graph G with vertex set X , there corresponds the partition \mathcal{C}_G of X whose blocks are the vertex sets of the connected components of G . We let $g(\mathcal{B})$ denote the number of simple graphs G with $V(G) = X$ and $\mathcal{C}_G = \mathcal{B}$. We let $f(\mathcal{B})$ denote the number of simple graphs G with $V(G) = X$ and where \mathcal{C}_G is a refinement of \mathcal{B} . Clearly,

$$f(\mathcal{B}) = \sum_{\mathcal{A} \preceq \mathcal{B}} g(\mathcal{A}).$$

We are interested in $g(1_{\Pi_n})$, where 1_{Π_n} is the partition with one block. But what is easy to calculate is $f(\mathcal{B})$; we get a graph counted by $f(\mathcal{B})$ by arbitrarily choosing a simple graph on each block of \mathcal{B} , so if \mathcal{B} has k_i blocks of size i , then

$$f(\mathcal{B}) = 2^{k_2 \binom{2}{2}} 2^{k_3 \binom{3}{2}} \dots 2^{k_n \binom{n}{2}}.$$

By Möbius inversion,

$$g(\mathcal{B}) = \sum_{\mathcal{A} \preceq \mathcal{B}} \mu(\mathcal{A}, \mathcal{B}) f(\mathcal{A}).$$

Specializing to $\mathcal{B} = 1_{\Pi_n}$, we have

$$(25.7) \quad g(1_{\Pi_n}) = \sum_{\mathcal{A}} \mu(\mathcal{A}, 1_{\Pi_n}) f(\mathcal{A}).$$

Recall that the number of partitions of X of type (k_1, k_2, \dots, k_n) is

$$\frac{n!}{(1!)^{k_1} k_1! (2!)^{k_2} k_2! \cdots (n!)^{k_n} k_n!};$$

cf. (13.3). And using Theorem 25.1(iv), we find the number of connected labeled graphs on n vertices to be

$$\sum (-1)^{k_1+k_2+\cdots+k_n-1} \frac{n! (k_1 + \cdots + k_n - 1)!}{(1!)^{k_1} k_1! \cdots (n!)^{k_n} k_n!} 2^{k_2 \binom{2}{2} + k_3 \binom{3}{2} + \cdots + k_n \binom{n}{2}}$$

where the summation is extended over all partitions (k_1, k_2, \dots, k_n) of the integer n , that is all nonnegative n -tuples with $1k_1 + 2k_2 + \cdots + nk_n = n$.

We do not mean to imply that this is a particularly nice answer to our original question. Indeed, it is a summation over a large collection of objects, whose number exceeds $e^{\sqrt{n}}$ for large n . But it is a natural illustration of Möbius inversion and does greatly reduce the problem. For $n = 5$, we have

partition of 5	number of \mathcal{A}	$f(\mathcal{A})$	$\mu(\mathcal{A}, 1_{\Pi_5})$
5	1	1024	1
41	5	64	-1
32	10	16	-1
311	10	8	2
221	15	4	2
2111	10	2	-6
11111	1	1	24

from which table and (25.7) we see that 728 out of the 1024 simple labeled graphs on 5 vertices are connected.

* * *

We give an application of Möbius inversion to coding theory. Recall the definition of MDS codes given in Example 20.3. Let C be such a code, i. e. an $[n, k, d]$ code over \mathbb{F}_q with $d = n - k + 1$. If we consider a set of d positions and then look at the subcode of C with zeros in all other positions, this subcode has dimension $\geq k - (n - d) = 1$. Since this subcode has minimum distance d , it must have dimension exactly 1 by Theorem 20.2. It follows that for $n \geq d' > d$, specifying a set of d' positions and requiring codewords to be zero in all other positions, will define a subcode of C with dimension $d' - d + 1$. We use this in the proof below. We shall show that the weight enumerator of an MDS code is determined by its parameters.

Theorem 25.7. *Let C be an $[n, k]$ code over \mathbb{F}_q with distance $d = n - k + 1$. Then the weight enumerator of C is $1 + \sum_{i=d}^n A_i z^i$, where*

$$A_i = \binom{n}{i} (q-1) \sum_{j=0}^{i-d} (-1)^j \binom{i-1}{j} q^{i-j-d}, \quad i = d, d+1, \dots, n.$$

PROOF: Let R be a subset of $N := \{0, 1, \dots, n\}$. Define $f(R)$ to be the number of codewords $(c_0, c_1, \dots, c_{n-1})$ for which $\{i : c_i \neq 0\} = R$. For a subset S of N , we define $g(S) := \sum_{R \subseteq S} f(R)$. As remarked above, we have

$$g(S) = \begin{cases} 1, & \text{if } |S| \leq d-1, \\ q^{|S|-d+1}, & \text{if } n \geq |S| \geq d. \end{cases}$$

The definition of f implies that $A_i = \sum_{R \subseteq N, |R|=i} f(R)$. We now

apply Möbius inversion with Theorem 25.1 (i). We find

$$\begin{aligned}
 A_i &= \sum_{R \subseteq N, |R|=i} \sum_{S \subseteq R} \mu(S, R) g(S) \\
 &= \binom{n}{i} \left\{ \sum_{j=0}^{d-1} \binom{i}{j} (-1)^{i-j} + \sum_{j=d}^i \binom{i}{j} (-1)^{i-j} q^{j-d+1} \right\} \\
 &= \binom{n}{i} \sum_{j=d}^i \binom{i}{j} (-1)^{i-j} (q^{j-d+1} - 1).
 \end{aligned}$$

The result follows if we replace j by $i - j$ and then use $\binom{i}{j} = \binom{i-1}{j-1} + \binom{i-1}{j}$. \square

Theorem 25.7 implies rather severe restrictions on the alphabet size of an MDS code.

Corollary. *If there exists an MDS code C over \mathbb{F}_q with length n and dimension k , then*

$$\begin{cases} \text{(i)} & q \geq n - k + 1 \text{ or } k \leq 1, \\ \text{(ii)} & q \geq k + 1 \text{ or } d = n - k + 1 \leq 2. \end{cases}$$

PROOF: (i) Let $d = n - k + 1$. From Theorem 25.7 we find for $d < n$ that

$$0 \leq A_{d+1} = \binom{n}{d+1} (q-1)(q-d).$$

(ii) Let $G := (I_k P)$ be the generator matrix of C . Since C has minimum weight d , every set of $d-1 = n-k$ columns of the parity check matrix $H := (-P^\top I_{n-k})$ is linearly independent. Hence every square submatrix of H is nonsingular. So, no codeword of C^\perp has $n-k$ zeros, i.e. C^\perp is also MDS. Apply the result of (i) to C^\perp . \square

Problem 25E. Let P be a partially ordered set. Remember that if $x < y$, then a sequence $x = x_0 < x_1 < \cdots < x_k = y$ is called a *chain* of length k from x to y . Let $c_k(x, y)$ denote the number of such chains (so $c_1(x, y) = 1$). Prove that

$$\mu(x, y) = \sum_{k \geq 1} (-1)^k c_k(x, y).$$

Problem 25F. We consider the lattice of subspaces of the vector space $V := \mathbb{F}_q^n$. Let S be another vector space over \mathbb{F}_q . Define for a subspace U :

$f(U) :=$ the number of linear maps from V to S with kernel U ,

$g(U) :=$ the number of linear maps from V to U with kernel $\supseteq U$.

(i) Determine $g(U)$ and then apply Möbius inversion to

$$g(U) = \sum_{W:W \supseteq U} f(W).$$

(ii) Show that

$$f(\{\mathbf{0}\}) = \sum_{k=0}^n \begin{bmatrix} n \\ k \end{bmatrix}_q (-1)^k q^{\binom{k}{2}} |S|^{n-k}.$$

(iii) Prove the polynomial identity

$$\prod_{k=0}^{n-1} (x - q^k) = \sum_{k=0}^n (-1)^k \begin{bmatrix} n \\ k \end{bmatrix}_q q^{\binom{k}{2}} x^{n-k}.$$

Notes.

The expression of the chromatic polynomial of a graph in terms of the Möbius function of $L(G)$ is due to G.-C. Rota (1964).

Theorem 25.1 (v) is essentially Euler's formula for polytopes:

$$f_0 - f_1 + f_2 - f_3 + \cdots + (-1)^n f_n = 0,$$

where f_i is the number of faces of rank i , or dimension $i - 1$ ($f_0 = f_n = 1$). See B. Grünbaum (1967). Also see R. Stanley (1986), where posets with the property that $\mu(x, y) = (-1)^d$ whenever the ranks of x and y differ by d are called *Eulerian* posets.

References.

T. Dowling (1977), A note on complementing permutations, *J. Combinatorial Theory* (B) **23**, 223–226.

- T. Dowling and R. M. Wilson (1975), Whitney number inequalities for geometric lattices, *Proc. Amer. Math. Soc.* **47**, 504–512.
- B. Grünbaum (1967), *Convex Polytopes*, J. Wiley (Interscience).
- G.-C. Rota (1964), On the foundations of combinatorial theory
I. Theory of Möbius functions, *Z. Wahrscheinlichkeitstheorie* **2**, 340–368.
- R. P. Stanley (1986), *Enumerative Combinatorics*, Vol. 1, Wadsworth.
- L. Weisner (1935), Abstract theory of inversion of finite series, *Trans. Amer. Math. Soc.* **38**, 474–484.

26

Combinatorial designs and projective geometries

Geometries over finite fields are a rich source of combinatorial designs and related combinatorial configurations. We begin with two topics (arcs and subplanes) that we choose to mention only in projective planes before going on to discuss quadrics and other configurations in general projective spaces.

An (m, k) -arc in a projective plane is a set of m points, no $k + 1$ of which are collinear. We were concerned with $(m, 2)$ -arcs in Problem 19I.

Let A be an (m, k) -arc in a projective plane of order n and let x be a point in A . The $n + 1$ lines on x each contain at most $k - 1$ other points of A , so

$$m \leq 1 + (n + 1)(k - 1).$$

An (m, k) -arc A is called *perfect* when equality holds above. Any line that contains a point of a perfect (m, k) -arc evidently contains exactly k points of the arc; that is,

$$|L \cap A| = 0 \text{ or } k$$

for any line L . Clearly, the nonempty intersections of lines with a perfect (m, k) -arc provide the blocks of a Steiner system $S(2, k, m)$.

A single point is a perfect $(1, 1)$ -arc. The set of n^2 points not on a fixed line of a projective plane of order n is a perfect (n^2, n) -arc and the corresponding Steiner system is an affine plane of order n . The hyperovals in Problem 19I are perfect $(q + 2, 2)$ -arcs. The corresponding designs are trivial. But these have ‘dual’ arcs where the corresponding Steiner systems are interesting—see Problem 26A.

The construction of perfect (m, k) -arcs in Desarguesian planes of even order given in part (2) of the following theorem is due to R. H. F. Denniston (1969). No examples of perfect (m, k) -arcs, $1 < k < n$, in projective planes of odd orders n are known at this time.

Theorem 26.1.

- (1) *If there exists a perfect (m, k) -arc in a projective plane of order n , then k divides n .*
- (2) *If q is a power of 2 and k divides q , then there exists a perfect (m, k) -arc in $PG_2(q)$.*

PROOF: Let x be a point not in a perfect (m, k) -arc A in a projective plane of order n . The lines on x partition the remaining points, but each line on x contains exactly 0 or k points of A . So k must divide $m = 1 + (n + 1)(k - 1)$. It follows that k divides n .

Now let q be a power of 2 and k a divisor of q . Let $f(x, y) = \alpha x^2 + \beta xy + \gamma y^2$ be any irreducible quadratic over \mathbb{F}_q , and let H be any subgroup of the additive group of \mathbb{F}_q with order k . In the affine plane $AG(2, q)$, let

$$A := \{(x, y) : f(x, y) \in H\}.$$

We claim that any (affine) line meets A in 0 or k points. When the affine plane is embedded in a $PG_2(q)$, A will be a perfect (m, k) -arc.

Consider a line $L = \{(x, y) : y = mx + b\}$ with b and m both nonzero. (We leave consideration of lines of the forms $\{(x, y) : y = mx\}$ and $\{(x, y) : x = c\}$ to the reader.)

The intersection $L \cap A$ is the set of points $(x, mx + b)$, where

$$\alpha x^2 + \beta x(mx + b) + \gamma(mx + b)^2 \in H, \quad \text{or}$$

$$F(x) \in H, \quad \text{where} \quad F(x) := (\alpha + \beta m + \gamma m^2)x^2 + \beta bx + \gamma b^2.$$

We are working over a field of characteristic 2, so

$$x \mapsto (\alpha + \beta m + \gamma m^2)x^2 + \beta bx$$

is a linear mapping; it has kernel of order 2 since the irreducibility of $f(x, y)$ ensures that both β and the coefficient of x^2 are nonzero.

The image K_F of this mapping is thus a subgroup of order $q/2$ of the additive group of \mathbb{F}_q . The image of F is a coset of K_F , but since $F(x)$ is never 0 (again by the irreducibility of $f(x, y)$), the image of F is the complement $\mathbb{F}_q \setminus K_F$. In summary,

$$|\{x : F(x) = a\}| = \begin{cases} 2 & \text{if } x \notin K_F, \\ 0 & \text{if } x \in K_F. \end{cases}$$

Thus $|L \cap A| = 2|H \cap (\mathbb{F}_q \setminus K_F)|$. The subgroup H is either contained in K_F , in which case $L \cap A = \emptyset$, or intersects K_F in a subgroup of order $k/2$, in which case $|L \cap A| = k$. \square

As a corollary of this theorem (with $n = 2^{m+1}$, $k = 2^m$), we obtain Steiner systems

$$S(2, 2^m, 2^{2m+1} - 2^m).$$

Steiner systems $S(2, k, v)$ are in many ways most interesting when v is close to k^2 , as is the case for affine and projective planes (Fisher's inequality, Theorem 19.6, shows $v \geq k^2 - k + 1$). These examples have $v < 2k^2$, which is still impressive.

Problem 26A. Let A be a perfect (m, k) -arc in a projective plane P of order n , $1 \leq k \leq n$. Let A^* be the set of lines that do not meet A . Show that A^* is a perfect $(m^*, [n/k])$ -arc in the dual plane P^* , and calculate m^* in terms of m, k, n .

Problem 26B. A *parallel class* in a Steiner system $S(2, k, m)$ is a set \mathcal{A} of m/k blocks so that each point is incident with exactly one block in \mathcal{A} . An $S(2, k, m)$ is *resolvable* when the blocks can be partitioned into parallel classes (cf. Problem 19K).

Let A be a perfect (m, k) -arc in a projective plane P of order n . Explain why the Steiner system $S(2, k, m)$ whose blocks are the nontrivial intersections of lines with A is resolvable.

A *subplane* \mathbf{S} of a projective plane \mathbf{P} is a substructure of \mathbf{P} that is a projective plane in its own right. Recall that a *substructure* of an incidence structure $(\mathcal{P}, \mathcal{B}, \mathbf{I})$ is an incidence structure $(\mathcal{P}_0, \mathcal{B}_0, \mathbf{I}_0)$ where $\mathcal{P}_0 \subseteq \mathcal{P}$, $\mathcal{B}_0 \subseteq \mathcal{B}$, and $\mathbf{I}_0 = \mathbf{I} \cap (\mathcal{P}_0 \times \mathcal{B}_0)$. Note that given an automorphism (or *collineation*) α of a projective plane \mathbf{P} , the

substructure \mathbf{S} consisting of the points of \mathbf{P} fixed by α and the lines of \mathbf{P} fixed by α has the property that two points of \mathbf{S} are incident with a unique line of \mathbf{S} , and two lines of \mathbf{S} are incident with a unique point of \mathbf{S} . If \mathbf{S} contains four points, no three collinear, then \mathbf{S} is a subplane; but it may be a nearpencil or have one or no lines.

Example 26.1. Let $V := \mathbb{F}_q^3$. The points and lines of $PG_2(q^n)$ are the 1-dimensional and 2-dimensional \mathbb{F}_{q^n} -subspaces of V . Define a substructure \mathbf{S} of $PG_2(q^n)$ whose points and lines are those 1- and 2-dimensional \mathbb{F}_{q^n} -subspaces of V that admit bases consisting of vectors whose entries are in the subfield \mathbb{F}_q . Then \mathbf{S} is a subplane. A line of \mathbf{S} is incident with $q^n + 1$ points in $PG_2(q^n)$, but only $q + 1$ of those are points of \mathbf{S} .

Theorem 26.2. *If a projective plane \mathbf{P} of order n contains a subplane \mathbf{S} of order $m < n$, then either*

- (i) $n = m^2$, or
- (ii) $n \geq m^2 + m$.

PROOF: Let L be a line of the subplane \mathbf{S} and x a point on L in \mathbf{P} but not in \mathbf{S} . The n other lines on x can contain at most one point of \mathbf{S} (since a line M in \mathbf{P} containing at least two points of \mathbf{S} would necessarily belong to the subplane, and then the point x in common to M and L would also belong to the subplane). The line L contains $m + 1$ points of \mathbf{S} , which has a total of $m^2 + m + 1$ points, each of which is on some line through x , so $m^2 \leq n$.

Equality will imply that every line of \mathbf{P} will meet \mathbf{S} (evidently in one or $m + 1$ points) since if there were a line N disjoint from \mathbf{S} , and x were taken as the point of intersection of L and N , each of the m^2 points of \mathbf{S} not on L would belong to one of $n - 1$ lines.

Now assume $m^2 < n$, so that there does exist a line N incident with no points of \mathbf{S} . Each of the $m^2 + m + 1$ lines of \mathbf{S} contains one point of N and no two such lines can contain the same point, so $m^2 + m + 1 \leq n + 1$. \square

Problem 26C. Show that if $PG_2(\mathbb{F})$ contains the Fano configuration $PG_2(2)$, then \mathbb{F} has characteristic 2. Suggestion: Without loss of generality, four points of the Fano configuration are $\langle 1, 0, 0 \rangle$, $\langle 0, 1, 0 \rangle$, $\langle 0, 0, 1 \rangle$, and $\langle 1, 1, 1 \rangle$. Calculate the homogeneous coordinates of the other three points (that must lie on a line).

Problem 26D. A *blocking set* in a projective plane is a set S of points that contains no line but such that every line meets S in at least one point. Show that a blocking set in a projective plane of order n contains at least $n + \sqrt{n} + 1$ points, and that equality holds if and only if S is the set of points of a Baer subplane.

We illustrate a ‘polynomial method’ with the proof of the following theorem on a type of affine blocking sets, due to Brouwer and Schrijver (1978).

Theorem 26.3. *If V is a subset of $AG(k, q)$ that meets all the hyperplanes, then*

$$|V| \geq k(q - 1) + 1.$$

PROOF: Let A be the blocking set. Without loss of generality $\mathbf{0} \in A$. Let $B := A \setminus \{\mathbf{0}\}$. Then B intersects all hyperplanes that do not contain $\mathbf{0}$. These are defined by equations $w_1x_1 + \cdots + w_kx_k = 1$, where \mathbf{w} runs through all non-zero vectors. Therefore

$$F(x_1, x_2, \dots, x_k) := \prod_{\mathbf{b} \in B} (b_1x_1 + b_2x_2 + \cdots + b_kx_k - 1)$$

is identically 0 on the space except in $\mathbf{0}$.

It is easily shown by induction that a polynomial that is identically 0 on the space must be in the ideal generated by the polynomials $x_i^q - x_i$, $i = 1, \dots, k$. Write $F(\mathbf{x})$ as

$$F(x_1, \dots, x_k) = \sum_{i=1}^k F_i(x_1, \dots, x_k)(x_i^q - x_i) + G(x_1, \dots, x_k),$$

where the highest degree of x_i in G is at most $q - 1$. For each i , the polynomial $x_i F(x_1, \dots, x_k)$ is identically 0, so this is also true for $x_i G(x_1, \dots, x_k)$. Therefore G is divisible by $\Pi(x_i^{q-1} - 1)$. Since $F(\mathbf{0}) \neq 0$, also $G(\mathbf{0}) \neq 0$ and therefore G has degree $k(q - 1)$. So, the degree of F , which is $|B|$, must be at least $k(q - 1)$. \square

A *quadratic form* in indeterminates x_1, x_2, \dots, x_n over a field \mathbb{F} is a homogeneous polynomial of degree 2 in those indeterminates, i.e.

$$(26.1) \quad f(\mathbf{x}) = f(x_1, x_2, \dots, x_n) = \sum_{i,j=1}^n c_{ij}x_ix_j$$

where the coefficients c_{ij} are in \mathbb{F} . The same quadratic form is defined by more than one matrix $C = (c_{ij})$ of coefficients, since it is only the diagonal entries and the sums $c_{ij} + c_{ji}$ that are important. We could require that $c_{ij} = 0$ for $i > j$ and then quadratic forms in x_1, x_2, \dots, x_n are in one-to-one correspondence with upper triangular $n \times n$ matrices C over \mathbb{F} .

A *quadric* in $PG_n(\mathbb{F})$ is a set of projective points

$$Q = Q(f) := \{\langle \mathbf{x} \rangle : f(\mathbf{x}) = 0\}$$

where f is a quadratic form in $n + 1$ indeterminates. We must choose a basis and identify the vectors with $(n + 1)$ -tuples over \mathbb{F} in order to make this definition.

Two quadratic forms f and g are *projectively equivalent* when g can be obtained from f by an ‘invertible linear substitution’, or in matrix notation, $g(\mathbf{x}) = f(\mathbf{x}A)$ for some nonsingular $n \times n$ matrix A over \mathbb{F} . So if f is given by a matrix C as in (26.1), i.e. $f(\mathbf{x}) = \mathbf{x}C\mathbf{x}^\top$, then g is given by the matrix ACA^\top . For example, for any positive integer n , $nx_1^2 + nx_2^2 + nx_3^2 + nx_4^2$ is projectively equivalent to $x_1^2 + x_2^2 + x_3^2 + x_4^2$ over the rationals; see equation (19.12).

We remark that the matrix notation does not lend itself well to changes of the names or number of the indeterminates, which we wish to allow. For example, replacing x_1 in a quadratic form f by $y_1 + y_2$, where y_1 and y_2 are new indeterminates, produces a projectively equivalent form.

The *rank* of a quadratic form is the least number of indeterminates that occur (with nonzero coefficients) in any projectively equivalent quadratic form. For example, $(x_1 + \dots + x_n)^2$ has rank 1. Projectively equivalent quadratic forms have the same rank. A quadratic form in r indeterminates is said to be *nondegenerate* when it has rank r .

Example 26.2. Consider quadratic forms in two indeterminates

$$f(x, y) = ax^2 + bxy + cy^2.$$

The form has rank 0 if and only if $a = b = c = 0$. The corresponding quadric contains all points of $PG_1(\mathbb{F})$ (the projective line). If not

zero, it will have rank 1 if and only if it is a scalar multiple of the square of a linear form $dx + ey$, which is the case if and only if the discriminant $b^2 - 4ac$ is 0. The corresponding quadric in $PG_1(\mathbb{F})$ will then consist of a single point. A rank 2 quadratic form in two indeterminates is either irreducible or can be factored into two distinct linear forms. In the first case, the corresponding quadric in $PG_1(\mathbb{F})$ will be empty, and in the second case, the corresponding quadric in $PG_1(\mathbb{F})$ will consist of two points.

It is clear that an irreducible quadratic form of rank 2 is not projectively equivalent to a reducible quadratic form, since the latter has zeros in \mathbb{F} and the former does not. A reducible quadratic form is projectively equivalent to x_1x_2 .

Problem 26E. Show that over a field \mathbb{F} of odd characteristic, a quadratic form f as in (26.1) is degenerate if and only if the symmetric matrix $C + C^\top$ is singular. For a field \mathbb{F} of characteristic 2, show that f is degenerate if and only if $C + C^\top$ is singular and $\mathbf{x}(C + C^\top) = 0$ for some \mathbf{x} with $f(\mathbf{x}) = 0$.

It is important to understand that the intersection of a quadric with a flat U of $PG_n(\mathbb{F})$ is a quadric in that flat. For example, suppose that U is a projective line $PG_1(\mathbb{F})$ and that f is a quadratic form in x_0, x_1, \dots, x_n . The homogeneous coordinates of points of U are $\langle y\mathbf{a} + z\mathbf{b} \rangle$ where $\mathbf{a} = (a_0, a_1, \dots, a_n)$ and $\mathbf{b} = (b_0, b_1, \dots, b_n)$ are linearly independent vectors. These points are in one-to-one correspondence with the homogeneous coordinates $\langle (y, z) \rangle$ of points of $PG_1(\mathbb{F})$. Say $f = \sum_{0 \leq i \leq j \leq n} c_{ij}x_i x_j$. Then

$$g(y, z) := \sum_{1 \leq i \leq j \leq n} c_{ij}(ya_i + zb_i)(ya_j + zb_j)$$

is a quadratic form in y and z and defines a quadric in $PG_1(\mathbb{F})$. The quadratic form g may be degenerate even if f is not. In view of Example 26.2, we see that a line is either contained fully in a quadric Q , or meets Q in 0, 1, or 2 points.

Lemma 26.4. Any quadratic form f of rank $n \geq 3$ is projectively equivalent to

$$(26.2) \quad x_1x_2 + g(x_3, \dots, x_n)$$

for some quadratic form $g(x_3, \dots, x_n)$.

PROOF: First assume q is odd. It is easy to see that a quadratic form f is projectively equivalent to some $\sum_{1 \leq i < j \leq n} c_{ij} x_i x_j$ where $c_{11} \neq 0$. Let $y := x_1 + \frac{1}{2c_{11}}(c_{12}x_2 + \dots + c_{1n}x_n)$. Then $f = c_{11}y^2 + g(x_2, \dots, x_n)$. Inductively, if the rank of f is at least 3, we find that f is projectively equivalent to

$$h(\mathbf{x}) = ax_1^2 + bx_2^2 + cx_3^2 + g'(x_4, \dots, x_n)$$

with a, b, c all nonzero. The three scalars can be changed by any nonzero square factor and a projectively equivalent quadratic form results; some pair must differ by a square factor, so we can assume that $b = c$, say.

We claim that there exist $s, t \in \mathbb{F}_q$ so that $s^2 + t^2 = -b^{-1}a$. One way to see this is to consider the addition table of \mathbb{F}_q , which is a Latin square. The number of squares in \mathbb{F}_q , including 0, is $(q+1)/2$. The element $-b^{-1}a$ (or any other) occurs $(q-1)/2$ times in the $(q-1)/2$ columns of the Latin square indexed by the nonsquares, and $(q-1)/2$ times in the $(q-1)/2$ rows indexed by the nonsquares; so $-b^{-1}a$ must occur at least once in the submatrix with rows and columns indexed by the squares. With s and t so chosen, h is projectively equivalent to

$$\begin{aligned} ax_1^2 + b(sx_2 + tx_3)^2 + b(tx_2 - sx_3)^2 + g'(x_4, \dots, x_n) \\ = ax_1^2 - ax_2^2 - ax_3^2 + g'(x_4, \dots, x_n) \\ = (ax_1 + ax_2)(x_1 - x_2) - ax_3^2 + g'(x_4, \dots, x_n), \end{aligned}$$

and the latter is clearly projectively equivalent to (26.2).

The case q even is a little more tedious; see the proof of Theorem 5.1.7 in J. W. P. Hirschfeld (1979). \square

Theorem 26.5.

(i) Any quadratic form f of odd rank n is projectively equivalent to

$$(26.3) \quad f_0(\mathbf{x}) := x_1x_2 + \dots + x_{n-2}x_{n-1} + cx_n^2$$

for some scalar c .

(ii) Any quadratic form f of even rank n is projectively equivalent to either

$$(26.4) \quad f_1(\mathbf{x}) := x_1x_2 + \cdots + x_{n-3}x_{n-2} + x_{n-1}x_n$$

or

$$(26.5) \quad f_2(\mathbf{x}) := x_1x_2 + \cdots + x_{n-3}x_{n-2} + p(x_{n-1}, x_n)$$

where $p(x_{n-1}, x_n)$ is an irreducible quadratic form in two indeterminates.

PROOF: This follows from Lemma 26.3 and induction. \square

Quadratic forms (and the corresponding quadrics) of odd rank are called *parabolic*. Quadratic forms of even rank projectively equivalent to (26.4) are called *hyperbolic*, and those equivalent to (26.5) are called *elliptic*. Any two hyperbolic quadratic forms of a given rank are projectively equivalent to (26.4) and hence to each other. It is also true that all parabolic quadratic forms of a given even rank are projectively equivalent, i.e. we may take $c = 1$ in (26.3), and that all elliptic quadratic forms of a given rank are projectively equivalent. See J. W. P. Hirschfeld (1979) for this and more on canonical forms. That hyperbolic and elliptic quadratic forms are not projectively equivalent is a consequence of the following theorem.

Theorem 26.6. *A nondegenerate quadric Q in $PG_n(q)$ has cardinality*

$$\left\{ \begin{array}{ll} \frac{q^n - 1}{q - 1} & \text{if } n \text{ is even, i.e. } Q \text{ is parabolic,} \\ \frac{(q^{(n+1)/2} - 1)(q^{(n-1)/2} + 1)}{q - 1} & \text{if } n \text{ is odd and } Q \text{ is hyperbolic,} \\ \frac{(q^{(n+1)/2} + 1)(q^{(n-1)/2} - 1)}{q - 1} & \text{if } n \text{ is odd and } Q \text{ is elliptic.} \end{array} \right.$$

PROOF: In general, if

$$f(x_1, \dots, x_r) = x_1x_2 + g(x_3, \dots, x_r)$$

and there are N vectors (x_3, \dots, x_r) such that $g(x_3, \dots, x_r) = 0$, then there are $(2q - 1)N + (q - 1)(q^{r-2} - N)$ vectors (x_1, \dots, x_r)

such that $f(x_1, \dots, x_r) = 0$. This allows us to verify by induction the following formulae for the number of zeros in \mathbb{F}_q^r of a rank r quadratic form f in r indeterminates as the following:

$$\begin{cases} q^{r-1} & \text{if } r \text{ is odd, i.e. } f \text{ is parabolic,} \\ q^{r-1} + q^{r/2} - q^{r/2-1} & \text{if } r \text{ is even and } f \text{ is hyperbolic,} \\ q^{r-1} - q^{r/2} + q^{r/2-1} & \text{if } r \text{ is even and } f \text{ is elliptic.} \end{cases}$$

Of course, the number of projective points in $PG_n(q)$ on the corresponding quadrics is found from the above numbers by replacing r by $n + 1$, subtracting 1 (the zero vector) and then dividing by $q - 1$. \square

Theorem 26.7. *Let Q be a nondegenerate quadric in $PG_n(q)$. The maximum projective dimension of a flat F with $F \subseteq Q$ is*

$$\begin{cases} n/2 - 1 & \text{if } n \text{ is even, i.e. } Q \text{ is parabolic,} \\ (n - 1)/2 & \text{if } n \text{ is odd and } Q \text{ is hyperbolic,} \\ (n - 3)/2 & \text{if } n \text{ is odd and } Q \text{ is elliptic.} \end{cases}$$

PROOF: Let f be a nondegenerate quadratic form in r indeterminates. The statement of the theorem is equivalent to the statement that the maximum dimension of a subspace U of \mathbb{F}_q^r such that f vanishes on U is

$$\begin{cases} (r - 1)/2 & \text{if } r \text{ is odd, i.e. } f \text{ is parabolic,} \\ r/2 & \text{if } r \text{ is even and } f \text{ is hyperbolic,} \\ r/2 - 1 & \text{if } r \text{ is even and } f \text{ is elliptic.} \end{cases}$$

First note that if $f = f_0$ in (26.3), then $f(\mathbf{x}) = 0$ for any $\mathbf{x} \in \text{span}(\mathbf{e}_2, \mathbf{e}_4, \dots, \mathbf{e}_{r-1})$, where $\mathbf{e}_1, \mathbf{e}_2, \dots, \mathbf{e}_r$ is the standard basis for \mathbb{F}_q^r . If $f = f_1$ in (26.4), then $f(\mathbf{x}) = 0$ for any $\mathbf{x} \in \text{span}(\mathbf{e}_2, \mathbf{e}_4, \dots, \mathbf{e}_r)$. If $f = f_2$ in (26.5), then $f(\mathbf{x}) = 0$ for any $\mathbf{x} \in \text{span}(\mathbf{e}_2, \mathbf{e}_4, \dots, \mathbf{e}_{r-2})$. These subspaces have dimensions $(r - 1)/2$, $r/2$, and $r/2 - 1$, respectively.

It remains to show that f cannot vanish on any subspace of larger dimension in any of these cases. We will use Theorem 26.5 and induction. The cases $r = 1$ and $r = 2$ are trivial. Suppose

$f(x_1, \dots, x_r) = x_1x_2 + g(x_3, \dots, x_r)$ and that $f(\mathbf{x}) = 0$ for all \mathbf{x} in some subspace $U \subseteq \mathbb{F}_q^r$ of dimension k . To complete the proof, we will show that there exists a subspace $U' \subseteq \mathbb{F}_q^{r-2}$ of dimension $\geq k - 1$ so that $g(\mathbf{y}) = 0$ for all $\mathbf{y} \in U'$.

Clearly, $g(\mathbf{y}) = 0$ for all \mathbf{y} in

$$U_0 := \{(x_3, \dots, x_r) : (0, 0, x_3, \dots, x_r) \in U\}.$$

We are done if $\dim(U_0) \geq k - 1$, so assume $\dim(U_0) = k - 2$. Then there exist vectors

$$(1, 0, a_3, \dots, a_r) \quad \text{and} \quad (0, 1, b_3, \dots, b_r)$$

in U . Then $(1, 1, a_3 + b_3, \dots, a_r + b_r) \in U$ so $g(a_3 + b_3, \dots, a_r + b_r) = -1$. The form g evidently vanishes on all vectors in

$$\text{span}((a_3, \dots, a_r)) + U_0 \quad \text{and} \quad \text{span}((b_3, \dots, b_r)) + U_0.$$

One of these subspaces must have dimension $> k - 2$ because otherwise $(a_3 + b_3, \dots, a_r + b_r) \in U_0$, which contradicts $g(a_3 + b_3, \dots, a_r + b_r) = -1$. \square

Example 26.3. Let f be a quadratic form in three indeterminates and consider the quadric $Q(f)$ in the projective plane $PG_2(q)$. If f is nondegenerate, there are $q + 1$ projective points on $Q(f)$. As we remarked above, any line L of $PG_2(q)$ meets $Q(f)$ in a quadric in L , which in this case consists of 0, 1, or 2 points since $Q(f)$ cannot contain L by Theorem 26.7. So $Q(f)$ is a set of $q + 1$ points, no three of which are collinear, i.e. an oval. See Problem 19I.

If f has rank 0, $Q(f)$ is all of $PG_2(q)$. If f has rank 1, $Q(f)$ consists of the points of a line in $PG_2(q)$. If f has rank 2, there are two cases. If f is reducible, say f is projectively equivalent to xy , then $Q(f)$ consists of the points on the union of two lines of $PG_2(q)$; if f is irreducible, then $Q(f)$ is a single point in $PG_2(q)$.

Example 26.4. The first order Reed-Muller codes were introduced in Chapter 18. Here is one way to introduce the entire family: Let $V = \mathbb{F}_2^m$. We consider vectors of length 2^m whose coordinates are indexed by elements of V ; for concreteness, write $V =$

$\{\mathbf{v}_0, \mathbf{v}_1, \dots, \mathbf{v}_{2^m-1}\}$. The k -th order Reed-Muller code $RM(k, m)$ is defined to consist of all vectors (of length 2^m)

$$(f(\mathbf{v}_0), f(\mathbf{v}_1), \dots, f(\mathbf{v}_{2^m-1}))$$

where f ranges over all polynomials in x_1, \dots, x_m of degree at most k .

Since a linear form $x_{i_1} + \dots + x_{i_k}$ gives the same function as the quadratic form $x_{i_1}^2 + \dots + x_{i_k}^2$ over \mathbb{F}_2 , the words in the second order code $RM(2, m)$ are given by binary quadratic forms $f(x_1, \dots, x_n)$ and their ‘complements’ $f(x_1, \dots, x_n) + 1$. Theorems 26.4 and 26.5 are useful for determining the weights that occur for codewords in $RM(2, m)$.

We must consider degenerate forms also; e.g. $x_1x_2 + x_3x_4$ corresponds to a codeword of weight 24 in $RM(2, 6)$. It will be found that the weights of codewords in $RM(2, 6)$ are 0, 16, 24, 28, 32, 36, 40, 48, and 64.

Problem 26F. Let $f(\mathbf{x}) := x_1x_2 + \dots + x_{2m-1}x_{2m}$. Then f determines a coset C of $RM(1, 2m)$ in $RM(2, 2m)$ consisting of words corresponding to $f(\mathbf{x}) + a(\mathbf{x})$, where $a(\mathbf{x})$ ranges over the 2^{2m+1} affine functions (linear plus possibly a constant term) in $2m$ variables. Show that in C half of the words have weight $2^{2m-1} + 2^{m-1}$ and half have weight $2^{2m-1} - 2^{m-1}$.

Example 26.5. Let Q_3 be a nondegenerate elliptic quadric in projective 3-space $PG_3(q)$. By Theorem 26.6, $|Q_3| = q^2 + 1$. By Theorem 26.7, Q_3 contains no lines. Any plane P meets Q_3 in a quadric in that plane; in view of Example 26.3, every plane must meet Q_3 in either an oval in that plane or a single point. Any three points of Q_3 are contained in a unique plane, so it follows that the nontrivial intersections of planes with Q_3 provide the blocks of a Steiner system

$$S(3, q + 1, q^2 + 1).$$

In general, a set of $q^2 + 1$ points, no three collinear, in $PG_3(q)$ is called an *ovoid* and an $S(3, n + 1, n^2 + 1)$ is called a *Möbius plane* or an *inversive plane*.

Example 26.6. Let Q_4 be a nondegenerate quadric in projective 4-space $PG_4(q)$. By Theorem 26.6, $|Q_4| = q^3 + q^2 + q + 1$. Let

\mathcal{Q} be the incidence structure whose points are the elements of Q_4 and whose blocks are the lines of $PG_4(q)$ fully contained in Q_4 . Each point of \mathcal{Q} is on exactly $q + 1$ blocks of \mathcal{Q} (see Problem 26F). Given a point x and a block L of \mathcal{Q} , the intersection of the plane $P := \{x\} \vee L$ with Q_4 is a quadric Q_2 in P that contains, obviously, a line and a point off that line. From Example 26.3, Q_2 must consist of the points on two (intersecting) lines. This implies that \mathcal{Q} is a partial geometry $pg(r, k, t)$, as defined in Chapter 21, where

$$r = q + 1, \quad k = q + 1, \quad t = 1.$$

Example 26.7. Let Q_5 be a nondegenerate elliptic quadric in $PG_5(q)$. By Theorem 26.6, $|Q_5| = (q + 1)(q^3 + 1)$. By Theorem 26.7, Q_5 contains no planes. Let \mathcal{Q} be the incidence structure whose points are the elements of Q_5 and whose blocks are the lines of $PG_5(q)$ fully contained in Q_5 . By Problem 26F, each point of \mathcal{Q} is on $q^2 + 1$ lines of \mathcal{Q} . By an argument similar to that of Example 26.6, \mathcal{Q} is a partial geometry $pg(r, k, t)$ where

$$r = q^2 + 1, \quad k = q + 1, \quad t = 1.$$

Partial geometries with $t = 1$ are called generalized quadrangles. See L. M. Batten (1986) for further results and references.

Problem 26G. Let f be a nondegenerate quadratic form in n indeterminates given by a matrix $C = (c_{ij})$ over \mathbb{F}_q as in (26.1). Let $Q = Q(f)$ be the corresponding quadric in $PG_{n-1}(\mathbb{F}_q)$. Let $p = \langle \mathbf{x} \rangle$ be one of the points on Q . Let

$$T_p := \{ \langle \mathbf{y} \rangle : \mathbf{x}(C + C^\top)\mathbf{y}^\top = 0 \}.$$

Then T_p is a hyperplane in $PG_{n-1}(\mathbb{F}_q)$ by Problem 26E. Show that $T_p \cap Q$ consists exactly of p and the union of any lines on p that are contained in Q . Further show that if W is any hyperplane of T_p not containing p , then $Q' := W \cap Q$ is a nondegenerate quadric in $W (= PG_{n-3}(\mathbb{F}_q))$ and that Q' is parabolic, hyperbolic, or elliptic according to whether Q is parabolic, hyperbolic, or elliptic. We see, in particular, that the number of lines on p that lie entirely in Q is equal to $|Q'|$.

A *hermitian form* in indeterminates x_1, \dots, x_n over \mathbb{F}_{q^2} is an expression of the form

$$(26.6) \quad h(\mathbf{x}) = h(x_1, \dots, x_n) = \sum_{i,j=1}^n c_{ij} x_i x_j^q,$$

where the coefficients c_{ij} are from \mathbb{F}_{q^2} and where $c_{ji} = c_{ij}^q$. In particular, the diagonal coefficients c_{ii} , being fixed by the Frobenius automorphism $x \mapsto x^q$, lie in \mathbb{F}_q .

Two hermitian forms f and g over \mathbb{F}_{q^2} are *projectively equivalent* when g can be obtained from f by an invertible linear substitution, or, in matrix notation, $g(\mathbf{x}) = f(\mathbf{x}A)$ for some nonsingular $n \times n$ matrix A over \mathbb{F}_{q^2} . So if f is defined by a matrix C as in (26.6), i.e. $f(\mathbf{x}) = \mathbf{x}C\mathbf{x}^\top$, then g is defined by the matrix ACA^* , where A^* is the *conjugate transpose* of A ; if $A = (a_{ij})$, then $A^* := (a_{ji}^q)$.

The *rank* of a hermitian form is the least number of indeterminates that occur (with nonzero coefficients) in any projectively equivalent hermitian form.

A *hermitian variety* in $PG_n(q^2)$ is a set of projective points

$$H = H(f) := \{\langle \mathbf{x} \rangle : f(\mathbf{x}) = 0\}$$

where f is a hermitian form in $n + 1$ indeterminates. We must choose a basis and identify the vectors with $(n + 1)$ -tuples over \mathbb{F}_{q^2} in order to make this definition. It can be seen that the intersection of a hermitian variety in $PG_n(q^2)$ with a flat is a hermitian variety in that flat.

Theorem 26.8. *A hermitian form of rank n is projectively equivalent to*

$$(26.7) \quad x_1^{q+1} + x_2^{q+1} + \dots + x_n^{q+1}.$$

PROOF: It is not hard to see that any nonzero hermitian form is projectively equivalent to h as in (26.6) where $c_{11} \neq 0$; we leave this to the reader. Let $y := c_{11}x_1 + c_{12}x_2 + \dots + c_{1n}x_n$. Then $h = c_{11}^{-1}yy^q + g(x_2, \dots, x_n)$ where g is a hermitian form in x_2, \dots, x_n . Since $c_{11} \in \mathbb{F}_q$, there exists $a \in \mathbb{F}_{q^2}$ such that $a^{q+1} = c_{11}^{-1}$ and then $h = z^{q+1} + g(x_2, \dots, x_n)$, where $z = ay$.

The theorem follows from this step and induction. \square

Theorem 26.9. *The number of points on a nondegenerate hermitian variety H in $PG_n(q^2)$ is*

$$\frac{(q^{n+1} + (-1)^n)(q^n - (-1)^n)}{q^2 - 1}.$$

PROOF: For each nonzero $a \in \mathbb{F}_q$, there are $q + 1$ values of $x \in \mathbb{F}_{q^2}$ such that $x^{q+1} = a$. If

$$f(x_1, \dots, x_n) = x_1^{q+1} + g(x_2, \dots, x_n)$$

and there are N vectors (x_2, \dots, x_n) such that $g(x_2, \dots, x_n) = 0$, then there are $N + (q+1)(q^{2(n-1)} - N)$ vectors (x_1, \dots, x_n) such that $f(x_1, \dots, x_n) = 0$. Inductively, there are $q^{2n-1} + (-1)^n(q^n - q^{n-1})$ vectors in $\mathbb{F}_{q^2}^n$ that are zeros of (26.7) and the theorem follows. \square

Example 26.8. Consider hermitian varieties in the projective line $PG_1(q^2)$. If a hermitian form f in two indeterminates has rank 0, then the variety $H(f)$ contains all $q^2 + 1$ points; if f has rank 1, $H(f)$ consists of one point; if f has rank 2, $H(f)$ contains $q + 1$ points. It follows that if H is a hermitian variety in $PG_n(q^2)$ for any n , then lines of $PG_n(q^2)$ meet H in 1, $q + 1$, or $q^2 + 1$ points.

Now consider a nondegenerate hermitian variety H_2 in the projective plane $PG_2(q^2)$. It has $q^3 + 1$ points by Theorem 26.9. Any line L meets H_2 in a hermitian variety $L \cap H_2$ in that line. As an exercise, the reader should check that no lines are contained in H_2 , so $|L \cap H_2| = 1$ or $q + 1$. It follows that the nontrivial intersections of lines of $PG_2(q^2)$ with H_2 provide the blocks of a Steiner system

$$S(2, q + 1, q^3 + 1)$$

on the point set H_2 .

Designs with these parameters are called *unitals*. Further analysis shows that the designs constructed above are resolvable; see R. C. Bose (1959).

We conclude this chapter with a construction of higher dimensional analogues of the Steiner systems $S(3, q + 1, q^2 + 1)$ of Example 26.5; those constructed below have been called *circle geometries*.

Theorem 26.10. *If q is a power of a prime and n a positive integer, then there exists a Steiner system $S(3, q + 1, q^n + 1)$.*

PROOF: Let V be a 2-dimensional vector space over \mathbb{F}_{q^n} and let \mathcal{X} be the set of 1-dimensional subspaces of V over \mathbb{F}_{q^n} (i.e. the $q^n + 1$ points of $PG_1(q^n)$, the projective line of order q^n).

Now think of V as a $2n$ -dimensional vector space over \mathbb{F}_q . The blocks of our Steiner system will come from the 2-dimensional subspaces U over \mathbb{F}_q of V that are not contained in any member of \mathcal{X} . For every such subspace U , let

$$B_U := \{P \in \mathcal{X} : P \cap U \neq \{\mathbf{0}\}\}.$$

Note that each $P \in B_U$ meets U in a 1-dimensional subspace over \mathbb{F}_q (that contains $q - 1$ of the $q^2 - 1$ nonzero vectors of U), so $|B_U| = q + 1$. If $W = \lambda U$ for some nonzero scalar $\lambda \in \mathbb{F}_{q^n}$, then $B_U = B_W$; we take only the distinct sets B_U as blocks.

Consider three distinct points $P_i \in \mathcal{X}$, $i = 1, 2, 3$. Say P_i is the \mathbb{F}_{q^n} -span of a vector \mathbf{x}_i , $i = 1, 2, 3$. These three vectors are linearly dependent over \mathbb{F}_{q^n} , say

$$\mathbf{x}_3 = \alpha \mathbf{x}_1 + \beta \mathbf{x}_2$$

with $\alpha, \beta \in \mathbb{F}_{q^n}$. But then it is clear that $U := \text{span}_{\mathbb{F}_q}\{\alpha \mathbf{x}_1, \beta \mathbf{x}_2\}$ meets P_1 , P_2 , and P_3 all nontrivially. Suppose some 2-dimensional subspace W over \mathbb{F}_q meets each of the P_i nontrivially, say W contains $\gamma_i \mathbf{x}_i$ with $0 \neq \gamma_i \in \mathbb{F}_{q^n}$, $i = 1, 2, 3$. Then these vectors are linearly dependent over \mathbb{F}_q , say

$$\gamma_3 \mathbf{x}_3 = a \gamma_1 \mathbf{x}_1 + b \gamma_2 \mathbf{x}_2$$

where $a, b \in \mathbb{F}_q$. Since \mathbf{x}_1 and \mathbf{x}_2 are linearly independent over \mathbb{F}_{q^n} , we have $\gamma_3 \alpha = a \gamma_1$ and $\gamma_3 \beta = b \gamma_2$. It follows that $\gamma_3 U = W$, and we see that three distinct points are contained in a unique block. \square

Problem 26H. Let α be a collineation of a projective plane \mathbf{P} .

(i) Show that if α fixes *all* points on a line l and two points not on l , then α fixes \mathbf{P} pointwise.

(ii) If α fixes *all* points on a line l , then there is a point P such that α fixes P and every line through P .

(Such an automorphism of \mathbf{P} is called a *central collineation*.)

Problem 26I. In Chapter 23 we saw that $AG(3, q)$ is a subgeometry of $PG(3, q)$, where the missing part is a projective plane P , sometimes called the *plane at infinity* for $AG(3, q)$. Let $q = 2^m$ and let O be a hyperoval in P . We define an incidence structure \mathbf{I} with as points the points of $AG(3, q)$ and as lines those lines of $AG(3, q)$ that meet P in a point of O . Show that \mathbf{I} is a generalized quadrangle.

Problem 26J. Consider a hyperoval O in $PG(2, 4)$. Define a graph G with as vertices the points of the plane not on O and edges (x, y) if the line through x and y meets O . Prove:

(i) Every edge is in a unique triangle.

(ii) For every triangle (x, y, z) all other vertices are joined to exactly one of x, y, z .

(iii) G is a generalized quadrangle.

Problem 26K. Consider an arbitrary symmetric (v, k, λ) -design. Define an *arc* to be a set S of points, no three on a block. A block is called a *tangent* of S if it meets S in one point. Find an upper bound on $|S|$ depending on whether S has a tangent or not.

Problem 26L. An *oval* in a symmetric design is an arc that meets the bound in Problem 26J. Consider a symmetric design with parameters $(4\lambda - 1, 2\lambda, \lambda)$. Show that the ovals of this design are the lines of size 3 of the complementary design.

Notes.

The term ‘maximal (m, k) -arc’ is often used in the literature for what we have called ‘perfect (m, k) -arcs’, but this is too much of an abuse of the word ‘maximal’ for us to tolerate.

The combinatorial properties of quadrics and hermitian varieties are discussed in more detail in D. K. Ray-Chaudhuri (1962) and R. C. Bose and I. M. Chakravarti (1966).

The polynomial method illustrated in the proof of Theorem 26.3 has further uses. E.g. A. Blokhuis (1994) proved that a nontrivial

blocking set in $PG(2, p)$ has at least $(3p + 1)/2$ points, a conjecture of J. di Paola. The idea is to note that the blocking set S must have a tangent, which without loss of generality is the line at infinity. Let the other points be (a_i, b_i) in the affine plane with $i = 1, \dots, p + k$. A one page complicated study of the polynomial

$$F(t, u) = \prod_{i=1}^{p+k} (t + a_i + ub_i)$$

shows that $k \geq \frac{p+1}{2}$.

References.

- L. M. Batten (1986), *Combinatorics of Finite Geometries*, Cambridge University Press.
- A. Blokhuis (1994), On the size of a blocking set in $PG(2, p)$, *Combinatorica* **14** (1994), 111–114.
- R. C. Bose (1959), On the application of finite projective geometry for deriving a certain series of balanced Kirkman arrangements, *Golden Jubilee Commemoration Volume (1958–59)*, Calcutta Math. Soc., pp. 341–354.
- R. C. Bose and I. M. Chakravarti (1966), Hermitian varieties in a finite projective space $PG(N, q^2)$, *Canad. J. Math* **18**, 1161–1182.
- A. E. Brouwer and A. Schrijver, The blocking number of an affine space, *J. Combinatorial Theory (A)* **24** (1978), 251–253.
- P. Dembowski (1968), *Finite Geometries*, Springer-Verlag.
- R. H. F. Denniston (1969), Some maximal arcs in finite projective planes, *J. Combinatorial Theory* **6**, 317–319.
- J. W. P. Hirschfeld (1979), *Projective Geometries over Finite Fields*, Clarendon Press.
- D. K. Ray-Chaudhuri (1962), Some results on quadrics in finite projective geometry based on Galois fields, *Canad. J. Math.* **14**, 129–138.

27

Difference sets and automorphisms

A class of symmetric designs arises from *difference sets* (defined below) in abelian groups. One such design appeared in Example 19.6. The group reappears in the automorphism group of the design.

In a simple incidence structure, we may identify the blocks with sets of points, i.e. the block set \mathcal{A} is a family of subsets of the point set X . An *automorphism* of a symmetric design (X, \mathcal{A}) , or any simple incidence structure, is a permutation α of X that takes \mathcal{A} to \mathcal{A} , i.e. for $A \subseteq X$, $A \in \mathcal{A}$ if and only if $\alpha(A) \in \mathcal{A}$. We begin with a theorem on automorphisms of symmetric designs in general.

Theorem 27.1. *Let $\mathcal{S} = (X, \mathcal{A})$ be a symmetric (v, k, λ) -design and α an automorphism of \mathcal{S} . Then the number of points fixed by α is equal to the number of blocks fixed by α .*

PROOF: Let N be the incidence matrix of \mathcal{S} . Define a permutation matrix P whose rows and columns are indexed by the points and where

$$P(x, y) := \begin{cases} 1 & \text{if } \alpha(x) = y, \\ 0 & \text{otherwise.} \end{cases}$$

Define a permutation matrix Q whose rows and columns are indexed by the blocks and where

$$Q(A, B) := \begin{cases} 1 & \text{if } \alpha(A) = B, \\ 0 & \text{otherwise.} \end{cases}$$

Note that the trace of P is equal to the number of fixed points, and the trace of Q is equal to the number of fixed blocks of α .

Now we have

$$\begin{aligned} PNQ^\top(x, A) &= \sum_{y \in X, B \in \mathcal{A}} P(x, y)N(y, B)Q(A, B) \\ &= N(\alpha(x), \alpha(A)) = N(x, A). \end{aligned}$$

That is, $PNQ^\top = N$. Equivalently, $P = NQN^{-1}$. Thus P and Q , being similar matrices, have the same trace and the theorem is proved. \square

Corollary. *The type of the cycle decomposition of α on the point set X is the same as the type of the cycle decomposition of α on the block set \mathcal{A} .*

PROOF: By Theorem 27.1, α^i has the same number of fixed points as fixed blocks, for each $i = 1, 2, \dots$

Suppose a permutation β has c_i cycles of length i on some set S , $i = 1, 2, \dots, |S|$. Let f_j denote the number of fixed points of β^j . Then

$$f_j = \sum_{i|j} ic_i,$$

and by Möbius inversion, Theorem 10.4,

$$jc_j = \sum_{i|j} \mu\left(\frac{j}{i}\right) f_i.$$

The point is that the numbers of cycles of each length (i.e. the type of β) are determined completely by the numbers of fixed points of the powers of β . \square

Corollary. *If Γ is a group of automorphisms of a symmetric design, then the number of orbits of Γ on the point set X is the same as the number of orbits of Γ on the block set \mathcal{A} . In particular, Γ is transitive on the points if and only if Γ is transitive on the blocks.*

PROOF: By Burnside's lemma, Theorem 10.5, the number of orbits of a group Γ of permutations of a set S is determined exactly by the multiset $(f(\alpha) : \alpha \in \Gamma)$ where $f(\alpha)$ is the number of elements of S fixed by α . \square

Before introducing difference sets, we digress to give one theorem on orbits of automorphism groups of arbitrary 2-designs. This has been called *Block's Lemma*; see Block (1967). This provides another proof of the above corollary, as the dual of a symmetric design is also a 2-design according to Theorem 19.9.

Theorem 27.2. *If Γ is a group of automorphisms of a $2-(v, k, \lambda)$ design with $v > k$, then the number of orbits of Γ on the point set X is less than or equal to the number of orbits of Γ on the block set \mathcal{A} .*

PROOF: Let X_1, X_2, \dots, X_s be the orbits of Γ on X and let $\mathcal{A}_1, \mathcal{A}_2, \dots, \mathcal{A}_t$ be the orbits of Γ on \mathcal{A} . Define two $s \times t$ matrices C, D as follows. $C(i, j)$ is to be the number of points $x \in X_i$ that are incident with a fixed block $A \in \mathcal{A}_j$ (this number is the same for any block A in \mathcal{A}_j). $D(i, j)$ is to be the number of blocks $A \in \mathcal{A}_j$ that are incident with a fixed point $x \in X_i$ (this number is the same for any point x in X_i).

Consider the $s \times s$ matrix product CD^\top . $CD^\top(i, \ell)$ is the sum over j of the number of ordered pairs $(x, A) \in X_i \times \mathcal{A}_j$ where x is incident with A and A is incident with a fixed point y in X_ℓ . So $CD^\top(i, \ell) = \lambda |X_i|$ if $i \neq \ell$, and $CD^\top(i, i) = (r - \lambda) + \lambda |X_i|$; that is,

$$CD^\top = (r - \lambda)I + \lambda \operatorname{diag}(|X_1|, |X_2|, \dots, |X_s|)J.$$

This is similar to the matrix equation (19.7). Since $v > k$, we have $r > \lambda$ and the matrix on the right can be seen to be nonsingular in several ways, e.g. by calculating its determinant. It follows that the rank of C (and D) is s , and this cannot be greater than the number t of columns. \square

* * *

Let G be an abelian group of order v . A (v, k, λ) -*difference set* in G is a k -subset $D \subseteq G$ such that each nonzero $g \in G$ occurs exactly λ times in the multiset $(x - y : x, y \in D)$ of differences from D . More formally, we are requiring that the number of ordered pairs (x, y) with $x, y \in D$ and $x - y = g$ is λ when $g \neq 0$ and this number is k for $g = 0$. Evidently, $\lambda(v - 1) = k(k - 1)$.

Example 27.1. Examples of difference sets include:

$$(7, 3, 1) \quad \{1, 2, 4\} \text{ in } \mathbb{Z}_7$$

$$(13, 4, 1) \quad \{0, 1, 3, 9\} \text{ in } \mathbb{Z}_{13}$$

$$(11, 5, 2) \quad \{1, 3, 9, 5, 4\} \text{ in } \mathbb{Z}_{11}$$

$$(16, 6, 2) \quad \{10, 20, 30, 01, 02, 03\} \text{ in } \mathbb{Z}_4 \times \mathbb{Z}_4$$

$$(16, 6, 2) \quad \{0000, 0001, 0010, 0100, 1000, 1111\} \text{ in } \mathbb{Z}_2 \times \mathbb{Z}_2 \times \mathbb{Z}_2 \times \mathbb{Z}_2$$

A difference set is *nontrivial* when $1 < k < v - 1$. A difference set with $\lambda = 1$ is sometimes called *planar* or *simple*.

Let G be an abelian group of order v . For $S \subseteq G$, $g \in G$, we denote by $S + g$ the *translate*, or *shift*,

$$S + g := \{x + g : x \in S\}$$

of S by g . Let D be a k -subset of G , and $x, y \in G$. In general, we claim that the number of shifts $D + g$ that contain both x and y is equal to the number of times $d := x - y$ occurs as a difference within D . This is because $g \mapsto (x - g, y - g)$ is a one-to-one correspondence between the set $\{g \in G : \{x, y\} \subseteq D + g\}$ and the set of ordered pairs (a, b) of elements of D such that $a - b = x - y$. (The reader may check that this common number is also equal to the cardinality of the intersection $(D + x) \cap (D + y)$.)

In particular, $(G, \{D + g : g \in G\})$ is a symmetric (v, k, λ) -design if and only if D is a (v, k, λ) -difference set.

Problem 27A. A (v, k, λ) -*quotient set* in an arbitrary group G of order v (written multiplicatively) is a k -subset $D \subseteq G$ such that any one of the following conditions holds:

- (1) Each nonidentity element $g \in G$ occurs exactly λ times in the list $(xy^{-1} : x, y \in D)$ of ‘right’ quotients from D .
- (2) Each nonidentity element $g \in G$ occurs exactly λ times in the list $(x^{-1}y : x, y \in D)$ of ‘left’ quotients from D .
- (3) $|D \cap (Dg)| = \lambda$ for each nonidentity $g \in G$.
- (4) $|D \cap (gD)| = \lambda$ for each nonidentity $g \in G$.
- (5) $(G, \{Dg : g \in G\})$ is a symmetric (v, k, λ) -design.
- (6) $(G, \{gD : g \in G\})$ is a symmetric (v, k, λ) -design.

Show that the above six conditions are equivalent.

Theorem 27.3. Let G be a group of order v . The existence of a (v, k, λ) -*quotient set* in G is equivalent to the existence of a sym-

metric (v, k, λ) -design that admits a group \hat{G} of automorphisms that is isomorphic to G and regular, i.e. sharply transitive, on the points of the design.

PROOF: Let D be a (v, k, λ) -quotient set in G . Then $(G, \{gD : g \in G\})$ is a symmetric (v, k, λ) -design. For $g \in G$, define a permutation \hat{g} of G by $\hat{g}(x) = gx$. Then each \hat{g} is in fact an automorphism of $(G, \{gD : g \in G\})$ and the group $\hat{G} = \{\hat{g} : g \in G\}$ of automorphisms is clearly isomorphic to G and regular on the points.

Conversely, let G be given and let (X, \mathcal{A}) be a symmetric (v, k, λ) -design with regular group \hat{G} of automorphisms of (X, \mathcal{A}) that is isomorphic to G . It will be sufficient to exhibit a (v, k, λ) -quotient set in \hat{G} .

Fix a point $x_0 \in X$ and a block $A_0 \in \mathcal{A}$. Let

$$D := \{\sigma \in \hat{G} : \sigma(x_0) \in A_0\}.$$

We claim that D is a (v, k, λ) -quotient set in \hat{G} . Since \hat{G} is regular and $|A_0| = k$, we have $|D| = k$. Let α be a nonidentity element of \hat{G} . Then $\alpha D = \{\alpha\sigma : \sigma(x_0) \in A_0\} = \{\tau : \tau(x_0) \in \alpha(A_0)\}$, so

$$D \cap (\alpha D) = \{\tau : \tau(x_0) \in A_0 \cap \alpha(A_0)\}.$$

Now since \hat{G} is regular, α has no fixed points and hence, by Theorem 27.1, fixes no blocks. Thus the block $\alpha(A_0)$ is distinct from A_0 , so $|A_0 \cap \alpha(A_0)| = \lambda$, and by regularity, $|D \cap (\alpha D)| = \lambda$. This holds for all nonidentity elements α and establishes our claim. \square

In particular, the existence of a *cyclic* (v, k, λ) -difference set, i.e. a difference set in \mathbb{Z}_v , is equivalent to the existence of a symmetric (v, k, λ) -design that admits a cyclic automorphism, i.e. an automorphism with cycle decomposition on the points—or blocks—consisting of one cycle of length v .

We now restrict our attention to difference sets in abelian groups. Ideally, we would like to describe and classify all difference sets—to find out which groups have difference sets, how many there are, etc. This we shall do for various small parameter triples, but in general the existence problem alone is already extremely difficult.

Observe that $D \subseteq G$ is a (v, k, λ) -difference set if and only if $G \setminus D$ is a $(v, v - k, v - 2k + \lambda)$ -difference set. Thus we may confine our attention to the case $k < \frac{1}{2}v$.

Also note that D is a difference set if and only if every translate of D is a difference set.

In the case that $(v, k) = 1$, it happens that we can choose a natural representative from the class of all translates; this can be a help in classification and will be useful in the next chapter. Call a subset of an abelian group G *normalized* in the case that the sum of its elements is zero.

Proposition 27.4. *Let D be a k -subset of an abelian group G of order v . If $(v, k) = 1$, then D has a unique normalized translate.*

PROOF: Let h be the sum of the elements of D . Then the sum of the elements of a translate $D + g$ is $h + kg$. Since $(v, k) = 1$, there is a unique group element g with $h + kg = 0$. \square

The reader is invited to verify to his or her satisfaction that the normalized difference sets with parameters $(v, k, \lambda) = (7, 3, 1)$, $(13, 4, 1)$, $(11, 5, 2)$, $(21, 5, 1)$ are, respectively:

$$\begin{aligned} & \{1, 2, 4\}, \{3, 5, 6\} \text{ in } \mathbb{Z}_7; \\ & \{0, 1, 3, 9\}, \{0, 2, 5, 6\}, \{0, 4, 10, 12\}, \{0, 7, 8, 11\} \text{ in } \mathbb{Z}_{13}; \\ & \{1, 3, 4, 5, 9\}, \{2, 6, 7, 8, 10\} \text{ in } \mathbb{Z}_{11}; \\ & \{7, 14, 3, 6, 12\}, \{7, 14, 9, 15, 18\} \text{ in } \mathbb{Z}_{21}. \end{aligned}$$

(This will be easy after Theorem 28.3—see Example 28.2.) Of course, for $(v, k) = 1$, the total number of difference sets is v times the number of normalized difference sets, e.g. there are 52 difference sets with parameters $(13, 4, 1)$ in \mathbb{Z}_{13} .

A final preliminary observation is that if α is any automorphism of the group G , then a subset $D \subseteq G$ is a difference set if and only if $\alpha(D)$ is a difference set. Thus from a given difference set we can obtain others by taking translates and by means of the symmetries of G . We say that difference sets D_1, D_2 in G are *equivalent* when there exists $\alpha \in \text{Aut}(G)$ and $g \in G$ such that $D_2 = \alpha(D_1) + g$. (Check that this is an equivalence relation.) The normalized difference sets shown above are, for each parameter triple, equivalent;

indeed, each can be obtained from the others by multiplication by some integer relatively prime to the order of the respective group.

Problem 27B. Show that all $(16, 6, 2)$ -difference sets in $\mathbb{Z}_2 \times \mathbb{Z}_2 \times \mathbb{Z}_2 \times \mathbb{Z}_2$ are equivalent.

Problem 27C. Recall from Example 19.4 that symmetric designs with parameters $v = 4t^2$, $k = 2t^2 - t$, $\lambda = t^2 - t$ are related to regular Hadamard matrices. Let A and B be, respectively, $(4x^2, 2x^2 - x, x^2 - x)$ - and $(4y^2, 2y^2 - y, y^2 - y)$ -difference sets in groups G and H (admit x or $y = 1$). Show that

$$D := (A \times (H \setminus B)) \cup ((G \setminus A) \times B)$$

is a $(4z^2, 2z^2 - z, z^2 - z)$ -difference set in $G \times H$ where $z = 2xy$. (Thus if G is the direct product of m groups of order 4, then there is a $(4^m, 2 \cdot 4^{m-1} - 2^{m-1}, 4^{m-1} - 2^{m-1})$ -difference set in G .)

We describe several known families of difference sets. The known constructions all seem to involve finite fields and/or vector spaces. The first of these examples is essentially contained in Chapter 18 on Hadamard matrices in the discussion of Paley matrices, but it is worth stating explicitly. Difference sets with parameters

$$(v, k, \lambda) = (4n - 1, 2n - 1, n - 1)$$

are often called *Hadamard* difference sets.

Theorem 27.5 (Paley, Todd). *Let $q = 4n - 1$ be a prime power. Then the set D of nonzero squares in \mathbb{F}_q is a $(4n - 1, 2n - 1, n - 1)$ -difference set in the additive group of \mathbb{F}_q .*

PROOF: Clearly, $|D| = 2n - 1$.

Since D is invariant under multiplication by elements of the set S of nonzero squares, the multiset M of differences from D also has this property. Also, M is obviously invariant under multiplication by -1 . Since $q \equiv 3 \pmod{4}$, $-1 \notin S$ and every nonzero element of \mathbb{F}_q is either in S or of the form $-s$ for some $s \in S$. In summary, M is invariant under multiplication by all nonzero elements of \mathbb{F}_q , and so D is a $(4n - 1, 2n - 1, \lambda)$ -difference set for some λ . The relation $\lambda(v - 1) = k(k - 1)$ forces $\lambda = n - 1$. \square

We obtain difference sets $\{1, 2, 4\}$ in \mathbb{Z}_7 , $\{1, 3, 4, 5, 9\}$ in \mathbb{Z}_{11} , and $\{1, 4, 5, 6, 7, 9, 11, 16, 17\}$ in \mathbb{Z}_{19} from Theorem 27.5. The $(27, 13, 6)$ -difference set later in the series will be in the elementary abelian group of order 27, *not* \mathbb{Z}_{27} .

Problem 27D. Show that the Paley–Todd difference sets are normalized if $q > 3$.

Stanton and Sprott (1958) found another family of Hadamard difference sets.

Theorem 27.6. *If q and $q + 2$ are both odd prime powers, then with $4n - 1 := q(q + 2)$, there exists a $(4n - 1, 2n - 1, n - 1)$ -difference set in the additive group of the ring $R := \mathbb{F}_q \times \mathbb{F}_{q+2}$.*

PROOF: Let $U := \{(a, b) \in R : a \neq 0, b \neq 0\}$ be the group of invertible elements of R . Let V be the subgroup of U consisting of those pairs (a, b) such that both a and b are squares in the respective fields \mathbb{F}_q and \mathbb{F}_{q+2} or both a and b are nonsquares. Check that V is an index 2 subgroup of U , and also that $(-1, -1) \notin V$. Put $T := \mathbb{F}_q \times \{0\}$. We claim that $D := T \cup V$ is a difference set as required. We do have $|D| = q + \frac{1}{2}(q - 1)(q + 1) = 2n - 1$.

Since D is invariant under multiplication by elements of V , the multiset of differences from D also has this property as well as the property that it is invariant under multiplication by $(-1, -1)$. So the multiset of differences from D is invariant under multiplication by elements of all of U . Thus every element of U occurs as a difference the same number of times, say λ_1 . Every element $(x, 0)$ of R with $x \neq 0$ will occur, say, λ_2 times; and every element $(0, y)$ of R with $y \neq 0$ will occur, say, λ_3 times as a difference from D . Of course, we have

$$(27.1) \quad k(k - 1) = (q - 1)(q + 1)\lambda_1 + (q - 1)\lambda_2 + (q + 1)\lambda_3.$$

It is easy to evaluate λ_2 and λ_3 . Differences of the form $(x, 0)$, $x \neq 0$ (there are $q - 1$ elements of this form) arise $q(q - 1)$ times from T , never as a difference between an element of T and V , and $(q + 1) \cdot (\frac{1}{2}(q - 1))(\frac{1}{2}(q - 1) - 1)$ times as differences of two elements of V ; thus

$$(q - 1)\lambda_2 = q(q - 1) + (q + 1) \cdot \left(\frac{1}{2}(q - 1)\right)\left(\frac{1}{2}(q - 1) - 1\right)$$

from which we conclude $\lambda_2 = \frac{1}{4}(q+3)(q-1)$. In a similar manner (Problem 27E), the reader will find that $\lambda_3 = \frac{1}{4}(q+3)(q-1)$. Then (27.1) implies that $\lambda_1 = \frac{1}{4}(q+3)(q-1)$ also. \square

Problem 27E. With the notation as in the proof of Theorem 27.6 prove that $\lambda_3 = \frac{1}{4}(q+3)(q-1)$.

In the case that q and $q+2$ are both primes (twin primes), Theorem 27.6 yields cyclic difference sets. For if s, t are relatively prime integers, $\mathbb{Z}_s \times \mathbb{Z}_t$ and \mathbb{Z}_{st} are isomorphic as additive groups—and also as rings. An isomorphism $\mathbb{Z}_{st} \rightarrow \mathbb{Z}_s \times \mathbb{Z}_t$ is provided by $x \pmod{st} \mapsto (x \pmod{s}, x \pmod{t})$. We obtain the $(15, 7, 3)$ -difference set $\{0, 5, 10, 1, 2, 4, 8\}$ in \mathbb{Z}_{15} .

Problem 27F. List the elements of a cyclic $(35, 17, 8)$ -difference set.

As a special case of Singer's theorem, Theorem 27.7, we will obtain another family of Hadamard difference sets: cyclic difference sets with

$$v = 2^t - 1, \quad k = 2^{t-1} - 1, \quad \lambda = 2^{t-2} - 1.$$

Recall from Chapter 23 that the points and the hyperplanes of $PG(n, q)$ form a symmetric design with

$$(27.2) \quad v = \frac{q^{n+1} - 1}{q - 1}, \quad k = \frac{q^n - 1}{q - 1}, \quad \lambda = \frac{q^{n-1} - 1}{q - 1}.$$

Theorem 27.7. *For any prime power q and positive integer n , there is a difference set D with parameters as in (27.2) in the cyclic group of order v so that the resulting symmetric design is isomorphic to the points and hyperplanes of $PG(n, q)$.*

PROOF: In view of Theorem 27.3, we need only show that there exists an automorphism of $PG(n, q)$ that permutes the points in a single cycle of length v , or equivalently so that the powers of the automorphism act transitively on the projective points. The points of $PG(n, q)$ are the 1-dimensional subspaces of an $(n+1)$ -dimensional vector space V over \mathbb{F}_q . Any nonsingular linear transformation T

from V to itself will take subspaces to subspaces of the same dimension and thus gives us an automorphism of $PG(n, q)$.

As an $(n + 1)$ -dimensional vector space over \mathbb{F}_q , we choose $V := \mathbb{F}_{q^{n+1}}$ as a vector space over its subfield \mathbb{F}_q . Let ω be a primitive element of $\mathbb{F}_{q^{n+1}}$ and consider the linear transformation $T : x \mapsto \omega x$ of V over \mathbb{F}_q . It is clear that T is nonsingular and that its powers are transitive on the projective points (even on the nonzero vectors!). \square

The difference sets constructed in the proof of Theorem 27.7 above are called *Singer difference sets*—see Singer (1938). We give a more concrete discussion and an example. Let ω be a primitive element of $\mathbb{F}_{q^{n+1}}$ and define $v := (q^{n+1} - 1)/(q - 1)$. The cyclic multiplicative group $\langle \omega \rangle$ of $\mathbb{F}_{q^{n+1}}$ has a unique subgroup of order $q - 1$, namely,

$$\langle \omega^v \rangle = \{\omega^0 = 1, \omega^v, \omega^{2v}, \dots, \omega^{(q-2)v}\}.$$

But the multiplicative group of the subfield \mathbb{F}_q has order $q - 1$, so we conclude $\mathbb{F}_q = \{0, \omega^0, \omega^v, \omega^{2v}, \dots, \omega^{(q-2)v}\}$.

Now two ‘vectors’ ω^i and ω^j in $\mathbb{F}_{q^{n+1}}$, considered as a vector space over \mathbb{F}_q , represent the same 1-dimensional subspace of $\mathbb{F}_{q^{n+1}}$ if and only if $\omega^i = \alpha \omega^j$ for some $0 \neq \alpha \in \mathbb{F}_q$, that is, if and only if $i \equiv j \pmod{v}$. Thus we have a one-to-one correspondence between the set X of 1-dimensional subspaces (projective points) and the group \mathbb{Z}_v of residue classes modulo v :

$$\begin{aligned} 0 &\leftrightarrow x_0 = \{0, \omega^0, \omega^v, \omega^{2v}, \dots, \omega^{(q-2)v}\} \\ 1 &\leftrightarrow x_1 = \{0, \omega^1, \omega^{v+1}, \omega^{2v+1}, \dots, \omega^{(q-2)v+1}\} \\ &\vdots \\ i &\leftrightarrow x_i = \{0, \omega^i, \omega^{v+i}, \omega^{2v+i}, \dots, \omega^{(q-2)v+i}\} \\ &\vdots \\ v-1 &\leftrightarrow x_{v-1} = \{0, \omega^{v-1}, \omega^{2v-1}, \omega^{3v-1}, \dots, \omega^{(q-1)v-1}\}. \end{aligned}$$

The map $x_i \mapsto x_{i+1}$ (subscripts modulo v) is an automorphism of the projective space. To obtain a difference set, let U be any n -dimensional subspace of $\mathbb{F}_{q^{n+1}}$ and let $D := \{i \in \mathbb{Z}_v : x_i \in U\}$. A normalized difference set is obtained if U is taken to be the subspace of elements with trace zero (the trace from $\mathbb{F}_{q^{n+1}}$ to \mathbb{F}_q).

Example 27.2. Consider $n = 2$, $q = 5$. We construct a $(31, 6, 1)$ -difference set. A zero ω of the polynomial $y^3 + y^2 + 2$ (coefficients in \mathbb{F}_5) is a primitive element of \mathbb{F}_{5^3} and $1, \omega, \omega^2$ furnish a basis for \mathbb{F}_{5^3} as a vector space over \mathbb{F}_5 . The 124 nonzero elements of \mathbb{F}_{5^3} fall into 31 cosets modulo the subgroup $\langle \omega^{31} \rangle = \{3, 4, 2, 1\} = \mathbb{F}_5 \setminus \{0\}$, each coset being the nonzero elements of a 1-dimensional subspace. Let us take $U := \text{span}\{1, \omega\}$ as our 2-dimensional subspace. Representatives of the projective points on U are $1, \omega, \omega + 1, \omega + 2, \omega + 3, \omega + 4$ and, after some computation,

$$\begin{aligned} 1 &= \omega^0 \\ \omega &= \omega^1 \\ \omega + 1 &= \omega^{29} \\ \omega + 2 &= \omega^{99} \\ \omega + 3 &= \omega^{80} \\ \omega + 4 &= \omega^{84}. \end{aligned}$$

The resulting Singer difference set is

$$\{0, 1, 29, 6, 18, 22\} \quad \text{in } \mathbb{Z}_{31}.$$

Problem 27G. Find a $(57, 8, 1)$ -difference set in \mathbb{Z}_{57} . (Some will probably not want to do this by hand.)

Consider $n = 3$, $q = 2$. Here the points of $PG(3, 2)$ are in one-to-one correspondence with the nonzero elements of \mathbb{F}_{2^4} that in turn are in one-to-one correspondence with the residues modulo 15. It may be instructive to write out all lines and planes of this smallest projective 3-space so that the cyclic automorphism is clear.

A zero ω of $y^4 + y + 1$ (coefficients in \mathbb{F}_2) is a primitive element of \mathbb{F}_{2^4} and $\omega^3, \omega^2, \omega, 1$ form a basis for \mathbb{F}_{2^4} over \mathbb{F}_2 . Any element of \mathbb{F}_{2^4} can be written uniquely as $a_3\omega^3 + a_2\omega^2 + a_1\omega + a_0$ that we abbreviate as $a_3a_2a_1a_0$ below. We have $\omega^4 + \omega + 1 = 0$, or $\omega^4 = 0011$. We first construct a table of vector representations of powers of ω .

\mathbb{F}_2^4

$\omega^0 = 0001$	$\omega^5 = 0110$	$\omega^{10} = 0111$
$\omega^1 = 0010$	$\omega^6 = 1100$	$\omega^{11} = 1110$
$\omega^2 = 0100$	$\omega^7 = 1011$	$\omega^{12} = 1111$
$\omega^3 = 1000$	$\omega^8 = 0101$	$\omega^{13} = 1101$
$\omega^4 = 0011$	$\omega^9 = 1010$	$\omega^{14} = 1001$

 $PG(3, 2)$

	Lines		Planes
$\{0,5,10\}$	$\{0,1,4\}$	$\{0,2,8\}$	$\{1,2,4,8,0,5,10\}$
$\{1,6,11\}$	$\{1,2,5\}$	$\{1,3,9\}$	$\{2,3,5,9,1,6,11\}$
$\{2,7,12\}$	$\{2,3,6\}$	$\{2,4,10\}$	$\{3,4,6,10,2,7,12\}$
$\{3,8,13\}$	$\{3,4,7\}$	$\{3,5,11\}$	$\{4,5,7,11,3,8,13\}$
$\{4,9,14\}$	$\{4,5,8\}$	$\{4,6,12\}$	$\{5,6,8,12,4,9,14\}$
	$\{5,6,9\}$	$\{5,7,13\}$	$\{6,7,9,13,5,10,0\}$
	$\{6,7,10\}$	$\{6,8,14\}$	$\{7,8,10,14,6,11,1\}$
	$\{7,8,11\}$	$\{7,9,0\}$	$\{8,9,11,0,7,12,2\}$
	$\{8,9,12\}$	$\{8,10,1\}$	$\{9,10,12,1,8,13,3\}$
	$\{9,10,13\}$	$\{9,11,2\}$	$\{10,11,13,2,9,14,4\}$
	$\{10,11,14\}$	$\{10,12,3\}$	$\{11,12,14,3,10,0,5\}$
	$\{11,12,0\}$	$\{11,13,4\}$	$\{12,13,0,4,11,1,6\}$
	$\{12,13,1\}$	$\{12,14,5\}$	$\{13,14,1,5,12,2,7\}$
	$\{13,14,2\}$	$\{13,0,6\}$	$\{14,0,2,6,13,3,8\}$
	$\{14,0,3\}$	$\{14,1,7\}$	$\{0,1,3,7,14,4,9\}$

Note that for $q = 2$, the Singer difference sets have Hadamard parameters. We obtain $(31, 15, 7)$ -difference sets both from Theorem 27.5 and Theorem 27.7. These two difference sets are not equivalent—and not even isomorphic. (Two difference sets are *isomorphic* when the corresponding symmetric designs are isomorphic. Equivalent difference sets are surely isomorphic, but the converse is not true.) The difference set D of quadratic residues modulo 31 has the property that

$$D \cap (D + 1) \cap (D + 3) = \{5, 8, 10, 19\}.$$

The design $(\mathbb{Z}_{31}, \{D + g : g \in \mathbb{Z}_{31}\})$ cannot be isomorphic to the points and hyperplanes of $PG(4, 2)$ since the intersection of flats is again a flat and $PG(4, 2)$ has no flats with precisely four points.

Gordon, Mills, and Welch (1962) have shown that the construction of Singer's theorem can be modified in some cases to produce many nonequivalent difference sets with the same parameters.

Problem 27H. Let D be an $(n^2 + n + 1, n + 1, 1)$ -difference set in an abelian group G . Show that $-D$ is an *oval* in the associated projective plane.

Problem 27I. Let $G = \{0, a_0, a_1, \dots, a_q\}$ be any group of order $q+2$, where q is a power of a prime. Let V be a 2-dimensional vector space over \mathbb{F}_q and let U_0, U_1, \dots, U_q be its 1-dimensional subspaces. Show that

$$D := \bigcup_{i=0}^q \{a_i\} \times U_i$$

is a difference set in $G \times V$. For example, we obtain a $(45, 12, 3)$ -difference set.

Notes.

The idea of group difference sets, as a generalization of cyclic difference sets, is due to R. H. Bruck (1955).

Problem 27I is a result of McFarland (1973).

Theorem 27.2 holds also for arbitrary 2-designs, simple or not. Of course, one must define an automorphism of an arbitrary incidence structures $\mathbf{S} = (\mathcal{P}, \mathcal{B}, \mathbf{I})$. Perhaps the most precise definition is as an ordered pair (α, β) , where α is a permutation of \mathcal{P} , β is a permutation of \mathcal{B} , and such that $(x, A) \in \mathbf{I}$ if and only if $(\alpha(x), \beta(A)) \in \mathbf{I}$. The automorphisms form a group under coordinate-wise composition. The permutations α that occur as first coordinates of a group Γ of automorphisms form a group Γ_1 of permutations of the points; the permutations β that occur as second coordinates of a group Γ of automorphisms form a group Γ_2 of permutations of the blocks. By the orbits of Γ on the points, respectively blocks, we mean the orbits of Γ_1 , respectively Γ_2 .

References.

- R. E. Block (1967), On the orbits of collineation groups, *Math Z.* **96**, 33–49.
- R. H. Bruck (1955), Difference sets in a finite group, *Trans. Amer. Math. Soc.* **78**, 464–481.
- B. Gordon, W. H. Mills, and L. R. Welch (1962), Some new difference sets, *Canad. J. Math.* **14**, 614–625.
- R. L. McFarland (1973), A family of difference sets in non-cyclic groups, *J. Combinatorial Theory (A)* **15**, 1–10.
- J. Singer (1938), A theorem in finite projective geometry and some applications to number theory, *Trans. Amer. Math. Soc.* **43**, 377–385.
- R. G. Stanton and D. A. Sprott (1958), A family of difference sets, *Canad. J. Math.* **10**, 73–77.

28

Difference sets and the group ring

The group ring provides a natural and convenient setting for the study of difference sets. The existence of a difference set will be seen to be equivalent to the existence of a solution to a certain algebraic equation in a group ring. We shall use the group ring to derive the celebrated Multiplier Theorem of M. Hall, Jr. as well as number-theoretic criteria on the parameters of a difference set which are stronger than the Bruck-Ryser-Chowla theorem.

Let R be a ring (commutative with one) and G a finite abelian group (written additively). The elements of the *group ring* $R[G]$ are all formal sums

$$A = \sum_{g \in G} a_g x^g,$$

where $a_g \in R$ for each $g \in G$. (Here the symbol x is just a place holder. The important thing is that we have an element a_g of R for each element g of G , i.e. the elements of the group ring are in one-to-one correspondence with mappings $G \rightarrow R$.)

We define addition and scalar multiplication in the obvious way:

$$\sum_{g \in G} a_g x^g + \sum_{g \in G} b_g x^g := \sum_{g \in G} (a_g + b_g) x^g,$$

$$c \sum_{g \in G} a_g x^g := \sum_{g \in G} (ca_g) x^g.$$

Multiplication in $R[G]$ is defined by

$$\sum_{g \in G} a_g x^g \sum_{g \in G} b_g x^g := \sum_{g \in G} \left(\sum_{h+h'=g} a_h b_{h'} \right) x^g.$$

With these definitions, $R[G]$ is a commutative, associative R -algebra. The notation we have chosen is appropriate for abelian groups and emphasizes an analogy with polynomials. Note that when G is the additive group of the residues modulo v , then the group ring $R[\mathbb{Z}_v]$ consists of all sums $\sum_{i=0}^{v-1} r_i x^i$ (exponents modulo v) and is isomorphic to the factor ring $R[x]/(x^v - 1)$ of the polynomial ring $R[x]$. In general, we shall even take to denoting elements of arbitrary group rings $R[G]$ as $A(x)$, $B(x)$, \dots when convenient. The element $x^0 \in R[G]$ is the multiplicative identity in $R[G]$ and we denote x^0 by 1.

We shall be concerned almost exclusively with the group rings $\mathbb{Z}[G]$ over the integers. For a subset $A \subseteq G$, we define $A(x) \in \mathbb{Z}[G]$ by

$$A(x) = \sum_{g \in A} x^g.$$

In particular, $G(x) = \sum_{g \in G} x^g$. For $A, B \subseteq G$,

$$A(x)B(x) = \sum_{g \in G} c_g x^g,$$

where c_g is the number of times g occurs in the multiset

$$(h + h' : h \in A, h' \in B)$$

of sums of elements of A and B .

For $A(x) = \sum_{g \in G} a_g x^g \in \mathbb{Z}[G]$, we write

$$A(x^{-1}) := \sum_{g \in G} a_g x^{-g}.$$

So for a k -subset D of a group G of order v , D is a (v, k, λ) -difference set in G if and only if the equation

$$D(x)D(x^{-1}) = n + \lambda G(x)$$

holds in the group ring $\mathbb{Z}[G]$, where $n := k - \lambda$.

An important homomorphism from $\mathbb{Z}[G]$ to \mathbb{Z} is given by

$$A(x) \mapsto A(1) := \sum_{g \in G} a_g \in \mathbb{Z}.$$

Proposition 28.1. *Let v, k, λ be positive integers such that*

$$\lambda(v - 1) = k(k - 1)$$

and let G be an abelian group of order v . The existence of a (v, k, λ) -difference set in G is equivalent to the existence of an element $A(x) \in \mathbb{Z}[G]$ satisfying the equation

$$(28.1) \quad A(x)A(x^{-1}) = n + \lambda G(x),$$

where $n := k - \lambda$.

PROOF: We have already pointed out that for a subset D of G , $D(x)$ satisfies (28.1) if and only if D is a (v, k, λ) -difference set. It remains to show that if there is a solution $A(x)$ to (28.1), then we can find a solution $B(x) = \sum_{g \in G} b_g x^g$ where the coefficients b_g are 0's and 1's.

Assume that $A(x)$ satisfies (28.1) and apply the homomorphism ' $x \mapsto 1$ ' from $\mathbb{Z}[G] \rightarrow \mathbb{Z}$. We find

$$(A(1))^2 = n + \lambda v = k^2,$$

so $A(1) = k$ or $-k$. Now if $A(x)$ satisfies (28.1), then so does $B(x) = -A(x)$, so we may assume $A(1) = \sum a_g = k$.

The coefficient of $1 = x^0$ in $A(x)A(x^{-1})$ is $k = \sum_{g \in G} a_g^2$. Thus $\sum_{g \in G} a_g(a_g - 1) = 0$. But $a(a - 1)$ is strictly positive unless the integer a is 0 or 1. \square

For any integer t , $g \mapsto tg$ is a homomorphism of the group G into itself and induces a ring homomorphism $\mathbb{Z}[G] \rightarrow \mathbb{Z}[G]$, namely

$$A(x) = \sum_{g \in G} a_g x^g \quad \mapsto \quad A(x^t) := \sum_{g \in G} a_g x^{tg}.$$

For $A, B \in \mathbb{Z}[G]$ and $n \in \mathbb{Z}$, we say $A \equiv B \pmod{n}$ when $A - B = nC$ for some $C \in \mathbb{Z}[G]$. Here is an easy lemma we will use often.

Lemma 28.2. *Let p be a prime and $A \in \mathbb{Z}[G]$. Then*

$$(A(x))^p \equiv A(x^p) \pmod{p}.$$

PROOF: We proceed by induction on the number of nonzero coefficients of $A(x)$. The lemma holds for $A(x) = 0$. Now if $A(x) = cx^g + B(x)$ where $B^p(x) \equiv B(x^p) \pmod{p}$, then

$$\begin{aligned} A^p(x) &= (cx^g + B(x))^p \equiv (cx^g)^p + B^p(x) \\ &= c^p x^{pg} + B^p(x) \equiv cx^{pg} + B(x^p) = A(x^p), \end{aligned}$$

where the congruences are modulo p . □

Let G be an abelian group and D a difference set in G . An automorphism α of G is said to be a *multiplier* of D if and only if the difference set $\alpha(D)$ is in fact a translate of D , i.e. if and only if $\alpha(D) = D + g$ for some $g \in G$. For example, the automorphism $x \mapsto 3x$ of \mathbb{Z}_{13} is a multiplier of the $(13, 4, 1)$ -difference set $\{0, 2, 3, 7\}$ since $\{0, 6, 9, 8\} = \{0, 2, 3, 7\} + 6$.

If t is an integer relatively prime to the order of G , then $x \mapsto tx$ is an automorphism of G since the maps $x \mapsto t_1x$ and $x \mapsto t_2x$ coincide if and only if $t_1 \equiv t_2 \pmod{v^*}$ where v^* is the exponent of G , i.e. the least common multiple of the orders of the elements of G . If $x \mapsto tx$ is a multiplier of a difference set D in G , we say that t is a *numerical multiplier* or *Hall multiplier* of D . It is at first surprising that many difference sets (e.g. all known cyclic difference sets) must necessarily have a nontrivial numerical multiplier.

Problem 28A. Let $q = p^t$, p prime. Show that p is a multiplier of the Singer difference sets described in the previous chapter.

Observe that an automorphism α of G is a multiplier of a difference set D in G if and only if in the group ring $\mathbb{Z}[G]$, $D(x^\alpha) = x^g \cdot D(x)$ for some $g \in G$.

Theorem 28.3 (Multiplier Theorem, first version). *Let D be a (v, k, λ) -difference set in an abelian group G of order v . Let p be a prime, $p|n$, $(p, v) = 1$, $p > \lambda$. Then p is a numerical multiplier of D .*

It will be convenient to isolate part of the proof as a lemma.

Lemma 28.4. *Let α be an automorphism of G and let D be a (v, k, λ) -difference set in G . Consider*

$$S(x) := D(x^\alpha)D(x^{-1}) - \lambda G(x).$$

Then α is a multiplier of D if and only if $S(x)$ has nonnegative coefficients.

PROOF: We begin by remarking that if α is a multiplier, then we have $D(x^\alpha) = x^g \cdot D(x)$ for some $g \in G$, and then

$$D(x^\alpha)D(x^{-1}) = x^g \cdot D(x)D(x^{-1}) = x^g(n + \lambda G(x)) = nx^g + \lambda G(x).$$

So in this case, $S(x)$, as defined above, is equal to nx^g for some $g \in G$. In particular, it has nonnegative coefficients. Note that, conversely, if $D(x^\alpha)D(x^{-1}) = nx^g + \lambda G(x)$, we can multiply this by $D(x)$ to find

$$D(x^\alpha) \cdot (n + \lambda G(x)) = nx^g \cdot D(x) + \lambda D(x)G(x),$$

$$nD(x^\alpha) + \lambda kG(x) = nx^g \cdot D(x) + \lambda kG(x).$$

So $D(x^\alpha) = x^g \cdot D(x)$ and α is a multiplier.

Now ' $x \mapsto x^\alpha$ ' is an automorphism of $\mathbb{Z}[G]$, so $D(x^\alpha)D(x^{-\alpha}) = n + \lambda G(x)$, i.e. $\alpha(D)$ is also a difference set, and

$$\begin{aligned} S(x)S(x^{-1}) &= \{D(x^\alpha)D(x^{-1}) - \lambda G(x)\}\{D(x^{-\alpha})D(x) - \lambda G(x)\} \\ &= \{n + \lambda G(x)\}^2 - 2\lambda k^2 G(x) + \lambda^2 v G(x) \\ &= n^2 + 2\lambda(n + \lambda v - k^2)G(x) = n^2. \end{aligned}$$

Suppose that $S(x) = \sum_{g \in G} s_g x^g$ with nonnegative coefficients s_g . If $s_g > 0$ and $s_h > 0$ for $g, h \in G$, then the coefficient of x^{g-h} in $S(x)S(x^{-1})$, $= n^2$, is at least $s_g s_h$, i.e. strictly positive, and so $x^{g-h} = x^0$, i.e. $g = h$. So $S(x)$ can have only one positive coefficient, say $S(x) = s_g x^g$. The equation $S(x)S(x^{-1}) = n^2$ forces $s_g = n$ and we have shown $S(x) = nx^g$. As noted above, we may conclude that α is a multiplier. \square

PROOF OF THEOREM 28.3: Let $S(x) := D(x^p)D(x^{-1}) - \lambda G(x)$. By Lemma 28.4, it will suffice to show that $S(x)$ has nonnegative coefficients. By Lemma 28.2,

$$\begin{aligned} D(x^p)D(x^{-1}) &\equiv D^p(x)D(x^{-1}) \equiv D^{p-1}(x)D(x)D(x^{-1}) \\ &\equiv D^{p-1}(x) \cdot (n + \lambda G(x)) \equiv nD^{p-1}(x) + \lambda k^{p-1}G(x) \\ &\equiv \lambda G(x) \pmod{p}, \end{aligned}$$

since p divides n and $\lambda k^{p-1} \equiv \lambda^p \equiv \lambda \pmod{p}$. Thus the coefficients of $D(x^p)D(x^{-1})$, which are clearly nonnegative, are all congruent to λ modulo p . Since $p > \lambda$, it must be that the coefficients of $D(x^p)D(x^{-1})$ are greater than or equal to λ , i.e. $S(x)$ has nonnegative coefficients. \square

Problem 28B. Find an element $S(x)$ in $\mathbb{Z}[\mathbb{Z}_7]$ with the property that $S(x)S(x^{-1}) = 4$, but with $S(x) \neq \pm 2x^g$.

Note that the hypothesis $p > \lambda$ was essential for our proof. Yet in every *known* difference set, *every* prime divisor of n (not dividing v) is a multiplier. It may be, then, that the hypothesis $p > \lambda$ is unnecessary and by now the question of whether this is so has acquired the status of a classical unsolved problem. There have also been several generalizations of the original Multiplier Theorem, all of which would be trivial if we could eliminate the condition $p > \lambda$, and we state such a generalization below after first giving some applications of the current version.

Corollary. For $\lambda = 1$, every prime divisor of n , and hence every divisor, is a multiplier of every $(n^2 + n + 1, n + 1, 1)$ -difference set.

Example 28.1. We claim that there are no $(n^2 + n + 1, n + 1, 1)$ -difference sets with $n \equiv 0 \pmod{6}$. Let D be such a hypothetical difference set, and without loss of generality, assume D is normalized so that it is fixed by all multipliers. Both 2 and 3 would be multipliers. Then for $x \in D$, $2x$ and $3x$ also are in D . Then the difference x occurs twice, once as $2x - x$, and once as $3x - 2x$; these are different occurrences as long as $3x \neq 2x$, i.e. $x \neq 0$. This contradicts $\lambda = 1$.

Problem 28C. Show that there are no $(n^2 + n + 1, n + 1, 1)$ -difference sets with n divisible by any of 10, 14, 15, 21, 22, 26, 34, 35.

It has been possible to prove, with the Multiplier Theorem and other techniques, that no planar difference sets exist for $n \leq 3600$ unless n is a prime power. But the conjecture that n must be a prime power remains open.

Example 28.2. Consider a normalized $(21, 5, 1)$ -difference set D in \mathbb{Z}_{21} . By the Multiplier Theorem, 2 is a multiplier and hence

$2D = D$. Thus D must be the union of the cycles of $x \mapsto 2x$ on \mathbb{Z}_{21} . These are

$$\{0\}, \quad \{1, 2, 4, 8, 16, 11\}, \quad \{3, 6, 12\}, \quad \{5, 10, 20, 19, 17, 13\}, \\ \{7, 14\}, \quad \text{and} \quad \{9, 18, 15\}.$$

But D has 5 elements, so *if* there is such a difference set, D must be $\{7, 14, 3, 6, 12\}$ or $\{7, 14, 9, 18, 15\}$. It turns out that both of these *are* difference sets. One consists of the negatives of the other, so the 42 difference sets with these parameters are all equivalent.

Problem 28D. Find all normalized difference sets with parameters $(7, 3, 1)$, $(11, 5, 2)$, $(13, 4, 1)$, $(19, 9, 4)$, $(31, 10, 3)$, and $(37, 9, 2)$. (Note: no difference sets exist for one of the parameter triples.)

We give two more easy lemmas on the group ring at this point.

Lemma 28.5. *Let G be an abelian group of order v and p a prime, $p \nmid v$. Let $A \in \mathbb{Z}[G]$ and suppose $A^m \equiv 0 \pmod{p}$ for some positive integer m . Then $A \equiv 0 \pmod{p}$.*

PROOF: Choose a power $q = p^e$ of p such that $q \geq m$ and $q \equiv 1 \pmod{v}$. Then surely $A^q(x) \equiv 0 \pmod{p}$. But by Lemma 28.2, $A^q(x) \equiv A(x^q) \pmod{p}$, so $A(x^q) \equiv 0 \pmod{p}$. Since $q \equiv 1 \pmod{v}$, $qx = x$ for every $x \in G$ and $A(x) = A(x^q)$. \square

Note that $x^g \cdot G(x) = G(x)$ in $\mathbb{Z}[G]$. It follows that

$$A(x)G(x) = A(1)G(x).$$

For $n \in \mathbb{Z}$ and $A, B \in \mathbb{Z}[G]$, we say $A \equiv B \pmod{n, G}$ when $A - B$ is an element of the ideal in $\mathbb{Z}[G]$ generated by n and $G = G(x)$, or equivalently, when

$$A - B = nC + mG$$

for some $C \in \mathbb{Z}[G]$.

Lemma 28.6. *Let G be an abelian group of order v and p a prime, $p \nmid v$. If $A \in \mathbb{Z}[G]$ and*

$$A^m \equiv 0 \pmod{p, G}$$

for some positive integer m , then $A \equiv 0 \pmod{p, G}$.

PROOF: Choose $q = p^e$ with $q \equiv 1 \pmod{v}$ and $q \geq m$. Then $A^q(x) \equiv 0 \pmod{p, G}$ and $A^q(x) \equiv A(x^q) = A(x) \pmod{p}$. \square

Theorem 28.7 (Multiplier Theorem, second version). *Let D be a (v, k, λ) -difference set in an abelian group G of exponent v^* . Let t be an integer, $(t, v) = 1$, and suppose we can find a divisor m of $n := k - \lambda$ such that $m > \lambda$ and for every prime divisor p of m , there is an integer f for which $p^f \equiv t \pmod{v^*}$. Then t is a numerical multiplier of D .*

PROOF: The proof will use Lemmas 28.2, 28.4, 28.5 and the following observation:

Let D be a (v, k, λ) -difference set in G , α an automorphism of G , and put $S(x) := D(x^\alpha)D(x^{-1}) - \lambda G(x)$. Assume that α has order e , so that $\alpha^e = \text{identity}$. Then, we assert, in the group ring $\mathbb{Z}[G]$,

$$S(x)S(x^\alpha)S(x^{\alpha^2}) \cdots S(x^{\alpha^{e-1}}) = n^e.$$

To see this, note that for any integer i , we have

$$D(x^{\alpha^i})D(x^{-\alpha^i}) = n + \lambda G(x) \equiv n \pmod{G}$$

and

$$\begin{aligned} S(x^{\alpha^i}) &= D(x^{\alpha^{i+1}})D(x^{-\alpha^i}) - \lambda G(x) \\ &\equiv D(x^{\alpha^{i+1}})D(x^{-\alpha^i}) \pmod{G}. \end{aligned}$$

Then

$$\begin{aligned} S(x)S(x^\alpha)S(x^{\alpha^2}) \cdots S(x^{\alpha^{e-1}}) & \\ &\equiv \{D(x^\alpha)D(x^{-1})\}\{D(x^{\alpha^2})D(x^{-\alpha})\} \cdots \{D(x)D(x^{-\alpha^{e-1}})\} \\ &\equiv \{D(x)D(x^{-1})\}\{D(x^\alpha)D(x^{-\alpha})\} \cdots \{D(x^{\alpha^{e-1}})D(x^{-\alpha^{e-1}})\} \\ &\equiv n^e \pmod{G}. \end{aligned}$$

Thus $S(x)S(x^\alpha) \cdots S(x^{\alpha^{e-1}}) = n^e + \ell G(x)$ for some integer ℓ . But $S(1) = (D(1))^2 - \lambda G(1) = k^2 - \lambda v = n$; so applying the homomorphism $x \mapsto 1$, we find $n^e = n^e + \ell v$, and hence $\ell = 0$.

To continue with the proof, let $S(x) := D(x^t)D(x^{-1}) - \lambda G(x)$. By Lemma 28.4, to show t is a multiplier, it will be sufficient to prove that $S(x)$ has nonnegative coefficients. Each coefficient of

$S(x)$ is at least $-\lambda$ in value and since $m > \lambda$, the nonnegativity of the coefficients will follow if we can establish that $S(x) \equiv 0 \pmod{m}$. To establish this, it will suffice to show that $S(x) \equiv 0 \pmod{p^i}$ whenever p is prime and p^i divides m . This we do below.

Let e be the order of t modulo v^* , so that $t^e \equiv 1 \pmod{v^*}$. As shown above,

$$S(x)S(x^t)S(x^{t^2}) \cdots S(x^{t^{e-1}}) = n^e.$$

Let p be a prime divisor of m and let f be such that $p^f \equiv t \pmod{v^*}$. Then

$$S(x)S(x^{p^f})S(x^{p^{2f}}) \cdots S(x^{p^{f(e-1)}}) = n^e.$$

Let p^i be the highest power of p dividing n and let p^j be the highest power of p dividing (all coefficients of) $S(x)$, so $S(x) = p^j T(x)$ where $T(x) \not\equiv 0 \pmod{p}$. Then

$$p^j T(x) p^j T(x^{p^f}) \cdots p^j T(x^{p^{f(e-1)}}) = n^e,$$

from which it follows that p^j divides n (so $j \leq i$) and

$$T(x)T(x^{p^f}) \cdots T(x^{p^{f(e-1)}}) = \left(\frac{n}{p^j}\right)^e.$$

Suppose that $j < i$, so that $(\frac{n}{p^j})^e$ is divisible by p . Then

$$\begin{aligned} 0 &\equiv T(x)T(x^{p^f}) \cdots T(x^{p^{f(e-1)}}) \\ &\equiv T(x)T^{p^f}(x) \cdots T(x)T^{p^{f(e-1)}}(x) \\ &\equiv (T(x))^{1+p^f+\cdots+p^{f(e-1)}} \pmod{p}. \end{aligned}$$

But then, by Lemma 28.5, $T(x) \equiv 0 \pmod{p}$, contradicting the choice of j . Thus $i = j$. \square

Corollary. *If $n = p^e$, p prime, $(p, v) = 1$, then p is a numerical multiplier of every (v, k, λ) -difference set.*

PROOF: A difference set D and its complement $G \setminus D$ have the same multipliers. Thus we may assume that $k < \frac{1}{2}v$ and hence $n > \lambda$. In Theorem 28.7, take $m = n$, $t = p$. \square

Example 28.3. Consider a hypothetical $(25,9,3)$ -difference set. Take $t = 2$ and $m = 6$ in the above theorem. Since $3^3 \equiv 2 \pmod{25}$, we may conclude that 2 is a multiplier.

Problem 28E. Find all normalized difference sets with parameters $(15, 7, 3)$, $(25, 9, 3)$, $(39, 19, 9)$, $(43, 15, 5)$, and $(61, 16, 4)$. Determine, for each parameter set, whether these normalized difference sets are equivalent. (Note: difference sets do not exist for most parameter sets.)

Problem 28F. Let D be a nontrivial (v, k, λ) -difference set. Prove that if -1 is a multiplier of D , then v is even.

Problem 28G. Find a $(36,15,6)$ -difference set in $\mathbb{Z}_6 \times \mathbb{Z}_6$ with -1 as a multiplier.

* * *

Suppose D is a (v, k, λ) -difference set in an abelian group G of even order v . By Theorem 19.11(i), we know that n is a square. But in the case of difference sets, we can say *what* n is the square of! Let A be any subgroup of G of index 2. Say D contains a elements of A and b elements of $B := G \setminus A$. Since every element of B occurs λ times as a difference from D , and only differences of one element in A and one in B lie in B , $2ab = \frac{1}{2}\lambda v$. From this and $a + b = k$, we find that $(a - b)^2 = n$.

Now suppose v is divisible by 3, let A be a subgroup of G of index 3, and let B and C be the cosets of A in G . Say D contains a elements of A , b elements of B , and c elements of C . The number of differences from D which lie in B , say, is $ba + cb + ac$, which on the other hand must be $\frac{1}{3}\lambda v$. From this and $a + b + c = k$, we can check that $4n = (b + c - 2a)^2 + 3(b - c)^2$. Now it is not true that every integer can be written as the sum of a square and three times another square, so this condition rules out the existence of certain difference sets. For example, there are no $(39, 19, 9)$ -difference sets, even though there are symmetric designs with these parameters, because $4n = 40$ cannot be written as above.

We generalize the above necessary conditions on the parameters of difference sets by considering homomorphisms of the group ring.

If α is a homomorphism $G \rightarrow H$, then α induces a ring homomorphism $\mathbb{Z}[G] \rightarrow \mathbb{Z}[H]$:

$$A(x) = \sum a_g x^g \quad \mapsto \quad A(x^\alpha) := \sum a_g x^{\alpha(g)} \in \mathbb{Z}[H].$$

Theorem 28.8. *Let D be a (v, k, λ) -difference set in an abelian group G . Let $u > 1$ be a divisor of v . If p is a prime divisor of n and*

$$p^f \equiv -1 \pmod{u}$$

for some integer f , then p does not divide the squarefree part of n .

PROOF: We prove something stronger. Let $\alpha : G \rightarrow H$ be a homomorphism onto a group H of order u and exponent u^* , say. Suppose p is prime and $p^f \equiv -1 \pmod{u^*}$ for some f . We will show that n is exactly divisible by an even power p^{2j} of p and that for this j ,

$$D(x^\alpha) \equiv 0 \pmod{p^j, H} \quad \text{in } \mathbb{Z}[H].$$

In other words, all the coefficients of $D(x^\alpha)$, which are the numbers of elements of D belonging to the various cosets of the kernel of α , are congruent to each other modulo p^j .

Let p^i be the highest power of p which divides n . Our hypothesis $p^f \equiv -1 \pmod{u^*}$ means that $D(x^{-\alpha}) = D(x^{p^f \alpha})$ in $\mathbb{Z}[H]$ (where we will do our calculations), so we have

$$(28.2) \quad D(x^\alpha)D(x^{p^f \alpha}) = \\ D(x^\alpha)D(x^{-\alpha}) = n + \lambda \frac{v}{u} H(x) \equiv 0 \pmod{p^i, H}.$$

Let p^j be the highest power of p so that $D(x^\alpha) \equiv 0 \pmod{p^j, H}$; say $D(x^\alpha) \equiv p^j A(x) \pmod{H}$. The reader may check that (28.2) implies that $2j \leq i$ and that if $2j < i$, then $A(x)A(x^{p^f}) \equiv 0 \pmod{p, H}$. But then Lemmas 28.2 and 28.6 imply in turn that $A(x)^{1+p^f} \equiv 0 \pmod{p, H}$ and then $A(x) \equiv 0 \pmod{p, H}$. This contradicts the choice of j , so $2j = i$. \square

Consequences of Theorem 28.8 are: if v is divisible by 3, then all prime divisors of the squarefree part of n are congruent to 0 or 1 (modulo 3); if v is divisible by 5, then all prime divisors of the squarefree part of n are congruent to 0 or 1 (modulo 5); if v is divisible by 7, then all prime divisors of the squarefree part of n are congruent to 0, 1, 2, or 4 (modulo 7).

Example 28.4. We give an application of the stronger claim given in the proof of Theorem 28.8. Consider a hypothetical $(154, 18, 2)$ -difference set D in G . Let $\alpha : G \rightarrow H$ be a homomorphism onto a group H of order $u := 11$. Take $p := 2$. Since $2^5 \equiv -1 \pmod{11}$, we conclude that $D(x^\alpha) \equiv 0 \pmod{4, H}$. This means the 11 coefficients of $D(x^\alpha)$ are all congruent to some integer h modulo 4; since the 11 coefficients sum to 18, h is 2. But then the coefficients would sum to at least 22 and this contradiction shows that no such difference sets exist.

Problem 28H. Let D be a $(q^4 + q^2 + 1, q^2 + 1, 1)$ -difference set in an abelian group G . Let $\alpha : G \rightarrow H$ be a homomorphism onto a group H of order $u := q^2 - q + 1$. Show that any coset of the kernel of α is the point set of a Baer subplane of the projective plane of order q^2 arising from D . For example, the 21 points of the projective plane of order 4 are partitioned into three Fano configurations.

Problem 28I. Let D be a $(q^3 + q^2 + q + 1, q^2 + q + 1, q + 1)$ -difference set in an abelian group G . Let $\alpha : G \rightarrow H$ be a homomorphism onto a group H of order $u := q + 1$. Show that the translates of D meet the cosets of the kernel of α in $q + 1$ points or a single point. Show further that if the symmetric design arising from D consists of the points and planes of $PG_3(q)$, then the cosets are ovoids (see Example 26.5).

Notes.

The celebrated Multiplier Theorem was first proved in the case of cyclic planar difference sets in Hall (1947). It was generalized to $\lambda > 1$ by Hall and Ryser (1951) and since then has been extended in many ways—see e.g. Mann (1965), Baumert (1971), and Lander (1983). Algebraic number theory and characters of abelian groups often play a role in the proofs of these results, but we have chosen here to give proofs of Theorem 28.7 and 28.8 using only the group ring.

Marshall Hall (1910–1990) did fundamental work in group theory and coding theory as well as on combinatorial designs. He has been a tremendous influence on many mathematicians, including the authors.

Theorem 28.8 is due to K. Yamamoto (1963).

References.

- L. D. Baumert (1971), *Cyclic Difference Sets*, Lecture Notes in Math. **182**, Springer-Verlag.
- M. Hall (1947), Cyclic projective planes, *Duke J. Math.* **14**, 1079–1090.
- M. Hall and H. J. Ryser (1951), Cyclic incidence matrices, *Canad. J. Math.* **3**, 495–502.
- E. S. Lander (1983), *Symmetric Designs: An Algebraic Approach*, London Math. Soc. Lecture Note Series **74**, Cambridge University Press.
- H. B. Mann (1965), *Addition Theorems*, Wiley.
- K. Yamamoto (1963), Decomposition fields of difference sets, *Pacific J. Math.* **13**, 337–352.

29

Codes and symmetric designs

In this chapter, we elaborate on some of the material introduced in Chapter 20. We saw in that chapter that the rows of the incidence matrix of a projective plane of order $n \equiv 2 \pmod{4}$ span a binary code which, when extended, is self-dual. It was observed by H. A. Wilbrink (1985) and others that that result can be used to show that planar difference sets do not exist for values of $n > 2$ with $n \equiv 2 \pmod{4}$; see Theorem 29.7.

One can consider the code spanned by the rows of the incidence matrix over other prime fields \mathbb{F}_p as well. With essentially the same proof as that of Theorem 20.6, we have the following theorem.

Theorem 29.1. *If p divides $n := k - \lambda$, then the \mathbb{F}_p -span C of the rows of the incidence matrix N of a symmetric (v, k, λ) -design has dimension at most $(v + 1)/2$ over \mathbb{F}_p . If $(p, k) = 1$ and p^2 does not divide n , then the dimension of this p -ary code is exactly $(v + 1)/2$.*

Problem 29A. Prove Theorem 29.1.

It is not possible, in general, to extend the code C to get a code of length $v + 1$ that is self-orthogonal with respect to the *standard* dot product on \mathbb{F}_p^v . But let us consider other ‘scalar products’ for odd primes p .

To a nonsingular $m \times m$ matrix B over a field \mathbb{F} , we may associate the scalar product (or bilinear form)

$$\langle \mathbf{x}, \mathbf{y} \rangle := \mathbf{x}B\mathbf{y}^\top$$

for $\mathbf{x}, \mathbf{y} \in \mathbb{F}^m$. For a subspace C of \mathbb{F}^m , let

$$C^B := \{\mathbf{x} : \langle \mathbf{x}, \mathbf{y} \rangle = 0 \text{ for all } \mathbf{y} \in C\}.$$

Then C and C^B have complementary dimensions and $(C^B)^B = C$. We say that C is *totally isotropic* when $C \subseteq C^B$; this is the appropriate terminology for this generalization of self-orthogonal. We have use for the following theorem of Witt, and we include a proof here as it is essentially a rephrasing of part of Theorem 26.6.

Theorem 29.2. *Given a symmetric nonsingular matrix B over a field \mathbb{F} of odd characteristic, there exists a totally isotropic subspace of dimension $m/2$ in \mathbb{F}^m if and only if $(-1)^{m/2} \det(B)$ is a square in \mathbb{F} .*

PROOF: A totally isotropic subspace of dimension $m/2$ is, when considered as a set of projective points in $PG(m - 1, 2)$, a flat of projective dimension $(m/2) - 1$ that is contained completely in the quadric Q defined by the nondegenerate quadratic form

$$f(\mathbf{x}) = \mathbf{x}B\mathbf{x}^\top.$$

By Theorem 26.6, such a subspace exists if and only if Q is hyperbolic. It remains only to verify that Q is hyperbolic if and only if $(-1)^{m/2} \det(B)$ is a square in \mathbb{F} .

If f_1 is a form projectively equivalent to f , then $f_1(\mathbf{x}) = \mathbf{x}B_1\mathbf{x}^\top$ where $B_1 = UB_1U^\top$ for some nonsingular matrix U . Of course, $(-1)^{m/2} \det(B)$ is a square if and only if $(-1)^{m/2} \det(B_1)$ is a square.

If Q is hyperbolic, then f is equivalent to $f_1 = x_1x_2 + \dots + x_{m-1}x_m$ and B_1 is block diagonal with $m/2$ matrices

$$W = \frac{1}{2} \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}$$

on the diagonal. Then $(-1)^{m/2} \det(B_1) = 1/2^m$, which is a square.

If Q is elliptic, then f is equivalent to $f_1 = x_1x_2 + \dots + x_{m-3}x_{m-2} + p(x_{m-1}, x_m)$ where $p(x, y) = ax^2 + 2bxy + cy^2$ is an irreducible quadratic form over \mathbb{F} , and here B_1 is block diagonal with $(m/2) - 1$ matrices W and one matrix

$$\begin{pmatrix} a & b \\ b & c \end{pmatrix}$$

on the diagonal. Then $(-1)^{m/2} \det(B_1) = (b^2 - ac)/2^{m-2}$, and this is a nonsquare in \mathbb{F} since p is irreducible. □

It will be convenient to retain the term *self-dual* for a totally isotropic subspace of dimension equal to half its length. E. S. Lander (1983) has shown how to associate a *family* of p -ary codes of length $v + 1$ and a scalar product to a symmetric design in such a way that one of the codes is self-dual when n is exactly divisible by an odd power of p . Theorem 29.2 then gives us a condition on the parameters of the symmetric design. It turns out that these conditions are already consequences of the Bruck–Ryser–Chowla theorem, Theorem 19.11. In some sense, then, these self-dual codes provide a ‘combinatorial interpretation’ of part of the BRC theorem. In any case, these codes carry information about the design and have further applications in the theory of symmetric designs—see Lander (1983).

Theorem 29.3. *Suppose there exists a symmetric (v, k, λ) -design where n is exactly divisible by an odd power of a prime p . Write $n = p^f n_0$ (f odd) and $\lambda = p^b \lambda_0$ with $(n_0, p) = (\lambda_0, p) = 1$. Then there exists a self-dual p -ary code of length $v + 1$ with respect to the scalar product corresponding to*

$$B = \begin{cases} \text{diag}(1, 1, \dots, 1, -\lambda_0) & \text{if } b \text{ is even,} \\ \text{diag}(1, 1, \dots, 1, n_0 \lambda_0) & \text{if } b \text{ is odd.} \end{cases}$$

Hence from Theorem 29.2,

$$\begin{cases} -(-1)^{(v+1)/2} \lambda_0 \text{ is a square (mod } p) & \text{if } b \text{ is even,} \\ (-1)^{(v+1)/2} n_0 \lambda_0 \text{ is a square (mod } p) & \text{if } b \text{ is odd.} \end{cases}$$

Towards the proof of Theorem 29.3, we first prove two propositions.

Given any integral $m \times m$ matrix A , we may consider the \mathbb{Z} -module $M(A)$ consisting of all *integral* linear combinations of its rows; that is,

$$M(A) := \{\mathbf{y}A : \mathbf{y} \in \mathbb{Z}^m\}.$$

Fix a prime p and for any positive integer i define modules

$$M_i := \{\mathbf{x} \in \mathbb{Z}^m : p^i \mathbf{x} \in M(A)\},$$

$$N_i := \{\mathbf{y} \in \mathbb{Z}^m : A\mathbf{y}^\top \equiv 0 \pmod{p^{i+1}}\}.$$

We have $M_0 = M(A)$, $M_i \subseteq M_{i+1}$ and $N_i \supseteq N_{i+1}$ for all i . Let

$$(29.1) \quad C_i := M_i \pmod{p}, \quad D_i := N_i \pmod{p}.$$

That is, read all the integer vectors in M_i or N_i modulo p to obtain C_i or D_i . Then each C_i and D_i is a subspace of the vector space \mathbb{F}_p^m , i.e. a p -ary linear code. Clearly,

$$C_0 \subseteq C_1 \subseteq C_2 \subseteq \dots \quad \text{and} \quad D_0 \supseteq D_1 \supseteq D_2 \dots$$

Proposition 29.4. *We have*

$$C_i^\perp = D_i$$

for all nonnegative integers i .

PROOF: Let \mathbf{x} and \mathbf{y} be integral vectors such that $\mathbf{x} \pmod{p} \in C_i$ and $\mathbf{y} \pmod{p} \in D_i$. This means

$$p^i(\mathbf{x} + p\mathbf{a}) = \mathbf{z}A \quad \text{and} \quad A(\mathbf{y} + p\mathbf{b})^\top \equiv 0 \pmod{p^{i+1}}$$

for some integral vectors \mathbf{a} , \mathbf{b} , and \mathbf{z} . Then

$$p^i(\mathbf{x} + p\mathbf{a}) \cdot (\mathbf{y} + p\mathbf{b})^\top = \mathbf{z}A(\mathbf{y} + p\mathbf{b})^\top \equiv 0 \pmod{p^{i+1}}$$

which implies that $\mathbf{x} \cdot \mathbf{y}^\top = 0$ over \mathbb{F}_p .

We complete the proof by showing that C_i and D_i have dimensions which add to m . There exist unimodular matrices E and F (integral matrices with integral inverses) such that $S := EAF$ is diagonal with integral diagonal entries d_1, d_2, \dots, d_m which successively divide one another: $d_1 | d_2 | \dots | d_m$. (S is the *Smith normal form* of A and the d_i 's are the *invariant factors*.) The reader should verify that the modules M_i and N_i are *equivalent* to

$$M'_i := \{\mathbf{x} : p^i \mathbf{x} \in M(S)\} \quad \text{and}$$

$$N'_i := \{\mathbf{y} : S\mathbf{y}^\top \equiv 0 \pmod{p^{i+1}}\},$$

respectively, in the sense that either can be obtained from the other by application of a unimodular transformation. Hence the dimensions over \mathbb{F}_p of M_i and M'_i are equal, as well as the dimensions of N_i and N'_i .

Suppose p^{i+1} does not divide d_1, \dots, d_t but that p^{i+1} does divide d_{t+1}, \dots, d_m . Then $\mathbf{y} \in N'_i$ implies that the first t coordinates of \mathbf{y} are divisible by p ; any vector \mathbf{y} with 0's in the first t coordinates is in N'_i . Thus $N'_i \pmod{p}$ is the span of the last $m - t$ standard basis vectors and has dimension $m - t$. Also, $\mathbf{x} \in M'_i$ implies that the last $d - t$ coordinates of \mathbf{x} are divisible by p and a little more thought shows that $M'_i \pmod{p}$ is the span of the first t standard basis vectors and has dimension t . \square

Proposition 29.5. *Let $A, B,$ and U be $m \times m$ integral matrices with*

$$(29.2) \quad ABA^\top = nU,$$

and where U and B are nonsingular modulo a prime p . Write $n = p^e n_0$ where $(p, n_0) = 1$. Define the sequence C_i of p -ary codes from A as in (29.1). Then $C_e = \mathbb{F}_p^m$ and

$$C_i^B = C_{e-i-1} \quad \text{for } i = 0, 1, \dots, e - 1.$$

In particular, if e is odd, then $C_{\frac{1}{2}(e-1)}$ is a self-dual p -ary code with respect to the scalar product given by B on \mathbb{F}_p^m .

PROOF: Let \mathbf{x} and \mathbf{y} be integral vectors such that $\mathbf{x} \pmod{p} \in C_i$ and $\mathbf{y} \pmod{p} \in C_{e-i-1}$. This means

$$p^i(\mathbf{x} + p\mathbf{a}_1) = \mathbf{z}_1 A \quad \text{and} \quad p^{e-i-1}(\mathbf{y} + p\mathbf{a}_2) = \mathbf{z}_2 A$$

for some integral vectors $\mathbf{z}_1, \mathbf{z}_2, \mathbf{a}_1,$ and \mathbf{a}_2 . Then

$$p^{e-1}\langle \mathbf{x}, \mathbf{y} \rangle = p^{e-1}\mathbf{x}B\mathbf{y}^\top \equiv \mathbf{z}_1 ABA^\top \mathbf{z}_2^\top \equiv 0 \pmod{p^e}$$

in view of (29.2). Thus $\langle \mathbf{x}, \mathbf{y} \rangle = 0$ in \mathbb{F}_p and we see $C_{e-i-1} \subseteq C_i^B$.

Now let $\mathbf{x} \in C_i^B$. This means $\mathbf{x}B \in C_i^\perp$, which is D_i by Proposition 29.4, and so for some integral vector \mathbf{x}' which reduces to \mathbf{x} when read modulo p ,

$$\mathbf{x}'BA^\top \equiv 0 \pmod{p^{i+1}}.$$

From (29.2), $A \cdot BA^\top U^{-1} = nI$, and since a matrix commutes with its inverse,

$$(29.3) \quad BA^\top U^{-1} \cdot A = nI.$$

Since U is nonsingular modulo p , dU^{-1} is integral for some d prime to p , e.g. $d := \det(U)$. We multiply (29.3) on the left by $d\mathbf{x}'$ to get

$$\mathbf{x}'BA^\top(dU^{-1})A = p^e dn_0 \mathbf{x}',$$

and then

$$\mathbf{z}A = p^{e-i-1} dn_0 \mathbf{x}'$$

where $\mathbf{z} := \frac{1}{p^{i+1}} \mathbf{x}'BA^\top(dU^{-1})$ is integral. This means $p^{e-i-1} dn_0 \mathbf{x}'$ is in M_{e-i-1} and hence $\mathbf{x} \in C_{e-i-1}$.

The assertion that $C_e = \mathbb{F}_p^m$ is left as an easy problem. □

Problem 29B. Prove that $C_e = \mathbb{F}_p^m$.

PROOF OF THEOREM 29.3: Let N be the incidence matrix of a symmetric (v, k, λ) -design and let p be a prime. Assume $\lambda = p^{2a} \lambda_0$ where $(\lambda_0, p) = 1$ and $a \geq 0$; we will explain later what to do when λ is exactly divisible by an odd power of p . Let

$$(29.4) \quad A := \begin{pmatrix} & & p^a \\ & N & \vdots \\ p^a \lambda_0 & \cdots & p^a \lambda_0 \\ & & k \end{pmatrix}, \quad B := \begin{pmatrix} 1 & & 0 \\ & \ddots & \\ & & 1 \\ 0 & & & -\lambda_0 \end{pmatrix}.$$

The reader should verify, using the properties of N and the relation $\lambda(v-1) = k(k-1)$, that $ABA^\top = nB$.

In the case λ is exactly divisible by an even power of p , we apply Proposition 29.5 with the matrices A and B as in (29.4), and where $U := B$.

If λ is exactly divisible by an odd power of p , we apply the above case to the *complement* of the given symmetric design, which is a symmetric $(v, v-k, \lambda')$ -design where $\lambda' = v-2k+\lambda$. Say $\lambda' = p^c \lambda'_0$ where $(\lambda'_0, p) = 1$. From $\lambda \lambda' = n(n-1)$, it follows that c is odd and that

$$\lambda_0 \lambda'_0 = n_0(n-1) \equiv -n_0 \pmod{p}.$$

We have replaced what would be $-\lambda'_0$ in the conclusion by $\lambda_0 n_0$, which is allowed since they differ by a square factor modulo p , in order to express the result in terms of the original parameters. \square

The following theorem is a consequence of Problem 19M, but we give a proof similar to that of Theorem 29.3.

Theorem 29.6. *If there exists a conference matrix of order $n \equiv 2 \pmod{4}$, then no prime $p \equiv 3 \pmod{4}$ can divide the square-free part of $n - 1$.*

PROOF: A conference matrix of order n is, in particular, an integral matrix A such that $AA^\top = (n - 1)I_n$. By Proposition 29.5 with $A = U = I$, there exists a self-dual p -ary code (self-dual with respect to the standard inner product) of length n for every prime divisor p of the square-free part of $n - 1$. Theorem 29.2 then implies that every such prime is $\equiv 1 \pmod{4}$. \square

* * *

When p is a prime not dividing the order v of an abelian group G , the group ring $\mathbb{F}_p[G]$ is a *semi-simple* algebra over $\mathbb{F}_p = \mathbb{Z}_p$. This means that there exist no nonzero nilpotents, i.e. nonzero elements a such $a^m = 0$ for some positive integer m . The nonexistence of nonzero nilpotents is proved in Lemma 28.5. By Wedderburn's theorem, every finite-dimensional commutative semi-simple algebra with identity \mathcal{A} over a field F is isomorphic to the direct product of fields, each an extension of F . It follows that each ideal \mathcal{I} of \mathcal{A} is principal and is generated by an *idempotent* e , i.e. an element e with $e^2 = e$. See any advanced text on algebra for proofs.

We do not need all of this information, but here are some facts about principal ideals which are generated by idempotents that we will need. These make good exercises.

First, if $\mathcal{I} = \langle e_1 \rangle$ and also $\mathcal{I} = \langle e_2 \rangle$, where both e_1 and e_2 are idempotent, then $e_1 = e_2$. Suppose $\mathcal{I}_1 = \langle e_1 \rangle$ and $\mathcal{I}_2 = \langle e_2 \rangle$, where e_1 and e_2 are idempotent. Then

$$\mathcal{I}_1 \cap \mathcal{I}_2 = \langle e_1 e_2 \rangle \quad \text{and} \quad \mathcal{I}_1 + \mathcal{I}_2 = \langle e_1 + e_2 - e_1 e_2 \rangle.$$

Note that $e_1 e_2$ and $e_1 + e_2 - e_1 e_2$ are again idempotents.

Theorem 29.7. *Let D be an $(n^2 + n + 1, n + 1, 1)$ -difference set in an abelian group G of order $v := n^2 + n + 1$. If $n \equiv 0 \pmod{2}$ but $n \not\equiv 0 \pmod{4}$, then $n = 2$. If $n \equiv 0 \pmod{3}$ but $n \not\equiv 0 \pmod{9}$, then $n = 3$.*

PROOF: Let D be a $(n^2 + n + 1, n + 1, 1)$ -difference set in an abelian group G and let p be a prime divisor of n . By Theorem 28.3, p is a multiplier of D and we will assume from now on that D is fixed by p . We work in the \mathbb{F}_p -algebra $\mathbb{F}_p[G]$.

Let \mathcal{I}_1 be the ideal in $\mathbb{F}_p[G]$ generated by $D(x)$ and \mathcal{I}_2 the ideal generated by $D(x^{-1})$.

We have $D(x^p) = D(x)$, but $D^p(x) = D(x^p)$ by Lemma 28.2, so $D^p(x) = D(x)$ in $\mathbb{F}_p[G]$. Then $D^{p-1}(x)$ is idempotent and will also generate \mathcal{I}_1 . Similarly, $D^{p-1}(x^{-1})$ is an idempotent generator for \mathcal{I}_2 . So the idempotent generator of $\mathcal{I}_1 \cap \mathcal{I}_2$ is

$$D^{p-1}(x)D^{p-1}(x^{-1}) = (n + G(x))^{p-1} = G(x),$$

and the idempotent generator of $\mathcal{I}_1 + \mathcal{I}_2$ is

$$D^{p-1}(x) + D^{p-1}(x^{-1}) - G(x).$$

We now wish to consider the dimensions of \mathcal{I}_1 and \mathcal{I}_2 over \mathbb{F}_p . In general, the rank of a principal ideal generated by $A(x)$ is the rank of the $v \times v$ matrix whose rows are the coefficients of $x^g A(x)$, $g \in G$. This matrix is the incidence matrix of a symmetric $(n^2 + n + 1, n + 1, 1)$ -design when $A(x) = D(x)$ or $D(x^{-1})$. If we now assume that p^2 does not divide n , then by Theorem 29.1, \mathcal{I}_1 and \mathcal{I}_2 have dimension $(v + 1)/2$. The intersection $\mathcal{I}_1 \cap \mathcal{I}_2$ has dimension 1, so their sum must have dimension v . The idempotent generator of the whole group ring, as an ideal in itself, is 1; so we conclude that

$$(29.5) \quad D^{p-1}(x) + D^{p-1}(x^{-1}) - G(x) = 1 \quad \text{in } \mathbb{F}_p[G].$$

We are only able to exploit the above equation when $p = 2$ or 3 . When $p = 2$, (29.5) asserts $D(x) + D(x^{-1}) \equiv 1 + G(x) \pmod{2}$ in $\mathbb{Z}[G]$. The number of odd coefficients of $1 + G(x)$ is $v - 1 = n^2 + n$,

but the number of odd coefficients of $D(x) + D(x^{-1})$ cannot exceed $2(n+1)$; it follows that $n \leq 2$.

When $p = 3$, (29.5) asserts $D^2(x) + D^2(x^{-1}) \equiv 1 + G(x) \pmod{3}$ in $\mathbb{Z}[G]$. We claim that the nonzero coefficients of $D^2(x)$ and $D^2(x^{-1})$ consist of $n+1$ coefficients that are 1's and $\binom{n+1}{2}$ coefficients that are 2's. If C is any planar difference set, there will be a term x^{2g} in $C^2(x)$ for each $g \in C$ and a term $2x^{g+h}$ for each unordered pair $\{g, h\} \subseteq C$; note that $\lambda = 1$ implies, e.g., that $g_1 + h_1 \neq g_2 + h_2$ unless $\{g_1, h_1\} = \{g_2, h_2\}$. The sum of two such group ring elements cannot have more than $\binom{n+1}{2} + 2(n+1)$ coefficients that are $\equiv 1 \pmod{3}$, but $1 + G(x)$ has $n^2 + n$ coefficients that are $\equiv 1$; it follows that $n \leq 4$. \square

Problem 29C. Suppose D is a difference set with $n \equiv 2 \pmod{4}$ and that 2 is a multiplier of D . What are the parameters of D , as functions of n ?

Notes.

Some of the material preceding the proof of Theorem 29.3 is more elegant when p -adic numbers are introduced as in Lander (1983), but we have chosen to present the material without them.

References.

- D. Jungnickel and K. Vedder (1984), On the geometry of planar difference sets, *European J. Combinatorics* **5**, 143–148.
- E. S. Lander (1983), *Symmetric Designs: An Algebraic Approach*, London Math. Soc. Lecture Note Series **74**, Cambridge University Press.
- V. Pless (1986), Cyclic projective planes and binary extended cyclic self-dual codes, *J. Combinatorial Theory* (A) **43**, 331–333.
- H. A. Wilbrink (1985), A note on planar difference sets, *J. Combinatorial Theory* (A) **38**, 94–95.

30

Association schemes

Given two k -subsets A, B of an n -set, $n \geq 2k$, there are $k + 1$ possible relations between them: they may be equal, they may intersect in $k - 1$ elements, they may intersect in $k - 2$ elements, \dots , or they may be disjoint.

Given two words (k -tuples) $\mathbf{a}, \mathbf{b} \in A^k$, where A is an ‘alphabet’ of size at least 2, there are $k + 1$ possible relations between them: they may be equal, they may agree in $k - 1$ coordinates, they may agree in $k - 2$ coordinates, \dots , or they may disagree in all coordinates.

These instances of a set together with a list of mutually exclusive and exhaustive binary relations are examples of *association schemes*, which we define shortly. Association schemes provide one of the foundations of combinatorics and so we include this chapter even though it will be difficult reading. They have been implicit in many of the previous chapters; we have explicitly discussed 2-class association schemes, as they are equivalent to the strongly regular graphs discussed in Chapter 21. This chapter elaborates on some of the material of Chapter 21 but has different goals.

Association schemes arose first in the statistical theory of design of experiments, but the work of Ph. Delsarte (1973) has shown how they serve to unify many aspects of our subject. In particular, certain results of coding theory and the theory of t -designs—which were originally discovered independently—are now seen to be ‘formally dual’ aspects of the same ideas in association schemes. For example, Fisher’s inequality and its generalization, Theorem 19.8, is formally dual to the sphere packing bound, Theorem 21.1. We use the machinery of association schemes in this chapter to give proofs of Lloyd’s theorem on perfect codes and its formal dual theorem for tight designs and orthogonal arrays. Delsarte’s inequalities,

Theorem 30.3, on the distribution vector of a subset of an association scheme provide a ‘linear programming bound’ on the size of codes and are also of interest in extremal set theory.

By a *binary relation* on a set \mathfrak{X} , we mean a subset of $\mathfrak{X} \times \mathfrak{X}$. A *k-class association scheme*, sometimes we say just *scheme*, on a set \mathfrak{X} of *points* consists of $k + 1$ nonempty symmetric binary relations R_0, R_1, \dots, R_k on \mathfrak{X} which partition $\mathfrak{X} \times \mathfrak{X}$, where $R_0 = \{(x, x) : x \in \mathfrak{X}\}$ is the identity relation, and such that for some nonnegative integers p_{ij}^ℓ , $0 \leq \ell, i, j \leq k$, the following system of axioms holds: given any $(x, y) \in R_\ell$, there are exactly p_{ij}^ℓ elements $z \in \mathfrak{X}$ such that $(x, z) \in R_i$ and $(z, y) \in R_j$. We say $x, y \in \mathfrak{X}$ are *i-th associates* when $(x, y) \in R_i$.

The numbers p_{ij}^ℓ , $0 \leq \ell, i, j \leq k$, are the *parameters* of the scheme. That p_{ii}^0 exists means that there is a constant number of *i-th associates* of any element of \mathfrak{X} , which is usually denoted by n_i . We have

$$(30.1) \quad p_{ii}^0 = n_i \quad \text{and} \quad p_{ij}^0 = 0 \quad \text{for } i \neq j$$

and

$$n_0 = 1, \quad n_0 + n_1 + \dots + n_k = N.$$

where $N := |\mathfrak{X}|$. The numbers n_0, n_1, \dots, n_k are called the *degrees* of the scheme.

Example 30.1. The Johnson schemes $J(v, k)$. The points of the scheme $J(v, k)$ are the $\binom{v}{k}$ k -subsets of a v -set S . Two k -subsets A, B are declared to be *i-th associates* when $|A \cap B| = k - i$. Thus 0-th associates are equal. The parameters p_{ij}^ℓ exist ‘by symmetry’ and may be expressed as sums of products of binomial coefficients, but we will not bother to write these out in general.

The scheme $J(6, 3)$, for example, is a 3-class scheme with 20 points. The reader should check that $n_1 = n_2 = 9$, $n_3 = 1$. A few of the other parameters are $p_{11}^1 = 4$, $p_{11}^2 = 4$, $p_{11}^3 = 0$.

Example 30.2. The Hamming schemes $H(n, q)$. The points of $H(n, q)$ are the q^n words of length n over an alphabet of size q . Two n -tuples x, y are declared to be *i-th associates* when they disagree in exactly i coordinates. Thus 0-th associates are equal. The

parameters p_{ij}^ℓ exist ‘by symmetry’ and may be expressed as sums of products of binomial coefficients and powers of $q - 1$, but we will not bother to write these out in general.

The scheme $H(5, 3)$, for example, is a 5-class scheme with 125 points. The reader should check that $n_1 = 5 \cdot 2$, $n_2 = 10 \cdot 4$, etc.

Each of the relations R_i may be thought of as the adjacency relation of a graph G_i on the vertex set \mathfrak{X} . (A scheme is a special kind of partition of the edges—or coloring of the edges—of a complete graph.) It should be clear that if we start with a 2-class scheme, then G_1 is a strongly regular graph with degree n_1 , $\lambda = p_{11}^1$, and $\mu = p_{11}^2$. In fact, any strongly regular graph gives rise to a 2-class association scheme when we declare that two distinct vertices are 1st associates when they are adjacent in G and 2nd associates if not adjacent; the other parameters exist, i.e. are constant, and can be computed from the parameters of the graph. For example, $p_{12}^1 = k - \lambda - 1$.

A *distance regular graph* is a graph G such that the number of vertices at distance i to x and distance j to y depends only on the distance ℓ between the vertices x and y , not on the particular vertices. That is, defining two vertices to be i -th associates if and only if their distance in G is i produces an association scheme (where the number of classes will be the diameter of the graph). See Brouwer, Cohen, and Neumaier (1989). Schemes which arise in this way are called *metric*. The schemes mentioned in Examples 30.1 and 30.2 above are metric, as are those in Examples 30.3 and 30.4 below.

It is important to know that the parameters p_{ij}^ℓ exist; it is not so important to know their exact values. This is lucky because there is often no convenient expression for these parameters. In the scheme $J(v, k)$, for example, a triple sum of binomial coefficients seems to be required for the general p_{ij}^ℓ . In the examples we have just given, we know that the p_{ij}^ℓ ’s exist because of ‘symmetry’. More precisely, in each case there exists a group G of permutations of \mathfrak{X} so that two ordered pairs of points (x_1, y_1) and (x_2, y_2) are in the same relation R_i if and only if there exists $\sigma \in G$ such that $\sigma(x_1) = x_2$ and $\sigma(y_1) = y_2$. That is, the relations R_0, R_1, \dots, R_k are the *orbits* of G on $\mathfrak{X} \times \mathfrak{X}$ (with R_0 the trivial orbit of all (x, x) , $x \in \mathfrak{X}$). In Example 30.1, G is the symmetric group S_v acting on all k -subsets of a v -set;

we can find a permutation which takes an ordered pair of k -subsets to another if and only if the size of the intersection of each pair is the same. In Example 30.2, G is the wreath product of S_q with S_n (that is, we allow any permutation of the n coordinates followed by independent permutations of the q symbols in each coordinate); we can find such a transformation which takes an ordered pair of n -tuples to another if and only if the pairs agree in the same number of coordinates.

In general, if G is a transitive group of permutations on a set \mathfrak{X} such that the orbits of G on $\mathfrak{X} \times \mathfrak{X}$ are symmetric, they may be taken as the relations of an association scheme on \mathfrak{X} . Our next three examples also arise in this way.

Example 30.3. This is the q -analogue of the Johnson scheme: Take the k -subspaces of a v -space V over \mathbb{F}_q as points. Two k -subspaces A, B are declared to be i -th associates when $\dim(A \cap B) = k - i$.

Example 30.4. Take the $k \times m$ matrices over \mathbb{F}_q as the points, where $k \leq m$, say. Two matrices A, B are declared to be i -th associates when the rank of $A - B$ is $k - i$.

To put this example into the framework above, we let \mathfrak{X} be the set of all $k \times m$ matrices and we may take G to be the set of all permutations $X \mapsto UXW + C$ as U ranges over the nonsingular $k \times k$ matrices, W over the nonsingular $m \times m$ matrices, and C over the $k \times m$ matrices. If (A, B) and (A', B') are pairs of $k \times m$ matrices such that the ranks of $A - B$ and $A' - B'$ are equal, then $U(A - B)W = A' - B'$ for some nonsingular U and W , and then $X \mapsto UXW + (B' - UBW)$ will map the first pair onto the second.

Example 30.5. The *cyclotomic schemes* are obtained as follows. Let q be a prime power and k a divisor of $q - 1$. Let C_1 be the subgroup of the multiplicative group of \mathbb{F}_q of index k , and let C_1, C_2, \dots, C_k be the cosets of C_1 . The points of the scheme are to be the elements of \mathbb{F}_q , and two points x, y are declared to be i -th associates when $x - y \in C_i$ (and 0-th associates when $x - y = 0$). In order to have a scheme with the above definition, we require $-1 \in C_1$ so that the relations will be symmetric, i.e. $2k$ must di-

vide $q - 1$ if q is odd. Cf. Example 21.3 which is the case $k = 2$.

We introduce the *association matrices* A_0, A_1, \dots, A_k (also called the *adjacency matrices*) of an association scheme. These matrices are square with both rows and columns indexed by the elements of the point set \mathfrak{X} of a scheme. For $i = 0, 1, \dots, k$, we define

$$A_i(x, y) = \begin{cases} 1 & \text{if } (x, y) \in R_i, \\ 0 & \text{otherwise.} \end{cases}$$

The matrices A_i are symmetric $(0, 1)$ -matrices and

$$A_0 = I, \quad A_0 + A_1 + \dots + A_k = J$$

where J is the all-one matrix of size $N \times N$. We denote by \mathfrak{A} the linear span over the reals of A_0, A_1, \dots, A_k . These matrices are linearly independent since each contains at least one 1; and a position in which A_i has a 1 contains a 0 in every other association matrix. The axioms of an association scheme are exactly what is required to ensure that \mathfrak{A} is closed under matrix multiplication. To see this, it suffices to show that the product of any two of the basis matrices is in \mathfrak{A} and, in fact, we have

$$(30.2) \quad A_i A_j = \sum_{\ell=0}^k p_{ij}^{\ell} A_{\ell}$$

because $A_i A_j(x, y)$ is the number of z such that $A_i(x, z) = 1$ and $A_j(z, y) = 1$, and this number is p_{ij}^{ℓ} where ℓ is such that $A_{\ell}(x, y) = 1$.

The algebra \mathfrak{A} is called the *Bose–Mesner algebra* of the scheme; this algebra was introduced for strongly regular graphs in Chapter 21. We note at this point that not only is \mathfrak{A} closed under normal matrix multiplication, but it is also closed under *Hadamard multiplication* as introduced in Problem 21E. The Hadamard product $A \circ B$ of two matrices is the matrix obtained by coordinate-wise multiplication:

$$(A \circ B)(x, y) := A(x, y)B(x, y).$$

As an algebra with respect to Hadamard multiplication, \mathfrak{A} is almost trivial. We have

$$A_i \circ A_j = \begin{cases} A_i & \text{if } i = j, \\ O & \text{if } i \neq j \end{cases}$$

(that is, A_0, A_1, \dots, A_k are *orthogonal idempotents*), and the sum of the A_i 's is J , the identity with respect to Hadamard multiplication. So Hadamard multiplication is extremely simple when matrices in \mathfrak{A} are expressed with respect to the basis A_0, A_1, \dots, A_k of \mathfrak{A} .

However, a well known result of matrix theory (an extension of the spectral theorem which says that a symmetric real matrix has an orthogonal basis of eigenvectors) asserts that a *commutative* algebra of real symmetric matrices has a basis of orthogonal idempotents *with respect to ordinary matrix multiplication* which sum to the identity. More geometrically, there exists an orthogonal decomposition

$$\mathbb{R}^{\mathfrak{X}} = V_0 \oplus V_1 \oplus \dots \oplus V_k$$

of the Euclidean space $\mathbb{R}^{\mathfrak{X}}$, the space of all vectors whose coordinates are indexed by the elements of \mathfrak{X} with the standard inner product, such that the orthogonal projections E_0, E_1, \dots, E_k from $\mathbb{R}^{\mathfrak{X}}$ onto the subspaces V_0, V_1, \dots, V_k , respectively, are a basis for \mathfrak{A} . We have

$$E_i E_j = \begin{cases} E_i & \text{if } i = j, \\ O & \text{if } i \neq j, \end{cases}$$

and

$$E_0 + E_1 + \dots + E_k = I.$$

Of course, when matrices are expressed with respect to the basis E_0, E_1, \dots, E_k , ordinary multiplication is also extremely simple.

The subspaces V_0, V_1, \dots, V_k are called the *eigenspaces* of the scheme: in a linear combination $M = \sum_{i=0}^k \lambda_i E_i$, each vector in V_i is an eigenvector of value λ_i for M . There is no natural numbering of the eigenspaces *in general* with one exception: since $J \in \mathfrak{A}$, and J has the vector \mathbf{j} of all 1's as an eigenvector of value N and all vectors orthogonal to \mathbf{j} as eigenvectors of value 0, it must be that one of the eigenspaces consists of scalar multiples of \mathbf{j} alone—we shall always assume that this is V_0 . Then the orthogonal projection

onto V_0 (which has \mathbf{j} as an eigenvector of value 1 and all vectors orthogonal to \mathbf{j} as eigenvectors of value 0) is

$$E_0 = \frac{1}{N}J.$$

We let m_i denote the dimension of V_i . Then

$$m_0 = 1, \quad m_0 + m_1 + \cdots + m_k = N.$$

Note that m_i is the trace of E_i since the eigenvalues of E_i are 1 (with multiplicity equal to the dimension of V_i) and 0. The numbers m_0, m_1, \dots, m_k are called the *multiplicities* of the scheme.

Example 30.6. We can explicitly describe the eigenspaces of the Hamming scheme $H(n, 2)$. The points of this scheme are the binary n -tuples (or words) a of \mathbb{F}_2^n .

For each $a \in \mathbb{F}_2^n$, define a vector \mathbf{v}_a with coordinates indexed by the point set by

$$\mathbf{v}_a(b) := (-1)^{\langle a, b \rangle}.$$

These vectors are orthogonal and are the rows of a Hadamard matrix; see Fig. 30.1 and Chapter 18. We claim that V_i may be taken to be the span of all vectors \mathbf{v}_a as a ranges over the words of weight i , $i = 0, 1, \dots, n$.

We check that each \mathbf{v}_a is an eigenvector of all association matrices A_j . Let a have weight ℓ . Then

$$\begin{aligned} (\mathbf{v}_a A_j)(b) &= \sum_c \mathbf{v}_a(c) A_j(c, b) \\ &= \sum_{c: d(b, c) = j} (-1)^{\langle a, c \rangle} = (-1)^{\langle a, b \rangle} \sum_{c: d(b, c) = j} (-1)^{\langle a, b+c \rangle} \\ &= \mathbf{v}_a(b) \sum_{u: \text{wt}(u) = j} (-1)^{\langle a, u \rangle} = \mathbf{v}_a(b) \sum_{i=0}^n (-1)^i \binom{\ell}{i} \binom{n-\ell}{j-i}. \end{aligned}$$

This calculation shows, with E_i the matrix of the orthogonal projection onto V_i , that

$$A_j = \sum_{\ell=0}^n \left(\sum_{i=0}^n (-1)^i \binom{\ell}{i} \binom{n-\ell}{j-i} \right) E_\ell$$

since the two sides give the same result when premultiplied by any \mathbf{v}_a . So $\mathfrak{A} \subseteq \text{span}\{E_0, \dots, E_n\}$. Equality holds because both spaces have dimension $n + 1$.

The eigenvalues of the schemes $H(n, q)$ for general q are given in Theorem 30.1 below.




Figure 30.1

For example, if we order the words of length $n = 3$ as

$$000, 100, 010, 001, 011, 101, 110, 111,$$

then the eigenspaces V_0, V_1, V_2, V_3 of the cube (= A_1 of $H(3, 2)$) shown at the right of Fig. 30.1 are spanned respectively by the first row, the next three rows, the next three rows, and the last row of the Hadamard matrix at the left of Fig. 30.1.

Example 30.7. We now describe the eigenspaces of the Johnson scheme $J(v, k)$. We omit the proofs; see Delsarte (1973) or Wilson (1984b).

The point set of this scheme is the set \mathfrak{X} of k -subsets S of a v -set X . For each subset $T \subseteq X$ of size $\leq k$, let \mathbf{e}_T be the vector of length $\binom{v}{k}$ in $\mathbb{R}^{\mathfrak{X}}$ where

$$\mathbf{e}_T(S) := \begin{cases} 1 & \text{if } T \subseteq S, \\ 0 & \text{otherwise.} \end{cases}$$

Let U_i be the span of $\{\mathbf{e}_T : T \subseteq X, |T| = i\}$ for $i = 0, 1, \dots, k$. We claim that $U_0 \subseteq U_1 \subseteq \dots \subseteq U_k = \mathbb{R}^{\mathfrak{X}}$ and that U_i has dimension $\binom{v}{i}$. Let $V_0 := U_0$ (the constant vectors) and for $i > 0$, let V_i be the orthogonal complement of U_{i-1} in U_i , i.e.

$$V_i := U_i \cap U_{i-1}^\perp.$$

It is clear that V_0, V_1, \dots, V_k are orthogonal and sum to $\mathbb{R}^{\mathfrak{X}}$. It can be shown that each vector in V_i is an eigenvector of A_j of value $P_j(i)$ as displayed in Theorem 30.1(i) below.

Since we have two bases of the vector space \mathfrak{A} , we may consider the transformation matrices between them, which are called the *eigenmatrices* of the scheme. Define P (the *first* eigenmatrix) and Q (the *second* eigenmatrix) as the $k+1 \times k+1$ matrices with rows and columns indexed by $0, 1, \dots, k$ such that

$$(A_0, A_1, \dots, A_k) = (E_0, E_1, \dots, E_k) P$$

and

$$N(E_0, E_1, \dots, E_k) = (A_0, A_1, \dots, A_k) Q.$$

We write $P_\ell(i)$ for the (i, ℓ) entry of P , and similarly, we let $Q_\ell(i)$ be the (i, ℓ) entry of Q , so that

$$(30.3) \quad A_\ell = P_\ell(0)E_0 + P_\ell(1)E_1 + \dots + P_\ell(k)E_k,$$

and

$$(30.4) \quad N E_\ell = Q_\ell(0)A_0 + Q_\ell(1)A_1 + \dots + Q_\ell(k)A_k.$$

Of course, we have

$$Q = N P^{-1}, \quad P = N Q^{-1}.$$

The ℓ -th column of P consists of the eigenvalues of A_ℓ .

While it is not so important to know the parameters p_{ij}^ℓ of a scheme, it is important for applications to know the eigenmatrices P and Q . See Bannai and Ito (1984) or Delsarte (1973) for proofs of the following theorem and the determination of the eigenmatrices of other schemes.

Theorem 30.1. (i) *For the Johnson scheme $J(v, k)$, the degrees are $n_\ell = \binom{k}{\ell} \binom{v-k}{\ell}$ and the multiplicities are $m_\ell = \binom{v}{\ell} - \binom{v}{\ell-1}$, $\ell = 0, 1, \dots, k$. The entries of the first eigenmatrix are $P_\ell(i)$ where*

$$P_\ell(x) = \sum_{\alpha=0}^{\ell} (-1)^{\ell-\alpha} \binom{k-\alpha}{\ell-\alpha} \binom{k-x}{\alpha} \binom{v-k+\alpha-x}{\alpha}.$$

(ii) For the Hamming scheme $H(n, q)$, the degrees and multiplicities are $n_\ell = m_\ell = \binom{n}{\ell}(q-1)^\ell$, $\ell = 0, 1, \dots, n$. The entries of the first eigenmatrix are $P_\ell(i)$ where

$$P_\ell(x) = \sum_{\alpha=0}^{\ell} (-q)^\alpha (q-1)^{\ell-\alpha} \binom{n-\alpha}{\ell-\alpha} \binom{x}{\alpha}.$$

Problem 30A. Calculate the eigenmatrix P of $J(8, 3)$ in the following way. First calculate $A_1 A_2$ as a linear combination of A_0 , A_1 , A_2 , and A_3 , and then fill in the missing line in the following table:

$$\begin{aligned} A_1^0 &= A_0, \\ A_1^1 &= A_1, \\ A_1^2 &= 15A_0 + 6A_1 + 4A_2, \\ A_1^3 &= , \\ A_1^4 &= 1245A_0 + 1036A_1 + 888A_2 + 720A_3. \end{aligned}$$

From this table, it is only mildly tedious to derive the minimal polynomial of A_1 . Find the eigenvalues of A_1 . Now express A_2 and A_3 as polynomials in A_1 , and so find their eigenvalues. Find the multiplicities. Check your work by verifying the orthogonality relations of Theorem 30.2 or just calculating the values from Theorem 30.1(i).

Problem 30B. Show how to calculate all the parameters p_{ij}^ℓ of a scheme given the eigenmatrix P . That is, prove that they are uniquely determined by P .

Problem 30C. The *Latin square graphs* are $srg(v, k, \lambda, \mu)$'s where for some integers n and r ,

$$v = n^2, \quad k = r(n-1), \quad \lambda = (n-2) + (r-1)(r-2), \quad \mu = r(r-1).$$

These were introduced in Example 21.7 for $r = 3$. Find the eigenmatrices P and Q for the 2-class schemes corresponding to these graphs.

The so-called *negative Latin square graphs* are strongly regular graphs $srg(v, k, \lambda, \mu)$ whose parameters are obtained from the above

by replacing n by $-n$ and r by $-r$. So $v = (-n)^2$, $k = (-r)(-n-1)$, etc. (It is strange that this should yield parameters satisfying (21.4), but it does.) Find the eigenmatrices P and Q for the corresponding 2-class schemes.

Theorem 30.2. *The eigenmatrices of a scheme satisfy the orthogonality relations*

$$P^\top \begin{pmatrix} 1 & 0 & \cdots & 0 \\ 0 & m_1 & & 0 \\ \vdots & & \ddots & \vdots \\ 0 & 0 & \cdots & m_k \end{pmatrix} P = N \begin{pmatrix} 1 & 0 & \cdots & 0 \\ 0 & n_1 & & 0 \\ \vdots & & \ddots & \vdots \\ 0 & 0 & \cdots & n_k \end{pmatrix}$$

and

$$Q^\top \begin{pmatrix} 1 & 0 & \cdots & 0 \\ 0 & n_1 & & 0 \\ \vdots & & \ddots & \vdots \\ 0 & 0 & \cdots & n_k \end{pmatrix} Q = N \begin{pmatrix} 1 & 0 & \cdots & 0 \\ 0 & m_1 & & 0 \\ \vdots & & \ddots & \vdots \\ 0 & 0 & \cdots & m_k \end{pmatrix}.$$

PROOF: The vector space \mathfrak{A} can be equipped with an inner product in a more-or-less natural way: We define $\langle A, B \rangle$ to be the sum of the entries of the Hadamard product $A \circ B$. Check that this is the same as the trace of the matrix product AB^\top (which is the same as $\text{tr}(AB)$ when B is symmetric, of course).

With respect to this inner product, the basis A_0, A_1, \dots, A_k is an orthogonal basis (but not orthonormal); we have $\langle A_i, A_i \rangle = N n_i$. But E_0, E_1, \dots, E_k is also an orthogonal basis since $E_i E_j = 0$ for $i \neq j$; we have $\langle E_i, E_i \rangle = \text{tr}(E_i) = m_i$. The derivation of the theorem from this is now elementary linear algebra.

Consider the first relation. The entry in the (α, β) position on the right is

$$\begin{aligned} \langle A_\alpha, A_\beta \rangle &= \left\langle \sum_i P_\alpha(i) E_i, \sum_j P_\beta(j) E_j \right\rangle \\ &= \sum_{i,j} P_\alpha(i) P_\beta(j) \langle E_i, E_j \rangle = \sum_i m_i P_\alpha(i) P_\beta(i), \end{aligned}$$

and this last expression is the entry in the (α, β) position on the left. The second relation is derived similarly. \square

Another way to express the content of the above theorem is

$$Q = \begin{pmatrix} 1 & 0 & \cdots & 0 \\ 0 & n_1 & & 0 \\ \vdots & & \ddots & \vdots \\ 0 & 0 & \cdots & n_k \end{pmatrix}^{-1} P^\top \begin{pmatrix} 1 & 0 & \cdots & 0 \\ 0 & m_1 & & 0 \\ \vdots & & \ddots & \vdots \\ 0 & 0 & \cdots & m_k \end{pmatrix}.$$

Equivalently,

$$(30.5) \quad m_j P_i(j) = n_i Q_j(i)$$

for all $i, j = 0, 1, \dots, k$.

With Theorems 30.1 and 30.2, we can find the second eigenmatrix Q for the schemes $J(v, k)$ and $H(n, q)$. It is somewhat surprising that $P = Q$ for $H(n, q)$; the reader should check this.

Problem 30D. Explain why the zeroth row and column of P and Q are as indicated below.

$$(30.6) \quad P = \begin{pmatrix} 1 & n_1 & \cdots & n_k \\ 1 & & & \\ \vdots & & & \\ 1 & & & \end{pmatrix}, \quad Q = \begin{pmatrix} 1 & m_1 & \cdots & m_k \\ 1 & & & \\ \vdots & & & \\ 1 & & & \end{pmatrix}.$$

Delsarte (1973) observed that the columns of the second eigenmatrix Q provide a system of linear constraints, which we will call *Delsarte's inequalities*, on, what he calls, the ‘inner distribution vector’ of a nonempty subset Y of the point set \mathfrak{X} of an association scheme. We define the *distribution vector* of Y to be $\mathbf{a} = (a_0, a_1, \dots, a_k)$ where

$$a_i := \frac{1}{|Y|} |(Y \times Y) \cap R_i|;$$

that is, a_i is the average number of i -th associates $y \in Y$ of an element $x \in Y$. We have

$$a_0 = 1, \quad a_0 + a_1 + \cdots + a_k = |Y|.$$

For many interesting subsets Y , the number of i -th associates $y \in Y$ of an element $x \in Y$ is constant, i.e. it does not depend on which x in Y is chosen. For example, this is true if C is a *linear*

code in $H(n, q)$ in which case the distribution vector coincides with what we called the weight enumerator of C in Chapter 21, and also for other beautiful configurations which have been discussed in previous chapters and whose distribution vectors we list below. Here Hamming(7) is the Hamming code of length 7, ‘Golay’ is short for ‘Golay code’, ‘X’ means ‘extended’, and a ‘*’ denotes ‘dual code’.

Object	Scheme	Distribution vector
$S(2, 3, 7)$	$J(7, 3)$	$(1, 0, 6, 0)$
$S_2(2, 5, 11)$	$J(11, 5)$	$(1, 0, 0, 10, 0, 0)$
$S_2(3, 6, 12)$	$J(12, 6)$	$(1, 0, 0, 20, 0, 0, 1)$
$S(5, 6, 12)$	$J(12, 6)$	$(1, 0, 45, 40, 45, 0, 1)$
$S(4, 7, 23)$	$J(23, 7)$	$(1, 0, 0, 0, 140, 0, 112, 0)$
$S(5, 8, 24)$	$J(24, 8)$	$(1, 0, 0, 0, 280, 0, 448, 0, 30)$
Hamming(7)	$H(7, 2)$	$(1, 0, 0, 7, 7, 0, 0, 1)$
X-Hamming(7)	$H(8, 2)$	$(1, 0, 0, 0, 14, 0, 0, 0, 1)$
Binary Golay	$H(23, 2)$	$(1, 0, 0, 0, 0, 0, 0, 253, 506, 0, 0, 1288, \dots)$
X-Binary Golay	$H(24, 2)$	$(1, 0, 0, 0, 0, 0, 0, 759, 0, 0, 0, 2576, 0, \dots)$
Ternary Golay	$H(11, 3)$	$(1, 0, 0, 0, 0, 132, 132, 0, 330, 110, 0, 24)$
*-Ternary Golay	$H(11, 3)$	$(1, 0, 0, 0, 0, 0, 132, 0, 0, 110, 0, 0)$

Theorem 30.3. *The distribution vector \mathbf{a} of a nonempty subset of an association scheme satisfies*

$$\mathbf{a}Q \geq \mathbf{0}$$

where $\mathbf{0}$ is the row vector of $k + 1$ zeros.

PROOF: Let $\phi \in \mathbb{R}^{\mathfrak{X}}$ be the characteristic vector of Y . That is,

$$\phi(x) = \begin{cases} 1 & \text{if } x \in Y, \\ 0 & \text{if } x \notin Y. \end{cases}$$

Then

$$a_i = \frac{1}{|Y|} \phi A_i \phi^\top.$$

Since E_ℓ is idempotent and symmetric,

$$\begin{aligned} 0 \leq \|\phi E_\ell\|^2 &= (\phi E_\ell)(\phi E_\ell)^\top = \phi E_\ell \phi^\top \\ &= \frac{1}{N} \phi \left(\sum_{i=0}^k Q_\ell(i) A_i \right) \phi^\top = \frac{|Y|}{N} \sum_{i=0}^k Q_\ell(i) a_i. \end{aligned}$$

□

We note for further reference that the ℓ -th inequality holds with equality if and only if the projection ϕE_ℓ is the zero vector. The zeroth inequality is trivial since the zeroth coordinate of $\mathbf{a}Q$ is $a_0 + a_1 + \cdots + a_k$, which of course is nonnegative.

Example 30.8. For $J(8, 3)$, Delsarte's inequalities when fractions are cleared are

$$\begin{aligned} 15 + 7a_1 - a_2 - 9a_3 &\geq 0, \\ 30 + 2a_1 - 5a_2 + 9a_3 &\geq 0, \\ 10 - 2a_1 + a_2 - a_3 &\geq 0. \end{aligned}$$

These can be viewed as necessary conditions for the existence of a family \mathcal{F} of 3-subsets of an 8-set with a given distribution vector $(1, a_1, a_2, a_3)$.

We can ask what they imply about $|\mathcal{F}|$ when we assume some of the a_i 's are zero. For example, assume $a_3 = 0$ (no two members of \mathcal{F} are disjoint). The maximum value of $1 + a_1 + a_2$ ($= |\mathcal{F}|$) subject to these inequalities is 21; this is a linear programming problem. We already knew $|\mathcal{F}| \leq 21$ because of the Erdős-Ko-Rado theorem, Theorem 6.4. Theorem 30.3 implies Theorem 6.4; see the notes.

Theorem 30.3 leads to a *linear programming bound* on the cardinalities of codes. For the Hamming scheme $H(n, q)$, given an integer d , we may consider the linear programming problem

$$\begin{aligned} &\text{"maximize } 1 + a_d + a_{d+1} + \cdots + a_n \text{ subject to } a_i \geq 0 \text{ and} \\ &\quad (1, 0, \dots, 0, a_d, a_{d+1}, \dots, a_n) Q \geq \mathbf{0}" \end{aligned}$$

where Q is the $n + 1$ by $n + 1$ second eigenmatrix of the scheme. If LPB denotes the maximum value of $1 + a_d + a_{d+1} + \cdots + a_n$ under these conditions and C is any q -ary code of length n with minimum distance at least d , then $|C| \leq \text{LPB}$ since the distribution vector \mathbf{a} of C satisfies the conditions and the coordinates sum to $|C|$.

We mention that for the Hamming schemes, if \mathbf{a} is the distribution vector of a *linear* code C , then $\frac{1}{|C|}\mathbf{a}Q$ is the distribution vector of the dual code C^\perp . To see this, just compare the formulae in MacWilliams' theorem, Theorem 20.3, with those in Theorem 30.1(ii). This certainly explains why $\mathbf{a}Q \geq \mathbf{0}$ for the distribution

vector \mathbf{a} of a linear code, but we have proved above that it holds even if C is not linear.

n	d	SPB	LPB	a_0	a_1	a_2	a_3	a_4	a_5	a_6	a_7	a_8	a_9	a_{10}	a_{11}	a_{12}	a_{13}	a_{14}	a_{15}
11	3	170.7	170.7	1	0	0	18.3	36.7	29.3	29.3	36.7	18.3	0	0	1				
11	5	30.6	24	1	0	0	0	0	11	11	0	0	0	0	1				
11	7	8.8	4	1	0	0	0	0	0	0	2	1	0	0	0				
12	3	315.1	292.6	1	0	0	20	45	48	56	65.1	40.7	11.4	3.4	1.7	0.1			
12	5	51.9	40	1	0	0	0	0	15	17.5	0	0	5	1.5	0	0			
12	7	13.7	5.3	1	0	0	0	0	0	0	2.7	1.7	0	0	0	0			
13	3	585.1	512	1	0	0	22	55	72	96	116	87	40	16	6	1	0		
13	5	89.0	64	1	0	0	0	0	18	24	4	3	10	4	0	0	0		
13	7	21.7	8	1	0	0	0	0	0	0	4	3	0	0	0	0	0		
14	3	1092.3	1024	1	0	0	28	77	112	168	232	203	112	56	28	7	0	0	
14	5	154.6	128	1	0	0	0	0	28	42	8	7	28	14	0	0	0	0	
14	7	34.9	16	1	0	0	0	0	0	0	8	7	0	0	0	0	0	0	
15	3	2048	2048	1	0	0	35	105	168	280	435	435	280	168	105	35	0	0	1
15	5	270.8	256	1	0	0	0	0	42	70	15	15	70	42	0	0	0	0	1
15	7	56.9	32	1	0	0	0	0	0	0	15	15	0	0	0	0	0	0	1

Figure 30.2

It is difficult to extract useful information in general from the linear programming bound (LPB), but it can be shown that it is always at least as good as the sphere packing bound (SPB), Theorem 21.1; see Delsarte (1973). For small values of the parameters, one can use the simplex algorithm and explicitly evaluate this bound. We have done so for some values of n and d in the case of binary codes and display the results in the table of Fig. 30.2. The table gives a nonnegative vector $(1, 0, \dots, 0, a_d, a_{d+1}, \dots, a_n)$ whose sum is maximum subject to $\mathbf{aQ} \geq \mathbf{0}$. It is a good exercise for the reader to try to decide whether codes meeting the LPB as in the table actually exist. We mention that several can be obtained from an interesting binary code of length 16 called the Nordstrom-Robinson code, which has 256 codewords and minimum distance 6. It is not linear. See problems 30I and 30J.

There appears to be a kind of ‘duality’ between the two bases of, and between ordinary and Hadamard multiplication on, the Bose–

Mesner algebra. It sometimes happens that there exists a second association scheme so that the E_i 's of the latter under Hadamard multiplication act like the A_i 's of the former under ordinary multiplication (apart from a scalar factor), and vice versa. Two schemes are said to be *formally dual* when the first eigenmatrix P of one is equal to the second eigenmatrix Q of the other (cf. Problem 30E below). Many examples of pairs of formally dual strongly regular graphs are known. The Hamming scheme, as mentioned above, is formally dual to itself. The Johnson scheme usually has no formal dual, because in general the Krein parameters defined below are not integers.

The *Krein parameters* of an association scheme are the $(k+1)^3$ numbers q_{ij}^ℓ defined by

$$(30.7) \quad N E_i \circ E_j = \sum_{\ell=0}^k q_{ij}^\ell E_\ell.$$

If the scheme has a formal dual, these are the parameters p_{ij}^ℓ for that formally dual scheme and hence are nonnegative integers. We always have

$$q_{ij}^\ell \geq 0, \quad \text{for all } 0 \leq i, j, \ell \leq k,$$

because the q_{ij}^ℓ 's are eigenvalues of the Hadamard product of two positive semidefinite matrices and are hence nonnegative; cf. Problem 21E. In principle, the Krein parameters are functions of the original parameters p_{ij}^ℓ (see Problem 30E) and their nonnegativity can be viewed as a necessary condition for the existence of a scheme with given parameters; we did this for strongly regular graphs in Theorem 21.3.

Problem 30E. Show how to calculate all the parameters q_{ij}^ℓ of a scheme given the eigenmatrix Q . That is, prove that they are uniquely determined by Q .

We need to know later that

$$(30.8) \quad q_{ii}^0 = m_i \quad \text{and} \quad q_{ij}^0 = 0 \quad \text{for } i \neq j.$$

This follows from (30.7) when we consider the sum of all entries of the matrices on both sides; the sum of the entries of the left-hand

side is N times

$$\langle E_i, E_j \rangle = \begin{cases} m_i & \text{if } i = j, \\ 0 & \text{otherwise.} \end{cases}$$

For some applications to codes and designs, we need to know more about a scheme. However, here is one interesting result we can prove for general schemes before we specialize.

Given a k -class scheme and a subset K of $\{1, 2, \dots, k\}$, a subset Y of the point set is called a K -clique when for every pair of distinct elements $x, y \in Y$, x and y are j -th associates for some $j \in K$. The subset Y is a K -coclique when no pair of elements $x, y \in Y$ are j -th associates for any $j \in K$. If G is the graph whose adjacency matrix is $\sum_{j \in K} A_j$, then cliques in G are the same as K -cliques in the scheme, and cocliques (independent sets of vertices) are the same as K -cocliques in the scheme.

Theorem 30.4. *Let $A \subseteq \mathfrak{X}$ be a K -coclique and $B \subseteq \mathfrak{X}$ a K -clique in a k -class association scheme on a set \mathfrak{X} where $K \subseteq \{1, 2, \dots, k\}$. Then*

$$|A||B| \leq N.$$

PROOF: Let $\mathbf{a} = (a_0, a_1, \dots, a_k)$ be the distribution vector of A and let $\mathbf{b} = (b_0, b_1, \dots, b_k)$ be the distribution vector of B . Take the inverse of the first equation of Theorem 30.2, premultiply by \mathbf{a} and postmultiply by \mathbf{b}^\top to get

$$(30.9) \quad \mathbf{a}Q \begin{pmatrix} 1 & 0 & \dots & 0 \\ 0 & m_1 & & 0 \\ \vdots & & \ddots & \vdots \\ 0 & 0 & \dots & m_k \end{pmatrix}^{-1} (\mathbf{b}Q)^\top = N \mathbf{a} \begin{pmatrix} 1 & 0 & \dots & 0 \\ 0 & n_1 & & 0 \\ \vdots & & \ddots & \vdots \\ 0 & 0 & \dots & n_k \end{pmatrix}^{-1} \mathbf{b}^\top.$$

By Theorem 30.3, both $\mathbf{a}Q$ and $\mathbf{b}Q$ are nonnegative vectors. Their zeroth coordinates are $|A|$ and $|B|$, respectively, so the scalar on the left of (30.9) is at least $|A||B|$. Our hypothesis implies that $a_i b_i = 0$ for $i > 0$, so the scalar on the right of (30.9) is N . \square

An example of equality in Theorem 30.4 in $J(v, k)$ occurs when there exists an $S(t, k, v)$. Take $K = \{1, 2, \dots, k - t\}$. Then the block set of the $S(t, k, v)$ is a K -coclique. The set of all k -subsets containing a fixed t -subset is a K -clique. An example of equality

in Theorem 30.4 in $H(n, q)$ occurs when there exists a perfect e -error-correcting code C . Take $K = \{1, 2, \dots, 2e\}$. Then C is a K -coclique. A sphere of radius e about a fixed word is a K -clique.

Problem 30F. Find an example of a regular graph G , a clique A , and a coclique B such that $|A||B| > |G|$.

Problem 30G. Prove that if A is a clique and B a coclique in a graph G which admits a transitive group of automorphisms, then $|A||B| \leq |G|$.

We now define *polynomial schemes*, of which there are two types. An association scheme (with a particular numbering A_1, A_2, \dots, A_k of its association matrices) is said to be *P -polynomial* when A_i is a polynomial of degree i in A_1 for $i = 0, 1, 2, \dots, k$. An association scheme (with a particular numbering E_1, E_2, \dots, E_k of its idempotents) is said to be *Q -polynomial* when E_i is a Hadamard polynomial of degree i in E_1 for $i = 0, 1, 2, \dots, k$ (we mean that there is a polynomial of degree i so that E_i results by applying the polynomial element-wise to, i.e. to *each entry* of, E_1).

Problem 30H. Prove that an association scheme is P -polynomial if and only if it is a metric scheme.

The Q -polynomial schemes are also called *cometric*, but there seems to be no simple geometric interpretation of cometric. We use the terms metric and cometric rather than P - and Q -polynomial.

It can be seen that the Hamming and Johnson schemes are cometric; see Delsarte (1973).

We define a *d -code* in a metric scheme to be a subset $S \subseteq \mathfrak{X}$ whose characteristic vector ϕ satisfies

$$\phi A_i \phi^\top = 0 \quad \text{for } i = 1, 2, \dots, d-1.$$

We define a *t -design* in a cometric scheme to be a subset $S \subseteq \mathfrak{X}$ whose characteristic vector ϕ satisfies

$$\phi E_i \phi^\top = 0 \quad \text{for } i = 1, 2, \dots, t.$$

The combinatorial significance of d -codes is straightforward: S is a d -code if and only if no two distinct elements of S are i -th

associates for $i < d$. So in the Hamming scheme, S is a $(2e + 1)$ -code if and only if it is e -error correcting, i.e. has minimum distance at least $2e + 1$. The combinatorial significance of t -designs is not so clear and can only be understood with more knowledge of the particular scheme. Note that S is a t -design if and only if the first t nontrivial inequalities on the distribution vector of S in Theorem 30.3 hold with equality, i.e. that $\phi E_i = \mathbf{0}$ for $i = 1, \dots, t$.

The following theorem explains that designs in the Johnson and Hamming schemes correspond to the classical concepts of t -designs and orthogonal arrays, respectively. An *orthogonal array* of index λ and strength t on a set A of q symbols is a subset $C \subseteq A^n$ of λq^t words so that for every choice of t of the n coordinates, each possible t -tuple of elements of A occurs exactly λ times in those t coordinates among the members of C .

Theorem 30.5.

(i) A family S of k -subsets of a v -set is a t -design when considered as a subset of $J(v, k)$ if and only if it is the set of blocks of a t -design in the classical sense.

(ii) A family S of n -tuples from an alphabet A of q elements is a t -design when considered as a subset of $H(n, q)$ if and only if it is the set of columns of an orthogonal array of strength t .

PARTIAL PROOF: We will show that the definition of t -design in the schemes implies that the family S is a classical t -design or orthogonal array and leave the converses of both parts (i) and (ii) for the reader.

Let S be a t -design in $J(v, k)$ in the sense of association schemes and ϕ its characteristic vector. In Example 30.7, we saw that $E_0 + E_1 + \dots + E_t$ is the orthogonal projection onto the space spanned by \mathbf{e}_T as T ranges over the t -subsets of the v -set. The number of members of S containing a t -subset T is

$$\phi \mathbf{e}_T^\top = \phi(E_0 + E_1 + \dots + E_t) \mathbf{e}_T^\top = \phi E_0 \mathbf{e}_T^\top.$$

Since E_0 is a scalar multiple of the all-one matrix J , this number is independent of the particular t -subset T .

Let S be a t -design in $H(n, q)$ in the sense of association schemes and ϕ its characteristic vector. In Example 30.6, we described the

eigenspaces for $q = 2$, and we prove the theorem only in this case. A complete proof may be found in Delsarte (1973).

With the notation of Example 30.6,

$$\langle \phi, \mathbf{v}_a \rangle = \sum_{b \in S} (-1)^{\langle a, b \rangle},$$

so S is a t -design if and only if

$$\sum_{b \in S} (-1)^{\langle a, b \rangle} = 0 \quad \text{for all nonzero } a \text{ of weight } \leq t.$$

For example, when a is taken of weight 1, the above equation implies that in any given coordinate position, half the members of S have entry 0 and half have entry 1. When a is taken of weight 2, e.g. as $(1, 1, 0, 0, \dots, 0)$, the equation implies that the number of members of S that begin with 00 or 11 is equal to the number that begin with 10 or 01; it follows from this and the previous sentence that exactly $1/4$ of the n -tuples in S begin with each of 00, 10, 01, 11.

In general, consider a t -subset $T \subseteq \{1, 2, \dots, n\}$ of coordinate positions. For each subset I of T , let λ_I denote the number of $a \in S$ with entry 1 in coordinates of I and entry 0 in coordinates of $T \setminus I$. For each subset J of T , let a_J denote the binary n -tuple with 1's in coordinates of J and 0's in the remaining $n - |J|$ coordinates. We have 2^t linear equations, one for each $J \subseteq T$:

$$\sum_{|I \cap J| \equiv 0 \pmod{2}} \lambda_I - \sum_{|I \cap J| \equiv 1 \pmod{2}} \lambda_I = \begin{cases} |S| & \text{if } J = \emptyset \\ 0 & \text{otherwise.} \end{cases}$$

Clearly $\lambda_I = |S|/2^t$ for all $I \subseteq T$ is a solution of this system. But the coefficient matrix of this system is a Hadamard matrix of order 2^t (see Chapter 18) and in particular is nonsingular, so the solution is unique. Thus S is an orthogonal array of strength t . \square

The next two theorems are 'formal duals'. That is, their proofs are similar but the roles of the bases of A_i 's and E_i 's are interchanged, as is the role of ordinary and Hadamard multiplication of matrices. For the Hamming schemes, Theorem 30.6(i) reduces

to the sphere packing bound, Theorem 21.1, and part (iii) gives a very strong condition, due to S. P. Lloyd (1957), for equality to hold (perfect codes—see Chapter 20). For the Johnson schemes, Theorem 30.7(i) reduces to Theorem 19.8, and part (iii) gives a very strong condition, due to Ray-Chaudhuri and Wilson (1975), for equality to hold (tight designs—see Chapter 19).

Theorem 30.6. *Let C be a $(2e + 1)$ -code in a k -class metric association scheme on a set \mathfrak{X} . Let $\phi \in \mathbb{R}^{\mathfrak{X}}$ be the characteristic vector of C .*

(i) *We have*

$$|C| \leq N/(1 + n_1 + n_2 + \cdots + n_e).$$

(ii) *There are at least e indices $i \in \{1, 2, \dots, k\}$ such that*

$$\phi E_i \phi^\top \neq 0.$$

(iii) *Equality holds in (i) if and only if equality holds in (ii), in which case the e indices i such that $\phi E_i \phi^\top \neq 0$ are exactly those integers i for which*

$$\sum_{\ell=0}^e P_\ell(i) = 0.$$

PROOF: Let ϕ be the characteristic vector of a $(2e + 1)$ -code C and consider the expression

$$\alpha := \phi(c_0 A_0 + c_1 A_1 + \cdots + c_e A_e)^2 \phi^\top$$

where c_0, c_1, \dots, c_e are scalars. We shall evaluate α in two ways.

Introduce

$$f(i) := c_0 P_0(i) + c_1 P_1(i) + \cdots + c_e P_e(i)$$

as a function of the c_j 's. By (30.3), $c_0 A_0 + c_1 A_1 + \cdots + c_e A_e = \sum_{i=0}^k f(i) E_i$ so

$$\alpha = \left(\sum_{i=0}^k f(i) \phi E_i \right) \left(\sum_{i=0}^k f(i) \phi E_i \right)^\top = \sum_{i=0}^k f(i)^2 \phi E_i \phi^\top.$$

On the other hand, A_i is a polynomial of degree i in A_1 , so $(A_0 + A_1 + \cdots + A_e)^2$ is a polynomial of degree $2e$ in A_1 and hence a linear combination of A_0, A_1, \dots, A_{2e} . Our hypothesis implies that $\phi A_i \phi^\top = 0$ for $i = 1, 2, \dots, 2e$. Thus to evaluate α , we need only the coefficient of A_0 when $(A_0 + A_1 + \cdots + A_e)^2$ is written as a linear combination of A_0, A_1, \dots, A_{2e} ; by (30.2) and (30.1),

$$\alpha = \left(\sum_{i,j=0}^e c_i c_j p_{ij}^0 \right) \phi A_0 \phi^\top = \left(\sum_{i=0}^e c_i^2 n_i \right) |C|.$$

Note that by (30.6), $f(0) = c_0 n_0 + c_1 n_1 + \cdots + c_e n_e$. We now combine the two values for α , remembering that $E_0 = \frac{1}{N} J$ so that $\phi E_0 \phi^\top = \frac{1}{N} |C|^2$, to obtain

$$\begin{aligned} (30.10) \quad (c_0^2 + c_1^2 n_1 + \cdots + c_e^2 n_e) |C| &= \sum_{i=0}^k f(i)^2 \phi E_i \phi^\top \\ &\geq \frac{1}{N} (c_0 + c_1 n_1 + \cdots + c_e n_e)^2 |C|^2. \end{aligned}$$

Everything will follow from (30.10). Part (i) follows when we take all $c_i := 1$.

To prove part (ii), suppose for contradiction that there are fewer than e indices $i \geq 1$ such that $\phi E_i \phi^\top \neq 0$. By elementary linear algebra, there exist scalars c_0, \dots, c_e , not all zero, such that $f(i) = 0$ for $i = 0$ and all i such that $\phi E_i \phi^\top \neq 0$. But then (30.10) gives $|C| \sum_{i=0}^e n_i c_i^2 = 0$, a contradiction.

Assume equality holds in (i). Then (30.10), with all c_i 's equal to 1, shows that $f(i) = \sum_{\ell=0}^e P_\ell(i) = 0$ for the e or more values of i for which $\phi E_i \phi^\top \neq 0$. We claim that $f(i) = 0$ cannot hold for more than e values of i . This is because $f(0), f(1), \dots, f(k)$ are the eigenvalues of $A_0 + A_1 + \cdots + A_e$, which is a polynomial of degree e in A_1 ; that is, $f(0), \dots, f(k)$ arise from evaluating a polynomial of degree e on the eigenvalues $P_1(0), \dots, P_1(k)$ of A_1 . (The matrix A_1 has $k + 1$ distinct eigenvalues since it generates an algebra of dimension $k + 1$.) Our claim follows from the fact that a polynomial of degree e has at most e zeros. So (ii) holds with equality and (iii) is proved in this case.

Finally, assume equality holds in (ii). Choose scalars c_0, \dots, c_e so that $f(i) = 0$ for all i such that $\phi E_i \phi^\top \neq 0$ and such that $f(0) = 1$. Then (30.10) yields $|C| = N(c_0^2 + c_1^2 n_1 + \dots + c_e^2 n_e)$. The Cauchy-Schwartz inequality shows that

$$1 = \left(\sum_{i=0}^e c_i n_i \right)^2 \leq \left(\sum_{i=0}^e c_i^2 n_i \right) \left(\sum_{i=0}^e n_i \right)$$

so $|C| \geq N/(1 + n_1 + n_2 + \dots + n_e)$. Thus equality holds in (i). \square

Corollary (Lloyd's theorem). *If a perfect e -error-correcting code of length n over an alphabet of size q exists, then*

$$L_e(x) := \sum_{i=0}^e (-1)^i \binom{n-x}{e-i} \binom{x-1}{i} (q-1)^{e-i}$$

has e distinct integral zeros.

PROOF: This is just Theorem 30.6(iii) stated for the Hamming scheme. The sum $\sum_{\ell=0}^e P_\ell(x)$ where $P_\ell(x)$ is as in Theorem 30.1(ii) simplifies to $L_e(x)$ as stated above. \square

Example 30.9. We show that there are no nontrivial perfect 2-error-correcting binary codes. If such a code has length $n > 2$, then its cardinality is $2^n / (1 + n + \binom{n}{2})$, so $1 + n + \binom{n}{2} = 2^r$ for some integer r . (That n has this property is unusual—but it may happen, e.g. for $n = 90$.) From Theorem 30.1(ii), for $H(n, 2)$,

$$P_0(x) + P_1(x) + P_2(x) = 2x^2 - 2(n+1)x + 1 + n + \binom{n}{2}$$

and Theorem 30.6(iii) then asserts that

$$x^2 - (n+1)x + 2^{r-1} = 0$$

has two integral roots x_1 and x_2 . We must have $x_1 = 2^a$ and $x_2 = 2^b$ for positive integers a and b where $a + b = r - 1$ and $2^a + 2^b = n + 1$. Then it may be easily verified that

$$(2^{a+1} + 2^{b+1} - 1)^2 = 2^{a+b+4} - 7.$$

If a and b are both ≥ 2 , then the left-hand side is $\equiv 1 \pmod{16}$ while the right-hand side is $\equiv 9 \pmod{16}$, a contradiction. The reader may consider other cases and will find that the only possibility is $\{a, b\} = \{1, 2\}$ in which case $n = 5$.

Theorem 30.7. *Let D be a $2s$ -design in a k -class cometric association scheme on a set \mathfrak{X} . Let $\phi \in \mathbb{R}^{\mathfrak{X}}$ be the characteristic vector of D .*

(i) *We have*

$$|D| \geq 1 + m_1 + m_2 + \cdots + m_s.$$

(ii) *There are at least s indices $i \in \{1, 2, \dots, k\}$ such that*

$$\phi A_i \phi^\top \neq 0.$$

(iii) *Equality holds in (i) if and only if equality holds in (ii), in which case the s indices i such that $\phi A_i \phi^\top \neq 0$ are exactly those integers i for which*

$$\sum_{\ell=0}^s Q_\ell(i) = 0.$$

PROOF: Let ϕ be the characteristic vector of a $2s$ -design D and consider the expression

$$\beta := \phi(c_0 E_0 + c_1 E_1 + \cdots + c_s E_s) \circ (c_0 E_0 + c_1 E_1 + \cdots + c_s E_s) \phi^\top$$

where c_0, c_1, \dots, c_s are scalars. We shall evaluate β in two ways.

Introduce

$$g(i) := \frac{1}{N}(c_0 Q_0(i) + c_1 Q_1(i) + \cdots + c_s Q_s(i))$$

as a function of the c_i 's. By (30.4), $c_0 E_0 + c_1 E_1 + \cdots + c_s E_s = \sum_{i=0}^k g(i) A_i$ so

$$\beta = \left(\sum_{i=0}^k g(i) \phi A_i \right) \circ \left(\sum_{i=0}^k g(i) \phi A_i \right)^\top = \sum_{i=0}^k g(i)^2 \phi A_i \phi^\top.$$

On the other hand, E_i is a Hadamard polynomial of degree i in E_1 , so the Hadamard square of $E_0 + E_1 + \cdots + E_s$ is a Hadamard polynomial of degree $2s$ in E_1 and hence a linear combination of E_0, E_1, \dots, E_{2s} . Our hypothesis implies that $\phi E_i \phi^\top = 0$ for $i = 1, 2, \dots, 2s$. Thus to evaluate β , we need only the coefficient of E_0 when the Hadamard square of $E_0 + E_1 + \cdots + E_s$ is written as a linear combination of E_0, E_1, \dots, E_{2s} ; by (30.7) and (30.8),

$$\beta = \left(\frac{1}{N} \sum_{i,j=0}^s c_i c_j q_{ij}^0 \right) \phi E_0 \phi^\top = \frac{1}{N^2} \left(\sum_{i=0}^s c_i^2 m_i \right) |C|^2.$$

Note that by (30.6), $g(0) = \frac{1}{N}(c_0 m_0 + c_1 m_1 + \cdots + c_s m_s)$. We now combine the two values for β to obtain

$$\begin{aligned} (30.11) \quad \frac{1}{N^2} (c_0^2 + c_1^2 m_1 + \cdots + c_s^2 m_s) |C|^2 &= \sum_{i=0}^k g(i)^2 \phi A_i \phi^\top \\ &\geq \frac{1}{N} (c_0 + c_1 m_1 + \cdots + c_s m_s)^2 |C|. \end{aligned}$$

Everything will follow from (30.11) in a manner similar to that of the proof of Theorem 30.6. \square

Problem 30I. Consider the extended Golay code G_{24} . For notational convenience, arrange the coordinates so that the word $\mathbf{c} = (1, \dots, 1, 0, \dots, 0)$ with 1's in the first eight positions, and 0's elsewhere, is a codeword.

(i) Use counting arguments to show that G_{24} contains 30 words of weight 8 that have no 1's in the first eight positions (so: distance 16 to \mathbf{c}). Then show that all the words in G_{24} that have no 1's in the first eight positions form a subcode that is essentially $R(1, 4)$.

(ii) Let A be the set of 16-tuples $(a_9, a_{10}, \dots, a_{24})$ obtained by dropping the first eight coordinates from words $\mathbf{a} = (a_1, a_2, \dots, a_{24})$ in G_{24} such that the weight of (a_1, a_2, \dots, a_7) is ≤ 1 . Show that A is a code of length 16 with 256 codewords and minimum distance 6.

(iii) Use A to construct some examples of codes where equality holds in Figure 30.2.

Problem 30J. Show that a binary linear code with parameters $[13, 6, 5]$ does not exist. (And hence there are no binary linear codes with parameters $[16, 8, 6]$ either.)

Problem 30K. The *odd graph* has as vertices the k -subsets of a $(2k + 1)$ -set, joined by an edge if they are disjoint. (For $k = 2$ this is the Petersen graph.)

(i) Show that this graph is distance regular.

(ii) Show that if $k = 3$, the vertices ‘corresponding to’ the Fano plane form a perfect code in the graph.

Problem 30L. Find all examples of perfect 3-codes in the Johnson scheme $J(v, 3)$. (All the examples are trivial.)

Notes.

Association schemes were introduced by statisticians at the same time as *partially balanced designs*. An incidence structure is *partially balanced* with respect to an association scheme on its points when each pair of i -th associates occurs in a constant number λ_i of blocks. Examples include the partial geometries of Chapter 21. Partially balanced designs were introduced to get around Fisher’s inequality $b \geq v$, or equivalently $r \geq k$, which need not hold for them. Replications cost money (r stands for ‘replication number’) or take time, so for practical reasons, one wants r small.

To do the analysis of an experiment for which a certain design (incidence structure) has been used, it is necessary to do calculations with NN^T where N is the incidence matrix; these calculations are vastly simplified for partially balanced designs because in an m -class scheme

$$NN^T = \lambda_0 A_0 + \lambda_1 A_1 + \cdots + \lambda_m A_m$$

lies in the small-dimensional Bose–Mesner algebra even though the size of the matrices may be very much more than the dimension $m + 1$.

Delsarte’s inequalities imply the general Erdős–Ko–Rado theorem: If $n \geq (t + 1)(k - t + 1)$ and \mathcal{F} is a family of k -subsets of an n -set so that any two of members of \mathcal{F} meet in at least t points, then $|\mathcal{F}| \leq \binom{n-t}{k-t}$. See Wilson (1984a).

See Van Lint (1999) for more on the nonexistence of perfect codes.

References.

- E. Bannai and T. Ito (1984), *Association Schemes*, Benjamin/Cummings.
- A. E. Brouwer, A. M. Cohen, and A. Neumaier (1989), *Distance Regular Graphs*, Springer-Verlag.
- Ph. Delsarte (1973), *An Algebraic Approach to the Association Schemes of Coding Theory*, Philips Res. Rep. Suppl. **10**.
- Ph. Delsarte (1975), The association schemes of coding theory, in: *Combinatorics* (Proc. Nijenrode Conf.), M. Hall, Jr. and J. H. van Lint, eds., D. Reidel.
- J. H. van Lint (1999), *Introduction to Coding Theory*, Third edition, Springer-Verlag.
- S. P. Lloyd (1957), Binary block coding, *Bell System Tech. J.* **36**, 517–535.
- D. K. Ray-Chaudhuri and R. M. Wilson (1975), On t -designs, *Osaka J. Math.* **12**, 737–744.
- R. M. Wilson (1984a), The exact bound in the Erdős-Ko-Rado theorem, *Combinatorica* **4**, 247–257.
- R. M. Wilson (1984b), On the theory of t -designs, pp. 19–50 in: *Enumeration and Design* (Proceedings of the Waterloo Silver Jubilee Conference), D. M. Jackson and S. A. Vanstone, eds., Academic Press.

31

(More) algebraic techniques in graph theory

We have used linear algebraic techniques on the adjacency matrices of graphs in Chapter 9, and extensively in Chapter 21. We collect here several other elegant applications. Also see Chapter 36.

A *tournament* is an orientation of a complete graph; that is, a directed graph such that for any two distinct vertices x and y , there is either an edge from x to y , or an edge from y to x , but not both. Tournaments were introduced briefly in Problem 3D. The *adjacency matrix* of a digraph has a 1 in position (x, y) when there is an edge from x to y , and 0 otherwise.

Lemma 31.1. *The rank of the adjacency matrix A of a tournament on n vertices is either n or $n - 1$.*

PROOF: The definition of tournament ensures that $A + A^\top = J - I$, where all matrices are $n \times n$. Suppose the rank of A is at most $n - 2$. Then there exists a nonzero row vector \mathbf{x} such that both $\mathbf{x}A = 0$ and $\mathbf{x}J = 0$. We then compute

$$0 = \mathbf{x}(A + A^\top)\mathbf{x}^\top = \mathbf{x}(J - I)\mathbf{x}^\top = -\mathbf{x}\mathbf{x}^\top < 0,$$

which contradicts the existence of \mathbf{x} . □

The following theorem is due to R. L. Graham and H. O. Pollak. Their original proof applied Sylvester's law, which they had also used for their proof of Theorem 9.1.

Theorem 31.2. *Suppose that the complete graph K_n can be expressed as the union of k edge-disjoint subgraphs H_1, H_2, \dots, H_k where each H_i is a complete bipartite graph. Then $k \geq n - 1$.*

PROOF: Orient each complete bipartite subgraph H_i by directing all edges from one of the two color classes to the other. This produces a tournament on n vertices whose adjacency matrix A is the sum of the k adjacency matrices A_i of the digraphs H_i (augmented to $n \times n$ matrices by including all vertices). The adjacency matrix of such a complete directed bipartite subgraph, after a suitable renumbering of the vertices, has the block form

$$\begin{pmatrix} O & J & O \\ O & O & O \\ O & O & O \end{pmatrix}$$

and in particular has rank 1. This implies that the rank of A is at most k , and Lemma 31.1 completes the proof. □

This brings to mind the De Bruijn–Erdős theorem, Theorem 19.1, which asserts, in a quite different terminology, and which was given a quite different proof, that if K_n is the union of k edge-disjoint complete subgraphs, then $k \geq n$. But no proof of Theorem 31.2 is known which does not use linear algebra.

As a real symmetric matrix, the adjacency matrix $A = A(G)$ of a finite graph G has an orthogonal basis of eigenvectors. (Eigenvectors corresponding to different eigenvalues are necessarily orthogonal.) By the ‘eigenvalues of G ’ we mean the eigenvalues of $A(G)$. Here is a short table of the spectra, i.e. the complete lists of eigenvalues, of several graphs:

graph	spectrum
K_5	$4, -1, -1, -1, -1$
$K_{3,3}$	$3, 0, 0, 0, 0, -3$
Cube	$3, 1, 1, 1, -1, -1, -1, -3$
Pentagon	$2, \frac{1}{2}(-1 + \sqrt{5}), \frac{1}{2}(-1 + \sqrt{5}),$ $\frac{1}{2}(-1 - \sqrt{5}), \frac{1}{2}(-1 - \sqrt{5})$
Petersen graph	$3, 1, 1, 1, 1, 1, -2, -2, -2, -2$
$L_2(3)$	$4, 1, 1, 1, 1, -2, -2, -2, -2$
Heawood graph	$3, \sqrt{2}, \sqrt{2}, \sqrt{2}, \sqrt{2}, \sqrt{2}, \sqrt{2},$ $-\sqrt{2}, -\sqrt{2}, -\sqrt{2}, -\sqrt{2}, -\sqrt{2}, -\sqrt{2}, -3$

(The Heawood graph is the ‘bipartite incidence graph’ of the Fano configuration, with seven vertices representing the points and seven others representing the lines. It appears again in Chapter 35.)

Nonisomorphic graphs may have the same spectra. For example, we mentioned in Chapter 21 that there exist four nonisomorphic strongly regular graphs with the parameters of $T(8)$; cf. Theorem 21.5.

Problem 31A. Show that it is not possible to find three edge-disjoint copies of the Petersen graph in K_{10} . Hint: if A_1 , A_2 , and A_3 are the adjacency matrices of three edge-disjoint Petersen subgraphs of K_{10} , then all three matrices have the same spectrum, all have the all-one vector \mathbf{j} as an eigenvector, and $A_1 + A_2 + A_3 = J - I$.

Let S be a symmetric matrix. The expression $\mathbf{x}S\mathbf{x}^\top / \mathbf{x}\mathbf{x}^\top$, for $\mathbf{x} \neq \mathbf{0}$, is called a *Raleigh quotient*. Let $\mathbf{e}_1, \mathbf{e}_2, \dots, \mathbf{e}_n$ be an orthonormal basis of eigenvectors with corresponding eigenvalues

$$\lambda_1 \geq \lambda_2 \geq \dots \geq \lambda_n.$$

If we write \mathbf{x} in this basis, say $\mathbf{x} = a_1\mathbf{e}_1 + \dots + a_n\mathbf{e}_n$, then

$$(31.1) \quad \frac{\mathbf{x}S\mathbf{x}^\top}{\mathbf{x}\mathbf{x}^\top} = \frac{\lambda_1 a_1^2 + \lambda_2 a_2^2 + \dots + \lambda_n a_n^2}{a_1^2 + a_2^2 + \dots + a_n^2}.$$

In particular, for any nonzero \mathbf{x} ,

$$\lambda_1 \geq \frac{\mathbf{x}S\mathbf{x}^\top}{\mathbf{x}\mathbf{x}^\top} \geq \lambda_n.$$

While most graphs we will consider are simple, we remark that there is nothing to prevent the consideration of adjacency matrices of multigraphs below (where the entry in row x and column y is the number of edges joining x and y), or the adjacency matrices of ‘weighted’ graphs (where the entry in row x and column y is a ‘weight’ associated to the edge joining x and y).

It is at first surprising that the spectrum of a graph has anything at all to do with the more geometric or combinatorial properties of the graph. One of the first connections observed was the following theorem of A. J. Hoffman. A *co clique*, or an *independent* set of vertices, in a graph G is a set of vertices no two of which are adjacent.

Theorem 31.3. *Let G be a graph on n vertices which is regular of degree d and let λ_{\min} be the least eigenvalue of G , so λ_{\min} is negative. Then for any coclique S in G ,*

$$|S| \leq \frac{-n\lambda_{\min}}{d - \lambda_{\min}}.$$

PROOF: Let A be the adjacency matrix of G and $\lambda := \lambda_{\min}$. Then $A - \lambda I$ is positive semidefinite, i.e. all eigenvalues are nonnegative; note that the eigenvectors of $A - \lambda I$ are the same as those of A . One of the eigenvectors is $\mathbf{j} := (1, 1, \dots, 1)$, and we have

$$\mathbf{j}(A - \lambda I) = (d - \lambda)\mathbf{j}.$$

Then with

$$M := A - \lambda I - \frac{d - \lambda}{n}J,$$

we will have $\mathbf{j}M = 0$. Every other eigenvector \mathbf{e} of A may be taken to be orthogonal to \mathbf{j} , so $\mathbf{e}J = 0$, and is seen also to be an eigenvector of M with nonnegative eigenvalue. That is, M is also positive semidefinite.

Now let ϕ be the characteristic vector of a coclique S consisting of m vertices of G , i.e. $\phi(x)$ is 1 if $x \in S$ and 0 otherwise. Then $\phi A \phi^\top = 0$ and we have

$$0 \leq \phi M \phi^\top = -\lambda \phi \phi^\top - \frac{d - \lambda}{n} \phi J \phi^\top = -\lambda m - \frac{d - \lambda}{n} m^2.$$

The stated inequality follows. □

There are extensions and variations on Theorem 31.3 for nonregular graphs—see Haemers (1979).

Problem 31B. Apply Theorem 31.3 to the complement of a simple regular graph G to obtain an upper bound on the size of a clique in G in terms of the spectrum. Find several examples where your bound is met.

Problem 31C. The *line graph* $L = L(G)$ of a simple graph G was introduced in Chapter 17. For example, $L_2(m)$ as defined in Chapter 21 is the line graph of $K_{m,m}$, $T(m)$ is the line graph of K_m ,

and the line graph of a pentagon is a pentagon. (i) Show that the Petersen graph is *not* the line graph of any graph. (ii) Prove that if G has more edges than vertices, then the minimum eigenvalue of the line graph $L(G)$ is -2 . (Suggestion: let N be the incidence matrix of G and consider $N^T N$.)

L. Lovász (1979) observed that the bound on the size of a coclique in Theorem 31.3 is also a bound on what is called the Shannon capacity of a graph. This is a concept that arose in information theory. Suppose a set of ‘letters’ is to be used for transmitting messages. Some pairs of letters are assumed to be ‘confusable’ or ‘confoundable’. We say two potential messages (words or strings of n of these letters) are *confoundable* when in each coordinate the letters are either identical or confoundable. We desire a set of words no two of which are confoundable.

To state this in more graph-theoretic terminology, we introduce the graph G whose vertices are the letters and where two vertices are adjacent if and only if the letters are confoundable. Thus a set of letters, no two of which are confoundable, is exactly a coclique in this graph. The *strong product* $G \otimes H$ of simple graphs G and H is the simple graph defined by $V(G \otimes H) := V(G) \times V(H)$ and where distinct vertices (x_1, y_1) and (x_2, y_2) are adjacent in $G \otimes H$ when x_1 and x_2 are equal or adjacent, and y_1 and y_2 are equal or adjacent. The vertices of $G^n := G \otimes G \otimes \cdots \otimes G$ (n factors) correspond to words of length n , and two are adjacent in G^n just when the words are confoundable. Thus we are interested in the size of a largest coclique in G^n .

The *independence number* $\alpha(G)$ of a graph G is the largest cardinality of a coclique in G . The *Shannon capacity* of a graph G is

$$\Theta(G) := \lim_{n \rightarrow \infty} (\alpha(G^n))^{1/n} = \sup_n (\alpha(G^n))^{1/n}.$$

That the limit exists and is equal to the supremum follows from the observation that the product of cocliques in G and H is a coclique in $G \otimes H$, and thus that $\alpha(G^{k+m}) \geq \alpha(G^k)\alpha(G^m)$. (See Fekete’s lemma in Chapter 11.)

Example 31.1. The problem of evaluating the Shannon capacity of such simple graphs as the pentagon P_5 was open for many years

before the relevance of algebraic techniques was noticed by Lovász. It is easy to find 2^n words of length n , no two of which are confoundable, e.g. all words of 1s and 3s. This shows $\Theta(P_5) \geq 2$. This is not so good: we get only four words of length 2 this way, when it is not hard to find a set of five:

$$(1, 1), (2, 3), (3, 5), (4, 2), (5, 4).$$

For even values of n , we can take the product of $n/2$ copies of the above five words to get $(\sqrt{5})^{n/2}$ pairwise nonconfoundable words of length n ; this shows $\Theta(P_5) \geq \sqrt{5}$. Can we do better, perhaps for very large values of n ? No, as we shall see after Theorem 31.6, $\Theta(P_5) \leq \sqrt{5}$.

Here is the approach of Lovász (1979). First, observe that with the definition of Kronecker product of Chapter 18, we have, for vectors $\mathbf{x}, \mathbf{y} \in \mathbb{R}^n$, $\mathbf{v}, \mathbf{w} \in \mathbb{R}^n$,

$$(31.2) \quad (\mathbf{x} \circ \mathbf{v})(\mathbf{y} \circ \mathbf{w})^\top = \langle \mathbf{x}, \mathbf{y} \rangle \langle \mathbf{v}, \mathbf{w} \rangle.$$

Let G be a graph. For simplicity we shall always assume that its vertices are $1, 2, \dots, n$. An *orthonormal representation* of G is a system $(\mathbf{v}_1, \dots, \mathbf{v}_n)$ of unit vectors in a Euclidean space such that if i and j are nonadjacent vertices, then \mathbf{v}_i and \mathbf{v}_j are orthogonal. Clearly, every graph has an orthonormal representation, for example by pairwise orthogonal vectors.

Lemma 31.4. *Let $(\mathbf{u}_1, \dots, \mathbf{u}_n)$ and $(\mathbf{v}_1, \dots, \mathbf{v}_m)$ be orthonormal representations of G and H respectively. Then the vectors $\mathbf{u}_i \circ \mathbf{v}_j$ form an orthonormal representation of $G \otimes H$.*

PROOF.: This is a consequence of (31.2). □

Define the *value* of an orthonormal representation $(\mathbf{u}_1, \dots, \mathbf{u}_n)$ to be

$$\min_{\mathbf{c}} \max_{1 \leq i \leq n} \frac{1}{\langle \mathbf{c}, \mathbf{u}_i \rangle^2},$$

where \mathbf{c} ranges over all unit vectors. The vector \mathbf{c} yielding the minimum is called the *handle* of the representation. Let $\theta(G)$ denote the minimum value over all representations of G . It is easy to see that this minimum is attained. A representation with value $\theta(G)$ is called *optimal*.

Lemma 31.5. $\theta(G \otimes H) \leq \theta(G)\theta(H)$.

PROOF: Let $(\mathbf{u}_1, \dots, \mathbf{u}_n)$ and $(\mathbf{v}_1, \dots, \mathbf{v}_m)$ be optimal orthonormal representations of G and H , with handles \mathbf{c} and \mathbf{d} , respectively. Then, by (31.2), $\mathbf{c} \circ \mathbf{d}$ is a unit vector, and again by (31.2),

$$\begin{aligned} \theta(G \otimes H) &\leq \max_{i,j} \frac{1}{\langle \mathbf{c} \circ \mathbf{d}, \mathbf{u}_i \circ \mathbf{v}_j \rangle^2} \\ &= \max_{i,j} \frac{1}{\langle \mathbf{c}, \mathbf{u}_i \rangle^2} \cdot \frac{1}{\langle \mathbf{d}, \mathbf{v}_j \rangle^2} \\ &= \theta(G)\theta(H). \end{aligned}$$

(One can prove that equality holds in this lemma.) □

Theorem 31.6. $\Theta(G) \leq \theta(G)$.

PROOF: We first show that $\alpha(G) \leq \theta(G)$. Let $(\mathbf{u}_1, \dots, \mathbf{u}_n)$ be an optimal orthonormal representation of G with handle \mathbf{c} . Suppose that $\{1, 2, \dots, k\}$ is a maximum independent set in G and hence $\mathbf{u}_1, \dots, \mathbf{u}_k$ are pairwise orthogonal. Therefore

$$1 = \|\mathbf{c}\|^2 \geq \sum_{i=1}^k \langle \mathbf{c}, \mathbf{u}_i \rangle^2 \geq \alpha(G)/\theta(G).$$

From this and Lemma 31.5 we find that $\alpha(G^n) \leq \theta(G^n) \leq \theta(G)^n$. □

Example 31.1, continued. We can now show that $\Theta(C_5) = \sqrt{5}$ by an elegant idea from Lovász (1979). Consider an umbrella whose handle and *five* ribs have unit length. If we open such an umbrella, we will pass a point where the angles between nonadjacent ribs are all $\pi/2$. If we call the handle \mathbf{c} and the ribs \mathbf{u}_1 to \mathbf{u}_5 , all oriented away from their common point, then $\mathbf{u}_1, \dots, \mathbf{u}_5$ is an orthonormal representation of C_5 in \mathbb{R}^3 . It is an easy calculation to show that $\langle \mathbf{c}, \mathbf{u}_i \rangle = 5^{-1/4}$. Theorem 31.6 and the definition of $\theta(C_5)$ then yield the result.

The result also follows from the corollary below.

Corollary. Let G be a graph on n vertices which is regular of degree d and let λ_{\min} be the least eigenvalue of G . Then

$$\Theta(G) \leq \frac{-n\lambda_{\min}}{d - \lambda_{\min}}.$$

PROOF: Let A be the adjacency matrix of G . In the proof of Theorem 31.3, we saw that with $\lambda := \lambda_{\min}$, $M := A - \lambda I - \frac{d-\lambda}{n}J$ was positive semidefinite (and singular). Thus $M = BB^\top$ for some real matrix B of rank $< n$. Let the rows of B be $\mathbf{x}_1, \dots, \mathbf{x}_n$; we have

$$\langle \mathbf{x}_i, \mathbf{x}_i \rangle = -\lambda - \frac{d-\lambda}{n}, \quad \langle \mathbf{x}_i, \mathbf{x}_j \rangle = -\frac{d-\lambda}{n},$$

the latter when i, j are not adjacent. Let \mathbf{c} be any unit vector orthogonal to the rows \mathbf{x}_i of B and define

$$\mathbf{v}_i := \frac{1}{\sqrt{-\lambda}}\mathbf{x}_i + \frac{1}{\sqrt{-\lambda n/(d-\lambda)}}\mathbf{c}.$$

Check that $\mathbf{v}_1, \dots, \mathbf{v}_n$ is an orthogonal representation of G . Finally note that for any i ,

$$\frac{1}{\langle \mathbf{c}, \mathbf{v}_i \rangle^2} = \frac{-\lambda n}{d-\lambda}.$$

The result follows from Theorem 31.6. □

Next, we give two applications of ‘interlacing’ of eigenvalues.

Lemma 31.8. *Let A be a symmetric matrix of order n with eigenvalues*

$$\lambda_1 \geq \lambda_2 \geq \dots \geq \lambda_n.$$

Suppose N is an $m \times n$ real matrix such that $NN^\top = I_m$, so $m \leq n$. Let $B := NAN^\top$, and let

$$\mu_1 \geq \mu_2 \geq \dots \geq \mu_m$$

be the eigenvalues of B . Then the eigenvalues of B interlace those of A , in the sense that

$$\lambda_i \geq \mu_i \geq \lambda_{n-m+i}$$

for $i = 1, 2, \dots, m$.

PROOF: Let $\mathbf{e}_1, \dots, \mathbf{e}_n$ be an orthonormal basis of eigenvectors of A corresponding to $\lambda_1, \dots, \lambda_n$, and let $\mathbf{f}_1, \dots, \mathbf{f}_m$ be an orthonormal basis of eigenvectors of B corresponding to μ_1, \dots, μ_m .

Fix i and consider $U := \text{span}\{\mathbf{f}_1, \dots, \mathbf{f}_i\}$. By (31.1),

$$\frac{\mathbf{x}B\mathbf{x}^\top}{\mathbf{x}\mathbf{x}^\top} \geq \mu_i$$

for every nonzero $\mathbf{x} \in U$. Let $W := \{\mathbf{x}N : \mathbf{x} \in U\}$. Then W is an i -dimensional subspace and

$$(31.3) \quad \frac{\mathbf{y}A\mathbf{y}^\top}{\mathbf{y}\mathbf{y}^\top} \geq \mu_i$$

for every $\mathbf{y} \in W$. Choose $\mathbf{y} \neq 0$ in $W \cap \text{span}\{\mathbf{e}_i, \mathbf{e}_{i+1}, \dots, \mathbf{e}_n\}$. Then in addition to (31.3), we have

$$\frac{\mathbf{y}A\mathbf{y}^\top}{\mathbf{y}\mathbf{y}^\top} \leq \lambda_i$$

from (31.1) and this proves $\lambda_i \geq \mu_i$.

A similar argument with $U := \text{span}\{\mathbf{f}_i, \dots, \mathbf{f}_m\}$ will prove that $\mu_i \geq \lambda_{n-m+i}$. \square

The term interlacing seems most natural in the case $m = n - 1$ where

$$\lambda_1 \geq \mu_1 \geq \lambda_2 \geq \mu_2 \geq \lambda_3 \geq \dots \geq \lambda_{n-1} \geq \mu_{n-1} \geq \lambda_n.$$

An important special case of Lemma 31.8 occurs when the rows of N are m distinct ‘standard basis’ vectors of length n , i.e. with a single 1 in each row. In this case the matrix B is just an $m \times m$ principal submatrix of A . The following observation is due to D. M. Cvetković.

Theorem 31.9. *The size of a coclique in a graph G cannot exceed the number of nonnegative eigenvalues, or the number of nonpositive eigenvalues, of G .*

PROOF: If G has a coclique of size m , then the adjacency matrix A has an $m \times m$ principal submatrix of all zeros. If the eigenvalues of A are $\lambda_1 \geq \lambda_2 \geq \dots \geq \lambda_n$, then by interlacing, $\lambda_m \geq 0$ and $0 \geq \lambda_{n-m+1}$, so A has at least m eigenvalues which are ≥ 0 and at least m which are ≤ 0 . \square

The next theorem is a result of A. J. Hoffman on the chromatic number of a graph. We remark that for regular graphs, this would follow from Theorem 31.3.

Theorem 31.10. *Let $\lambda_1 \geq \dots \geq \lambda_n$ be the eigenvalues of a graph G . Then*

$$\chi(G) \geq 1 + \lambda_1/(-\lambda_n).$$

PROOF: Suppose G can be properly colored with m colors. The color classes induce a partition of the adjacency matrix

$$A = \begin{pmatrix} A_{11} & \cdots & A_{1m} \\ \vdots & & \vdots \\ A_{m1} & \cdots & A_{mm} \end{pmatrix},$$

where A_{ij} is the submatrix consisting of the rows indexed by the vertices of color i and columns indexed by the vertices of color j . Each of the diagonal blocks A_{ii} is a square zero matrix.

Let \mathbf{e} be an eigenvector of A corresponding to the maximum eigenvalue λ_1 and write $\mathbf{e} = (\mathbf{e}_1, \dots, \mathbf{e}_m)$ where \mathbf{e}_i has coordinates indexed by the vertices of color i . Let

$$N := \begin{pmatrix} \frac{1}{\|\mathbf{e}_1\|}\mathbf{e}_1 & 0 & 0 & \cdots \\ 0 & \frac{1}{\|\mathbf{e}_2\|}\mathbf{e}_2 & 0 & \cdots \\ 0 & 0 & \frac{1}{\|\mathbf{e}_3\|}\mathbf{e}_3 & \cdots \\ \vdots & \vdots & \vdots & \cdots \end{pmatrix}$$

(an $m \times n$ matrix) and let $B := NAN^\top$. By Lemma 31.8, the eigenvalues μ_1, \dots, μ_m of B interlace those of A and hence are between λ_1 and λ_n . On the other hand, we have constructed B so that λ_1 is an eigenvalue since

$$(\|\mathbf{e}_1\|, \dots, \|\mathbf{e}_m\|)B = \mathbf{e}AN^\top = \lambda_1\mathbf{e}N^\top = \lambda_1(\|\mathbf{e}_1\|, \dots, \|\mathbf{e}_m\|).$$

Finally note that the diagonal entries of B are zeros, so

$$0 = \text{trace}(B) = \mu_1 + \dots + \mu_m \geq \lambda_1 + (m - 1)\lambda_n.$$

This proves the theorem. (But perhaps we should have said that if some of the \mathbf{e}_i are zero, those rows should not be included in N .)

□

Problem 31D. Show that for any finite graph G , $\chi(G) \leq 1 + \lambda_1$ where λ_1 is the largest eigenvalue of G . Hint: consider the degrees of an induced subgraph of G that is minimal with respect to having the same chromatic number as G .

In addition to being symmetric, the adjacency matrix of a graph is also a *nonnegative* matrix. There is a useful theory of such matrices, at the center of which is the Perron–Frobenius theorem, Theorem 31.11 below. A complete proof may be found in Gantmacher (1959).

A square matrix A with rows and columns indexed by a set X , say, is called *irreducible* when it is *not* possible to find a proper subset S of X so that $A(x, y) = 0$ whenever $x \in S$ and $y \in X \setminus S$. Equivalently, A is not irreducible if and only if it is possible to apply a simultaneous row and column permutation to obtain a matrix of the form

$$\begin{pmatrix} B & O \\ C & D \end{pmatrix}$$

where B and D are square and of order at least 1. It should be clear that if A is the incidence matrix of a graph, then it is irreducible if and only if the graph is connected.

Problem 31E. Let D be a finite digraph. Let A the adjacency matrix of D , or any matrix with rows and columns indexed by the vertices of D and where $A(x, y) = 0$ if there are no edges directed from x to y and $A(x, y) > 0$ if there are such edges. (i) Show that $A^k(x, y) > 0$ if and only if there is a directed walk of length k from x to y in D . (ii) Show that A is irreducible if and only if D is *strongly connected*, that is, if and only if for any two vertices of D , there is a directed path from x to y .

Theorem 31.11 (Perron–Frobenius). *Let A be an irreducible $n \times n$ nonnegative matrix. There is, up to scalar multiples, a unique eigenvector $\mathbf{a} = (a_1, \dots, a_n)$ all of whose coordinates a_i are nonnegative. The coordinates of this vector \mathbf{a} are, in fact, strictly positive. The corresponding eigenvalue λ (which is called the dominant eigenvalue of A) has algebraic multiplicity 1 and has the property that $\lambda \geq |\mu|$ for any eigenvalue μ of A .*

PARTIAL PROOF: We omit the proof of the existence of a nonnegative eigenvector, but show how irreducibility is used and give much of the rest of the proof.

We will show that any nonnegative eigenvector \mathbf{a} of A , corresponding to eigenvalue λ , say, is positive in all coordinates. Consider A as the matrix of a strongly connected digraph as in Problem 31E. Since there is a directed path from any vertex to any other of length $\leq n - 1$,

$$I + A + A^2 + \cdots + A^{n-1} > O.$$

Here and below, an inequality for matrices or vectors is understood to hold in all coordinates. Since $\mathbf{a} \geq \mathbf{0}$ but $\mathbf{a} \neq \mathbf{0}$,

$$\mathbf{0} < \mathbf{a}(I + A + A^2 + \cdots + A^{n-1}) = (1 + \lambda + \cdots + \lambda^{n-1})\mathbf{a},$$

and so $\mathbf{0} < \mathbf{a}$.

Next we show the eigenvalue λ has geometric multiplicity 1, i.e. that the corresponding eigenspace has dimension 1. Let \mathbf{a}' be any eigenvector corresponding to eigenvalue λ , with coordinates that are positive, negative, or zero. If we add or subtract small scalar multiples of \mathbf{a}' from \mathbf{a} , we obtain other positive or nonnegative eigenvectors $\mathbf{a} - c\mathbf{a}'$ corresponding to eigenvalue λ . We can choose c so that $\mathbf{a} + c\mathbf{a}' \geq \mathbf{0}$, but so that at least one coordinate is zero. This contradicts the result of the previous paragraph unless $\mathbf{a} - c\mathbf{a}' = \mathbf{0}$. We omit the proof that λ has algebraic multiplicity 1, i.e. is a simple zero of the characteristic polynomial.

Let \mathbf{a} be the positive eigenvector for A , with eigenvalue λ . Let \mathbf{b} be the positive eigenvector of A^\top ; say $\mathbf{A}\mathbf{b}^\top = \nu\mathbf{b}^\top$. Then

$$\lambda\mathbf{a}\mathbf{b}^\top = (\mathbf{a}\mathbf{A})\mathbf{b}^\top = \mathbf{a}(\mathbf{A}\mathbf{b}^\top) = \nu\mathbf{a}\mathbf{b}^\top.$$

This is a contradiction unless $\nu = \lambda$, so $\mathbf{A}\mathbf{b}^\top = \lambda\mathbf{b}^\top$. Suppose \mathbf{u} is an eigenvector of A that is not a scalar multiple of \mathbf{a} , say $\mathbf{u}\mathbf{A} = \mu\mathbf{u}$ with $\mu \neq \lambda$. Then

$$\lambda\mathbf{u}\mathbf{b}^\top = \mathbf{u}(\mathbf{A}\mathbf{b}^\top) = (\mathbf{u}\mathbf{A})\mathbf{b}^\top = \mu\mathbf{u}\mathbf{b}^\top.$$

which implies $\mathbf{u}\mathbf{b}^\top = 0$. So any other eigenvector \mathbf{u} cannot have nonnegative coordinates. Now let $\hat{\mathbf{u}} := (|u_1|, \dots, |u_n|)$ and check that $\hat{\mathbf{u}}A \geq |\mu|\hat{\mathbf{u}}$ follows easily from $A \geq O$. Then

$$\lambda\hat{\mathbf{u}}\mathbf{b}^\top = \hat{\mathbf{u}}(A\mathbf{b}^\top) = (\hat{\mathbf{u}}A)\mathbf{b}^\top \geq |\mu|\hat{\mathbf{u}}\mathbf{b}^\top,$$

from which we have $\lambda \geq |\mu|$. □

Theorem 31.12. *Let λ be the dominant eigenvalue of a connected graph G . Then G is bipartite if and only if $-\lambda$ is also an eigenvalue of G .*

PROOF: First suppose G is bipartite. Then the adjacency matrix A of G is, after renumbering the vertices if necessary so that the color classes consist of the first k and last $n - k$, of the form

$$A = \begin{pmatrix} O & B \\ B^\top & O \end{pmatrix}$$

where B is $k \times n - k$. Let \mathbf{e} be an eigenvector corresponding to an eigenvalue μ and write $\mathbf{e} = (\mathbf{e}_1, \mathbf{e}_2)$ where \mathbf{e}_1 consists of the first k coordinates. It may be checked that $(\mathbf{e}_1, -\mathbf{e}_2)$ is then an eigenvector of eigenvalue $-\mu$. So if G is bipartite (connected or not), its spectrum is in fact symmetric about 0.

Now suppose λ is the dominant eigenvalue of a connected graph G and that $-\lambda$ is also an eigenvalue. Let $\mathbf{e} = (\mathbf{e}_1, -\mathbf{e}_2)$ be an eigenvector of unit length corresponding to $-\lambda$, where we have numbered the vertices so that \mathbf{e}_1 and \mathbf{e}_2 both have all nonnegative coordinates. Partition the adjacency matrix A accordingly:

$$A = \begin{pmatrix} B & C \\ D & E \end{pmatrix}.$$

Then

$$-\lambda = \mathbf{e}A\mathbf{e}^\top = \mathbf{e}_1B\mathbf{e}_1^\top + \mathbf{e}_2E\mathbf{e}_2^\top - \mathbf{e}_1C\mathbf{e}_2^\top - \mathbf{e}_2D\mathbf{e}_1^\top,$$

and hence

$$(31.4) \quad (\mathbf{e}_1, \mathbf{e}_2)A(\mathbf{e}_1, \mathbf{e}_2)^\top \geq \lambda$$

with equality if and only if

$$(31.5) \quad \mathbf{e}_1 B \mathbf{e}_1^\top = \mathbf{e}_2 E \mathbf{e}_2^\top = 0.$$

The equation (31.1) and the fact that λ is the dominant eigenvalue imply that equality must hold in (31.4) and that $(\mathbf{e}_1, \mathbf{e}_2)$ is an eigenvector corresponding to eigenvalue λ . Then Theorem 31.11 implies that all coordinates of $(\mathbf{e}_1, \mathbf{e}_2)$ are positive. Finally, (31.5) shows that $B = E = O$ and this means that G is bipartite. \square

Theorem 31.13. *Let G be a finite graph and A its adjacency matrix. There exists a polynomial $f(x)$ such that $f(A) = J$ if and only if G is connected and regular.*

PROOF: Suppose $f(A) = J$ for some polynomial $f(x)$. Then, since polynomials in a given matrix commute, $AJ = JA$. The entry in row x and column y of AJ is $\deg_G(x)$; the entry in that position of JA is $\deg_G(y)$. Hence G is regular.

If $f(A) = J$, then, in particular, for any x and y , we must have $A^k(x, y) \neq 0$ for some k . The entry in row x and column y of A^k is the number of walks of length k from x to y in G . Hence G is connected.

Now suppose G is connected and regular of degree d . Then \mathbf{j} is an eigenvector of A corresponding to eigenvalue d . By Theorem 31.11, the eigenvalue d has multiplicity one. For any symmetric matrix M , the matrix of the orthogonal projection onto any of its eigenspaces is a polynomial in M ; explicitly, if $(x - \mu_1)(x - \mu_2) \cdots (x - \mu_k)$ is the minimal polynomial of M , then it is an exercise to show that

$$\frac{1}{(\mu_1 - \mu_2) \cdots (\mu_1 - \mu_k)} (M - \mu_2 I) \cdots (M - \mu_k I)$$

is the orthogonal projection onto the eigenspace $\{\mathbf{a} : \mathbf{a}M = \mu_1 \mathbf{a}\}$. Since the orthogonal projection onto the span of \mathbf{j} is $\frac{1}{v} J$, this matrix is a polynomial in A . \square

Isomorphic graphs will have the same eigenvalues, but, as we mentioned earlier, the converse is not true: nonisomorphic graphs may have the same spectra (multisets of eigenvalues). See Problem 21O. But we may have a partial converse, in particular for ‘circulant graphs’ with a prime number of vertices.

Let G be an abelian group, written additively. For $S \subseteq G$, the Cayley graph $\Gamma(G, S)$ has vertex set G , and there is an edge directed from x to y in $\Gamma(G, S)$ if and only if $y - x \in S$. Cayley graphs have arisen numerous times in the preceding chapters. A Cayley graph may be thought of as an undirected graph when $-S = S$, and will have no loops when $0 \notin S$. A *circulant graph* is a Cayley graph $\Gamma(G, S)$ where G is cyclic.

(Cayley graphs can also be defined for nonabelian groups. But we consider only the abelian case below.)

A G -matrix is a square matrix A whose rows and columns are indexed by the elements of G and where for some vector of objects $(a_g : g \in G)$, $A(i, j) = a_{j-i}$. A *circulant matrix* (or simply a *circulant*) is a G -matrix where G is cyclic. In general, the adjacency matrix of a Cayley graph based on G is a G -matrix.

We remark that G -matrices over a ring R are closed under multiplication and the algebra of such matrices is isomorphic to the group ring $R[G]$ as in Chapter 28.

Proposition 31.14. *Let ω be a primitive n th root of unity in some field F and U the matrix with rows and columns indexed by \mathbb{Z}_n with $U(i, j) = \omega^{ij}$. Let A be a circulant based on elements $(a_i : i \in \mathbb{Z}_n)$ of F . Then UAU^{-1} is the diagonal matrix with diagonal entries*

$$\lambda_j := \sum_{i=0}^{n-1} a_i \omega^{ji}, \quad j = 0, 1, \dots, n-1.$$

That is, the eigenvalues of A are $\lambda_0, \lambda_1, \dots, \lambda_{n-1}$ (and the corresponding eigenvectors are the rows of U).

Problem 31F. (i) Prove Proposition 31.14. (ii) For those familiar with the characters of an abelian group: Show that the eigenvalues of a rational G -matrix A are $\lambda_\chi = \sum_{g \in G} a_g \chi(g)$, as χ ranges over the characters of G . Cf. Example 30.6.

The following is from Elspas and Turner (1970).

Theorem 31.15. *Let A and B be rational circulant matrices of prime order $p > 2$, based on vectors $(a_i : i \in \mathbb{Z}_p)$ and $(b_i : i \in \mathbb{Z}_p)$, respectively. If A and B have the same spectrum, then for some*

$t \neq 0$ in \mathbb{Z}_p , $a_i = b_{ti}$ for all $i \in \mathbb{Z}_p$, where the subscripts are read modulo p .

PROOF: Let ω be a complex primitive p th root of unity. Then, in view of Proposition 31.14, $\alpha := \sum_{i=0}^{n-1} a_i \omega^i$ is an eigenvalue of A and so is one of the eigenvalues of B , and so

$$\sum_{i=0}^{n-1} a_i \omega^i = \sum_{i=0}^{n-1} b_i \omega^{si}$$

for some s .

First, assume $s \neq 0$, and choose t so that $st \equiv 1 \pmod{p}$. Then

$$\sum_{i=0}^{p-1} (a_i - b_{ti}) \omega^i = 0.$$

But as the minimal polynomial of ω over the rationals is $1 + x + x^2 + \dots + x^{p-1}$, we may conclude that for some constant c , $a_i - b_{ti} = c$ for all i . The traces of A and B , which must be equal, are, respectively, pa_0 and pb_0 . Hence $a_0 = b_0$, and then $c = 0$.

If $s = 0$, then α is rational and

$$(a_0 - \alpha) + a_1 \omega + \dots + a_{p-1} \omega^{p-1} = 0.$$

We may conclude that all coefficients above are equal to some constant c ; this means $A = \alpha I + cJ$.

We repeat the argument with the roles of A and B interchanged, and we find that either the statement of the theorem holds or that $B = \beta I + dJ$ for some rational numbers β and d .

The eigenvalues of $aI + bJ$ are $a + pb$ of multiplicity 1 and $a + b$ of multiplicity $p - 1$. If $A = \alpha I + cJ$ and $B = \beta I + dJ$ have the same spectra and $p > 2$, it follows that $A = B$ and the theorem holds for any t . □

We remark that for $p = 2$, the statement of the theorem is not valid, since e.g. the circulants

$$\begin{pmatrix} 1 & 1 \\ 1 & 1 \end{pmatrix} \quad \text{and} \quad \begin{pmatrix} 1 & -1 \\ -1 & 1 \end{pmatrix}$$

have the same spectrum $\{2, 0\}$. However, it is valid if A and B are both nonnegative.

Corollary. *Circulant graphs of prime order are isomorphic if and only if they (their adjacency matrices) have the same eigenvalues.*

PROOF: We have asserted before that isomorphic graphs have the same spectra.

Suppose the circulant graphs $\Gamma(\mathbb{Z}_p, S)$ and $\Gamma(\mathbb{Z}_p, T)$, for some $S, T \subseteq \mathbb{Z}_p$, p prime, have adjacency matrices A and B with the same spectra. Here A is the circulant based on $(a_i : i \in \mathbb{Z}_p)$ where $a_i = 1$ if $i \in S$ and $a_i = 0$ otherwise; similarly, and B is based on $(b_i : i \in \mathbb{Z}_p)$ where $b_i = 1$ if $i \in T$ and $b_i = 0$ otherwise. Theorem 31.15 says (for $p = 2$, we need the remark) $a_i = b_{ti}$ for some $t \neq 0$. Then the permutation $\phi : i \mapsto ti$ of \mathbb{Z}_p is an isomorphism of $\Gamma(\mathbb{Z}_p, S)$ onto $\Gamma(\mathbb{Z}_p, T)$ because

$$\begin{aligned} i \rightarrow j \text{ in } \Gamma(\mathbb{Z}_p, S) &\iff i - j \in S \\ &\iff t(i - j) \in T \iff ti \rightarrow tj \text{ in } \Gamma(\mathbb{Z}_p, T), \end{aligned}$$

where $x \rightarrow y$ means there is an edge directed from x to y . □

Corollary. *Given $S, T \subseteq \mathbb{Z}_p$, the circulant graphs $\Gamma(\mathbb{Z}_p, S)$ and $\Gamma(\mathbb{Z}_p, T)$ are isomorphic if and only if $T = tS$ for some ‘multiplier’ $t \neq 0$ in \mathbb{Z}_p .*

PROOF: If $\Gamma(\mathbb{Z}_p, S)$ and $\Gamma(\mathbb{Z}_p, T)$ are isomorphic, then they have the same spectra, and as in the proof of the preceding corollary, we have $a_i = b_{ti}$ for some $t \neq 0$, which means $T = tS$.

Conversely, if $T = tS$, then as we saw above, $\phi : i \mapsto ti$ of \mathbb{Z}_p is an isomorphism. □

It had been conjectured that the corollary above holds when p is replaced by any integer n , and the condition $t \neq 0$ replaced by $(t, n) = 1$, but counterexamples exist for $n = 8, 9$ and other values. In fact, the corollary with p replaced by n holds exactly when n is square-free or 4 times an odd square-free number. See M. Muzychuk (1997).

Problem 31G. Prove that the vertices of any finite simple graph may be colored red and blue so that each red vertex is adjacent to an even number of red vertices, and each blue vertex is adjacent to an odd number of red vertices. First prove the lemma: if $S = (a_{ij})$ is a

symmetric $(0, 1)$ -matrix, then the diagonal $\mathbf{a} = (a_{11}, a_{22}, \dots, a_{nn})$, considered as a column-vector, is in the span of the columns of S over the field \mathbb{F}_2 .

Problem 31H. Let G be a connected regular graph with exactly three distinct eigenvalues. Show that G is strongly regular.

Problem 31I. Let G be a nontrivial strongly regular graph and for $x \in V(G)$, let $\Delta(x)$ denote the subgraph induced by the vertices nonadjacent to x . Prove that $\Delta(x)$ is connected by (1) explaining why $k - \mu$ would be an eigenvalue of G if $\Delta(x)$ were not connected, and (2) showing by calculation that $k - \mu$ is not an eigenvalue of G .

Problem 31J. Suppose the Petersen graph P is the union of spanning subgraphs H, K , that are regular of degrees 1 and 2, respectively. Let A be the adjacency matrix of P and B, C the adjacency matrices of H and K , so that $A = B + C$.

Show that there exists a vector \mathbf{u} that is an eigenvector of A corresponding to eigenvalue 1 and also an eigenvector of B corresponding to eigenvalue -1 (and hence an eigenvector of C corresponding to eigenvalue 2). Next, explain why K cannot be a connected graph. (This shows that P is not Hamiltonian.)

Problem 31K. Let G be a directed graph on n vertices without multiple edges. We allow edges $a \rightarrow b$ and $b \rightarrow a$ to occur simultaneously in which case we call $\{a, b\}$ an undirected edge. Suppose that for any two vertices a, b there is exactly one walk of length 3 from a to b if $a \neq b$ and no such walk if $a = b$. If A is the adjacency matrix of G , then this property is expressed by the equation

$$(31.6) \quad A^3 = J - I.$$

- (i) Prove that G is regular;
- (ii) If c is the valency of G , show that $n = c^3 + 1$;
- (iii) Prove that G has exactly $\frac{1}{2}(c^2 + c)$ undirected edges;
- (iv) Construct an example of such a graph if $n = 9$.

Notes.

Theorem 31.3 was never published by Hoffman, one of the first ‘algebraic graph theorists’, but caught the fancy of many of those who heard of it, and has become a classic.

Problem 31D is a result of H. Wilf. Problem 31A is an unpublished result of A. J. Schwenk.

References.

- N. Biggs (1974), *Algebraic Graph Theory*, Cambridge University Press.
- D. M. Cvetković, M. Doob, and H. Sachs (1979), *Spectra of Graphs, a Monograph*, V. E. B. Deutscher Verlag der Wissenschaften.
- B. Elspas and J. Turner (1970), Graphs with circulant adjacency matrices, *J. Combinatorial Theory* **9**, 297–307.
- F. R. Gantmacher (1959), *The Theory of Matrices*, Chelsea.
- W. Haemers (1979), *Eigenvalue Techniques in Design and Graph Theory*, Mathematisch Centrum, Amsterdam.
- L. Lovász (1979), On the Shannon capacity of a graph, *IEEE Trans. Information Theory* **25**, 1–7.
- M. Muzychuk (1997), On Adam's conjecture for circulant graphs, *Discrete Math.* **176**, 285–298.

32

Graph connectivity

For $k \geq 2$, a graph G is said to be *k-vertex connected*, or simply *k-connected*, when $|V(G)| \geq k+1$ and the removal of any $k-1$ vertices (and any incident edges) from G does not result in a disconnected graph. We use 1-connected as a synonym for connected.

If a graph G with at least $k+1$ vertices is not k -connected and the deletion of a set S of $k-1$ vertices disconnects it, there is a partition of $V(G) \setminus S$ into nonempty sets X, Y with no edges crossing (one end in X , one in Y). Let H and K be the subgraphs induced by $X \cup S$ and $Y \cup S$, except that edges with both ends in S are to be put in one and only one of H or K . Then we obtain edge-disjoint subgraphs H and K whose union is G and such that $|V(H) \cap V(K)| = k-1$. Conversely, if such subgraphs H and K exist and each contains at least one more vertex than their intersection, then G is not k -connected.

A graph is said to be *nonseparable* when it is 2-connected and has no loops, or when it is a bond-graph (with two vertices and any positive number of edges joining them, including the link-graph with one such edge), a loop-graph (one edge joining a single vertex to itself), or a vertex-graph. All polygons, for example, are nonseparable; path-graphs or other trees with at least two edges are not.

(We do not want loops, if there are other edges, because while the deletion of the incident vertex may not disconnect the graph in a combinatorial sense, it does in a topological sense. With another type of 2-connectivity, that of Tutte, we would not need to prohibit loops, or allow the small graphs, explicitly; see Problem 32D.)

Here is a small observation about the ‘structure’ of nonseparable graphs.

Lemma 32.1. *Let G be a finite nonseparable graph with at least two edges and H a maximal proper nonseparable subgraph of G . Then G is the union of H and a path-graph P that joins distinct vertices of H and has none of its internal vertices in H .*

The path in the statement of the lemma may be called a ‘handle’. Figure 32.1 is suggestive.




Figure 32.1

PROOF: It may be that $V(H) = V(G)$. In this case, let e be an edge in G but not H and let P be the link-graph consisting of e and its ends. Since adding e to H produces a nonseparable graph and H is maximal among the proper nonseparable subgraphs, the union of H and P is G .

If $V(H) \neq V(G)$, the connectivity of G implies that there exists an edge e with one end $x \in V(H)$ and the other $y \notin V(H)$. By the connectivity of $G - x$, there exists a simple path that does not pass through x , joining y to some other vertex w of H . If z is the first vertex of H on this path (as we proceed from y to w), the edge e and the initial part of this path provide a path-graph P joining x to z that has no edge terms in H and no vertex terms in H other than its ends. Then $H \cup P$ is a nonseparable graph larger than H , and so is equal to G . \square

As a consequence of the lemma, given a finite nonseparable graph G with at least two edges, there is a sequence of nonseparable subgraphs

$$H_0 \subseteq H_1 \subseteq H_2 \subseteq \cdots \subseteq H_k = G$$

where H_0 is a link-graph and where each H_{i+1} is the union of H_i and a handle.

A *subdivision* of a graph G is, informally, a graph H obtained by inserting extra vertices into some edges. More precisely, we

can replace the edges of G by (finite) path-graphs whose internal vertices are ‘new’, i.e. not vertices of the original G ; and we allow the replacing of loops by polygons. Two graphs are said to be *homeomorphic* if they are isomorphic to subdivisions of the same graph. Subdivision of a nonseparable graph (other than the link-graph) preserves nonseparability.

Problem 32A. Let us define the *rank* of a connected graph G as $|E(G)| - |V(G)| + 1$. (In Chapter 34, we will see that this is the dimension of what is called there the cycle space of G .) When we add a handle to a nonseparable graph, the rank goes up by one. Connected graphs of rank 0 are trees. The nonseparable graphs of rank 1 are the polygons. The nonseparable graphs of rank 2 are the θ -graphs, homeomorphic to the letter θ , i.e. subdivisions of the bond-graph with three edges, since that is all that can arise by adding a handle to a polygon. Describe all nonseparable graphs of rank 3 as subdivisions of four graphs.

It is clear that if G is not nonseparable and H, K are edge-disjoint subgraphs with at most one vertex in common, whose union is G , then an edge of H and an edge of K cannot be contained together in any polygon of G .

Theorem 32.2. *Any two edges in a nonseparable graph G are contained in the edge set of a polygon subgraph.*

PROOF: We assert that given distinct vertices x, y and an edge e of a nonseparable graph G , there exists a path from x to y which traverses e . So if x, y are the ends of another edge e' , we obtain a polygon containing e and e' . We prove the assertion by induction on the total number of edges (or the rank).

The link-graph with edge e is a nonseparable subgraph. Let H be a maximal proper nonseparable subgraph containing e . If both x and y are in H , we are done by the induction hypothesis. Otherwise G is the union of H and a path-graph P joining vertices a and b of H , say, and at least one of x or y is an *internal* vertex of P . If both x and y are vertices of P , a path from a to b in H that traverses e together with segments of P provides the required path. Finally, assume x is internal to P and $y \in V(H)$. Say $y \neq a$. Then a path

in H from y to a that traverses e together with the segment of P from x to a provides the required path. \square

Corollary. *Any two vertices of a nonseparable graph G (other than the link-graph) are contained in some polygon in G .*

PROOF: Choose an edge on each vertex and apply the theorem, if the edges are distinct. If the edges are the same, there is a polygon containing that edge, as long as the graph has a second edge somewhere. \square

The corollary is actually equivalent to Theorem 32.2, since the theorem can be derived by inserting new vertices into the middle of the given edges, and applying the corollary to the new vertices.

The corollary is the special case $k = 2$ of the following theorem of H. Whitney (1932).

Theorem 32.3. *A graph G with at least $k + 1$ vertices is k -vertex connected if and only if, for any two distinct vertices x and y of G , there exist k internally disjoint paths joining x and y , i.e. paths which share no vertices other than their ends x and y .*

This will be an immediate consequence of Menger's Theorem below. We give the latter in the version for directed graphs. As usual, an undirected graph may be considered as a digraph when we replace each undirected edge by a pair of directed edges, one in each direction.

We will apply Theorem 7.2 on integral flows, and require the following observation. (This is almost identical to Problem 7B.)

Problem 32B. Let f be a nonnegative flow from s to t in a digraph D (capacities are not required).

(i) Show that if f has positive strength, then there exists a directed path from s to t all of whose edge terms e have $f(e) > 0$.

(ii) Conclude that if f is integral and has strength k , then there exist k directed paths p_1, p_2, \dots, p_k from s to t in D such that for all edges $e \in E(D)$, the number of paths p_i that traverse e is $\leq f(e)$.

Problem 32C. Let s and t be distinct vertices in a digraph D . Show that the maximum number of edge-disjoint directed paths from s to t is equal to the minimum number of edges in a set E

whose deletion disconnects s and t in that direction, i.e. such that every directed path from s to t contains at least one edge from E .

Let s, t be two distinct vertices in a digraph D . An (s, t) -*separating set* is a subset $S \subseteq V(D) \setminus \{s, t\}$ so that any directed path from s to t contains at least one vertex of S .

Theorem 32.4 (Menger's Theorem). *Let s, t be two distinct vertices in a digraph D and assume there is no edge directed from s to t . If no (s, t) -separating set has size less than k , then there exist k internally disjoint directed paths from s to t in D .*

PROOF: We construct a transportation network N whose vertices are s, t , and a pair of new vertices x_1, x_2 for each vertex x of D other than s, t . For each edge of D directed from s to a vertex x of D , there is an edge of N directed from s to x_1 of infinite capacity (or any integer capacity $\geq k$). For each edge of D directed from a vertex x of D to t , there is an edge of N directed from x_2 to t of infinite capacity. For each edge e of D directed from x to y , where x, y are vertices of D other than s, t , there is an edge directed from x_2 to y_1 of infinite capacity. Finally, for each vertex x of D other than s, t , there is an edge directed from x_1 to x_2 of capacity 1.

Note that, by construction, a directed path from s to t in N must have vertex terms of the form

$$s, a_1, a_2, b_1, b_2, \dots, z_1, z_2, t$$

where s, a, b, \dots, z, t are the vertex terms of some directed path from s to t in D .

Suppose we have an integral flow f from s to t in N of strength k . The values of f can only be 0 and 1, because every edge of N either enters a vertex x_1 for which the only edge leaving has capacity 1, leaves a vertex x_2 for which the only edge entering has capacity 1, or is an edge $x_1 \rightarrow x_2$ of capacity 1. By Problem 32B, there exists a set of k directed paths from s to t in N that pass through any edge e at most once. These paths are edge-disjoint and hence internally disjoint, because two directed paths sharing a vertex x_1 or x_2 must share that single edge $x_1 \rightarrow x_2$. So the corresponding k paths in D are internally disjoint.

To ensure that such a flow f exists, we consider a cut (S, T) in N separating s and t and suppose, for contradiction, that the cut has capacity $< k$. The only edges of N with capacity possibly less than k are those directed from x_1 to x_2 for some $x \in V(D)$. If we let V be the set of vertices x of D such that $x_1 \in S$ and $x_2 \in T$, then the capacity of the cut is $|V|$. Every directed path from s to t in N must pass through one of these edges $x_1 \rightarrow x_2$. Equivalently, every directed path in D must pass through a vertex x of V , so V is an (s, t) -separating set. If the hypothesis of the theorem holds, we have a contradiction. \square

* * *

A *convex polytope* P in \mathbb{R}^n is the convex hull of finitely many points, i.e.

$$P = \{\lambda_1 \mathbf{x}_1 + \cdots + \lambda_k \mathbf{x}_k : \lambda_i \geq 0, \lambda_1 + \cdots + \lambda_k = 1\}.$$

The dimension of a polytope is the dimension of its affine span.

A *supporting hyperplane* of P is a hyperplane

$$H = \{\mathbf{x} : \ell(\mathbf{x}) = c\}$$

(where ℓ is a nonzero linear functional $\mathbb{R}^n \rightarrow \mathbb{R}$ and c a scalar) with $H \cap P \neq \emptyset$ but such that P lies entirely in one of the closed halfspaces of H , say

$$P \subseteq \{\mathbf{x} : \ell(\mathbf{x}) \geq c\}.$$

A *face* of P is the intersection of a supporting hyperplane of P with P (though the empty set is often included as a face). A *vertex* of P is a 0-dimensional face; an *edge* of P is a 1-dimensional face. The *graph* G of a polytope P (also called the *1-skeleton* of P) has $V(G)$ and $E(G)$ equal to the vertices and edges, respectively, of P with incidence determined by inclusion.

A face F is a convex polytope in its own right; indeed, it is the convex hull of the vertices of P that it contains (see Grünbaum, 1967). The graph of F is a subgraph of the graph of P .

The following result is due to M. Balinski (1961). For the proof, we require the following fact from the theory of linear programming; see Grünbaum (1967). If s is a vertex of a polytope P in \mathbb{R}^m and ℓ a linear functional, either $\ell(s) \geq \ell(x)$ for all $x \in P$ or there exists a vertex t of P adjacent to s such that $\ell(t) > \ell(s)$.

Theorem 32.5. *The graph G of an n -dimensional convex polytope is n -connected.*

PROOF: We will use induction on n . A 0-dimensional polytope consists of a single point. The graph of a 1-dimensional polytope consists of two vertices and an edge joining them.

Let $x_1, x_2, \dots, x_{n-1}, a, b$ be distinct vertices in the graph G of a convex polytope P of dimension n . We may assume $P \subseteq \mathbb{R}^n$. We want to find a walk in G from a to b that avoids the vertices x_1, \dots, x_{n-1} . Choose an $(n-2)$ -dimensional affine space S that contains x_1, \dots, x_{n-1} . Some hyperplane H , i.e. an $(n-1)$ -dimensional affine subspace, on S is such that both a and b are on the same side of H , i.e. $H = \{z : \ell(z) = \alpha\}$ and $\ell(a) \geq \alpha, \ell(b) \geq \alpha$, for some linear functional ℓ on \mathbb{R}^n and some scalar α . (We allow the case that one or both points are in H .)

Since $P \not\subseteq H$, we can assume P contains points z with $\ell(z) > \alpha$ (otherwise a and b are in H and we can replace ℓ and α by their negatives—i.e. consider the other side of H).

By the above fact from linear programming, there exist paths p and q in G from a and b to vertices a' and b' , respectively, at which ℓ attains its maximum value α' , and such that no vertices of p and q other than their initial vertices lie in H . The intersection $P \cap H'$, where $H' := \{z : \ell(z) = \alpha'\}$, is a face of P of dimension at most $n-1$, and in particular contains a connected graph, so there is a path r in G from a' to b' with vertices in H' . We concatenate p, r , and the reverse of q to find a walk from a to b . \square

Problem 32D. A graph G is said to be k -Tutte-connected when for every $\ell < k$, it is not possible to find a pair (H, K) of nonempty edge-disjoint subgraphs of G , each containing at least ℓ edges, such that $H \cup K = G$ and $|V(H) \cap V(K)| = \ell$. Such a pair of subgraphs may be called an ℓ -separation of G . The concepts of vertex-connectivity and Tutte-connectivity differ. But it is easy to see, for

a nonnull graph, that 1-Tutte-connectivity is the same as ordinary connectivity and that 2-Tutte-connectivity is the same as nonseparability. A 2-Tutte-connected graph with at least two edges cannot have any loops, since otherwise we have two edge-disjoint subgraphs (one a loop-graph and the other with all other edges), each with at least one edge, but with only one vertex in common. Prove that for a graph G with $|V(G)| \geq k + 1$, G is k -Tutte-connected if and only if G is k -vertex connected and has no polygons with fewer than k edges.

Notes.

See the notes to Chapter 34 for some remarks on H. Whitney.

Karl Menger (1902–1985) was an Austrian mathematician who left Austria in 1937 for the United States, where he spent the rest of his life. He worked in many fields, including logic, didactics, and economics, but is best known for his work on dimension theory and curve theory. After his Ph.D., he worked with L. E. J. Brouwer in Amsterdam to return to Vienna as professor in 1927. There he founded the Vienna Mathematical Colloquium that had such famous members as K. Gödel and A. Wald and a great number of visitors. Their results were published in eight volumes before the seminar was forced to stop because of its many Jewish contributors.

References.

- M. Balinski (1961), On the graph structure of convex polyhedra in n -space, *Pacific J. Math.* **11**, 431–434.
- L. R. Ford, Jr. and D. R. Fulkerson (1962), *Flows in Networks*, Princeton University Press.
- B. Grünbaum (1967), *Convex Polytopes*, J. Wiley (Interscience).
- H. Whitney (1932), Nonseparable and planar graphs, *Trans. Amer. Math. Soc.* **34**, 339–362.

33

Planarity and coloring

We start with some material on deletion and contraction. We shall see in the next chapter that these are ‘dual’ concepts; cf. Problem 34C.

Let G be a graph and $e \in E(G)$. We define two graphs G'_e and G''_e with the same edge set $E(G) \setminus \{e\}$. The first G'_e is obtained from G by deleting the edge e . (It is sometimes convenient subsequently to remove any isolated vertices that may arise, but we shall allow them to remain.) The second G''_e is obtained by identifying the endpoints of e and removing e itself. We can think of ‘reeling in’ or ‘shrinking’ an edge in a drawing of a graph as in Fig. 33.1.




Figure 33.1

The *chromatic polynomial* χ_G of a finite graph G was introduced in Chapter 25: $\chi_G(\lambda)$ is the number of proper colorings of G with λ colors. For example, note that

$$\chi_{K_n}(\lambda) = \lambda(\lambda - 1)(\lambda - 2) \cdots (\lambda - n + 1).$$

That χ_G is a polynomial in λ was shown in Chapter 25—also see the remark following (33.1).

Example 33.1. We claim that for a tree T on n vertices,

$$\chi_T(\lambda) = \lambda(\lambda - 1)^{n-1}.$$

To see this, observe that if x is a monovalent vertex of a tree T , there are $\lambda - 1$ colors available for x after the tree on $n - 1$ vertices, obtained by removing x , is given any proper coloring. The claim follows by induction on the number of vertices.

If e is an edge of G , not a loop, we can break the proper colorings of G'_e into two classes: those in which the endpoints of e have different colors (these are proper colorings of G) and those in which the endpoints of e have the same color (and these are in one-to-one correspondence with the proper colorings of G''_e). This establishes

$$(33.1) \quad \chi_G(\lambda) = \chi_{G'_e}(\lambda) - \chi_{G''_e}(\lambda).$$

The equation (33.1) provides another way of seeing that $\chi_G(\lambda)$ is a polynomial in λ . A graph H with loops has no proper colorings, i.e. $\chi_H(\lambda) = 0$. For an edgeless graph H on n vertices, $\chi_H(\lambda) = \lambda^n$. These are both polynomials. Now use (33.1) and induction on the number of edges.

The chromatic polynomial of a tree T could also be obtained by induction and (33.1): T'_e is a tree and T''_e has two components that are trees.

Problem 33A. Let $\tau(G)$ denote the number of spanning trees in a graph G (this is sometimes called the *complexity* of G). Show that for any nonloop $e \in E(G)$, $\tau(G) = \tau(G'_e) + \tau(G''_e)$.

Problem 33B. Find the chromatic polynomial of the n -gon C_n . Find the chromatic polynomial of the n -wheel W_n (this is the graph obtained from C_n by adding a new vertex and joining it to all vertices of C_n).

It makes no sense to ask for the number of proper colorings of a graph with -1 colors, but since $\chi_G(\lambda)$ is a polynomial, we can evaluate $\chi_G(-1)$. R. P. Stanley (1973) discovered the combinatorial interpretation of $|\chi_G(-1)|$ that follows. An *orientation* of a graph is one of the directed graphs arising by choosing for each edge one of its endpoints to be the *head*; the other is the *tail*. (So the number of orientations of a graph is 2^m where m is the number of edges that are not loops—although for topological purposes, there are reasons why a loop should also be considered to admit two directions.)

Theorem 33.1. *The number of acyclic orientations, i.e. orientations in which there are no directed circuits, of a graph G is $(-1)^{|V(G)|}\chi_G(-1)$.*

PROOF: If G has loops, then $\chi_G(\lambda) = 0$ and G has no acyclic orientations, so the theorem holds in this case.

Consider an acyclic orientation of G'_e where e is not a loop. There are two ways to direct e to get an orientation of G . We claim that one or both of them are acyclic, and that the cases where both are acyclic are in one-to-one correspondence with acyclic orientations of G''_e . This is because directing e from one end x to the other y produces a nonacyclic orientation if and only if there is a directed path from y to x in G'_e ; there cannot be directed paths from x to y and also from y to x in G'_e since we assumed an acyclic orientation; and there is no directed path from y to x in G'_e if and only if identifying x and y produces an acyclic orientation of G''_e .

Thus

$$\omega(G) = \omega(G'_e) + \omega(G''_e)$$

when $\omega(H)$ is taken to be the number of acyclic orientations of a graph H . But by (33.1), this same recursion is also satisfied when $\omega(H)$ is taken to be $(-1)^{|V(H)|}\chi_H(-1)$. The theorem follows by induction on the number of edges after we check that it is valid for edgeless graphs. \square

By an *embedding* or *proper drawing* of a graph G on a surface \mathcal{S} , we mean a drawing where the edges do not cross but meet only at vertices. More precisely, we mean a representation of the graph where the vertices correspond to points in \mathcal{S} , the edges correspond to Jordan arcs (continuous one-to-one images of the unit interval) in \mathcal{S} that join the points of \mathcal{S} corresponding to the ends of the edge in G , and where no internal point of any of the Jordan arcs is a point of any other Jordan arc or one of the points corresponding to the vertices of G . We consider only embeddings of finite graphs. While the plane is not compact, it can be naturally embedded in the sphere (its one-point compactification) and *a graph is planar if and only if it admits an embedding on the sphere*.

Examples of graphs that are not planar include $K_{3,3}$ and K_5 ; we will mention several ways to see this later. Subdivisions of these

graphs, and any graph containing one of these subdivisions, will also not be planar. An important theorem that we shall not prove here is the following. Proofs may be found in Chartrand and Lesniak (1986), Tutte (1984), and Diestel (1997).

Theorem 33.2 (Kuratowski). *A graph G is planar if and only if it has no subgraphs isomorphic to subdivisions of K_5 or $K_{3,3}$.*

Problem 33C. Find a subdivision of $K_{3,3}$ as a subgraph of the Petersen graph.

A *minor* of a graph G is a graph H obtained from G by deleting and contracting edges, and then possibly deleting some or all isolated vertices.

It can be seen that that the order in which edges are deleted or contracted is not important. For example, if the edges of a subset $S \subseteq E(G)$ are contracted in any order, we obtain a graph isomorphic to the graph G''_S , called a *contraction* of G , defined as follows. The vertices of G''_S are, formally, the components of the spanning subgraph, denoted $G:S$, of G with edge set S . The edge set of G''_S is $E(G) \setminus S$. The ends of an edge $e \in E(G) \setminus S$ are, in G''_S , to be the components of $G:S$ that contain the ends of e as an edge of G . Informally, the components of $G:S$ are being shrunk to single vertices.

We use the notation G'_S for the graph obtained by deleting the edges in S , i.e. $G:(E(G) \setminus S)$, but it is convenient to require that any isolated vertices are also deleted when using this notation.

Example 33.2. Let A be the five ‘spokes’ in the usual drawing of the Petersen graph P , on the left of Fig. 1.4. The subgraph $P:A$ has five components, so P''_A will have five vertices. The contraction G''_S in this case is K_5 . If B is the set of five edges in the interior pentagram, then $P:B$ has six components and P''_B is the wheel W_5 . If C is the edge set of a spanning tree of P , then P''_C consists of a single vertex and six loops. (A graph with one vertex may be called a *cotree*.)

Note that it is quite likely that G''_S will have loops and/or parallel edges even if G is simple. (Those contractions of a simple graph G that *have no loops* are in one-to-one correspondence with the

elements of the lattices $\Pi(G)$, sublattices of the partition lattices, introduced in Example 23.6).

A graph G is a contraction of any of its subdivisions H , since contracting any $k - 1$ edges of a path-graph with k edges produces a link-graph.

If we have a drawing of a graph G on a surface \mathcal{S} and $e \in E(G)$, it is clear that there is a natural drawing of G'_e on \mathcal{S} . If e is a nonloop, there is also a natural *induced* drawing of G''_e on \mathcal{S} : the ends of the edge can be continuously brought closer on the surface (see Fig. 33.1). (According to our combinatorial definition, contracting a loop is the same as deleting it.) In particular, if G admits an embedding on a surface \mathcal{S} , then so does every minor of G .

Problem 33D. Show that a graph G that has a minor isomorphic to K_5 or $K_{3,3}$ also contains a subdivision of K_5 or $K_{3,3}$. Somewhat more generally, prove:

(i) if a trivalent graph H occurs as a minor of a graph G , then G contains (as a subgraph) a subdivision of H . So if $K_{3,3}$ is a minor, then a subdivision of $K_{3,3}$ is a subgraph;

(ii) if K_5 is a minor of G , then G contains a subdivision of K_5 or a subdivision of $K_{3,3}$.

A deep and extremely important theorem due to N. Robertson and P. Seymour states that in every infinite set of graphs there are two such that one is a minor of the other. See Chapter 12 of Diestel (1997) for a discussion of part of this work. It follows that the set of graphs that do not embed on a given surface and are minimal with respect to this property (every proper minor being embeddable) is finite. For the plane, there are two.

Given an embedding of a graph G on a surface \mathcal{S} , we define the *faces* or *regions* with respect to the embedding to be the topologically connected components that result when the vertices and edges (more precisely, the points corresponding to vertices and sets of points in the Jordan arcs corresponding to edges) are removed from \mathcal{S} . We denote the set of faces by $F(G)$. We realize that this is *horrible* notation, since the faces depend on the embedding (in particular, on the surface) and are not in general determined by G . But we will use it anyway.

In general, these faces may or may not be 2-cells (homeomorphic to the open unit disk, i.e. without ‘holes’). But for an embedding of a connected graph on the sphere, the regions *will* be 2-cells. This fact is related to the Jordan curve theorem which asserts that if the points of a one-to-one continuous image of the unit circle in the sphere are removed, the resulting topological space has exactly two simply connected components that are 2-cells.

Theorem 33.3 (Euler’s formula). *For a drawing of a connected planar graph G on the sphere or plane,*

$$f - e + v = 2$$

where f , e , and v are, respectively, the numbers of faces, edges, and vertices. More generally, for any graph G embedded on the sphere,

$$(33.2) \quad 1 - |F(G)| + |E(G)| - |V(G)| + |C(G)| = 0,$$

where $C(G)$ denotes the set of components of G .

PROOF: We prove the latter assertion by induction on the number of edges of G . For an edgeless graph, $|C(G)| = |V(G)|$ and $|F(G)| = 1$, so (33.2) holds.

Suppose G has a nonloop a . Consider an embedding of G and note that contracting an edge will not affect the number of faces. Apply the induction hypothesis to G''_a to get

$$1 - |F(G''_a)| + |E(G''_a)| - |V(G''_a)| + |C(G''_a)| = 0.$$

We have $|E(G)| = |E(G''_a)| + 1$, $|V(G)| = |V(G''_a)| + 1$, $|C(G)| = |C(G''_a)|$, and also $|F(G)| = |F(G''_a)|$. So (33.2) holds for G .

Suppose G has loops; let a be one of these, and apply the induction hypothesis to G'_a to get

$$1 - |F(G'_a)| + |E(G'_a)| - |V(G'_a)| + |C(G'_a)| = 0.$$

Of course, $|E(G)| = |E(G'_a)| + 1$, $|V(G)| = |V(G'_a)|$, and $|C(G)| = |C(G'_a)|$. On the sphere, the Jordan curve theorem implies that the two faces incident with e are distinct, so $|F(G)| = |F(G'_a)| + 1$ and we obtain (33.2) for G . \square

Example 33.3. We show that K_5 and $K_{3,3}$ are not planar. The set of edges incident with a face in a planar embedding of a non-separable graph G (other than the link-graph) contains a polygon subgraph; see Chapter 34. The *degree* of a face is the number of incident edges (i.e. its degree as a vertex of the dual graph of Chapter 34). The sum of the degrees of the faces is twice the number of edges, since every edge is incident with two faces.

Consider a hypothetical embedding of K_5 in the plane. By Euler's formula, there are seven faces. But each has degree at least 3, so the sum of the degrees is at least 21, which, of course, is a contradiction to $|E(K_5)| = 10$.

Similarly, there would be five faces in a hypothetical embedding of $K_{3,3}$ in the plane, each of degree at least 4 since $K_{3,3}$ has girth 4. Then the sum of the degrees would be at least 20, contradicting $|E(K_{3,3})| = 9$.

(A similar argument shows that the Petersen graph is not planar. But we already knew this since both K_5 and $K_{3,3}$ occur as minors of the Petersen graph and they are not planar.)

Problem 33E. Determine all pairs (d_1, d_2) of integers with $d_i \geq 2$, $i = 1, 2$, so that there exists a planar graph (not necessarily simple) that is regular of degree d_1 and such that all faces have degree d_2 . (This will include the degrees of the vertices and faces of the five Platonic solids.)

E. Steinitz (1922) characterized the graphs of 3-dimensional convex polytopes.

Theorem 33.4. *A graph G is the graph of a 3-dimensional convex polytope if and only if G is simple, planar, and 3-connected.*

That the graph of a 3-dimensional polytope is 3-connected is a special case of Theorem 32.5. We do not prove the rest of the theorem.

The question "Can the countries of a map on the sphere be colored with four or fewer colors so that adjacent countries are colored differently?", occurs in a letter dated October 23, 1852, from Augustus de Morgan to Sir William Rowan Hamilton. It is likely that the originator of the question was the brother, Francis Guthrie, of a student, Frederick Guthrie, of de Morgan.

Coloring the countries (regions) of a planar map is equivalent to coloring the vertices of the *dual graph* that we will introduce in the next chapter. So for us, the ‘four color problem’ is the question of whether every planar graph is 4-colorable.

Four colors are clearly necessary since K_4 is planar, but it is easy to find many other planar graphs G that cannot be 3-colored. This problem has motivated a great deal of graph theory. More on the history of the four color problem may be found in Biggs, Lloyd, and Wilson (1976).

In 1890, P. J. Heawood proved the Five Color Theorem, Theorem 33.6 below: a loopless planar graph G has chromatic number $\chi(G) \leq 5$. Heawood used ideas of A. B. Kempe (in particular, the recoloring idea reviewed below). In 1976, K. Appel and W. Haken finally settled the four color problem with an announcement of a proof of the Four Color Theorem: $\chi(G) \leq 4$. Surprisingly, perhaps, their proof did not use the vast quantity of work and theories developed in this century but went back to the ideas of Kempe and Heawood. Another surprise, perhaps, is that their proof required over 1000 hours of computer time. It was not clear when they began that the computer would ever finish. As an oversimplification, there were many cases to consider but it was not certain that their number would be finite; the computer was programmed to generate cases itself and could conceivably have gone on forever breaking cases into subcases. See Appel, Haken, and Koch (1977), and Appel and Haken (1977). We have no space to discuss this work in any detail, but will prove the Five Color Theorem below.

Proposition 33.5. *Every nonnull simple planar graph G has a vertex of degree at most 5.*

PROOF: This follows quickly from Euler’s formula. It suffices to prove that a component has such a vertex, so assume G is connected. Suppose a drawing of G has f regions, e edges, and v vertices. If no vertex of degree less than six exists, then the sum of the v degrees of the vertices, which is $2e$, is at least $6v$; that is,

$$v \leq \frac{e}{3}.$$

Since G is simple (and we may assume it is not a link-graph with

two vertices joined by a single edge), each region is incident with at least three edges, so the sum of the f degrees of vertices of G^* , which is $2e$, is at least $3v$; that is

$$f \leq \frac{2e}{3}.$$

But then we have the contradiction

$$2 = f - e + v \leq \frac{e}{3} - e + \frac{2e}{3} = 0.$$

□

Of course, coloring a loopless graph is equivalent to coloring a simple graph (just suppress the multiple edges). An immediate consequence of the above result is the Six Color Theorem: a loopless planar graph G has $\chi(G) \leq 6$. When a vertex x of degree at most five is deleted from a simple planar graph and the result colored with six colors inductively, there is always a color available for x .

We recall the idea of recoloring introduced in Chapter 3. Suppose G is properly colored and let α and β be two of the colors. The colors α and β can be switched on any *component* of the subgraph of G induced by the vertices of colors α and β to obtain another proper coloring. So given two vertices x and y of colors α and β , respectively, either there is a path (of odd length) with vertex terms $a_0 = x, a_1, \dots, a_n = y$ that alternate colors α and β (a so-called *Kempe chain*), or there is a proper coloring in which both x and y have color α , say, while vertices of colors other than α and β retain the same color.

Theorem 33.6. *If G is a loopless planar graph, then $\chi(G) \leq 5$.*

PROOF: We use induction on the number of vertices. The assertion is surely true for graphs with at most five vertices. Consider a planar drawing of a loopless graph G and assume the theorem holds for all graphs with one vertex less. We can assume G is simple.

By Proposition 33.5, there exists a vertex $x \in V(G)$ of degree ≤ 5 . Let G_x denote the graph obtained from G by deleting the vertex x and the incident edges. We have a natural planar drawing of G_x obtained from the drawing of G . By the induction hypothesis,

G_x has a proper coloring with five colors. There is a color available for x , and we are done, unless x has degree exactly five and the vertices y_1, y_2, \dots, y_5 (which we write in the cyclic order given by the drawing) adjacent to x in G have received five distinct colors in the coloring of G_x . So we assume that y_i has received color i , $i = 1, 2, 3, 4, 5$. See Fig. 33.2.

Consider colors 1 and 3. Either there exists a proper coloring of G_x in which y_1 and y_3 both have color 1 (while y_2, y_4 , and y_5 retain their original colors) or there exists a simple path with vertex terms

$$(33.3) \quad y_1, a_1, b_1, a_2, b_2, \dots, a_s, b_s, y_3,$$

say, in G_x with vertices alternately colored 1 and 3. In the first case, x may be assigned color 3 and we are done. Similarly, either there exists a proper coloring of G_x in which y_2 and y_4 both have color 2 (while y_1, y_3 , and y_5 retain their original colors) or there exists a simple path with vertex terms

$$(33.4) \quad y_2, c_1, d_1, c_2, d_2, \dots, c_t, d_t, y_4,$$

say, in G_x with vertices alternately colored 2 and 4. In the first case, x may be assigned color 4 and we are done.

To complete the proof, we note that both paths above cannot exist. If the path in (33.3) exists, then

$$(33.5) \quad x, y_1, a_1, b_1, a_2, b_2, \dots, a_s, b_s, y_3, x$$

is the vertex sequence of a simple closed path, which divides the plane into two regions. The vertex y_2 is in one region while y_4 is in the other. Any path from y_2 to y_4 in G_x must necessarily have a vertex in common with the path in (33.4) and in particular must have a vertex of color 1 or 3; thus a path as in (33.5) cannot exist.

□




Figure 33.2

In Chapter 17, we treated list-colorings of graphs to explain Galvin's proof of the Dinitz conjecture. We shall now treat a result of C. Thomassen (1994) that provides a second proof of the five color theorem by first giving each vertex of the graph a list of five different colors, not necessarily the same list for each vertex. One of the ideas of the proof should be especially noted because it often can be used to make proofs easier. It involves making an induction hypothesis more stringent with the effect that the induction step goes more easily.

Theorem 33.7. *Let G be a planar graph with N vertices v_1, v_2, \dots, v_N . For $i = 1, \dots, N$ let S_i be a set of five elements (which we call colors). There exists a mapping f on the vertices, with $f(v_i) \in S_i$ such that $f(v_i) \neq f(v_j)$ for all adjacent pairs v_i, v_j (a five list-coloring of G).*

PROOF: We first make the problem harder by adding extra edges which change G into a triangulated polygon. Let the numbering be such that v_1, v_2, \dots, v_k are the successive vertices of the polygon (see Fig. 33.3). For each of these vertices *remove* two colors from its list so that vertices on the perimeter of the polygon only have lists of three available colors. Again, the problem is more difficult. Finally, restrict matters even further by selecting two adjacent vertices on the perimeter and assigning to each a color from their list. We claim that with these initial conditions, the coloring can be completed. The proof is by induction on the number of vertices (small cases are trivial).




Figure 33.3

For the induction, we distinguish two cases. In the first, we assume that the polygon has an edge connecting two vertices on the perimeter that are not adjacent on the perimeter, i.e. a chord. The chord divides the polygon into two parts, one of which has both of the precolored vertices (one possibly as an endpoint of the chord). The coloring of that part can be completed by the induction hypothesis. From this coloring, the other part inherits a (pre)coloring of two adjacent vertices on the perimeter and again induction finishes the job.

Now assume that there is no chord. Let v_1 and v_2 be the precolored vertices on the perimeter and let $v_1, u_1, u_2, \dots, u_m, v_{k-1}$, in that order (clockwise, see Fig. 33.3) be the vertices adjacent to v_k . The vertices u_i are interior points and because of the triangulation, there are edges $(v_1, u_1), (u_1, u_2), \dots, (u_{m-1}, u_m), (u_m, v_{k-1})$. The list of v_k has at least two colors not equal to the color of v_1 . We pick (these) two and remove them from the lists of u_1 to u_m and, if necessary, further shorten these lists to size 3. By induction, we can complete the coloring of $G \setminus \{v_k\}$. Possibly v_{k-1} has obtained one of the two colors on v_k 's list but there is one left to complete the coloring of G . \square

Notes.

A. B. Kempe (1849–1922) took a degree in 1872 with special distinction in mathematics at Trinity College, Cambridge where he also gained a musical reputation with his fine countertenor voice.

He chose law as his profession while not relinquishing his mathematical studies.

The Polish mathematician Kazimierz (or Casimir) Kuratowski (1896–1980) taught at Warsaw University (for nearly 40 years) and Lwów Polytech before retiring in 1966. His celebrated theorem characterizing planar graphs was proved in 1930.

Ernst Steinitz (1871–1928) was professor of mathematics at Breslau (now Wrocław) and Kiel. He made important contributions to field theory (with Hilbert).

In 1993, M. Voigt found an example of a planar graph with 238 vertices that is *not* four list-colorable.

References.

- K. Appel and W. Haken (1977), The solution of the four-color map problem, *Scientific American* **237**, 108–121.
- K. Appel, W. Haken, and J. Koch (1977), Every planar map is four colorable, *Illinois J. Math.* **21**, 429–567.
- N. L. Biggs, E. K. Lloyd, and R. J. Wilson (1976), *Graph Theory 1736–1936*, Oxford University Press.
- G. Chartrand and L. Lesniak (1986), *Graphs and Digraphs*, 2nd edn., Wadsworth.
- R. Diestel (1997), *Graph Theory*, Springer-Verlag Graduate Texts in Mathematics **173**.
- R. P. Stanley (1973), *Acyclic orientations of graphs*, *Discrete Math.* **5**, 171–178.
- E. Steinitz (1922), Polyeder und Raumeinteilungen, *Enzykl. Math. Wiss.* **3**, 1–139.
- C. Thomassen (1994), Every planar graph is 5-choosable, *J. Combin. Theory Ser. B* **62**, 180–181.
- W. T. Tutte (1984), *Graph Theory*, *Encyclopedia of Math. and its Appl.* **21**, Addison-Wesley. Reissued by Cambridge University Press.

34

Whitney duality

A Jordan arc divides a small neighborhood of one of its internal points into two ‘halves’. Thus in addition to being incident with two vertices (which may coincide), an edge in a map is incident with two regions (which may coincide). See Fig. 34.1.





Figure 34.1

This allows us to define the *dual* graph G^* of a graph G with respect to a 2-cell embedding of G on a surface \mathcal{S} . The vertices $V(G^*)$ are to be the regions with respect to the embedding; the edges $E(G^*)$ are to be the same as the edges of G ; the ends of an edge e in G^* are to be the regions with which e is incident. Two examples are shown in Fig. 34.2.


We have defined G^* abstractly, but it is important to note that it admits an embedding on the same surface \mathcal{S} : we can represent a region by a point in its interior; the interior points in two regions sharing an edge e can be joined by a Jordan arc crossing only the Jordan arc representing e in G . The drawing of the dual of the cube in Fig. 34.2 is shown in Fig. 34.3.

Examples will convince the reader that $(G^*)^*$ is isomorphic to G . Two other facts that we invite the reader to think about but do

not attempt to prove formally are: a graph that is not connected cannot have a 2-cell embedding; the dual graph with respect to a 2-cell embedding is always connected.



ends in G	edge	ends in G^*
1,2	a	I,II
1,3	b	I,II
2,3	c	I,II
3,4	d	I,I
4,4	e	I,III



ends in G	edge	ends in G^*
1,2	a	I,II
2,3	b	I,III
3,4	c	I,IV
4,1	d	I,V
5,6	e	II,VI
6,7	f	III,VI
7,8	g	IV,VI
8,5	h	V,VI
1,5	i	II,V
2,6	j	II,III
3,7	k	III,IV
4,8	l	IV,V

Figure 34.2

The planar duals of the series of polygons are the *bond-graphs*, i.e. the graphs with two vertices and any positive number of edges joining them. In particular, the loop-graph and the link-graph are dual. The planar dual of a tree is a cotree, and a planar dual of a cotree is a tree.




Figure 34.3

In general, a graph may have several planar dual graphs. Fig. 34.4 shows two isomorphic cotrees and their nonisomorphic planar duals with respect to the two embeddings. Fig. 34.5 shows two embeddings of a nonseparable graph G and the dual graphs with respect to each embedding, which are not isomorphic.




Figure 34.4




Figure 34.5

The goal of this chapter is to understand the relation between a planar graph and its dual graph(s) ‘combinatorially’. We will use this understanding (Whitney duality) to prove some theorems

about planar graphs and their duals (without any reference to planar drawings or topology).

Recall that the *incidence matrix* $N = N(G)$ of a graph G is the matrix whose rows are indexed by $V(G)$, whose columns are indexed by $E(G)$, and where

$$N(x, e) = \begin{cases} 1 & \text{if } x \text{ is incident with a nonloop } e, \\ 2 & \text{if } e \text{ is a loop incident with } x \\ 0 & \text{if } x \text{ is not incident with } e. \end{cases}$$

We are going to work over the field \mathbb{F}_2 of two elements, so loops essentially correspond to columns of all zeros. Every other column contains two ones and, in particular, the sum modulo 2 of all rows of N is the zero vector.

We may consider the *code* $\mathcal{C}(G)$ of a graph G , which is the binary code generated by the incidence matrix $N(G)$. A graph H is a *Whitney dual* of a graph G when $E(G) = E(H)$ and the code $\mathcal{C}(G)$ of G is equal to the dual code $\mathcal{C}(H)^\perp$ of H . Clearly, H is a Whitney dual of G if and only if G is a Whitney dual of H . This definition requires that G and H have the same edge set, which is convenient notationally. But, informally, it is only necessary that the edges of G and H be labeled by the same set, or otherwise put in one-to-one correspondence.

Note that the code of a polygon with n edges consists of all even-weight words of length n ; the code of a bond-graph with n edges consists of the two constant words. The code of a tree consists of all words; the code of a cotree consists of only the zero word.

Some terms in graph theory are used in many contexts, with varying meanings. In this chapter, we use ‘cycle’, ‘circuit’, ‘cutset’, and ‘bond’ of a graph G to mean certain subsets, described below, of the edge set $E(G)$. Other uses of these terms the reader may know must be temporarily forgotten.


As in Chapter 20, we use the term *support* of a codeword \mathbf{x} to denote the subset of the indexing set for its coordinates that are nonzero in \mathbf{x} . For binary codes, we can identify the codewords with their supports. The supports of words in $\mathcal{C}(G)$ are called *cutsets* of G ; supports of words in $\mathcal{C}(G)^\perp$ are called *cycles* of G . The terms *circuits* and *bonds* are used, respectively, for minimal nonempty

cycles and cutsets. We use *cycle space* and *cutset space* to mean the set of all cycles and cutsets, respectively. Of course, these are vector spaces over the field \mathbb{F}_2 , with addition of two sets equal to their symmetric difference.

It is easy enough to understand when a subset $S \subseteq E(G)$ is a cycle, or a cutset. The binary sum of the rows of the incidence matrix indexed by vertices in X has support equal to the set $\times(X, Y)$ of edges that ‘cross’ from X to $Y := V(G) \setminus X$. i.e. that have one end in X and one end in Y . That is, S is a cutset if and only if $S = \times(X, Y)$ for some X, Y . We use this notation only when X and Y partition the vertex set; we allow X or Y to be empty, in which case S is empty.

A vector, with support S , say, is orthogonal over \mathbb{F}_2 to a row of N indexed by a vertex x when and only when x is incident with an even number of edges in S , loops being counted twice. So the cycles are those subsets of $E(G)$ so that every vertex has even degree in $G:S$, the spanning subgraph of G with edge set S .

Example 34.1. Let G be the graph below.



The incidence matrix of G is

$$\begin{array}{c} \\ 1 \\ 2 \\ 3 \\ 4 \end{array} \begin{array}{ccccc} & a & b & c & d & e \\ \left(\begin{array}{ccccc} 1 & 0 & 0 & 1 & 1 \\ 1 & 1 & 0 & 0 & 0 \\ 0 & 1 & 1 & 0 & 1 \\ 0 & 0 & 1 & 1 & 0 \end{array} \right) . \end{array}$$

There are four cycles in G : \emptyset , $\{a, b, e\}$, $\{c, d, e\}$, and $\{a, b, c, d\}$. The latter three are, in fact, circuits. There are eight cutsets. The

set $\{a, b, c, d\}$ is both a cycle and a cutset; it is the support of the sum of rows 2 and 4. But $\{a, b, c, d\}$ is not a bond; it contains a smaller cutset, e.g. the support $\{a, b\}$ of row 2. The set $\{a, b\}$ is a bond. Another example of a bond is $\{b, d, e\}$; it is the support of the sum of rows 1 and 2, or of 3 and 4.

Problem 34A. (i) Let G be connected. Prove one of the equivalent statements: the number of cutsets of G is exactly $2^{|V(G)|-1}$; the dimension of the cutset space of G is $|V(G)| - 1$.

(ii) Prove, in general, that the dimension of the cutset space of G is $|V(G)| - |C(G)|$, where $C(G)$ is the set of components of G . (As a corollary, the dimension of the cycle space is $|E(G)| - |V(G)| + |C(G)|$.)

Example 34.2. The cycle spaces of K_6 and of the Petersen graph are binary codes of length 15 of dimensions 10 and 6, respectively. (Fig. 35.1 in the next chapter shows that K_6 is the dual of the Petersen graph with respect to an embedding in the real projective plane, but they are not Whitney duals, since the dimensions of their codes sum to more than the number of edges.) The minimum distances of these codes are 3 and 5, respectively. We remark that the vector of all 1s can be added to a generating set for these two codes and the minimum distances remain 3 and 5 while the dimension goes up by 1 in both cases.

Theorem 34.1. *Let G be a graph.*

(i) *A set $S \subseteq E(G)$ is a circuit if and only if it is the edge set of a polygon subgraph of G .*

(ii) *Assume G is connected. A cutset $\times(X, Y)$ is a bond of G if and only if the subgraphs of G induced by X and Y are both connected.*

PROOF: Clearly the edge set of a polygon is a minimal nonempty cycle. A nonempty cycle is certainly not the edge set of a forest (since every tree has monovalent vertices, say) and so contains the edge set of a polygon; so a minimal nonempty cycle is the edge set of a polygon.

Let $S = \times(X, Y)$. If the subgraphs induced by X and Y are connected, then S cannot properly contain a nonempty cutset because deleting any proper subset of the edges in S does not produce a

disconnected graph. If the subgraph induced on Y , say, is not connected, there is a partition of Y into nonempty subsets Y_1 and Y_2 with no edges between them. Then $S' := \times(X \cup Y_1, Y_2)$ is contained in S . Connectivity implies that there are edges between X and Y_1 and X and Y_2 , and this means S' is both nonempty and a proper subset of S . \square

The reader may check that a set of edges of an arbitrary graph G is a bond of G if and only if it is a bond in one of the components of G . Also note that a subset S of edges of a graph G is a bond of G if and only if the deletion of the edges in S results in a graph with more components than G (e.g. a disconnected graph, if G is connected to start with) and S is minimal with respect to this property.

Given a set S of edges of a graph G , S is a circuit if and only if deleting the edges not in S (and any isolated vertices that result) produces a polygon; S is a bond if and only if contracting the edges not in S (and deleting any isolated vertices that result) produces a bond-graph.

Notice that the set $S(x)$ of edges of a graph G that are incident with a vertex x , not including loops, is always a cutset. These span the cutset space—they are the supports of the rows of the incidence matrix. In view of Theorem 34.1(ii), $S(x)$ is a bond for every $x \in V(G)$ if and only if G is 2-connected (or is a connected graph with two vertices).

Problem 34B. Show that the circuits of a graph span the cycle space, and the bonds span the cutset space. To do this, just verify that the nonzero codewords in a binary linear code \mathcal{C} , whose supports are minimal among the supports of all nonzero codewords, generate the code. (This is true for linear codes over any field.) Hence G and H are Whitney duals when the circuits of G are exactly the bonds of H , or when the bonds of G are exactly the circuits of H .

Example 34.3. The two graphs described by each table in Fig. 34.2 are Whitney duals. This is because each pair consists of planar duals (see Theorem 34.2 below). For example, $\{a, e, g, c\}$ and $\{a, j, b\}$ are bonds in the cube G and circuits in G^* ; the set

$\{a, b, c, d\}$ is a circuit in G and a bond in G^* .

Problem 34C. Let G and H be Whitney duals with $E(G) = E(H) = E$. Explain why G'_e and H''_e are Whitney duals for any $e \in E$.

Problem 34D. Let G and H be Whitney duals with $E(G) = E(H) = E$, both of which are connected. Show that S is the edge set of a spanning tree in G if and only if $E \setminus S$ is the edge set of a spanning tree in H .

Theorem 34.2. *A graph G is planar if and only if it has a Whitney dual. A dual G^* of G with respect to any planar drawing of G is a Whitney dual of G .*

We prove only the second sentence (which implies the ‘only if’ part of the first sentence) at this time, and postpone the other part until the very end of the chapter.

PROOF: Let G^* be a planar dual of G with respect to some planar drawing of G .

Let S be a circuit of G . So S is the edge set of a polygon subgraph P of G that in the drawing, by the Jordan curve theorem, divides the sphere or plane into two parts; let \mathcal{F}_1 be the set of faces inside, and \mathcal{F}_2 the set of faces outside, P . This is a partition of the vertices of G^* . Clearly, each edge of P is incident with one face of \mathcal{F}_1 and one of \mathcal{F}_2 . Any other edge of G lies (except possibly for its ends) in one of the parts and so is incident only with members of \mathcal{F}_1 or \mathcal{F}_2 . In summary, $S = \times(\mathcal{F}_1, \mathcal{F}_2)$ is a cutset in G^* . The circuits generate the cycle space of G , so we have shown that the cycle space of G is contained in the cutset space of G^* .

Now we note the fact that the cutset space of G^* is contained in the cycle space of G for an embedding on *any* surface. There is a cyclic ordering to the edges incident with with a given vertex (loops appear twice). Partition the vertices of G^* (the regions or faces)—say they are colored red and blue—and consider the cutset C of G^* consisting of edges incident with one red and one blue region. The number of edges of C incident with a vertex of G is certainly even; see Fig. 34.6. (This is the same as saying that if the vertices of a polygon are colored red and blue, then the number of edges with ends of different colors is even.) So C is a cycle in G .

Hence the cycle space of G is equal to the cutset space of G^* . \square




Figure 34.6

Euler's formula is a corollary of what we have proved so far. Problem 34A says the dimension of the cycle space of G is $|E(G)| - (|V(G)| - |C(G)|)$, while the dimension of the cutset space of G^* is $|F(G)| - 1$ (we have remarked that G^* is always connected). When we equate these, we obtain (33.2).

Whitney's Theorem allows a quick proof of the following theorem of S. MacLane (1937).

Theorem 34.3. *A graph G is planar if and only if the cycle space of G has a basis $\mathcal{B} = \{B_1, B_2, \dots, B_k\}$ so that each edge of G occurs in at most two members of \mathcal{B} .*

PROOF: If G is planar, the boundaries of all but one face will provide such a basis. For if G^* is the dual of G with respect to some embedding on the plane, then, since G^* is connected, the sets of all nonloops incident with all but one of the vertices of G^* (faces of G) provide a basis for the cutset space of G^* (cycle space of G) and each edge is an element of at most two of these sets.

Now assume the cycle space of G has a basis as in the statement of the theorem. Let $B_0 = B_1 + B_2 + \dots + B_k$. Any edge of G is in 0 or 2 of the sets B_i , $0 \leq i \leq k$. Define a graph H whose vertices are $0, 1, \dots, k$, whose edge set is $E(G)$ and where an edge e is incident in H with the two integers j and ℓ so that $e \in B_j$ and $e \in B_\ell$ when e is in two of the sets B_i , and where e is a loop in H (at any vertex i) if e is in none of the sets B_i . We claim H is a Whitney dual of G .

The set of nonloops of H that are incident in H with a vertex i is B_i , of course, and this is a cutset in H . Since the B_i s generate the cycles of G , the cycle space of G is contained in the cutset space of

H . But we know that the cycle space of G has dimension k , while the cutset space of H has dimension $\leq k$, since H has $k+1$ vertices. We conclude that the cycle space of G is equal to the cutset space of H , i.e. they are Whitney duals. Hence G is planar by Theorem 34.2. \square

As promised, we now give some results about planar graphs and their duals using Whitney duality (and not referring to the plane or sphere at all).

Theorem 34.4. *If G and H are Whitney duals and H is connected, then G is bipartite if and only if H is Eulerian (admits an Eulerian circuit).*

PROOF: G is bipartite if and only if the entire edge set $E(G)$ is a cutset of G . Since G^* is connected, it is Eulerian if and only if $E(G)$ is a cycle of G^* ; see Theorem 1.2. The two conditions are equivalent since G^* is a Whitney dual of G . \square

A *Tait coloring* (after the English mathematician P. G. Tait) of a trivalent graph is a coloring of the *edges* with three colors, say α , β , and γ , so that each color appears at every vertex. Fig. 34.7 shows such a coloring. The existence of a Tait coloring of a trivalent graph is equivalent to partitioning the edges into three perfect matchings (cf. Chapter 5) and so a bipartite trivalent graph has a Tait coloring by Problem 5A.




Figure 34.7

Theorem 34.5. *If G and H are Whitney duals and G is trivalent, then G admits a Tait coloring if and only if H is 4-colorable.*

PROOF: We claim that a trivalent graph G admits a Tait coloring if and only if there exist two cycles S_1 and S_2 in G so that $E(G) = S_1 \cup S_2$. Given the coloring, take S_1 to be the union of the edges of colors α and γ , and S_2 to be the union of the edges of colors β and γ . These are both cycles since every vertex is incident with two edges of S_1 and two edges of S_2 . Conversely, if $E(G)$ is the union of two cycles S_1 and S_2 , color an edge e with color

$$\begin{cases} \alpha & \text{if } e \in S_1, e \notin S_2, \\ \beta & \text{if } e \notin S_1, e \in S_2, \\ \gamma & \text{if } e \in S_1 \cap S_2. \end{cases}$$

Every vertex x has even degree (between 0 and 3) in the spanning subgraphs with edge sets S_1 and S_2 ; but $E(G) = S_1 \cup S_2$ implies that both degrees are 2 and that there is one edge of each color incident with x .

Our second claim is that a graph H can be properly 4-colored if and only if $E(H)$ can be expressed as the union of two cutsets of H . If $E(H)$ is the union of $\times(X_1, X_2)$ and $\times(Y_1, Y_2)$, then $X_1 \cap Y_1, X_1 \cap Y_2, X_2 \cap Y_1, X_2 \cap Y_2$ are the color classes of a proper 4-coloring. If A, B, C, D are the color classes of a proper 4-coloring, then $E(H)$ is the union of $\times(A \cup B, C \cup D)$ and $\times(A \cup C, B \cup D)$.

The two observations and the definition of Whitney duals complete the proof. \square

An *isthmus* of a graph is an edge whose deletion increases the number of components (i.e. disconnects the graph if it was originally connected). This is the dual concept of a loop. An isthmus is an edge e so that the singleton set $\{e\}$ is a cutset; a loop is an edge e so that the singleton set $\{e\}$ is a cycle. (Some authors use *acyclic edge* for an isthmus since it is an edge contained in no circuits. The term *bridge* has also been used.)

Problem 34E. Show that a trivalent graph with an isthmus does not have a Tait coloring.

In view of the Four Color Theorem, every isthmus-free trivalent planar graph does admit a Tait coloring. (An isthmus in G would be a loop in the dual which could then not be properly colored.)

Planarity is necessary, since the Petersen graph is an example of an isthmus-free trivalent graph which has no Tait coloring.

Conversely, we claim that to prove the Four Color Theorem it would be sufficient to establish that every isthmus-free trivalent planar graph does admit a Tait coloring. For suppose that the regions of every isthmus-free trivalent planar graph G can be properly 4-colored. Then, given a planar graph G , replace each vertex x of degree $\neq 3$ by the configuration indicated for the case of a vertex of degree 5 in Fig. 34.8. (This may be done even for vertices of degrees 1 and 2.) This creates more regions (more vertices in the dual G^*) but preserves adjacency of the original regions, so if the regions of this larger but trivalent graph can be 4-colored, then we obtain a coloring for the original graph. By Theorem 34.5, the regions of the larger but trivalent graph can be 4-colored if and only if it has a Tait coloring.




Figure 34.8

Tait conjectured in 1880 that every 3-connected planar trivalent graph has a Hamiltonian circuit, which would have implied that the graph admits a Tait coloring. W. T. Tutte (1956) found a counterexample but did prove that every 4-connected planar trivalent graph is Hamiltonian.

Theorem 34.6. *If G and H are Whitney duals without isolated vertices and G is nonseparable, then H is nonseparable.*

PROOF: Theorem 32.2 shows that any two edges of G are contained in a circuit of G . Hence any two edges of H are contained in a bond of H . But if two edges a and b are contained in a bond $\times(X, Y)$, we can find a simple path in the subgraph induced by X , joining one end of a and one of b , and a simple path in the subgraph induced

by Y joining the other ends, and we find a polygon containing a and b . So any two edges of H are contained in a circuit of H . This implies that H is nonseparable. \square

Corollary. *The set of edges incident with a face in a planar embedding of a nonseparable graph G , not a link-graph, is a circuit in G .*

PROOF: The set S of edges incident with a face is the set of edges incident with a vertex in G^* . But G^* is nonseparable by Theorem 34.5, so S is a bond in G^* . Then S is a circuit in G . \square

Problem 34F. Two edges a and b of a connected graph G that are contained together in a circuit of G are also contained in some bond of G .

Theorem 34.7. *Let G and H be simple graphs without isolated vertices that are Whitney duals. If G is 3-connected, then H is 3-connected.*

PROOF: Assume G is 3-connected. For $x \in V(G)$, let $S(x)$ denote the set of edges incident with x . Each set $S(x)$ is a bond with the property that $G'_{S(x)}$ is nonseparable, and these bonds span the cutset space of G by definition.

Thus in H , there exists a family \mathcal{F} of circuits that spans the cycle space of H and where each member S of \mathcal{F} is a circuit with the property that H''_S is nonseparable.

We know H is nonseparable; suppose for contradiction that it is not 3-connected. Then H is the edge-disjoint union of subgraphs A and B of H , each with at least two edges, and where $A \cap B$ is a graph consisting of two isolated vertices, say x and y . If a polygon in H contains edges of both A and B , it must have x and y among its vertices. If the edges of such a polygon are contracted, we would obtain a separable graph since it would be the union of the graphs obtained from A and B by contraction of the edges of the polygon in each (which would identify x and y); these contracted subgraphs will have only this vertex resulting from the identification of the vertices of the polygon in common (and the reader can check that there still remains at least one edge in each contracted subgraph).

Thus the circuits in \mathcal{F} are contained completely in either $E(A)$ or $E(B)$. Let C be any circuit of H . Since \mathcal{F} spans the cycle space of H , $C \cap E(A)$ and $C \cap E(B)$ are, respectively, the modulo 2 sum of members of \mathcal{F} that are contained in $E(A)$ and $E(B)$. Hence each of $C \cap E(A)$ and $C \cap E(B)$ would be cycles, and then the minimality of C would imply that $C \cap E(A)$ or $C \cap E(B)$ is empty. It follows that *every* circuit of H is contained in either $E(A)$ or $E(B)$, which contradicts the nonseparability of H . \square

Problem 34G.

(i) Let G be a simple 3-connected graph and S a bond in G . Show that G'_S is nonseparable if and only if S is equal to $S(x)$, the set of edges incident with x , for some vertex x of G .

(ii) Prove: If G and H are simple 3-connected graphs with equivalent codes, then G is isomorphic to H .

Theorem 34.8. *Let G be a simple 3-connected graph embedded on the sphere. A circuit C of G is the set of edges incident with some face in this embedding if and only if G''_C is nonseparable.*

PROOF: The circuit C is the set of edges incident with a face if and only if it is the set of edges incident with a vertex in the dual $H := G^*$. By Problem 34G(i), this is the case if and only if H'_C is nonseparable. This latter graph is a Whitney dual of G''_C . \square

Thus the polygons that are boundaries of faces in an embedding of a simple 3-connected planar graph are *uniquely determined*. This is not true for nonseparable graphs in general—see Fig. 34.5. If we know the faces, i.e. the circuits that bound faces, the embedding is determined (this is explained somewhat in the next chapter), and we have the following result.

Corollary. *A simple 3-connected planar graph has a unique embedding on the sphere.*

Example 34.4. If K_5 were planar, no 4-gon would be a face, since contracting the four edges of a 4-gon produces a graph with two vertices, four links, and two loops at one of the vertices, and this graph is not nonseparable. On the other hand, a triangle would necessarily be a face.

We can obtain yet another proof that the simple 3-connected graphs K_5 , $K_{3,3}$, and the Petersen graph are not planar: contracting the edges of any 3-gon in K_5 , any 4-gon in $K_{3,3}$, and any 5-gon in the Petersen graph, always yields a nonseparable graph. So if these graphs were planar, every 3-gon, 4-gon, and 5-gon, respectively, would bound a face in the embedding in view of Theorem 34.8. But every edge belongs to three 3-gons, to four 4-gons, and to four 5-gons in the respective graphs, a contradiction to planarity.

E. Steinitz (1922) characterized the graphs of 3-dimensional convex polytopes.

Theorem 34.9. *A graph G is the graph of a 3-dimensional convex polytope if and only if G is simple, planar, and 3-connected.*

That the graph of a 3-dimensional polytope is 3-connected is a special case of Theorem 32.5. We do not prove the rest of the theorem here.

We need a lemma for the ‘if’ part of Theorem 34.2.

Lemma 34.10. *Let G and H be graphs with the same edge set E . Suppose G is the union of edge-disjoint subgraphs G_1 and G_2 so that $|V(G_1) \cap V(G_2)| \leq 1$. Let H_1 and H_2 be the subgraphs of H that have edge sets $E(G_1)$ and $E(G_2)$, respectively, with isolated vertices deleted.*

(i) *If G and H are Whitney duals, then G_i and H_i are Whitney duals for both $i = 1$ and $i = 2$.*

(ii) *If G_i and H_i are Whitney duals for both $i = 1$ and $i = 2$ and $|V(H_1) \cap V(H_2)| \leq 1$, then G and H are Whitney duals.*

PROOF: From Theorem 34.1, it is easy to see that every bond of G is contained fully in either $E(G_1)$ or $E(G_2)$. Moreover, a subset $S \subseteq E(G_i)$ is a bond of G_i if and only if it is a bond of G .

Suppose G and H are Whitney duals. If S is a bond of G_i , then S is a circuit of H contained in $E(H_i)$ and so is a circuit of H_i . And if S is a circuit of H_i , then it is a circuit of H , hence a bond of G contained in $E(G_i)$ and so is a bond of G_i .

Suppose that G_i and H_i are Whitney duals for $i = 1, 2$ and that $|V(H_1) \cap V(H_2)| \leq 1$. Let S be a bond of G . Then S is a bond of

G_1 or G_2 and hence a circuit in either H_1 or H_2 . But then certainly S is a circuit in H . If S is a circuit of H , then it is a circuit in either H_1 or H_2 . Hence it is a bond of G_1 or G_2 and so is a bond of G . \square

PROOF OF THEOREM 34.2, CONTINUED: For the proof of the converse, we first establish the following assertion. Given a pair G, H of Whitney duals with the same edge set E and no isolated vertices, we claim that there exists a possibly different Whitney dual H^0 which admits what we will call a *system of walks* for G . This is a family $\{w_x : x \in V(G)\}$ of walks w_x in H^0 , one for each vertex x of G , such that w_x traverses in H^0 exactly the edges incident with x in G , loops being traversed twice and nonloops once. We will use induction on the number of edges. We may assume G has no isolated vertices.

First note that the assertion is easy if G is nonseparable. Of course, it is true for a loop-graph. Otherwise there are no loops and for every vertex x , the set $S(x)$ of edges incident with x in G is a bond in G and hence a circuit in H . We need only let w_x be a simple closed path in H traversing the edges of the circuit $S(x)$ in H .

If G is not nonseparable, there exist edge-disjoint subgraphs G_1 and G_2 , each with at least one edge, and that have no vertices or one vertex in common, such that their union is G . With H_1 and H_2 as in Lemma 34.10, H_i is a Whitney dual of G_i , $i = 1, 2$. By the induction hypothesis, there exist graphs H_i^0 that are Whitney duals of G_i and that admit systems of walks $\{w_x^{(i)} : x \in V(G_i)\}$ for G_i , $i = 1, 2$. We may take H_1^0 and H_2^0 to be vertex disjoint. If G_1 and G_2 are disjoint, let H^0 be the disjoint union of H_1^0 and H_2^0 ; then the union of the two systems of walks provides a system of walks for G . If G_1 and G_2 have one vertex z in common, there are walks $w_z^{(1)}$ and $w_z^{(2)}$ in H_1^0 and H_2^0 that traverse the edges incident with z in G_1 and G_2 , respectively. Then let H^0 be obtained as the union of H_1^0 and H_2^0 but where we identify some vertex in the walk $w_z^{(1)}$ in H_1^0 with some vertex in the walk $w_z^{(2)}$ in H_2^0 . We combine these two walks into one which traverses the edges incident with z in G ; this together with the remaining walks in the systems in H_1 and H_2 provides a system of walks for G . In either case, H^0 is a

Whitney dual of G by Lemma 34.10.

Finally, we prove the following. Let G be a graph with a Whitney dual H which admits a system of walks $\{w_x : x \in V(G)\}$ for G . We assert that G has an embedding in the sphere so that the edges incident with x in G occur in the same cyclic order as they occur in the walk w_x . We proceed by induction on the number of edges.

If G has only loops, then H is a forest. Let e be a loop in G such that e is incident with a monovalent vertex in H . Let z be the vertex incident with e in G . The walk w_z in H evidently traverses e twice in succession, say

$$w_z = (s_0, e, s_1, e, s_2 = s_0, a_3, s_3, a_4, s_4, \dots, a_k, s_0),$$

where the s_i s are vertices of H . The graphs G'_e and H''_e are Whitney duals and suppressing e in w_z will provide a system of walks in H''_e for G'_e , so that by the induction hypothesis, G'_e admits a planar drawing such that the edges incident with z in G'_e occur in the same cyclic order as they occur in the walk w_z with e suppressed. In a small neighborhood of the point representing z in the embedding, we can insert the loop e to obtain the required embedding of G (see Fig. 34.9).




Figure 34.9

Now let e be a nonloop in G with ends y and z . Then G''_e and H'_e are Whitney duals and we claim that there is a natural system of walks $\{u_x : x \in V(G''_e)\}$ in H'_e for G''_e . For $x \neq y, z$, we take $u_x := w_x$. For the new vertex x_0 , obtained by identifying y and z , we combine w_y and w_z omitting e as follows. Say

$$w_y = (s_0, e, s_1, a_2, s_2, \dots, s_{k-1}, a_k, s_0)$$

and

$$w_z = (t_0, e, t_1, b_2, t_2, \dots, t_{m-1}, b_m, t_0),$$

where e, a_2, a_3, \dots, a_k and e, b_2, b_3, \dots, b_m are the edges incident with y and z , respectively, in G (loops appearing twice) and the s_i s and t_j s are vertices of H . By reversing one of these walks if necessary, we can assume $s_0 = t_0$ and $s_1 = t_1$. Then take

$$u_{x_0} := (s_1, a_2, s_2, \dots, s_{k-1}, a_k, s_0, b_m, t_{m-1}, b_{m-1}, \dots, b_3, t_2, b_2, s_1).$$

By the induction hypothesis, G''_e admits an embedding in the plane so that the edges incident with x in G''_e occur in same cyclic order as they occur in the walk u_x . In a small neighborhood of the point representing x_0 in the embedding, we can ‘uncontract’ e to obtain the required embedding of G (see Fig. 34.10). \square




Figure 34.10

Problem 34H. In a k -Tutte-connected graph (defined in Problem 32D) with at least $2k - 2$ edges, every circuit and every bond contains at least k edges.

Problem 34I. A *matroid* consists of a set X (which we assume here to be finite) and a family \mathcal{C} of nonempty subsets called *circuits* such that no circuit is a proper subset of another circuit and, if $A, B \in \mathcal{C}$, $x \in A \cap B$, $y \in A \setminus B$, then there exists $C \in \mathcal{C}$ so that $C \subseteq A \cup B$, $y \in C$, $x \notin C$. This latter property is called the ‘elimination axiom’.

(i) Prove that the edge set of a finite graph together with the family of all circuits (edge sets of polygons) is a matroid.

(ii) Prove that the family of minimal nonempty supports of code words in a linear code over any field provides the circuits of a matroid.

(iii) Let (X, \mathcal{F}) be a combinatorial geometry as defined in Chapter 23, and let \mathcal{C} be the family of minimal dependent subsets of X . Show that (X, \mathcal{C}) is a matroid.

(To do all parts of this problem, it can save work to do part (iii) first and to derive the others from it.)

Notes.

Hassler Whitney (1907–1989), a pioneer in topology who was also intensely concerned with mathematical education for the last twenty years of his life, was a professor at Harvard and later at the Institute for Advanced Study in Princeton. He was awarded the Wolf Prize in 1982. Whitney had a degree in music from Yale, played the violin, viola and piano, and was concertmaster of the Princeton Community Orchestra.

Matroids were introduced by Hassler Whitney in 1935 in order to abstract certain properties of linear independence, of circuits and bonds in graphs, and of duality. Their theory is ‘cryptomorphic’ to that of geometric lattices. See Welsh (1976) and Crapo and Rota (1971).

References.

- H. Crapo and G.-C. Rota (1971), *On the Foundations of Combinatorial Theory: Combinatorial Geometries*, M. I. T. Press.
- S. MacLane (1937), A structural characterization of planar combinatorial graphs, *Duke math. J.* **3**, 460–472.
- P. G. Tait (1880), Remarks on the colouring of maps, *Proc. Roy. Soc. Edinburgh* **10**, 501–503.
- W. T. Tutte (1956), A theorem on planar graphs, *Trans. Amer. Math. Soc.* **82**, 99–116.
- W. T. Tutte (1984), *Graph Theory*, Encyclopdedia of Math. and its Appl. **21**, Addison-Wesley.
- D. J. A. Welsh (1976), *Matroid Theory*, Academic Press.
- H. Whitney (1932), Nonseparable and planar graphs, *Trans. Amer. Math. Soc.* **34**, 339–362.
- H. Whitney (1935), On the abstract properties of linear dependence, *Amer. J. Math.* **57**, 509–533.

35

Embeddings of graphs on surfaces

We consider embeddings of graphs on surfaces other than the sphere. The classification of surfaces (see Fréchet and Fan, 1967) shows that there are two infinite families of surfaces, up to homeomorphism. We use \mathcal{T}_g , $g \geq 0$, to denote the orientable surface of *genus* g (the g -torus). This can be realized as a sphere with g ‘handles’ or g ‘holes’; \mathcal{T}_0 is the sphere. We use \mathcal{N}_n , $n \geq 1$, to denote the nonorientable surface which can be constructed by inserting n ‘cross-caps’ on the sphere (these cannot be embedded in \mathbb{R}^3). We state the extension of Euler’s formula. A proof may be found in Fréchet and Fan (1967), or in Chartrand and Lesniak (1986) for the orientable case.

Theorem 35.1. *For a 2-cell embedding of a graph G on \mathcal{T}_g ,*

$$|F(G)| - |E(G)| + |V(G)| = 2 - 2g.$$

For a 2-cell embedding of a connected graph G on \mathcal{N}_n ,

$$|F(G)| - |E(G)| + |V(G)| = 2 - n.$$

For any embedding, not necessarily a 2-cell embedding, the inequalities which result by replacing ‘=’ by ‘ \geq ’ in the equations above will hold.

Example 35.1. Fig. 35.1 shows an embedding of the Petersen graph P on the real projective plane \mathcal{N}_1 . In this diagram, diametrically opposite points on the boundary are to be identified. There are six faces, each a pentagon. More precisely, the dual graph with respect to this embedding is the complete graph K_6 .




Figure 35.1

(This establishes a curious one-to-one correspondence between the 15 edges of P and the 15 edges of K_6 . We have previously seen that there is a one-to-one correspondence between the 10 vertices of P and the 10 edges of K_5 .)

(The real projective plane can be thought of as the surface of the sphere where diametrically opposite points have been identified. The Petersen graph can be thought of as the graph of a regular dodecahedron where diametrically opposite points have been identified.)

Example 35.2. Fig. 35.2 shows an embedding of the complete graph K_7 on the torus \mathcal{T}_1 . We use the usual representation of the torus; here the horizontal and vertical boundary lines are to be identified. There are 14 triangular faces. The dual graph with respect to this embedding has 14 vertices of degree 3 and seven hexagonal faces, any two of which are adjacent. This is the *Heawood graph* (defined in Chapter 31), which is given as an example of a map on the torus whose faces require seven colors.




Figure 35.2

Theorem 35.2. *If a loopless graph G admits an embedding in \mathcal{T}_g , $g > 0$, then*

$$\chi(G) \leq \frac{7 + \sqrt{1 + 48g}}{2}.$$

PROOF: Suppose G can be embedded in \mathcal{T}_g . We can assume that G is simple, connected and has at least three vertices. We claim that there exists a vertex x of degree at most $N - 1$ where $N := (7 + \sqrt{1 + 48g})/2$. Once this is established, the theorem will follow by induction on the number of vertices; for if this vertex x is deleted and the remaining graph properly $[N]$ -colored, there remains a color free for x .

By Theorem 35.1, we have

$$2 - 2g \leq f - e + v$$

where $f := |F(G)|$, $e := |E(G)|$, $v := |V(G)|$. Since every face is incident with at least three edges, $3f \leq 2e$. Let d be the average degree of the vertices of G . We assume for contradiction that $d > N - 1$. This implies that $v > N$. Also $d > 6$ since $N \geq 7$ for $g \geq 1$, and we have

$$2 - 2g \leq \frac{2}{3}e - e + v = -\frac{1}{3}e + v = -\frac{1}{6}vd + v = \frac{1}{6}v(6 - d),$$

$$12g - 12 \geq v(d - 6) > N(N - 7) = 12g - 12.$$

This provides the promised contradiction. □

Here is a small table of bounds from Theorem 35.2:

genus g	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
$\chi \leq$	7	8	9	10	11	12	12	13	13	14	15	15	16	16	16

The assertion that Theorem 35.2 was the best possible result, i.e. that $\lfloor \frac{7 + \sqrt{1 + 48g}}{2} \rfloor$ colors were required for some graph which could be embedded in \mathcal{T}_g , was known as the Heawood conjecture until it was proved by Ringel and Youngs in 1968. See Ringel (1974). What they did is to prove the following stronger result.

Theorem 35.3 (Ringel–Youngs). Given $g \geq 0$, let

$$n := \lfloor \frac{7 + \sqrt{1 + 48g}}{2} \rfloor.$$

Then the complete graph K_n can be embedded in \mathcal{T}_g .

We will prove here only a small part of this result (see Theorem 35.4 below). For example, Theorem 35.3 shows that $\chi(G) \leq 19$ for graphs G embedded in \mathcal{T}_{20} , \mathcal{T}_{21} , and \mathcal{T}_{22} . Theorem 35.4 shows that K_{19} can be embedded in \mathcal{T}_{20} (and hence in \mathcal{T}_{21} and \mathcal{T}_{22}), verifying the Heawood conjecture for $g = 20, 21, 22$.

We need to understand 2-cell embeddings combinatorially, in terms of the graph itself. Here is what is important.

Given a 2-cell embedding of a graph G on a surface \mathcal{S} , we may traverse the boundary of any face F and we obtain a closed walk w_F in G . The starting vertex is not important, nor is the direction. In many cases, this may be a simple closed path in G , but, e.g., when G is a tree embedded in the sphere, there is a single face and this walk passes through every edge twice (see Fig. 2.4). In general, every edge will either belong to exactly two walks in $\{w_F : F \in F(G)\}$ or occur twice in one of these walks. A system \mathcal{M} of closed walks in G with this property that every edge of G occurs twice among the walks in \mathcal{M} will be called a *mesh* in G .

Example 35.3. Here are two meshes in K_5 . The walks are described by their vertex sequences:

$$\begin{aligned} \mathcal{M}_1 &= \{(1, 2, 3, 4, 5, 1), \\ &\quad (1, 2, 4, 1), (2, 3, 5, 2), (3, 4, 1, 3), (4, 5, 2, 4), (5, 1, 3, 5)\}, \\ \mathcal{M}_2 &= \{(1, 2, 4, 5, 1), (1, 3, 2, 5, 3, 4, 2, 3, 5, 4, 1), (1, 4, 3, 1, 5, 2, 1)\}. \end{aligned}$$

The mesh \mathcal{M}_1 consists of simple paths (one pentagon and five triangles), but the second walk in \mathcal{M}_2 traverses two edges twice.

A *triangular mesh* is a mesh consisting of simple closed paths of length 3. So a triangular mesh for K_n is equivalent to a 2-design $S_2(2, 3, n)$ with blocks of size 3 and index 2. But these designs rarely correspond to embeddings of K_n on surfaces because there is an important additional condition that must hold.

Given a mesh \mathcal{M} in a connected graph G , we may try to construct a 2-cell embedding of G in a surface so that these walks bound the faces. There is really no choice—we must proceed as follows. For each walk $w \in \mathcal{M}$ of length ℓ , we need a corresponding closed disk F_w , for example a convex ℓ -gon and its interior in the plane (even for $\ell = 1$ and 2, although we cannot use straight line segments as the edges in these cases). Label the vertices and edges of F_w with the vertices of the walk w in the order they occur in w . (So some vertices and perhaps edges of F_w will receive the same label if w is not a simple closed path.) We will ‘paste’ or ‘sew’ these disks together at their boundaries.

Consider the disjoint union of all disks F_w . For each vertex x of G , identify all the points labeled with an x . For each edge e of G , identify the interior points of the edges of the disks labeled with e in a one-to-one continuous manner in the direction indicated by their ends. (It is necessary to agree that loops have two directions.)




Figure 35.3




Figure 35.4

Figs. 35.3 and 35.4 show, respectively, polygonal regions in the plane (disks) labeled by the vertices of the walks in the meshes of

Example 35.3. In Fig. 35.5, we have started the pasting process for the disks in Fig. 35.3; it remains to identify diametrically opposite points on the boundary (and we obtain the real projective plane with K_5 drawn on it).




Figure 35.5

In general, the topological space constructed by this pasting has neighborhoods homeomorphic to the open disk (2-cell) about points x in the interior of the disks F_x and also for points in the interior of an edge on the boundary of the disks (because every edge is in two of the walks of the mesh). But there may be trouble at vertices, where many of the disks F_w meet. For example, suppose that the walks that traverse a vertex x in a certain mesh have vertex sequences

$$(\dots, 1, x, 2, \dots), (\dots, 2, x, 3, \dots), (\dots, 3, x, 1, \dots), \\ (\dots, 4, x, 5, \dots), (\dots, 5, x, 6, \dots), \text{ and } (\dots, 6, x, 4, \dots).$$

The disks corresponding to the first three walks fit together to make a neighborhood of x which is a 2-cell, but with the other three, a neighborhood of x will look like two cones touching at their apexes. The graph \mathcal{M}_x defined in the next paragraph would consist of two disjoint triangles in this case.

For a vertex $x \in V(G)$, consider the graph \mathcal{M}_x where $V(\mathcal{M}_x)$ is the set of edges of G incident with x and where two members a, b of $V(\mathcal{M}_x)$ are adjacent in \mathcal{M}_x when they occur as consecutive edges of some walk in \mathcal{M} (with the vertex x between them). Of course, join a and b by two edges in \mathcal{M}_x if they occur consecutively twice, which probably will not often be the case. Clearly, \mathcal{M}_x is regular

of degree 2. The *vertex condition* requires that \mathcal{M}_x is connected (i.e. a single polygon) for every vertex x .

The topological space constructed by this pasting from a mesh in a connected graph is a surface if and only if the mesh satisfies the vertex condition. There is a natural embedding of the graph G in this surface. The meshes in Example 35.3 satisfy the vertex condition. See Example 35.4 and Fig. 35.6.




Figure 35.6

To discover what surface \mathcal{S} has been constructed from a mesh \mathcal{M} , we first compute the *Euler characteristic* $h := |\mathcal{M}| - |E(G)| + |V(G)|$. In view of Theorem 35.1, if h is odd, we must have $\mathcal{S} = \mathcal{N}_{2-h}$. But if h is even, we must decide whether the surface is orientable or not (unless $h = 2$, when the sphere is the only possibility): $\mathcal{S} = \mathcal{T}_{1-h/2}$ if \mathcal{S} is orientable, $\mathcal{S} = \mathcal{N}_{2-h}$ otherwise. We state without proof that \mathcal{S} is orientable if and only if the walks can be directed (one of the two possible directions being chosen for each walk) so that *every edge is traversed exactly once in each direction*, in which case we say the mesh is *orientable*.

It is easy to check whether a mesh satisfying the vertex condition is orientable. We give one walk a direction and that determines the directions of all walks sharing an edge, which in turn determines the directions of further walks. The vertex condition implies that the direction of every walk in the mesh is determined (why?). Then we check each edge to see in what directions it is traversed.

Example 35.3 (continued). The mesh \mathcal{M}_1 provides an embedding of K_5 on the real projective plane \mathcal{N}_1 . The mesh \mathcal{M}_2 is orientable—the walks may be directed as they have been written down—and we have a 2-cell embedding of K_5 on the double torus \mathcal{T}_2 .

In describing walks in simple graphs in the examples that follow, we list the vertex sequences in square brackets but suppress the terminal vertex since it is the same as the initial one. And it is convenient to refer to paths of length 3, 4, ... as triangles, quadrilaterals, etc., ignoring the difference between walks in a graph and subgraphs that are polygons.

Example 35.4. We show that K_8 can be embedded on the double torus \mathcal{T}_2 . This shows that at least eight colors are required for \mathcal{T}_2 and proves the Heawood conjecture for $g = 2$.

There must be 18 faces (so that $f - e + v = -2$), and their degrees must add to 56. We display a solution with two quadrilaterals and 16 triangles as the faces. We use ‘difference methods’ (cf. Chapter 19).

As the vertices of K_8 , we take \mathbb{Z}_8 , the integers modulo 8. The quadrilaterals will have vertex sequences $[0, 2, 4, 6]$ and $[1, 3, 5, 7]$. The triangles are to be the translates modulo 8 of the two initial triangles $[0, 1, 4]$ and $[0, 3, 2]$. The reader should check that every edge appears in exactly two of these walks. Let us check the vertex condition. Since translation modulo 8 preserves the polygons, we need only check the vertex 0. The walks traversing 0 are $[0, 2, 4, 6]$, $[0, 1, 4]$, $[7, 0, 3]$, $[4, 5, 0]$, $[0, 3, 2]$, $[5, 0, 7]$, and $[6, 1, 0]$. They fit together to form a single polygon as indicated in Fig. 35.6.

It remains to check whether the mesh is orientable. It turns out that if the quadrilaterals are directed as $[0, 2, 4, 6]$ and $[7, 5, 3, 1]$, and every other triangle is also reversed (i.e. whenever the initial triangles are translated by an odd element of \mathbb{Z}_8), we obtain an oriented mesh.

Problem 35A. Find a mesh of five 4-gons in K_5 , a mesh of six 5-gons in K_6 , and a mesh of seven 6-gons in K_7 , all of which satisfy the vertex condition. What surfaces have you constructed?

Problem 35B. Find a mesh of 16 pentagons in the Clebsch graph (see Example 21.4). Check the vertex condition and also check for orientability. What surface, if any, has been constructed? What is the dual graph with respect to this embedding? (Cf. Problem 35G.)

Problem 35C. (i) Show that if a simple graph G is embedded in

the nonorientable surface \mathcal{N}_g , $g \geq 1$, then

$$\chi(G) \leq \frac{7 + \sqrt{1 + 24g}}{2}.$$

(ii) Show that if a simple graph is embedded in the Klein bottle \mathcal{N}_2 , then either it has a vertex of degree ≤ 5 or it is regular of degree 6. Show that there is a unique mesh of 14 triangles in K_7 that satisfies the vertex condition and that it is orientable, and so K_7 does not embed in the Klein bottle. Conclude that $\chi(G) \leq 6$ for graphs G embedded in \mathcal{N}_2 .

(Thus K_7 does not embed in the Klein bottle after all. We conclude that $\chi(G) \leq 6$ for graphs embedded in \mathcal{N}_2 .)

Problem 35D. Before we continue with surfaces other than the sphere, we remark that our understanding of meshes allows a quick proof of the fact that if G and H are *nonseparable* Whitney duals, then there exists an embedding of G in the sphere with respect to which the dual G^* is isomorphic to H . As in the proof of Theorem 34.2, the set of edges incident with a vertex of H is a circuit in G . The system of walks we get in G is a mesh \mathcal{M} . Show that \mathcal{M} satisfies the vertex condition. Explain why the surface constructed is the sphere and why the dual G^* is isomorphic to H .

Problem 35E. Consider a connected graph G and a mesh \mathcal{M} in G satisfying the vertex condition (i.e. a map). To keep things simple, assume that G is simple and that the walks in \mathcal{M} are simple closed paths—which we identify with polygons and call *faces*. An *automorphism* of this map is a permutation of $V(G)$ which takes edges to edges and faces to faces (i.e. an automorphism of G that preserves \mathcal{M}). Show that if an automorphism α fixes a vertex x , an edge e incident with x , and a face F incident with e , then it is the identity.

(It follows, for example, that a simple map as above with graph G has at most $4|E(G)|$ automorphisms. Examples where equality occurs include the Platonic solids and the maps in Examples 35.1 and 35.2.)

Theorem 35.8. *If $n \equiv 7 \pmod{12}$, then the complete graph K_n*

admits a triangular embedding on an orientable surface of genus

$$g := (n - 3)(n - 4)/12.$$

PROOF: We construct an orientable triangular mesh in K_n satisfying the vertex condition. Write $n = 12s + 7$. As the vertices of K_n , we use \mathbb{Z}_n .

The construction is encoded in the diagrams of Fig. 35.7. The diagrams are for the cases $n = 7$, $n = 19$, $n = 31$, and $n = 12s + 7$ in general. (In the general case, the vertical edges are directed alternately and are labeled $1, 2, \dots, 2s$, consecutively.) We could describe this construction simply as an application of difference methods and not give any figures, but that would be a shame since the diagrams were conceptually very helpful in finding this and other embeddings.

Note that the edges are labeled with the integers from 1 to $6s+3$. The ‘conservation’ law, or ‘Kirchhoff’s current law’, holds: at every vertex, the sum of values on the incoming edges is equal to the sum of the values on the outgoing edges. (Except that we have no source or sink, this is a flow of strength zero as defined in Chapter 7.)

Actually, it will be useful to think that the reverses of the indicated directed edges are also present; the reverse of the edge shown in Fig. 35.7 will carry a label equal to the negative of the shown edge. Then all nonzero values modulo $n = 12s + 7$ appear on the directed edges, each exactly once. The vertices are of two types: solid (representing ‘clockwise’) and hollow (representing ‘counterclockwise’).

Every vertex in the diagrams of Fig. 35.7 will provide a family of n directed triangles in K_n which are translates of one another modulo n . For each solid vertex that is the tail of directed edges with values a, b, c in clockwise order, we take the n directed triangles

$$[x, x + a, x + a + b], \quad x \in \mathbb{Z}_n.$$

Remember that $a + b + c = 0$ in \mathbb{Z}_n , so we get the same triangles (but with different initial vertices) if we take $[y, y + b, y + b + c]$, $y \in \mathbb{Z}_n$ or $[z, z + c, z + c + a]$, $z \in \mathbb{Z}_n$. For each hollow vertex that

is the tail of directed edges with values a, b, c in counter-clockwise order, we take the n directed triangles

$$[x, x + a, x + a + b], \quad x \in \mathbb{Z}_n.$$

For example, in the third diagram in Fig. 35.7 (when $n = 31$), there is a hollow vertex with incoming edges labeled 7 and 2 and an outgoing edge labeled 9. We regard this as outgoing edges labeled $-7, -2,$ and 9 (counter-clockwise), and take the 31 directed triangles obtained as the translates of $[0, -7, -9]$ modulo 31 (or translates of $[0, 9, 2]$ or $[0, -2, 7]$). Another vertex in that diagram yields the 31 directed triangles obtained as the translates of $[0, 14, 13]$ modulo 31.

It is not hard to see that the collection of directed triangles obtained from the diagrams form an oriented triangular mesh. For example, when $n = 31$, to find a triangle traversing the edge joining 4 to 23 in that direction, notice that $23 - 4 = -12$ in \mathbb{Z}_n . The edge labeled -12 leaves a solid vertex with other outgoing edges labeled 15 and -3 , and the triangle $[4, 4 + (-12), 4 + (-12) + 15] = [4, 23, 7]$ is found. The triangle traversing the edge joining 23 to 4 in that order is found to be $[23, 4, 6]$.




Figure 35.7

It will suffice to check the vertex condition only at 0. Let e_i denote the edge $\{0, i\}$ of K_n . Consider the triangle of the mesh that traverses 0 and enters 0 on edge e_a . In the diagram, the edge labeled a will enter a vertex that is the tail of edges with labels $-a, p, q$, say, in clockwise or counter-clockwise order, depending on whether the vertex is solid or hollow. That is, the triangle is $[a, 0, p]$ and leaves 0 on the edge e_p . To summarize, if a triangle enters 0 on an edge e_i of K_n , the value j such that the triangle leaves 0 on e_j is found from the diagram as follows: find the edge labeled i in the diagram—turn clockwise or counter-clockwise, as appropriate, at the head of that edge and leave on the next edge—the label on that edge of the diagram will be j .

For example, when $n = 31$, we find the sequence of edges e_{i_ℓ} of K_n so that the triangle which enters 0 on e_{i_ℓ} will leave on $e_{i_{\ell+1}}$ to be

$$\begin{aligned} e_1, e_{-13}, e_{-8}, e_{-9}, e_{-7}, e_{-10}, e_{-6}, e_5, \\ e_{13}, e_{14}, e_{12}, e_{15}, e_{11}, e_6, e_{-4}, e_{-15}, e_{-3}, e_7, e_{-2}, e_{-14}, \\ e_{-1}, e_8, e_{-5}, e_{-11}, e_4, e_{10}, e_3, e_{-12}, e_2, e_9, e_1, \dots \end{aligned}$$

Consecutive pairs above will be adjacent in \mathcal{M}_0 , which is seen to be a single polygon. The reader should check that all diagrams in Fig. 35.7 will similarly yield under this procedure a sequence traversing each edge of the diagram once in each direction. This is quite amazing. \square

Problem 35F. (i) If the complete graph K_n admits an embedding on the orientable surface \mathcal{T}_g so that all faces are bounded by triangles, then $g = (n - 3)(n - 4)/12$.

(ii) If the complete bipartite graph $K_{n,n}$ admits an embedding on the orientable surface \mathcal{T}_g so that all faces are bounded by quadrilaterals, what is g in terms of n ? What is the least value of $n > 2$ for which such an embedding exists?

In order to present the proof of Theorem 35.8 as quickly and as simply as possible, we have taken the construction out of its original context. We close this chapter with a brief discussion of some of the ideas that allowed Ringel and Youngs to come up with constructions for all values of n .

A technique for embedding graphs on orientable surfaces was described by J. Edmonds (1960). It may be thought of as arising from the mesh in the dual graph with respect to the embedding. If we have a connected simple graph G embedded in an orientable surface \mathcal{S} , then the choice of an orientation on \mathcal{S} will induce at every vertex a cyclic permutation of the edges incident with that vertex. Edmonds pointed out that any such ‘local cyclic permutations’ determine an embedding. Let G be a simple graph. Suppose a cyclic permutation σ_x of the set $S(x)$ of edges incident with x is given for each vertex x . Then there is a natural oriented mesh \mathcal{M} determined as follows. In the directed walk traversing an edge e directed from one of its ends y to the other x , the edge following e is to be $\sigma_x(e)$.

The examples below concern simple graphs, so the local permutations may be abbreviated as permutations of the adjacent vertices and walks may be described by their vertex sequences.

Example 35.5. Consider K_5 with vertex set $\{1, 2, 3, 4, 5\}$ and the following local permutations:

$$\begin{aligned} 1 &: (2435) \\ 2 &: (1435) \\ 3 &: (4125) \\ 4 &: (1325) \\ 5 &: (1234). \end{aligned}$$

It might be good to think of the resulting walks as a decomposition of the edges of the complete directed graph on 5 vertices. Let e_{ij} denote the edge directed from i to j . Here are the edge terms of the walks:

$$\begin{aligned} &(e_{12}, e_{24}, e_{45}, e_{51}), \\ &(e_{13}, e_{32}, e_{25}, e_{53}, e_{34}, e_{42}, e_{23}, e_{35}, e_{54}, e_{41}), \\ &(e_{14}, e_{43}, e_{31}, e_{15}, e_{52}, e_{21}). \end{aligned}$$

The vertex sequences of these walks are exactly those of \mathcal{M}_2 in Example 35.3.

In the family of graphs with $4s + 2$ vertices in Fig. 35.7, we specified a cyclic order at each vertex by the use of a solid vertex to indicate that the local permutation is to be clockwise and a

hollow vertex to indicate counter-clockwise. As part of the proof of Theorem 35.8, we had to check that the resulting embeddings have exactly one face.

Given a finite group Γ and a subset S of nonidentity elements of Γ such that $\alpha \in S$ implies that $\alpha^{-1} \in S$, the *Cayley graph* $G(\Gamma, S)$ is the simple graph with vertex set Γ and where vertices α and β are adjacent if and only if $\beta\alpha^{-1} \in S$. A complete graph K_n is a Cayley graph with respect to any group of order n , where S consists of all nonidentity elements. Often it is required that S generates the group—this ensures that the corresponding Cayley graph is connected.

W. Gustin (1963) introduced the theory of ‘quotient manifolds’ and developed methods to embed Cayley graphs into orientable surfaces. We have no space to describe this precisely, but give some examples. Consider the case where the local permutations at the vertices of a Cayley graph are all ‘shifts’ of an initial cyclic permutation $(s_1 s_2 \dots s_k)$ of the set S of vertices adjacent to 0; that is, the local permutation at α is

$$(s_1 + \alpha \quad s_2 + \alpha \quad \dots \quad s_k + \alpha)$$

(with additive notation).

Example 35.6. Consider K_7 with vertex set $\{0, 1, 2, 3, 4, 5, 6\}$ and with local permutation $(1 + i \ 3 + i \ 2 + i \ 6 + i \ 4 + i \ 5 + i) \pmod{7}$ at i as below:

$$\begin{aligned} 0 : & (132645) \\ 1 : & (243056) \\ 2 : & (354160) \\ 3 : & (465201) \\ 4 : & (506312) \\ 5 : & (610423) \\ 6 : & (021534). \end{aligned}$$

The walks are:

$$\begin{aligned} [1, 2, 4] \quad [2, 3, 5] \quad [3, 4, 6] \quad [4, 5, 0] \quad [5, 6, 1] \quad [6, 0, 2] \quad [0, 1, 3] \\ [3, 5, 6] \quad [4, 6, 0] \quad [5, 0, 1] \quad [6, 1, 2] \quad [0, 2, 3] \quad [1, 3, 4] \quad [2, 4, 5]. \end{aligned}$$

This is the triangular embedding of K_7 on the torus we have seen in Example 35.2.

If we try this method on K_{31} , for example, with vertex set \mathbb{Z}_{31} and initial local permutation

$$(1, -13, -8, -9, -7, -10, -6, 5, 13, 14, 12, 15, 11, 6, -4, \\ -15, -3, 7, -2, -14, -1, 8, -5, -11, 4, 10, 3, -12, 2, 9),$$

we obtain the same triangular mesh as in the proof of Theorem 35.8. The diagrams of Fig. 35.7 actually represent the ‘quotient manifolds’ of the dual graphs of K_n with respect to the prescribed embeddings. For $n = 12s + 7$, the embedded graph represented by the diagram has $4s + 2$ vertices, $6s + 3$ edges, and 1 face; the resulting embedding of K_n has $(4s + 2)n$ faces, $(6s + 3)n$ edges, and $(1)n$ vertices.

Problem 35G. Let ω be a nonzero element in \mathbb{F}_q where q is a power of a prime. Say ω has order m in the multiplicative group and assume that -1 is a power of ω . Consider the Cayley graph $G(\mathbb{F}_q, \langle \omega \rangle)$ where $\langle \omega \rangle = \{1, \omega, \omega^2, \dots\}$. We are using the additive group of \mathbb{F}_q for the Cayley graph, so a and b are adjacent if and only if $a - b \in \langle \omega \rangle$. (This is a complete graph when ω is a primitive element in \mathbb{F}_q ; it is the Clebsch graph when $q = 16$ and $m = 5$.)

Let us take the local permutation at 0 to be $(1, \omega, \omega^2, \dots, \omega^{m-1})$ and obtain the other local permutations as shifts. What is the size and number of the faces in the resulting mesh?

Notes.

P. J. Heawood (1861–1955) spent most of his career at Durham, England as professor of mathematics, finally to become vice-chancellor.

References.

- G. Chartrand and L. Lesniak (1986), *Graphs and Digraphs*, 2nd edn., Wadsworth.
- J. Edmonds (1960), A combinatorial representation for polyhedral surfaces, *Notices Amer. Math. Soc.* **7**, 646.
- M. Fréchet and K. Fan (1967), *Initiation to Combinatorial Topology*, Prindle, Weber and Schmidt.

- W. Gustin (1963), Orientable embedding of Cayley graphs, *Bull. Amer. Math. Soc.* **69**, 272–275.
- G. Ringel (1974), *Map Color Theorem*, Springer-Verlag.
- G. Ringel and J. W. T. Youngs (1968), Solution of the Heawood map coloring problem, *Proc. Nat. Acad. Sci. U.S.A.* **60**, 438–445.
- A. T. White (1973), *Graphs, Groups, and Surfaces*, Mathematical Studies **8**, North-Holland.

36

Electrical networks and squared squares

We start with the *matrix-tree* theorem, which expresses the number of spanning trees in a graph as the determinant of an appropriate matrix.

Theorem 36.1. *The number of spanning trees in a connected graph G on n vertices and without loops is the determinant of any $(n - 1) \times (n - 1)$ principal submatrix of the matrix $D - A$, where A is the adjacency matrix of G and D is the diagonal matrix whose diagonal contains the degrees of the corresponding vertices of G .*

For multigraphs G without loops we agree that the adjacency matrix A is defined to have $A(x, y)$ equal to the number of edges joining x and y , for distinct vertices x and y . We postpone the proof until we have developed some tools, but we give some examples now.




Figure 36.1

Example 36.1. Let G be the graph in Fig. 36.1. Then

$$D - A = \begin{pmatrix} 2 & -1 & 0 & -1 \\ -1 & 3 & -1 & -1 \\ 0 & -1 & 2 & -1 \\ -1 & -1 & -1 & 3 \end{pmatrix}$$

and G has 8 spanning trees.

Example 36.2. Take G to be the complete graph K_n in Theorem 36.1. In this case, the matrix $D - A$ is $nI - J$, where I is the identity matrix of order n and J is the $n \times n$ matrix of all 1s. The calculation of the determinant of a $(n-1) \times (n-1)$ principal submatrix of this simple matrix can be done in several ways (row operations, consideration of eigenvalues) and is left as an exercise. Once this is done, we obtain yet another proof of Cayley's theorem, cf. Chapter 2, that the complete graph K_n has n^{n-2} spanning trees.

Problem 36A. Let M be an $n \times n$ matrix all of whose line-sums are 0. Then one of the eigenvalues of M is $\lambda_1 = 0$; let $\lambda_2, \lambda_3, \dots, \lambda_n$ denote the other eigenvalues. Show that all principal $(n-1) \times (n-1)$ submatrices of M have the same determinant, and this value is equal to the product $\frac{1}{n} \lambda_2 \lambda_3 \cdots \lambda_n$.

Example 36.3. We can use the observation of the above problem to calculate the number of spanning trees in regular graphs whose spectrum is known. For example, let A be the adjacency matrix of the Petersen graph. Then A has eigenvalues

$$3, 1, 1, 1, 1, 1, -2, -2, -2, -2$$

(see Chapter 21). The matrix M is $3I - A$, which has eigenvalues

$$0, 2, 2, 2, 2, 2, 5, 5, 5, 5.$$

We conclude that the Petersen graph has 2000 spanning trees.

The following lemma is known as the Cauchy–Binet theorem. It is more commonly stated and applied with the diagonal matrix Δ below taken to be the identity matrix.

Lemma 36.2. Let A and B be, respectively, $r \times m$ and $m \times r$ matrices. Let Δ be the $m \times m$ diagonal matrix with entry e_i in row i , column i . For an r -subset S of $\{1, 2, \dots, m\}$, let A_S and B^S denote, respectively, the $r \times r$ submatrices of A and B consisting of the columns of A , or the rows of B , indexed by elements of S . Then

$$\det(A\Delta B) = \sum_S \det(A_S) \det(B^S) \prod_{i \in S} e_i$$

where the sum is extended over all r -subsets S of $\{1, 2, \dots, m\}$.

PROOF: We will prove this assuming that e_1, \dots, e_m are independent indeterminates. Of course, it will then hold for all values of e_1, \dots, e_m .

The entries of the $r \times r$ matrix $A\Delta B$ are linear forms in the indeterminates e_1, \dots, e_m ; explicitly, if $A = (a_{ij})$ and $B = (b_{ij})$, then the (i, k) entry of $A\Delta B$ is $\sum_{j=1}^m a_{ij}b_{jk}e_j$. Thus $\det(A\Delta B)$ is a homogeneous polynomial of degree r in e_1, \dots, e_m .

Consider a monomial $e_1^{t_1}e_2^{t_2}\dots$ where the number of distinct indeterminates e_i that occur, i.e. that have exponent $t_i > 0$, is less than r . Substitute 0 for the indeterminates e_i which do not occur in $e_1^{t_1}e_2^{t_2}\dots$. The monomial $e_1^{t_1}e_2^{t_2}\dots$ and its coefficient are unaffected by this substitution. But after this substitution, the rank of Δ is less than r so the polynomial $\det(A\Delta B)$ evaluates to the zero polynomial.

So we see that the coefficient of a monomial in the polynomial $\det(A\Delta B)$ is 0 unless the monomial is a product of r distinct indeterminates e_i , i.e. unless it is of the form $\prod_{i \in S} e_i$ for some r -subset S . The coefficient of a monomial $\prod_{i \in S} e_i$ in $\det(A\Delta B)$ can be obtained by setting $e_i, i \in S$, equal to 1 and $e_j, j \notin S$, equal to 0. When this substitution is made in Δ , $A\Delta B$ evaluates to $A_S B^S$. So the coefficient of $\prod_{i \in S} e_i$ in $\det(A\Delta B)$ is $\det(A_S) \det(B^S)$. \square

We will deal extensively with directed graphs H in this chapter. All graph-theoretic terms (trees, components, circuits, etc.) will be applied to a directed graph with the same meaning as for the underlying undirected graph we obtain by ignoring the directions of the edges. Thus a path in a digraph will traverse some edges in a 'forward' direction, other edges will be traversed 'backward'. It is really undirected graphs we are interested in, but it is convenient for the theory to choose an orientation and produce a digraph; any orientation will do and produces essentially the same theory.

As we have often done in previous chapters, we use the functional notation $M(i, j)$ to denote the entry in row i and column j of a matrix M , and $f(i)$ to denote the i th coordinate of a vector f .

The *incidence matrix* N of a directed graph H is the matrix whose rows are indexed by $V(H)$, whose columns are indexed by

$E(H)$, and where

$$N(x, e) = \begin{cases} 0 & \text{if } x \text{ is not incident with } e, \text{ or } e \text{ is a loop,} \\ 1 & \text{if } x \text{ is the head of } e, \\ -1 & \text{if } x \text{ is the tail of } e. \end{cases}$$

We mention that

$$(36.1) \quad \text{rank}(N) = |V(H)| - |C(H)|$$

where $C(H)$ is the set of components of H . To see this, suppose that g is a row vector with coordinates indexed by $V(H)$ and that $gN = 0$. This means for every edge e , directed from x to y , say, that $g(y) - g(x) = 0$. It is clear then, that $gN = 0$ if and only if g is constant on the vertex set of every component of H , and hence the dimension of the space of all g such that $gN = 0$ is $|C(H)|$.

We also mention that the determinant of any square matrix that has at most one 1 and at most one -1 in any column, all other entries being 0, is equal to 0 or ± 1 . This follows by induction: if every column has a $+1$ and a -1 , then the sum of all rows is the zero vector, so the matrix is singular. Otherwise, expand the determinant by a column with one nonzero entry to find it is ± 1 times the determinant of a smaller matrix with the same property. So every square submatrix of the incidence matrix of a digraph has determinant 0 or ± 1 . (Matrices with this property are called *totally unimodular*.)

PROOF OF THEOREM 36.1: Let H be a connected digraph with n vertices, with incidence matrix N . Let S be a set of $n - 1$ edges and, with the notation of the Cauchy–Binet theorem, consider the $n \times n - 1$ submatrix N_S , whose columns are indexed by elements of S , of the incidence matrix N . By (36.1), N_S has rank $n - 1$ if and only if the spanning subgraph of H with edge set S is connected, i.e. if and only if S is the edge set of a tree in H . Let N'_S be obtained by dropping any single row from the incidence matrix N . Since the sum of all rows of N (or N_S) is the zero vector, the rank of N'_S is the same as the rank of N_S . The observations of this and the preceding paragraph prove that

$$(36.2) \quad \det(N'_S) = \begin{cases} \pm 1 & \text{if } S \text{ is the edge set of a spanning tree in } H, \\ 0 & \text{otherwise.} \end{cases}$$

Let a connected loopless graph G on n vertices be given, let H be any orientation of G , and let N be the incidence matrix of H . Then $NN^\top = D - A$ because

$$\begin{aligned} NN^\top(x, y) &= \sum_{e \in E(G)} N(x, e)N(y, e) \\ &= \begin{cases} \deg(x) & \text{if } x = y, \\ -t & \text{if } x \text{ and } y \text{ are joined by } t \text{ edges in } G. \end{cases} \end{aligned}$$

An $(n-1) \times (n-1)$ principal submatrix of $D - A$ is of the form $N'N'^\top$ where N' is obtained from N by dropping any one row. By Cauchy–Binet,

$$\det(N'N'^\top) = \sum_S \det(N'_S) \det(N'_S{}^\top) = \sum_S (\det(N'_S))^2,$$

where the sum is extended over all $(n-1)$ -subsets S of the edge set. By (36.2), this is the number of spanning trees of G . \square

Remark. If we view $E(G)$ as a set of indeterminates and apply Lemma 36.2 to $(n-1) \times (n-1)$ principal submatrices of $N\Delta N^\top$ where here Δ is the diagonal matrix whose rows and columns are indexed by the edges and where the diagonal entries are the edges themselves (i.e. $\Delta(e, e) := e$), we find that $\det(N\Delta N^\top)$ is the sum of monomials corresponding to the edge sets of the trees in G . For example, for the graph G in Fig. 36.1,

$$N\Delta N^\top = \begin{pmatrix} a+b & -b & 0 & -a \\ -b & b+c+e & -c & -e \\ 0 & -c & c+d & -d \\ -a & -e & -d & a+d+e \end{pmatrix}.$$

Of course, $N\Delta N^\top$ is a singular matrix (all line-sums are 0), but the determinant of the 3×3 matrix obtained by dropping, e.g., the last row and column is

$$\begin{aligned} (a+b)(b+c+e)(c+d) - b^2(c+d) - c^2(a+b) = \\ abc + abd + acd + ace + ade + bcd + bce + bde, \end{aligned}$$

representing the eight spanning trees in G .

We now give a generalization of Theorem 36.1 due to W. T. Tutte (1948), with a proof that is shorter than the one we gave for the first theorem! (The generalized statement allows a type of induction that is not possible in the original.) The statement of Theorem 36.1 is recovered when we apply Theorem 36.3 to the directed graph obtained from an undirected graph by replacing each undirected edge with a pair of directed edges, one in each direction.

Theorem 36.3. *Let G be a directed graph with vertices x_1, \dots, x_n . Define the matrix M , or $M(G)$, as follows: $M = (m_{ij})$ where m_{ii} is the number of edges pointing away from x_i , not counting loops, and for $i \neq j$, m_{ij} is the negative of the number of edges directed from x_i to x_j . Then the number A_ℓ , or $A_\ell(G)$, of spanning arborescences of G with x_ℓ as root is the minor of position (ℓ, ℓ) in M , i.e. the determinant of the $(n-1) \times (n-1)$ principal submatrix of the matrix M obtained by dropping row ℓ and column ℓ .*

PROOF: For notational convenience, we take $\ell = 1$. If, for some $i > 1$, there are no edges directed away from x_i , then the statement of the theorem holds: row i of $M(G)$ is the zero-vector; both the minor of position $(1, 1)$ and the number of arborescences are zero.

If, for some $i > 1$, there is more than one edge directed away from x_i , let G_1 and G_2 be directed graphs equal to G except that some (≥ 1) of those edges are put into G_1 and the others (≥ 1) are put into G_2 . Since every spanning arborescence of G with root x_1 must contain exactly one edge directed away from x_i , $A_1(G) = A_1(G_1) + A_1(G_2)$. Also note that $M(G)$, $M(G_1)$, and $M(G_2)$ are identical except for the i th rows, and the i th row of $M(G)$ is the sum of the i th rows of $M(G_1)$ and $M(G_2)$. So the minor of position $(1, 1)$ in the first matrix is the sum of those minors in the latter two matrices.

Hence it will be sufficient to verify the statement of the theorem for digraphs G such that $m_{ii} = 1$ for all $i > 1$. That is, with the property that there is a unique edge directed away from any vertex x_i , $i > 1$.

If such a digraph G has a directed closed path not passing through x_1 , say $x_2 \rightarrow x_3, x_3 \rightarrow x_4, \dots, x_k \rightarrow x_2$, then the sum of rows 2

through k is $\mathbf{0}$ and hence the minor of position $(1, 1)$ is 0. There are no directed paths from any of these vertices to x_1 , so there are no spanning arborescences.

If such a digraph G has no directed closed paths not passing through x_1 , the directed path starting at any vertex x_j , and following the edge directed away from each vertex that is met, must reach x_1 . We see that the digraph G , when edges leaving x_1 are deleted (these edges may not occur in any spanning arborescence), *is itself* a spanning arborescence; so $A_1(G) = 1$. The minor of position $(1, 1)$ in $M(G)$ is also seen to be 1, e.g. by induction: expand the determinant by a column j corresponding to a vertex x_j that has indegree 0 in the arborescence (and so a 1 in position (j, j) and 0s in positions (i, j) , $i > 1$, $i \neq j$). \square

We remark that if the edges of a digraph G are viewed as independent indeterminates and a matrix like $M(G)$ is formed but where the entries are formal sums of edges rather than integers, then the minors are the formal sums of all arborescences, each represented by the product of its edges. The reader may easily modify the above proof. For example, if G is the digraph on vertices 1, 2, 3 with edge a directed from 2 to 1, edge b directed from 3 to 1, and edge c directed from 3 to 2, then we consider the matrix

$$M = \begin{pmatrix} 0 & 0 & 0 \\ -a & a & 0 \\ -b & -c & b+c \end{pmatrix}.$$

The minor of position $(1, 1)$ is $ab + ac$, which represents the two arborescences rooted at 1.

Problem 36B. (Easy.) Let T_n be the ‘transitive tournament’ on vertices $1, 2, \dots, n$ with edges directed from j to i whenever $i < j$. What is $M(T_n)$? What is the number of spanning arborescences rooted at 1 in T_n ? Describe all such arborescences.

We can now give a second proof of Theorem 8.2 on the number of De Bruijn sequences. Let the digraph G_n be as defined in Chapter 8. All the indegrees and outdegrees of G_n are equal to 2. The solution of Problem 2B suggested in Appendix 1 shows that the number of (directed) Eulerian cycles in G_n is equal to the number of spanning

arborescences in G_n rooted at any vertex. By Theorem 36.3 and Problem 36A, this number can be obtained from knowledge of the eigenvalues of the matrix $M(G_n)$.

Number the rows and columns of a matrix B_n of size 2^{n-1} by the integers 0 to $2^{n-1} - 1$. Let $b_{ij} = 1$ if $j = 2i$ or $2i + 1 \pmod{2^{n-1}}$. (Note that the top half and bottom half of B_n are the same.) Then $M(G_n) = 2I - B_n$. We now calculate the determinant $D_n(x)$ of $xI - M(G_n)$. By the obvious row and column operations on the lower half of this determinant we find

$$D_n(x) = (x - 2)^{2^{n-2}} D_{n-1}(x).$$

Since $D_2(x) = x(x - 2)$, we see that all the nonzero eigenvalues of M_n are equal to 2 and hence by Problem 36A, the number of De Bruijn cycles of length 2^n is

$$\frac{1}{2^{n-1}} \cdot 2^{2^{n-1}-1} = 2^{2^{n-1}-n}.$$

* * *

Let N be the incidence matrix of a digraph H . The rowspace of N is called the *coboundary space* of H ; the nullspace of N^T , i.e. the space of all row vectors f such that $fN^T = 0$, is called the *cycle space* of H . These are of importance in the theory of electrical networks and algebraic topology. From (36.1), the dimension of the coboundary space of a digraph H is $|V(H)| - |C(H)|$, and hence the dimension of the cycle space is $|E(H)| - |V(H)| + |C(H)|$.

From the definition, a vector f is a cycle if and only if for each vertex x , the sum of the values $f(e)$ on outgoing edges is equal to the sum of the values $f(e)$ on incoming edges. An example of a cycle f (a so-called *elementary* cycle) is obtained from any simple closed path p in H by defining $f(e)$ to be +1 on the forward edges of the path, -1 on the backward edges, and 0 on all edges not in the path. A vector is a coboundary if and only if it is orthogonal to all cycles, so in particular, the sum of the values of a coboundary on the forward edges of a simple closed path will equal the sum of the values on the backward edges of the path.

Problem 36C. A vector g with coordinates indexed by $E(H)$ is a coboundary on a digraph H if and only if for every closed walk w , the signed sum of the values of g on the edges (the sum of the values of g on the forward edges of w minus the sum of the values of g on the backward edges of w) is zero.

Let us agree that an *electrical network* consists of a digraph H , together with a function r associating to each edge e a ‘resistance’ $r(e) \geq 0$, and a function s associating to each edge e an ‘impressed electromotive force’ or ‘voltage source’ $s(e)$. That is, each edge is to be thought of as a resistor or a battery or both. If batteries and resistors are connected, a ‘current flow’ $f(e)$ will pass through each edge and a ‘potential difference’ or ‘voltage’ $g(e)$ will be measurable across each edge. All that we need to know here is that the vectors f and g are determined from r and s by the rules called *Kirchhoff’s laws* and *Ohm’s law*. Kirchhoff’s current law and voltage law assert, respectively, that f is a cycle and that g is a coboundary. Ohm’s law says that $g(e) = -s(e) + r(e)f(e)$, or, in matrix notation, $g = -s + fR$ where R is the diagonal matrix with the numbers $r(e)$ on the diagonal and where we think of s , g , and f as row vectors.

Problem 36D. Suppose $\{e : r(e) = 0\}$ contains no circuits, i.e. is the edge set of a forest. Show that the electrical network has a unique solution, by which we mean that for any s there exist unique vectors f and g satisfying the above laws.




Figure 36.2

By a *squared rectangle* we mean a rectangle which has been partitioned into a finite number of squares. Two examples appear in Figs. 36.2 and 36.3. These rectangles have dimensions 33 by 32, and 177 by 176, respectively. Squared rectangles are thought to be elegant when all internal squares have distinct sizes and when they contain no smaller squared rectangle.




Figure 36.3

Problem 36E. Find integral dimensions for the small squares in Fig. 36.4 so that the diagram represents a squared rectangle.




Figure 36.4

For many years, it was not known whether a *square* could be partitioned into a finite number of *unequal* smaller squares. In the late 1930s, such squared squares were finally discovered. One example was shown on the cover of the *Journal of Combinatorial Theory* until a smaller example was found by A. J. W. Duijvestijn (1978); the cover illustration was updated in January of 1979. This is a partition into the least possible number (21) of squares. Computers are used for these results, but an important tool in the study of squared rectangles is the connection with electrical networks which was discovered by four undergraduates at Cambridge in 1936–1938. A popular account of some of their work is given by W. T. Tutte (1961) and (1965) who was one of them.

We give an informal description of this connection with electrical networks. Let us use the term *special network* for an electrical network with a distinguished edge e_0 so that $s(e) = 0$ for $e \neq e_0$, and where

$$r(e) = \begin{cases} 1 & \text{if } e \neq e_0, \\ 0 & \text{if } e = e_0. \end{cases}$$

That is, we have a system of unit resistors and a single battery.




Figure 36.5

A special electrical network arises from a squared rectangle as follows. Define a digraph H whose vertices are the maximal horizontal line segments in the diagram. The edges of H are to be the small squares, and we include one special edge e_0 for the entire

rectangle. We direct each edge (except e_0) downward, i.e. towards the lower line segment. An example is shown in Fig. 36.5. The digraph H is clearly planar. There is a real number $f(e)$ naturally associated to edge e , namely the size of the corresponding small square; we take $f(e_0)$ to be the width of the large rectangle. It is not hard to see that f is a cycle on H : for each maximal horizontal line segment, the sum of the sizes of the squares ‘sitting on’ that segment is equal to the sum of the squares ‘hanging from’ it. Moreover, were it not for the special edge, f would also be a coboundary: if for each vertex (horizontal line segment) x , we take $h(x)$ to be the distance of the line segment from the top side of the large rectangle, then for $e \neq e_0$, $f(e)$ is equal to $h(\text{head of } e) - h(\text{tail of } e)$. So if we let $s(e_0)$ be the height of the rectangle and take g to be the coboundary of h , then f and g are the current flow and voltage vectors which solve this special network, i.e. $g = -s + Rf$.

Conversely, a special electrical network where the digraph is *planar* leads to the construction of a squared rectangle. We do not give a proof. The ratio of its width to its height will be the ratio of the current flow $f(e_0)$ to the voltage $-g(e_0)$ in the solution to the network. (Some of the edges may have negative current flow when the network is solved, but we could reverse the direction on these edges to get a positive value. The edges with zero current flow may be deleted—or contracted; they will not give rise to squares.) Thus a squared square corresponds to a planar network of resistors which have the net effect of a resistance of one ohm.

Problem 36F. Solve the special networks in Fig. 36.6 below by any means you wish, and sketch the corresponding squared rectangles. The dual graphs may also be thought of as special networks—what are the squared rectangles that arise from the dual networks?




Figure 36.6

Let N be the incidence matrix of a digraph D and Δ a diagonal matrix indexed by $E(D)$ with $\Delta(e, e) = r(e) > 0$, the resistance of the edge e ; let $C := N\Delta^{-1}N^\top$. If an additional edge e_0 is directed from one vertex y to another vertex x of D , and a sufficient voltage source is impressed on that single edge so that a current $f(e_0)$ flows through it, then Kirchhoff's laws imply that the potential difference $g(e)$ across an edge e joining vertex a to vertex b , say, is given by

$$(36.3) \quad g(e) = \frac{f(e_0)}{\tau(D)}(xy.ab)$$

where $(xy.ab)$ denotes the cofactor of the element c_{yb} in the cofactor of the element c_{xa} of $C = (c_{ij})$ and $\tau(D)$ denotes the number of spanning trees of D (the complexity of D). See Jeans (1908).

A consequence of this is the following theorem.

Theorem 36.4. *If the voltage source $s(e_0)$ on the distinguished edge e_0 of a special network with graph G is taken to be the number of spanning trees on the edge e_0 , then all values $f(a)$ of the resulting current flow will be integral, and the current flow $f(e_0)$ through the distinguished edge will be equal to the number of spanning trees off the edge e_0 .*

PROOF: In the discussion preceding the statement of the theorem, take D to be an orientation of G'_{e_0} and Δ the identity matrix. If the current flow $f(e_0)$ is $\tau(D) = \tau(G'_{e_0})$, then it is clear from (36.3) that all values of $f(a) = g(a)$ are integral. It remains only to show that $-g(e_0)$ is equal to the number of spanning trees on the edge e_0 .

By (36.3), $g(e_0) = (xy.yx) = -(xy.xy)$. By definition, $(xy.xy)$ is the determinant of the matrix $N''N''^\top$ where N'' consists of N with rows x and y deleted. By the Cauchy–Binet theorem, this is equal to

$$\sum_S (\det(N''_S))^2$$

where the sum is extended over all $(n-2)$ -subsets S of the edge set and N''_S is the square submatrix of N'' whose rows are indexed by elements of S .

The proof is completed by the observation that $\det(N_G'')$ is 0 unless $S \cup \{e_0\}$ is the edge set of a spanning tree in G , in which case it is ± 1 . This is similar to the proof of (36.2) and is left as an exercise. \square

In summary, Theorem 36.4 says that the resistance between the ends of an edge e_0 of a graph G when all other edges are thought of as unit resistors, is the ratio $\tau(G''_{e_0})/\tau(G'_{e_0})$. Readers might check that this agrees with their knowledge of electrical networks when G is a polygon or a bond-graph. A squared *square* arises when we find a planar graph G and an edge e_0 so that $\tau(G''_{e_0}) = \tau(G'_{e_0})$. This statement alone *does not necessarily help* in the search for squared squares (and electrical engineers will think this would be a waste of resistors anyway). Such graphs appear to be quite rare.

Notes.

The first appearance in the literature of the problem of using incongruent squares to make a rectangle seems to be M. Dehn (1903).

The first extensive tables of squared squares were published by C. J. Bouwkamp, A. J. W. Duijvestijn, and P. Medema (1960).

W. T. Tutte (1918–) has made numerous significant contributions to graph theory. He is Emeritus Professor of Mathematics in the Department of Combinatorics and Optimization of the University of Waterloo, one of the few academic departments in the world whose name includes the word ‘combinatorics’.

For the proof of Theorem 36.3, we have followed De Bruijn and Van Aardenne-Ehrenfest (1951).

One of the Cambridge students mentioned earlier, C. A. B. Smith, wrote a very nice account of the history of their collaboration, called ‘Did Erdős save Western Civilization?’ (see Graham and Nešetřil (1997)). Apparently, Erdős conjectured that any dissection of a square into smaller squares must contain at least two squares of equal size. One thing led to another and Tutte ended up at Bletchley Park instead of in the army. It is rumored that there he supplied the vital clue to the deciphering of the Enigma, which explains the title of the paper.

References.

N. G. de Bruijn and T. van Aardenne-Ehrenfest (1951), Circuits


- and trees in oriented linear graphs, *Simon Stevin* **28**, 203–217.
- C. J. Bouwkamp, A. J. W. Duijvestijn, P. Medema (1960), *Tables relating to simple squared rectangles of order nine through fifteen*, T. H. Eindhoven.
- A. J. W. Duijvestijn (1978), Simple perfect squared square of lowest order, *J. Combinatorial Theory* (B) **25**, 555–558.
- M. Dehn (1903), Zerlegung von Rechtecke in Rechtecken, *Math. Ann.* **57**.
- R. L. Graham and J. Nešetřil (Eds.) (1997), *The Mathematics of P. Erdős*, Springer.
- J. H. Jeans (1908), *The Mathematical Theory of Electricity and Magnetism*, Cambridge University Press.
- W. T. Tutte (1948), The dissection of equilateral triangles into equilateral triangles, *Proc. Camb. Phil. Soc.* **44**, 463–482.
- W. T. Tutte (1961), Squaring the square, in: M. Gardner, *The 2nd Scientific American Book of Mathematical Puzzles and Diversions*, Simon and Schuster.
- W. T. Tutte (1965), The quest of the perfect square, *Amer. Math. Monthly* **72**, No. 2, 29–35.

37

Pólya theory of counting

We return to counting in this chapter. There are many instances when we are not interested in the number of primitive objects, but rather the number of equivalence classes of objects with respect to an appropriate equivalence relation. Moreover, these equivalence relations are often induced by certain permutation groups in a natural way.

Question 1. What is the number of ‘essentially different’ necklaces which can be made with n beads of two different colors? For $n = 6$, this number is, by inspection, 13.



Note that we choose to regard the necklaces

$$(37.1) \quad \begin{array}{c} \bullet \bullet \\ \bullet \circ \\ \bullet \circ \end{array} \quad \text{and} \quad \begin{array}{c} \bullet \bullet \\ \circ \bullet \\ \circ \bullet \end{array}$$

as essentially the same, since one can be reflected through a vertical axis (or flipped over) to get the other. Evidently, underlying our concept of ‘essentially different’ is the dihedral group D_n of automorphisms of the n -gon.

Question 2. What is the number of nonisomorphic simple graphs on n vertices? For $n = 4$, there are 11.

Question 3. What is the number of essentially different ways to paint the faces (or edges, or vertices) of the cube with n colors?

Question 4. Given three white balls and one black ball, what is the number of ways to distribute them into two square boxes and one round box?

$[\circ\circ\circ\bullet] [] ()$	$[\circ\circ\circ] [\bullet] ()$	$[\circ\circ] [\circ\bullet] ()$	$[\circ\circ\bullet] [\circ] ()$
$[\circ\circ\circ] [] (\bullet)$	$[\circ\circ] [\circ] (\bullet)$	$[\circ\circ\bullet] [] (\circ)$	$[\circ\circ] [\bullet] (\circ)$
$[\circ\bullet] [\circ] (\circ)$	$[\circ\bullet] [] (\circ\circ)$	$[\circ] [\bullet] (\circ\circ)$	$[\circ\circ] [] (\circ\bullet)$
$[\circ] [\circ] (\circ\bullet)$	$[\bullet] [] (\circ\circ\circ)$	$[\circ] [] (\circ\circ\bullet)$	$[] [] (\circ\circ\circ\bullet)$

Let A and B be finite sets and G a group of permutations of A (or more generally, a finite group acting on A). The elements of B will be called *colors*. The group G acts on the set B^A of mappings $f : A \rightarrow B$ when for $\sigma \in G$ and $f \in B^A$, we define $(\sigma(f)) \in B^A$ by

$$(\sigma(f))(x) := f(\sigma^{-1}(x)).$$

It is the orbits of an appropriate G on the set B^A that we wish to count in the first three questions above.

(The use of σ^{-1} rather than σ on the right-hand side above is not an error. It is required to ensure that $\sigma(\tau(f)) = (\sigma\tau)(f)$, which is necessary in order to have a legitimate ‘action’ of G on B^A . Formally, we have a homomorphism of G into the symmetric group on B^A .)

In the necklace problem, we would take A to be the vertex set of an n -gon, and G as its automorphism group represented as a permutation group on the vertices (i.e. the dihedral group D_n of order $2n$ in its usual representation). A slightly different problem arises when the beads to be used are not round, but, say, flat on one side. Then the necklaces cannot be flipped over and those in (37.1) are regarded as distinct.

Here, we would take G to be the cyclic group of order n in its regular representation; cf. Example 10.5.

Asking for the number of orbits of mappings is the simplest question we can pose. We might further want to know the number of orbits of a given ‘weight’; for example, the number of necklaces of n beads, k of which are to be white, or the number of graphs on n vertices with k edges. We might introduce a permutation group

H on B and, with respect to a more general equivalence relation, ask for the number of ‘configurations’. (This would be necessary for the distribution problem.)

To begin, we recall Burnside’s lemma, Theorem 10.5: the number of orbits of a finite group G on a set X is the average number of fixed points:

$$(37.2) \quad \frac{1}{|G|} \sum_{\sigma \in G} \psi(\sigma),$$

where $\psi(\sigma)$ denotes the number of points of S that are fixed by the permutation σ . Recall that this formula followed from counting ordered pairs $(x, \sigma) \in X \times G$ such that $\sigma(x) = x$.

Theorem 37.1. *Let A and B be finite sets and let G act on A . Denote by $c_k(G)$ the number of permutations in G that have exactly k cycles in their cycle decomposition on A . Then the number of orbits of G on the set B^A of all mappings $f : A \rightarrow B$ is*

$$\frac{1}{|G|} \sum_{k=1}^{\infty} c_k(G) |B|^k.$$

PROOF: By Burnside’s lemma, the number of orbits is given by (37.2) where $\psi(\sigma)$ is here the number of mappings $f : A \rightarrow B$ such that $\sigma(f) = f$, i.e. $f(a) = f(\sigma^{-1}(a))$ for all $a \in A$. But a mapping f is fixed by σ if and only if f is constant on every cycle of σ ; the reader should check this. Such mappings are obtained by assigning an element of B to each cycle of σ , and thus if σ has k cycles, the number of mappings f fixed by σ is $|B|^k$. \square

We encourage the reader to pause at this point and to verify that Theorem 37.1 produces the answer 13 when applied to the necklace counting problem raised as Question 1 above.

Since it is to be used extensively later, it is appropriate to introduce the *cycle index* of a permutation group at this point. First, in this chapter, it will be convenient to use the venerable notation $(1^{k_1} 2^{k_2} \dots n^{k_n})$ for the partition of the integer n which has k_i parts of size i , $i = 1, 2, \dots, n$. Do not compute powers or multiply; this is just notation.

For a permutation σ of a set A , let $z_i(\sigma)$ denote the number of cycles of σ having length i ; so $(1^{z_1(\sigma)}2^{z_2(\sigma)}\dots)$ is a partition of $n = |A|$, called the *type* of σ . Given a group G acting on A , we define the cycle index Z_G as a polynomial in n letters X_1, X_2, \dots, X_n by

$$Z_G(X_1, X_2, \dots, X_n) := \frac{1}{|G|} \sum_{\sigma \in G} X_1^{z_1(\sigma)} \dots X_n^{z_n(\sigma)}.$$

The assertion of Theorem 37.1 is that the number of orbits of G on B^A is

$$Z_G(b, b, \dots, b) = \frac{1}{|G|} \sum_{\sigma \in G} b^{z_1(\sigma) + z_2(\sigma) + \dots + z_n(\sigma)}$$

where $b := |B|$.

Example 37.1. A cyclic group C_n of order n has $\varphi(d)$ elements of order d for each divisor d of n . As a permutation in the regular representation of C_n , an element of order d has n/d cycles of length d . Thus, for the regular representation of C_n , we have

$$Z_{C_n}(X_1, \dots, X_n) = \frac{1}{n} \sum_{d|n} \varphi(d) X_d^{n/d}.$$

We can now count the number of ‘one-sided’ necklaces of n beads of two colors. The answer is $Z_{C_n}(2, 2, \dots, 2) = \frac{1}{n} \sum_{d|n} \varphi(d) 2^{n/d}$; cf. equation (10.12). For $n = 6$, we get 14, one more than with dihedral equivalence (the two necklaces in (37.1) are now distinguished). For $n = 10$, we get 108.

Example 37.2. To find the cycle index of the dihedral group D_n in its usual representation on n points, we must account for the permutations (reflections) outside of its cyclic subgroup of order n . There are two cases depending on the parity of n :

$$Z_{D_n} = \begin{cases} \frac{1}{2n} \left(\sum_{d|n} \varphi(d) X_d^{n/d} + n X_1 X_2^{\frac{n-1}{2}} \right) & \text{for } n \text{ odd,} \\ \frac{1}{2n} \left(\sum_{d|n} \varphi(d) X_d^{n/d} + \frac{n}{2} X_1^2 X_2^{\frac{n}{2}-1} + \frac{n}{2} X_2^{\frac{n}{2}} \right) & \text{for } n \text{ even.} \end{cases}$$

The number of ‘two-sided’ necklaces with n beads of two different colors is $Z_{D_n}(2, 2, \dots, 2)$. For $n = 6$, we get 13 (verifying the list following Question 1). For $n = 10$, we get 78.

Problem 37A. Compute the cycle index of the group of rotations of the cube represented as permutations of the six faces. (There are 24 rotations—including the identity—that map the cube, as a rigid body in 3-space, onto itself. We are ignoring the 24 reflections of the cube.) What is the number of essentially different ways to paint the faces of the cube in 2 colors? In 3 colors? In n colors?

Before going further, let us write down the cycle index of the symmetric groups. We noted the formula for the number of *partitions* of a given type $(1^{k_1} 2^{k_2} \dots n^{k_n})$ in equation (13.3). Each block of size i may be equipped with a cyclic permutation in $(i - 1)!$ ways, so we have

$$Z_{S_n} = \sum_{(1^{k_1} 2^{k_2} \dots)} \frac{1}{1^{k_1} 2^{k_2} \dots n^{k_n} k_1! k_2! \dots k_n!} X_1^{k_1} X_2^{k_2} \dots X_n^{k_n}.$$

We list the first several polynomials below:

$$1!Z_{S_1} = X_1,$$

$$2!Z_{S_2} = X_1^2 + X_2,$$

$$3!Z_{S_3} = X_1^3 + 3X_1X_2 + 2X_3,$$

$$4!Z_{S_4} = X_1^4 + 6X_1^2X_2 + 3X_2^2 + 8X_1X_3 + 6X_4,$$

$$5!Z_{S_5} = X_1^5 + 10X_1^3X_2 + 15X_1X_2^2 + 20X_1^2X_3 + 20X_2X_3 \\ + 30X_1X_4 + 24X_5,$$

$$6!Z_{S_6} = X_1^6 + 15X_1^4X_2 + 45X_1^2X_2^2 + 40X_3^2 + 40X_1^3X_3 + 15X_2^3 \\ + 120X_1X_2X_3 + 90X_1^2X_4 + 90X_2X_4 + 144X_1X_5 + 120X_6.$$

Example 37.3. Theorem 37.1 can be used for the enumeration of graphs. Let V be a fixed set of n vertices and let E consist of all 2-subsets of V . Then the simple graphs with vertex set V can be viewed as mappings $f : E \rightarrow \{0, 1\}$, the graph corresponding to f having edge set $f^{-1}(1) = \{e : f(e) = 1\}$.

Two graphs on V are isomorphic if and only if there exists a permutation of V taking the edges of one onto the edges of the other. To describe this in a manner suitable for the application of Theorem 37.1, let S_n be the symmetric group on V and let $S_n^{(2)} = \{\sigma^{(2)} : \sigma \in S_n\}$ be the induced group, isomorphic to S_n , of permutations of E where

$$\sigma^{(2)} : \{x, y\} \mapsto \{\sigma(x), \sigma(y)\}.$$

Then $S_n^{(2)}$ acts on $\{0, 1\}^E$ and we note that $f, g : E \rightarrow \{0, 1\}$ correspond to isomorphic graphs if and only if they lie in the same orbit of $S^{(2)}$ on $\{0, 1\}^E$.

It is not a pleasant task to compute the types of all permutations in $S_n^{(2)}$. For example, if $\sigma \in S_5$ has type $(2^1 3^1)$, then it turns out that $\sigma^{(2)}$ has type $(1^1 3^1 6^1)$ on the 10 edges of K_5 . The cycle index of $S_5^{(2)}$ is

$$\begin{aligned} \frac{1}{120} (X_1^{10} + 10X_1^4 X_2^3 + 15X_1^2 X_2^4 + 20X_1 X_3^3 \\ + 20X_1 X_3 X_6 + 30X_2 X_4^2 + 24X_5^2). \end{aligned}$$

In general, we will have a sum over all partitions of n . The number of nonisomorphic graphs on five vertices is found, by substituting 2 for all indeterminates, to be 34.

We now generalize Theorem 37.1 to allow for weights. Let A be an n -set, let G act on A , and let B be a finite set of colors. Let R be a commutative ring containing the rationals and let $w : B \rightarrow R$ assign a *weight* $w(b) \in R$ to each color $b \in B$. For $f : A \rightarrow B$, define

$$W(f) := \prod_{a \in A} w(f(a)) \in R;$$

here $W(f)$ is the *weight* of the function f . Note that two mappings representing the same orbit of G on B^A have the same weight, i.e. $W(\sigma(f)) = W(f)$ for every $\sigma \in G$. The sum

$$\sum_{f \in R} W(f),$$

extended over a system of representatives R for the orbits, is called the *configuration counting series*. (The orbits are often called *configurations*; the term *series* becomes appropriate when the weights are monomials.) If all weights $w(b)$ are 1, then the following theorem reduces to Theorem 37.1.

Theorem 37.2. *With the terminology as above, the configuration counting series is given by*

$$\sum W(f) = Z_G \left(\sum_{b \in B} w(b), \sum_{b \in B} [w(b)]^2, \dots, \sum_{b \in B} [w(b)]^n \right).$$

PROOF: Let $N = \sum W(f)$, the sum extended over all pairs (σ, f) with $\sigma \in G$, $f \in B^A$, and $\sigma(f) = f$. We have

$$N = \sum_{f \in B^A} W(f) |G_f|,$$

where G_f is the stabilizer of f . Consider the terms $W(f) |G_f|$ as f ranges over an orbit \mathcal{O} of G on B^A : each is equal to $W(f_0) |G| / |\mathcal{O}|$ where f_0 is a representative of the orbit \mathcal{O} , so these terms sum to $|G| W(f_0)$. It is now clear that N is $|G|$ times the configuration counting series.

On the other hand,

$$N = \sum_{\sigma \in G} \left(\sum_{\sigma(f)=f} W(f) \right).$$

Recalling the definition of Z_G , we see that the proof will be complete if we show that

$$\sum_{\sigma(f)=f} W(f) = \left(\sum_{b \in B} w(b) \right)^{k_1} \left(\sum_{b \in B} [w(b)]^2 \right)^{k_2} \cdots \left(\sum_{b \in B} [w(b)]^n \right)^{k_n}$$

whenever σ is a permutation of type $(1^{k_1} 2^{k_2} \dots n^{k_n})$.

A mapping $f : A \rightarrow B$ is fixed by σ if and only if f is constant on every cycle of σ on A . Let

$$C_1, C_2, \dots, C_k, \quad k := k_1 + k_2 + \cdots + k_n$$

be the cycles of σ . The mappings $f \in B^A$ fixed by σ are in one-to-one correspondence with k -tuples (b_1, b_2, \dots, b_k) of elements of B (the corresponding mapping is the one associating b_i to all elements of C_i). The weight of the mapping f corresponding to (b_1, \dots, b_k) is

$$W(f) = \prod_{i=1}^k [w(b_i)]^{|C_i|},$$

and summing over all k -tuples (b_1, b_2, \dots, b_k) ,

$$\begin{aligned} \sum_{\sigma(f)=f} W(f) &= \sum_{b_1, b_2, \dots, b_k} [w(b_1)]^{|C_1|} [w(b_2)]^{|C_2|} \dots [w(b_k)]^{|C_k|} \\ &= \left(\sum_{b_1} [w(b_1)]^{|C_1|} \right) \left(\sum_{b_2} [w(b_2)]^{|C_2|} \right) \dots \\ &= \prod_{c=1}^n \left(\sum_b [w(b)]^c \right)^{k_c}, \end{aligned}$$

as required. □

Example 37.4. Consider the necklace problem with cyclic equivalence. Here $G = C_n$, $B = \{\text{black}, \text{white}\}$. We take R to be the polynomial ring $Q[X]$ and define $w(\text{black}) = 1$, $w(\text{white}) = X$. Then the weight of a coloring $f : A \rightarrow B$ is

$$W(f) = X^k$$

where k is the number of white beads.

Thus the number of essentially different cyclic necklaces with n beads, k of which are white, is the coefficient of X^k in the configuration counting series

$$\begin{aligned} Z_{C_n}(1 + X, 1 + X^2, 1 + X^3, \dots, 1 + X^n) \\ &= \frac{1}{n} \sum_{d|n} \varphi(d) [1 + X^d]^{n/d} \\ &= \frac{1}{n} \sum_{d|n} \varphi(d) \sum_{r=0}^{n/d} \binom{n/d}{r} x^{rd}. \end{aligned}$$

This coefficient is

$$\frac{1}{n} \sum_{d|(k,n)} \varphi(d) \binom{n/d}{k/d}.$$

So if k and n are relatively prime, the number is simply $\frac{1}{n} \binom{n}{k}$, while for $n = 12$, $k = 4$, there are $\frac{1}{12} \left(\varphi(1) \binom{12}{4} + \varphi(2) \binom{6}{2} + \varphi(4) \binom{3}{1} \right) = 43$ necklaces.

Problem 37B. What is the number of essentially different ways to paint the faces of a cube such that one face is red, two are blue, and the remaining three are green? Do this ‘by hand’ (which may be quicker) as well as by using Theorem 37.2, and compare your answers.

Let A and B be finite sets, $|A| = n$, and let G and H be finite groups, G acting on A and H on B . The direct product $G \times H$ acts on B^A when for $f \in B^A$ and $(\sigma, \tau) \in G \times H$ we define $(\sigma, \tau)(f)$ by

$$((\sigma, \tau)(f))(a) = \tau(f(\sigma^{-1}(a))).$$

Theorem 37.3. *The number of orbits of $G \times H$ on B^A is*

$$\frac{1}{|H|} \sum_{\tau \in H} Z_G(m_1(\tau), m_2(\tau), \dots, m_n(\tau))$$

where

$$m_i(\tau) := \sum_{j|i} j z_j(\tau), \quad i = 1, 2, \dots, n.$$

PROOF: By Burnside’s lemma, the number of orbits is

$$\frac{1}{|G||H|} \sum_{\sigma \in G, \tau \in H} \psi(\sigma, \tau)$$

where $\psi(\sigma, \tau)$ is the number of mappings $f \in B^A$ with $(\sigma, \tau)(f) = f$. To complete the proof, it will suffice to show that for each $\tau \in H$,

$$(37.3) \quad \frac{1}{|G|} \sum_{\sigma \in G} \psi(\sigma, \tau) = Z_G(m_1(\tau), m_2(\tau), \dots, m_n(\tau)).$$

Fix $\sigma \in G$ and $\tau \in H$, and let

$$C_1, C_2, \dots, C_k, \quad k := z_1(\sigma) + z_2(\sigma) + \dots + z_n(\sigma)$$

be the cycles of σ on A . A mapping $f : A \rightarrow B$ is fixed by (σ, τ) if and only if all the restrictions $f_i := f|_{C_i}$ are fixed, $1 \leq i \leq k$. So $\psi(\sigma, \tau)$ is the product, over i in the range $1 \leq i \leq k$, of the numbers of mappings $f_i : C_i \rightarrow B$ satisfying

$$f_i(\sigma(a)) = \tau(f_i(a)) \quad \text{for all } a \in C_i.$$

Let C_i have length ℓ and fix $a_o \in C_i$. Suppose that $f_i : C_i \rightarrow B$ is fixed by $(\sigma|_{C_i}, \tau)$ and that $f_i(a_o) = b$. Then f_i is completely determined: $f_i(\sigma^t(a_o)) = \tau^t(b)$. Moreover, $b = f_i(a_o) = f_i(\sigma^\ell(a_o)) = \tau^\ell(b)$ and so we see that the cycle of τ containing b must have length ℓ' , a divisor of ℓ .

Conversely, if b is an element of B lying in a cycle of τ having a length dividing $\ell := |C_i|$, then we can define a mapping f_i on C_i by $f_i(\sigma^t(a_o)) := \tau^t(b)$ (check that f_i is well defined) and this f_i is fixed by $(\sigma|_{C_i}, \tau)$.

In summary, when $|C_i| = \ell$, the fixed mappings $f_i : C_i \rightarrow B$ are equinumerous with the elements of B lying in cycles of τ of length dividing ℓ . The number of such elements is, of course,

$$m_\ell(\tau) = \sum_{j|\ell} j z_j(\tau).$$

Then

$$\psi(\sigma, \tau) = \prod_{i=1}^k m_{|C_i|}(\tau) = [m_1(\tau)]^{z_1(\sigma)} [m_2(\tau)]^{z_2(\sigma)} \dots [m_n(\tau)]^{z_n(\sigma)},$$

from which the desired equation (37.3) is immediate. \square

Example 37.5. What is the number of ways to distribute 2 red, 2 yellow, and 4 green balls into 1 round and 3 square boxes? We take

$$A = \{R_1, R_2, Y_1, Y_2, G_1, G_2, G_3, G_4\},$$

$$G = S_2 \times S_2 \times S_4, \quad B = \{r, s_1, s_2, s_3\}, \quad H = S_1 \times S_3.$$

It is easy to see that the cycle index of G is the product of the cycle indices of the symmetric groups of which it is the product, so

$$(37.4) \quad \begin{aligned} Z_G &= Z_{S_2} \cdot Z_{S_2} \cdot Z_{S_4} \\ &= \frac{1}{2!2!4!} (X_1^2 + X_2)^2 (X_1^4 + 6X_1^2X_2 + 3X_2^2 + 8X_1X_3 + 6X_4). \end{aligned}$$

There are three types of permutations in H . If τ is the identity, then

$$m_1(\tau) = 4, \quad m_2(\tau) = 4, \quad m_3(\tau) = 4, \quad m_4(\tau) = 4;$$

if τ transposes two of $\{s_2, s_2, s_3\}$, then

$$m_1(\tau) = 2, \quad m_2(\tau) = 4, \quad m_3(\tau) = 2, \quad m_4(\tau) = 4;$$

if τ fixes only r , then

$$m_1(\tau) = 1, \quad m_2(\tau) = 1, \quad m_3(\tau) = 4, \quad m_4(\tau) = 1.$$

By Theorem 37.3, the number of distributions is

$$\begin{aligned} &\frac{1}{3!} \frac{1}{2!2!4!} [(4^2 + 4)^2 (4^4 + 6 \cdot 4^2 \cdot 4 + 2 \cdot 4^2 + 8 \cdot 4 \cdot 4 + 6 \cdot 4) \\ &\quad + 3(2^2 + 4)^2 (2^4 + 6 \cdot 2^2 \cdot 4 + 3 \cdot 4^2 + 8 \cdot 2 \cdot 2 + 6 \cdot 4) \\ &\quad + 2(1^2 + 1)^2 (1^4 + 6 \cdot 1^2 \cdot 1 + 3 \cdot 1^2 + 8 \cdot 1 \cdot 4 + 6 \cdot 1)] \\ &= 656 \text{ (if we did the arithmetic correctly).} \end{aligned}$$

Problem 37C. Given G on A , H on B , find an expression for the number of orbits of injective mappings $f : A \rightarrow B$.

We give, without proof, a statement of the extension of Theorem 37.3 to include weights. See De Bruijn (1964) for a proof. If all weights are 1, then this reduces to Theorem 37.3.

Theorem 37.4. Let G act on A , H on B , let R be a commutative ring and $w : B \rightarrow R$. Assume that w is constant on each orbit of H on B . With $W(f) := \prod_{a \in A} w[f(a)]$, the sum $\sum W(f)$, extended

over a system of representation for the orbits of $G \times H$ on B^A , is equal to

$$\frac{1}{|H|} \sum_{\tau \in H} Z_G(M_1(\tau), M_2(\tau), \dots, M_n(\tau))$$

where

$$M_i(\tau) = \sum_{\tau^i(b)=b} [w(b)]^i.$$

Example 37.6. We continue Example 13.5. Take

$$w(r) = r, \quad w(s_1) = w(s_2) = w(s_3) = s,$$

where $R = \mathbb{Q}[r, s]$. The number of distributions with t balls in the round box and the remaining $8 - t$ in square boxes is the coefficient of $r^t s^{8-t}$ in

$$\frac{1}{6} \left(Z_G(r + 3s, r^2 + 3s^2, r^3 + 3s^3, r^4 + 3s^4) \right. \\ \left. + 3Z_G(r + s, r^2 + 3s^2, r^3 + s^3, r^4 + 3s^4) + 2Z_G(r, r^2, r^3 + 3s^3, r^4) \right)$$

where Z_G is the polynomial in (37.4).

Problem 37D. Identify necklaces of two types of colored beads with their *duals* obtained by switching the colors of the beads. (We can now distinguish between the two colors, but we can't tell which is which.) Now how many of these reduced configurations are there? (For example, with $n = 6$ and dihedral equivalence, there are 8 distinct configurations.) How many necklaces are self-dual?

Problem 37E. The faces of the cube are to be colored with s colors, and the vertices with t colors (which can be assumed different, though it is not important). In how many essentially different ways (with respect to the rotation group of the cube) can this be done?

* * *

The theorems of this chapter are also sources of algebraic identities.

Consider the case of ‘distribution of like objects into unlike cells’. (We are recalling something which was discussed in Chapter 13.) For example, in how many ways can we distribute 23 apples to Fred, Jane, and George? More generally, consider the distributions of a set A of n apples to a set B of x individuals (the elements of A are ‘like’, whereas the elements of B remain distinct, i.e. are ‘unlike’). Such a distribution amounts to the selection of a family $(k_b : b \in B)$ of nonnegative integers k_b with $\sum_{b \in B} k_b = n$, k_b apples going to individual b .

Thus the number of distributions, as shown in Theorem 13.3, is

$$\binom{n+x-1}{n}.$$

However, the best formal definition of such a distribution is as an orbit of mappings $f : A \rightarrow B$ with respect to the symmetric group S_n acting on A . (Two mappings $f, g \in B^A$ determine the same distribution if and only if they ‘differ’ by a permutation of the apples.) By Theorem 37.1, the number of distributions is

$$\frac{1}{n!} \sum_{k=0}^n c_k(S_n) x^k,$$

where $c_k(S_n)$ is the number of permutations of n letters with exactly k cycles. In Chapter 13, the numbers $c_k(S_n)$ were called the signless Stirling numbers of the first kind, and denoted by $c(n, k)$. By Theorem 37.2, for every nonnegative integer x ,

$$(x+n-1)_{(n)} = \sum_{k=0}^n c_k(S_n) x^k,$$

and hence this must hold as a polynomial identity. We have therefore re-proved the formula (13.7).

Take G to be S_n on an n -set A , let B be finite and let w be the insertion of B into the polynomial ring $\mathbb{Q}[B]$. Here the weight of a mapping $f : A \rightarrow B$ is a monomial and two mappings are equivalent, that is, represent the same configuration, if and only if

they have the same weight. The configuration counting series

$$(37.5) \quad \sum W(f) = Z_{S_n} \left(\sum_{b \in B} b, \sum_{b \in B} b^2, \dots, \sum_{b \in B} b^n \right)$$

expresses the so-called homogeneous-product-sum symmetric functions as a polynomial in the power-sum symmetric functions. For example, with $n = 3$ and $B = \{X, Y\}$,

$$6(X^3 + X^2Y + XY^2 + Y^3) = (X + Y)^3 + 3(X + Y)(X^2 + Y^2) + 2(X^3 + Y^3).$$

With $n = 4$ and $B = \{X, Y, Z\}$, (37.5) expresses

$$\sum_{i+j+k=4} X^i Y^j Z^k$$

as a polynomial in

$$X + Y + Z, X^2 + Y^2 + Z^2, X^3 + Y^3 + Z^3, \text{ and } X^4 + Y^4 + Z^4.$$

Notes.

We remark that $Z_{S_n}(X_1, \dots, X_n)$ is the coefficient of Y^n in

$$\exp \left(X_1 Y + \frac{1}{2} X_2 Y^2 + \frac{1}{3} X_3 Y^3 + \dots \right)$$

as an element of $(\mathbb{Q}[X_1, X_2, \dots])[Y]$.

The answers provided by Pólya theory have the advantage (over inclusion-exclusion, say) that the formula produced is the sum of positive terms rather than an alternating sum.

G. Pólya (1887–1985) was a Hungarian mathematician whose book *Problems and Theorems in Analysis* written in 1924 with G. Szegő is still a classic. But he is perhaps best known for *How to Solve It*, which has sold more than one million copies. He wrote papers on number theory, complex analysis, combinatorics, probability theory, geometry and mathematical physics.

References.

- N. G. de Bruijn (1964), Pólya's theory of counting, in: E. F. Beckenbach (ed.), *Applied Combinatorial Mathematics*, Wiley.
 F. Harary and E. D. Pulver (1966), The power group enumeration theorem, *J. Combinatorial Theory* **1**.


38

Baranyai's theorem

In this chapter we shall give an elegant application of the integrality theorem on flows to a problem in ‘combinatorial design’.

Example 38.1. Suppose we have been entrusted to draw up a schedule for the ‘Big Ten’ football teams. Each weekend they are to divide into 5 pairs and play. At the end of 9 weeks, we want every possible pair of teams to have played exactly once.


Here is one solution. Put 9 teams on the vertices of a regular 9-gon and one in the center. Start with the pairing indicated below and obtain the others by rotating the figure by multiples of $2\pi/9$.



Explicitly, here is the schedule:

$x \bullet 0$	$x \bullet 1$	$x \bullet 2$	$x \bullet 3$	$x \bullet 4$	$x \bullet 5$	$x \bullet 6$	$x \bullet 7$	$x \bullet 8$
$1 \bullet 8$	$2 \bullet 0$	$3 \bullet 1$	$4 \bullet 2$	$5 \bullet 3$	$6 \bullet 4$	$7 \bullet 5$	$8 \bullet 6$	$0 \bullet 7$
$2 \bullet 7$	$3 \bullet 8$	$4 \bullet 0$	$5 \bullet 1$	$6 \bullet 2$	$7 \bullet 3$	$8 \bullet 4$	$0 \bullet 5$	$1 \bullet 6$
$3 \bullet 6$	$4 \bullet 7$	$5 \bullet 8$	$6 \bullet 0$	$7 \bullet 1$	$8 \bullet 2$	$0 \bullet 3$	$1 \bullet 4$	$2 \bullet 5$
$4 \bullet 5$	$5 \bullet 6$	$6 \bullet 7$	$7 \bullet 8$	$8 \bullet 0$	$0 \bullet 1$	$1 \bullet 2$	$2 \bullet 3$	$3 \bullet 4$

There are many other ways to do this. For example, start with the initial pairing shown below.



A perfect matching in a graph is also called a *1-factor*. A partition of the edge set of a graph into 1-factors is a *1-factorization*. In the above example, we constructed 1-factorizations of K_{10} . There are 396 nonisomorphic 1-factorizations of K_{10} , a computer result of E. N. Gelling (1973). See also Mendelsohn and Rosa (1985).

Example 38.2. Let Γ be any abelian group of odd order. Consider the complete graph on the vertex set $\Gamma \cup \{\infty\}$. For $g \in \Gamma$, let

$$\mathcal{M}_g := \{\{g, \infty\}\} \cup \{\{a, b\} : a + b = 2g, a \neq b\}.$$

Then $\{\mathcal{M}_g : g \in \Gamma\}$ is a 1-factorization of the complete graph.

We consider the following generalization of this problem: let us use the term *parallel class* of k -subsets of an n -set to mean a set of n/k k -subsets which partition the n -set. Can the set of all k -subsets be partitioned into parallel classes of k -subsets? Of course, this necessitates that k divides n . The number of parallel classes required would be $\frac{k}{n} \binom{n}{k} = \binom{n-1}{k-1}$.

This was not hard for $k = 2$. It is much harder for $k = 3$, but was done by R. Peltesohn in 1936, and for $k = 4$ by J.-C. Bermond (unpublished). The reader might try to find appropriate parallel classes for $n = 9, k = 3$. It is certainly not clear that our generalization always admits a solution and so it was surprising when Zs. Baranyai proved Theorem 38.1 in 1973. All known proofs use a form or consequence of Theorem 7.2 or 7.4. The proof we give is due to A. E. Brouwer and A. Schrijver (1979).

Theorem 38.1. *If k divides n , the set of all $\binom{n}{k}$ k -subsets of an n -set may be partitioned into disjoint parallel classes $\mathcal{A}_i, i = 1, 2, \dots, \binom{n-1}{k-1}$.*

PROOF: In this proof, we will use the term *m-partition* of a set X for a multiset \mathcal{A} of m pairwise disjoint subsets of X , some of which

may be empty, whose union is X . (The normal use of ‘partition’ forbids the empty set, but it is important here to allow it to occur, perhaps with a multiplicity, so that the total number of subsets is m .)

In order to get an inductive proof to work, we prove something seemingly stronger than the original statement. Let n and k be given, assume k divides n , and let $m := n/k$, $M := \binom{n-1}{k-1}$. We assert that for any integer ℓ , $0 \leq \ell \leq n$, there exists a set

$$\mathcal{A}_1, \mathcal{A}_2, \dots, \mathcal{A}_M$$

of m -partitions of $\{1, 2, \dots, \ell\}$ with the property that each subset $S \subseteq \{1, 2, \dots, \ell\}$ occurs in exactly

$$(38.1) \quad \binom{n - \ell}{k - |S|}$$

of the m -partitions \mathcal{A}_i . (The binomial coefficient above is interpreted as zero if $|S| > k$, of course, and for $S = \emptyset$, the m -partitions containing \emptyset are to be counted with multiplicity equal to the number of times the empty set appears.)

Our assertion will be proved by induction on ℓ . Notice that it is trivially true for $\ell = 0$, where each \mathcal{A}_i will consist of m copies of the empty set. Also notice that the case $\ell = n$ will prove Theorem 38.1, since the binomial coefficient in (38.1) is then


$$\binom{0}{k - |S|} = \begin{cases} 1 & \text{if } |S| = k, \\ 0 & \text{otherwise.} \end{cases}$$

Remark. This somewhat technical statement is not really more general, but would follow easily from Theorem 38.1. If M parallel classes exist as in the statement of Theorem 38.1, then for any set L of ℓ points of X , the intersections of the members of the parallel classes with L will provide m -partitions of L with the above property.

Assume for some value of $\ell < n$ that m -partitions $\mathcal{A}_1, \dots, \mathcal{A}_M$ exist with the required property. We form a transportation network as follows. There is to be a source vertex σ , another named \mathcal{A}_i

for each $i = 1, 2, \dots, M$, another vertex named S for every subset $S \subseteq \{1, 2, \dots, \ell\}$, and a sink vertex τ . There is to be a directed edge from σ to each \mathcal{A}_i with capacity 1. There are to be directed edges from \mathcal{A}_i to the vertices corresponding to members of \mathcal{A}_i (use j edges to \emptyset , if \emptyset occurs j times in \mathcal{A}_i); these may have any integral capacity ≥ 1 . There is to be a directed edge from the vertex corresponding to a subset S to τ of capacity

$$\binom{n - \ell - 1}{k - |S| - 1}.$$



We exhibit a flow in this network: assign a flow value of 1 to the edges leaving σ , a flow value of $(k - |S|)/(n - \ell)$ to the edges from \mathcal{A}_i to each of its members S , and a flow value of $\binom{n - \ell - 1}{k - |S| - 1}$ to the edge from S to τ . This is easily checked to be a flow: the sum of the values on edges leaving a vertex \mathcal{A}_i is

$$\sum_{S \in \mathcal{A}_i} \frac{k - |S|}{n - \ell} = \frac{1}{n - \ell} \left(mk - \sum_{S \in \mathcal{A}_i} |S| \right) = \frac{1}{n - \ell} (mk - \ell) = 1.$$

The sum of the values on the edges into a vertex S is

$$\sum_{i: S \in \mathcal{A}_i} \frac{k - |S|}{n - \ell} = \frac{k - |S|}{n - \ell} \binom{n - \ell}{k - |S|} = \binom{n - \ell - 1}{k - |S| - 1}.$$

Since all the edges leaving σ are saturated, this is a maximum flow and has strength M . The edges into τ are also saturated in this flow, and hence in any maximum flow.

By Theorem 7.2, this network admits an *integral*-valued maximum flow f . All edges leaving σ will be saturated, so it is clear that for each i , f assigns the value 1 to one of the edges leaving \mathcal{A}_i and 0 to all others. Say f assigns 1 to the edge from \mathcal{A}_i to its member S_i . For each subset S , the number of values of i such that $S_i = S$ is $\binom{n-\ell-1}{k-|S|-1}$.

(The desired integral flow f could also have been obtained without explicitly introducing capacities and using Theorem 7.2, but simply by applying Theorem 7.4 to the exhibited rational flow completed to a circulation with the aid of an extra edge from τ to σ with flow value M .)

Finally, we obtain a set of m -partitions $\mathcal{A}'_1, \dots, \mathcal{A}'_M$ of the set $\{1, 2, \dots, \ell + 1\}$ by letting \mathcal{A}'_i be obtained from \mathcal{A}_i by replacing the distinguished member S_i by $S_i \cup \{\ell + 1\}$, $i = 1, \dots, M$. Readers should check that each subset T of $\{1, 2, \dots, \ell + 1\}$ occurs exactly

$$\binom{n - (\ell + 1)}{k - |T|}$$

times among $\mathcal{A}'_1, \dots, \mathcal{A}'_M$. This completes the induction step. \square

Problem 38A. Let v and u be integers with $v \geq 2u$ and v even, and consider the complete graph K_u as a subgraph of K_v . Suppose the edges of K_u are colored with $v-1$ colors so that distinct edges of the same color are disjoint. Show that this coloring can be extended to a coloring of $E(K_v)$ with $v-1$ colors so that edges of the same color are disjoint. (Such a coloring of $E(K_v)$ is equivalent to a 1-factorization of K_v , with the edges of any given color forming a 1-factor.)

Notes.

Zsolt Baranyai (1948–1978) was a Hungarian mathematician who was also a professional recorder player. He toured Hungary with the *Barkfark Consort* giving concerts and died in a car accident on a country road after one of them. His mathematical work included many other wonderful results on ‘complete uniform hypergraphs’.

One-factorizations of complete graphs are related to symmetric Latin squares—see Chapter 17. The result of Problem 38A is due

to Cruse (1974). Generalizations may be found in Baranyai and Brouwer (1977).

References.

- Zs. Baranyai and A. E. Brouwer (1977), Extension of colourings of the edges of a complete (uniform hyper) graph, *Math. Centrum Dep. Pure Math. ZW.* **91**, 10 pp.
- A. E. Brouwer and A. Schrijver (1979), Uniform hypergraphs, in: A. Schrijver (ed.), *Packing and Covering in Combinatorics*, Mathematical Centre Tracts **106**, Amsterdam.
- A. Cruse (1974), On embedding incomplete symmetric Latin squares, *J. Combinatorial Theory (A)* **16**, 18–22.
- E. N. Gelling (1973), On 1-factorizations of the complete graph and the relationship to round robin schedules, M.Sc. Thesis, University of Victoria.
- E. Mendelsohn and A. Rosa (1985), One-factorizations of the complete graph—a survey, *Journal of Graph Theory* **9**.
- R. Pelsesohn (1936), *Das Turnierproblem für Spiele zu je dreien*, Dissertation Berlin, August Pries, Leipzig.

Appendix 1

Hints and comments on problems

Problem 1A. Show that the $\binom{5}{2}$ pairs from $\{1, \dots, 5\}$ can be used to label the vertices in such a way that a simple rule determines when there is an edge. To find the full automorphism group, consider the subgroup that fixes a vertex and its three neighbors. This graph is known as the *Petersen graph*. It was first studied by the Danish mathematician J. P. C. Petersen (1839–1910). See also Chapter 21.

Problem 1B. Let the vertex set V be the disjoint union of V_1 and V_2 , with no edges from V_1 to V_2 . What is the maximum number of edges possible?

Problem 1C. Use (1.1). (i) Consider a vertex of degree 1; use induction. (ii) A circuit has as many edges as vertices; if the graph is connected, every vertex has degree ≥ 1 .

Problem 1D. Call the vertices a_1, a_2, a_3 and b_1, b_2, b_3 . First, omit a_3 and show that there is only one way to draw the graph with the remaining six edges in the plane. A better way is to use Euler's formula (see Chapter 33).

Problem 1E. Each color occurs an even number of times in a circuit. See J. A. Bondy, Induced subsets, *J. Combinatorial Theory* (B) **12** (1972), 201–202. The problem can also be formulated as follows. Given a square $(0, 1)$ -matrix with distinct rows, it is possible to delete a column so that the resulting matrix has distinct rows. This fact can also easily be proved by induction.

Problem 1F. Consider the vertices at distance 2 from a fixed

vertex. See Fig. 1.4.

Problem 1G. Use the pigeonhole principle.

Problem 1H. Consider when $a_{ij} = a_{jk} = 1$.

Problem 1I. Find an inductive procedure for constructing the required circuit.

Problem 1J. For (i), establish a one-to-one correspondence between the vertices adjacent to x and those adjacent to y .

Problem 2B. Any ordering of 22335 works.

Problem 2C. Let A_i be the number of spanning arborescences with x_i as root and denote by r_i the number of edges out of x_i . The assertion can be proved by showing that the number of *different* Eulerian circuits in G is

$$A_i \prod_{j=1}^n (r_j - 1)!.$$

To do this, take $i = 1$ and consider some spanning arborescence with x_1 as root. Fix some edge out of x_1 as the first edge of an Eulerian circuit. Number the other edges out of x_1 arbitrarily. For $i = 2, 3, \dots, n$, number the edges out of x_i arbitrarily but such that the edge of the spanning arborescence has number r_i . This numbering leads in a natural way to the construction of an Eulerian circuit and this process can be reversed. See Chapter 9 of J. H. van Lint, *Combinatorial Theory Seminar Eindhoven University of Technology*, Lecture Notes in Mathematics **382**, Springer-Verlag, 1974.

Problem 2D. One approach is as follows. Show that T_n has the property that for each of its edges a , a has ends in different components of $G : \{e \in E(G) : c(e) < c(a)\}$. Then show that any spanning tree T with this property is a cheapest spanning tree.

Problem 2E. There is only one way to obtain the difference $n - 1$, etc.

Problem 2F. Use Problem 1C.

Problem 2G. Show that if G is a graph with this property, there is a graph G' with the same property, the same number of edges,

and in which the vertex of degree m is connected to all other vertices with degree > 1 . Then use induction ($m \rightarrow m + 2$). The construction can be done inductively by the same idea.

Problem 3A. For part (ii), if the conclusion fails, then H can be written as the union of two edge-disjoint subgraphs A, B which intersect in two vertices s, t . Apply the induction hypothesis to graphs A', B' obtained by adding an edge joining s, t to A, B , respectively.

Problem 3B. It is possible to use the same type of argument as given for K_6 (below this problem). Show that there must be a vertex that is in two monochromatic triangles. Then, argue on the remaining six vertices. The argument will be long and tricky. The reader who has cheated and has read on, knows the Corollary to Theorem 3.2.

Problem 3C. Call the terms, both even, on the right-hand side n_1 and n_2 . Suppose equality holds and consider a graph with $n_1 + n_2 - 1$ vertices. If there is no red K_p and no blue K_q , what is the red-degree of any vertex? How many red edges are there in this graph?

Problem 3D. In \mathbb{Z}_{17} consider $\pm 2^i$, with $i = 0, 1, 2, 3$. For the other problem use \mathbb{Z}_{13} . Apply (3.4).

Problem 3E. (a) Fix a vertex and consider all edges to, respectively from, this vertex. Pick the larger set and use induction.

(b) Use the probabilistic method. A solution can be found in Theorem 1.1 of P. Erdős and J. Spencer (1974), where this problem is used to illustrate the method.

Problem 3F. Take as vertices $\{1, 2, \dots, n\}$. Color $\{i, j\}$ with the color of $|i - j|$. To avoid a triple for two colors, if 1 is red, then 2 must be blue and hence 4 must be red, etc. $N(2) = 5$. Separate two such 2-colored configurations by five numbers with a third color to estimate $N(13)$. See I. Schur, Über die Kongruenz $x^m + y^m \equiv z^m \pmod{p}$, *Jber. Deutsche Math. Ver.* **25** (1916), 114–116.

Problem 3G. Color with four ‘colors’ as follows:

$$\{i, j\} \mapsto (a_{ij}, a_{ji}) \quad (i < j).$$

Problem 3H. Use the argument that was used for K_6 and two colors.

Problem 3I. Let the color depend on $\nu \pmod{3}$. Show that the sum of two cubes in \mathbb{F}_{16}^* is not a cube.

Problem 3J. Consider a maximal subgraph with the required property and then count the vertices not in that subgraph.

Problem 3K. Consider vertices of a fixed color and delete edges in such a way that recoloring is possible.

Problem 4A. (i) Color K_{10} in such a way that red corresponds to an edge of G , blue to a nonedge. There are triangles with 3 red edges, 2 red and 1 blue, 2 blue and 1 red, and finally with 3 blue edges. Let a_i ($i = 1, 2, 3, 4$) be the numbers of these. Set up a system of equations and inequalities for these numbers, expressed in the degrees of the vertices of G . These should show that there are at least four triangles in G and equality can then be excluded, again by looking at the equations.

(ii) A second solution is as follows. Show there is a triangle. Then consider a triangle, the aryl 7-set, and edges in between. This gives a number of new triangles of two types; estimate it.

Problem 4B. Use induction. First review the proof of Theorem 4.1.

Problem 4C. The number of triangles on an edge a with ends x and y is at least $\deg(x) + \deg(y) - n$. Sum this over all edges a .

Problem 4D. Fix any vertex x and let D_i denote the set of vertices at distance i from x in G .

For $g = 2t + 1$, $|V(G)| \geq 1 + r + r(r - 1) + \cdots + r(r - 1)^{t-1}$ since it is easy to see that $|D_i| = r(r - 1)^{i-1}$ for $i = 1, 2, \dots, t$.

For $g = 2t$, we still have $|D_i| = r(r - 1)^{i-1}$ for $i = 1, 2, \dots, t - 1$. We can also get a lower bound $|D_t| \geq \frac{r-1}{r}D_{t-1}$ since each vertex $y \in D_{t-1}$ is adjacent to $r - 1$ vertices in D_t while a vertex $y \in D_t$ can of course be adjacent to at most r vertices in D_{t-1} .

Problem 4E. The graph is bipartite.

Problem 4F. By Theorem 4.3, there exists a Hamiltonian circuit H . Assume that H does not contain an edge e with ends x and y .

Let x' , respectively y' , be the successors of x , respectively y , on H . Consider the path P from x' to y along H , then along $\{y, x\}$, and from x to y' along H in the reverse direction. If the edge $\{x', y'\}$ is in G , we are done. If not, argue as in the proof of Theorem 4.3 to show that P can be completed to a circuit by removing one edge and adding two others.

For a further generalization, see L. Lovász (1979).

Problem 4G. Show that the maximum value of S occurs when $z_i > 0$ only on points of a clique.

Problem 4H. Count pairs of edges with a common vertex in two ways.

Problem 5A. (i) Given $A \subseteq X$, one side of a bipartition, count the number of edges that have one end in A and the other in $\Gamma(A)$.

(ii) A trivalent graph with no perfect matching is the graph on four vertices and six edges with one vertex incident with three non-loops and loops incident with the other three vertices. Replace the loops by appropriate simple graphs.

(iii) Same hint as for part (i).

Problem 5B. Construct a sequence of sets A_i of size m_i using new elements only when it is necessary to keep condition H satisfied. A solution is given on p. 41 of Van Lint (1974).

Problem 5C. Use induction on the number of nonzero entries of the matrix. The argument of Theorem 5.5 can be used similarly.

Problem 5D. Theorem 5.5.

Problem 5E. Express the number of SDR's with 1, respectively 2, representing A_1 in terms of S_i with $i < n$. See Problem 14A.

Problem 5F. Count the number of sets $\{x_1, x_2, \dots, x_n\}$ with $x_k \in A_k$ for all k and with $x_i = x_j$.

Problem 5G. (i) is easy but (ii) gets messier. Consult Example 10.1

Problem 6A. Define a poset using both the index and the size of the integers a_i .

Problem 6B. (i) Consider A and \bar{A} . (ii) Let x be in all the sets.

Problem 6C. Show that large sets can be replaced by their complements, and apply Theorem 6.5.

Problem 6D. (i) No two of the subsets are in the same chain. (ii) Use induction.

Problem 6E. See C. Greene and D. Kleitman, Strong versions of Sperner's Theorem, *J. Combinatorial Theory (A)* **20** (1976), 80–88.

Problem 7A. This is a straightforward application of the algorithm. The minimum cut capacity is 20.

Problem 7B. Given a flow f with nonzero strength, show that the edges e with $f(e) \neq 0$ contain the edges of a simple directed path from s to t . Subtract a scalar multiple of the corresponding elementary flow to obtain a flow f' which vanishes on more edges than f and proceed by induction.

Four vertices suffice for the required example.

Problem 7C. Consider a maximum flow f . From Equation (7.1), edges from X_i to Y_i are saturated and edges from Y_i to X_i have zero flow value.

Problem 7D. Given the bipartite graph G with vertices $X \cup Y$, construct a network by adding two vertices s and t , edges directed from s to elements of X of capacity 1, and edges directed from elements of Y to t of capacity 1. Direct all original edges from X to Y ; it is convenient to assign them a large capacity, say $|X| + 1$, so that no such edges are present in a minimum cut. Explain why there exists a complete matching from X to Y in G if and only if this network has maximum flow strength $|X|$.

Problem 7E. For (iv), apply Theorem 7.2, with $d = 2$, to the incidence matrix of the graph. (This result is also a quick consequence of Theorem 1.2.) For (v), consider the *bipartite incidence matrix* M of a bipartite graph G , which is defined as follows. Say G has bipartition (X, Y) . The rows of M are indexed by the vertices in X , and the columns of M are indexed by the vertices in Y . The entry in row $x \in X$ and column $y \in Y$ is the number of edges joining x and y (0 or 1 if G is a simple graph).

Problem 7F. Let T be a spanning tree in D . Show that for any assignment of real numbers to the $|E(D)| - |V(D)| + 1$ edges of D not in T , there is a unique way to extend this to a circulation f on D . It may be useful to remember that a tree with at least one edge has a monovalent vertex.

Problem 8A. Assume that some subsequence of n consecutive elements occurs twice. Show that α satisfies an equation of degree less than n .

Problem 8B. The vertices of the digraph are the ordered pairs from $\{0, 1, 2\}$; the edges are the 27 ordered triples.

Problem 8C. The sequence must contain four 0's and four 1's. Three consecutive 0's force 00010111 which does not work; the pair 00 must occur twice and this then forces 00110011 which does not work either.

Problem 8D. Since every vertex in G_n has indegree 2 and outdegree 2, we do get a closed path from $00\dots 0$ to $00\dots 0$. The final edge must come from $10\dots 0$ (which we identify with the integer 1 in binary). The fact that this edge is used implies that the edge from $1 = 10\dots 0$ to $0\dots 01$ has already been used. So, we came into the vertex 1 twice, i. e. from $2 = 010\dots 0$ and from $3 = 110\dots 0$. For the same reason as above, both 2 and 3 were entered twice. Proceeding by induction, we see that all vertices were visited twice on the path through G_n , proving the assertion.

Problem 9A. Apply the algorithm.

Problem 9B. A trivial addressing of length n as in Theorem 9.2 is easily found. What is the diameter of the graph?

Problem 9C. Use Theorems 9.1 and 9.6. Somewhere in the calculation $\sum k \cos(kx)$ will appear. This is the derivative of $\sum \sin(kx)$ and that sum is determined by multiplying by $\sin(\frac{1}{2}x)$.

Problem 9D. See Theorem 9.7.4.

Problem 10A. Use Theorem 10.1, where E_i ($i = 1, 2, 3, 4$) are the integers ≤ 1000 divisible by 2,3,5,7, respectively.

Problem 10B. Use inclusion-exclusion and the fact that if $f(i) = 0$, then $(x - i)$ divides $f(x)$.

Problem 10C. Use $[x] = \sum_{k \leq x} 1$ and Theorem 10.3.

Problem 10D. Multiply $\sum a_n n^{-s}$ and $\sum b_m m^{-s}$. Determine the coefficient of k^{-s} , and use Theorem 10.3.

Problem 10E. Determine $\sum_{d|n} \log f_d(z)$; use Theorem 10.3 or 10.4.

Problem 10F. There are clearly $2n + 1$ colorings. Use inclusion-exclusion where a set E_i consists of colorings with i red and $i - 1$ blue. To determine N_j , use Example 10.6.

For a direct solution, calculate

$$\sum_{n=0}^{\infty} \sum_{k=0}^n (-1)^k \binom{2n-k}{k} 2^{2n-2k} x^{2n}.$$

To do this, use (10.6) and the fact that $\sum (2n + 1)x^{2n} = (\frac{x}{1-x^2})'$.

Problem 10G. Use Theorem 10.1.

Problem 10H. Count permutations of $1, 2, \dots, n$ that fix none of $1, 2, \dots, n - k$.

Problem 11A. Consider an all-one matrix of size n by k . Adjoin a column of 0's and then complete to a square matrix by adding rows of type $(0, \dots, 0, 1)$.

Problem 11B. (i) Theorem 5.3; (ii) Theorem 11.5; (iii) use a direct product of matrices J_k .

Problem 11C. Determine $A = (a_{ij})$ with $a_{ij} = |A_i \cap B_j|$. To find the permanent of this matrix, compare with the *problème des ménages*.

Problem 11D. Use Theorem 11.7.

Problem 11E. Calculate the corresponding permanent B_n by expanding by the first row and column. Show that $B_n = B_{n-1} +$

$B_{n-2} - 2$. So $\{B_n - 2 \mid n \geq 3\}$ is a Fibonacci sequence. Also see Problem 5E.

Problem 12A. Use Theorem 12.1.

Problem 12B. Suppose AA^\top is decomposable. Explain the block of 0 entries by considering some row of A , its nonzero entries, and the inner products with other rows.

Problem 12C. Do four averaging operations on pairs of rows and similarly for columns. Note that the element a_{55} does not change during these operations. Determine the permanent and minimize. This shows that the matrix was $\frac{1}{5}J$ from the start.

Problem 13A. Use Theorem 13.1.

Problem 13B. (i) Multiply two powers of $(1 - x)$. (ii) Let k be in position $a + 1$; what can precede this term?

Problem 13C. (i) Choose A_1 and then choose A_2 as a subset of its complement; determine the sum of products of binomial coefficients. (ii) Consider a 2 by n matrix for which the rows are the characteristic functions of A_1 , respectively A_2 . Translate the condition on A_1 and A_2 to a condition on this matrix.

Problem 13D. First, fix the union U of the sets in \mathcal{A} . Apply Example 13.6 and then sum over all choices of U . The answer shows that we could have found a better solution. To find this better solution, again depict \mathcal{A} by a (0,1)-matrix of size k by n . To this matrix adjoin a ‘special’ row, namely the characteristic function of the union of the sets of \mathcal{A} . Calculate the number of these (0,1)-matrices that have a 1 in a specified position in their ‘special’ row.

Problem 13E. In each path, consider the *last* step of type $(x, y) \rightarrow (x + 1, y + 1)$. Use Theorem 13.1. For the last question, insert k balls into $n + k$ possible positions; let x_k be the length of the interval preceding the k -th ball.

Problem 13F. (i) Prove by induction. If a permutation of 1 to $n - 1$ is written as a product of cycles, there are n ways to adjoin

the element n , one of which has one more cycle. (ii) In Theorem 13.7, sum both sides over k ; use (13.5).

Problem 13G. Insert (13.13) into (13.11) and change the order of summation.

Problem 13H. Use (10.6).

Problem 13I. Use the relation $F(a) = G(a)$ of page 123.

Problem 13J. Use the binomial formula with $x = \zeta$, where $\zeta^3 = 1$.

Problem 13K. Count partitions of an n -set into $n - 2$ parts directly.

Problem 14A. (i) The sequences end in 10 or in 1. Establish the Fibonacci recursion and solve by trying $a_n = t^n$ as a solution (use linearity). The method of Example 14.3 also can be used.

(ii) Express b_n in terms of the numbers c_n of such sequences ending in a 1. Find a recurrence for c_n . The constant c will be the largest root of a polynomial equation of degree 4; it is approximately 1.22075.

Problem 14B. Consider a trivalent planted plane tree T . Make a new tree T' as follows. Take as vertices the root of T and all its vertices of degree 3. Join two vertices in T' if there is a path from one to the other in T using exactly one edge with slope to the left (see Figure 14.3). Finally, add a new root at the bottom. Show how to reverse this mapping. Show that the number of vertices of T' equals the number of vertices of degree 1 in T . See p. 25. of J. H. van Lint *Combinatorial Theory Seminar, Eindhoven University of Technology*, Lecture Notes in Mathematics **382**, Springer-Verlag, 1974.

Problem 14C. Fix one edge; number others cyclicly: a, b, c, \dots . Give the chords the obvious names; be careful about the order in which these names are given. See also p. 25. of Van Lint (1974), *ibid.*

Problem 14D. Use the method of Fig. 2.2. One fixed point produces an arborescence; the remainder is a mapping with no fixed points. See (14.15). Take $M_1(0) = 1$, $A(0) = 0$.

Problem 14E. Fix an edge and then consider the quadrilateral that it belongs to. The other three sides divide the $(n+1)$ -gon into possibly empty polygons; see (14.10). Solve $f = x + f^3$ by applying Theorem 14.3.

A combinatorial proof that the number of ways of dividing an $(n+1)$ -gon into quadrangles by nonintersecting diagonals is 0 if n is even, and $\frac{1}{3k+1} \binom{3k+1}{k}$ if $n = 2k+1$, can be given as follows. Since the case of even n is trivial, we assume $n = 2k+1$. There are $k-1$ diagonals and k quadrangles in the dissection. Put a vertex in each quadrangle and on each edge; fix one edge-vertex as a root. Vertices of quadrangles are joined by an edge if the quadrangles share a diagonal; an edge-vertex is joined to the quadrangle-vertex of its quadrangle. Describe a walk around the tree, that was just defined, by a sequence of symbols x and y , where we use an x every time we reach a quadrangle vertex not visited before, and similarly a y for edge-vertices. We find a sequence of k symbols x and $2k+1$ symbols y . We know, see Example 10.6, that there are $\frac{1}{3k+1} \binom{3k+1}{k}$ circular sequences of this type. It remains to show a one-one correspondence between these circular sequences and the sequences describing the trees. Describe the x, y sequence as follows: an x corresponds to a step in the X - Y plane one unit to the right and one unit upwards; a y to a step one unit to the right and $k/(2k+1)$ steps downward. The walk starts in $(0,0)$ and ends in $(3k+1, 0)$, never meeting the X -axis in between. If we describe a circular sequence of the given type in the same way, it will have a *unique* minimum because $(k, 2k+1) = 1$. This will give us the unique starting point to make it correspond to one of the trees.

Problem 14F. See Appendix 2 on formal operations. Take logarithms and use Theorem 10.3.

Problem 14G. Show equivalence with Example 14.11.

Problem 14H. Make a path as in Example 14.8 and find a lowest point.

Problem 14I. (i) See (14.10). (ii) Put a vertex on the circle, say between 1 and $2n$. This will be the root of a tree. Put a vertex in each region and join vertices in the obvious way. Show equivalence with one of the Catalan problems. See Van Lint (1974), p.26.

Problem 14J. A labeled regular graph of valency 2 is a union of (labeled) polygons. Apply Theorem 14.2.

Problem 14K. Call the number of walks A_{4n} and define $A(z) := 1 + \sum_{n=1}^{\infty} A_{4n}z^{4n}$. If B_{2n} is the number of walks from $(0,0)$ to (n,n) that avoid points (i,i) , then we know from (14.12) that $B(z) := \sum_{n=1}^{\infty} B_{2n}z^{2n} = 1 - \sqrt{1 - 4z^2}$. Find a relation between $A(z)$ and $B(z)$ by considering the first crossing of $x = y$ for each walk.

It is also possible to prove the result by finding a one to one mapping from the walks counted by A_{4n} to the walks counted in Example 14.8. This is difficult. For a solution see the solution to Problem 3096 by W. Nichols in *American Mathematical Monthly* **94** (1987).

Problem 14L. Show that $a_n = 3a_{n-1} - a_{n-2}$ and that F_{2n} satisfies the same recurrence.

Problem 14M. For g with k fixed points, count their number and the number of appropriate f and sum over k ; for f with image of size i , split $\{1, 2, \dots, r\}$ into preimages, count the f and the number of appropriate g ; sum over i . Use (13.9) and (13.11). This is the solution to Problem 3057 of the *American Mathematical Monthly* **94** (1988), given by J. M. Freeman, S. C. Locke, and H. Niederhausen.

Problem 14N. Introduce $b_{k,n} :=$ the number of walks from $(0,0)$ to (n,n) that meet the line $x = y$ for the second time in (k,k) .

Problem 15A. Distinguish between $x_k = 1$ and $x_k > 1$, in which case take $y_i = x_i - 1$. Use induction.

Problem 15B. Let E , I , and S denote the number of equilateral, isosceles, and scalene triangles, respectively. Calculate E , $I + E$, and express $\binom{n}{3}$ in E , I , and S .

(This proof is due to J. S. Frame, *Amer. Math. Monthly* **47**, (1940), 664.)

Problem 15C. Use partial fractions. Find c using the coefficient of $(1-x)^{-t}$ and (10.6).

Problem 15D. Count the compositions of n into k parts which have a 3 in position j . Do this for all j and sum; (a composition with m parts 3 is thus counted m times).

A second solution with a more general result is as follows. First show that in a list of all possible compositions there are exactly $(n + 1) \cdot 2^{n-2}$ integers. This can be done using the argument with the red balls. Then prove by induction on n that for $1 \leq m < n$ a list of the 2^{n-1} compositions of n contains the integer m exactly $(n - m + 3)2^{n-m-2}$ times. For this, use the formula $1 + \sum_{k=1}^{n-1} (k + 3)2^{k-2} = (n + 1) \cdot 2^{n-2}$ which is also shown by induction.

Problem 15E. Leave out the first column.

Problem 15F. For the unequal odd parts, use ‘hook’ shaped figures to form a Ferrers diagram and read this in the usual way.

Problem 15G. Show a correspondence with Example 14.8.

Problem 15H. See Chapter 13.

Problem 15I. Generalize Theorem 15.4.

Problem 15J. Apply Theorem 15.10 to an $n \times n$ square.

Problem 16A. Use induction; compare two initial segments of \mathbf{r} and \mathbf{s} .

Problem 16B. Determine the first column of a matrix with row-sum \mathbf{r} and column-sum \mathbf{r}^* . Use induction.

Problem 16C. Use Problem 16A and switch edges. Another possibility is to describe the graph by its adjacency matrix and use the same idea as in the proof of Theorem 16.2.

Problem 16D. Estimate the number of solutions of $s_1 + \cdots + s_n = \frac{1}{2}n^2$ by just using the fact that each s_i is at most n .

Problem 16E. For the ‘if’ part, first note that there exists a tournament with degree sequence $(n - 1, \dots, 2, 1, 0)$. Then use Problem 16A. Show that if in a tournament the outdegree of x is greater than the outdegree of y , then there is a tournament on the same vertex set and with the same outdegrees except that outdegree of x is one less than it was originally, and the outdegree of y is 1 greater. One can do this by changing the directions on at most two edges.

Problem 16F. For the generalization, one considers the hypergraph given by choosing the first m of the k -subsets in lexicographical order. For the ‘if’ parts, again use Problem 16A.

Problem 16G. $A(5, 3) = A(5, 2)$. See (16.2). Counting directly is possible as follows: (i) Fix the first row as $(1, 1, 0, 0, 0)$; this means that the final result must be multiplied by 10. (ii) Put a 1 in position $(2,1)$; this means that we should also multiply by 4. (iii) Split into two cases: a 1 in position $(2,2)$, etc. or a 1 in position $(2,3)$, in which case a factor 3 is introduced, etc.

Another solution is obtained by observing that $\mathcal{A}^*(5, 2)$ has cardinality $\frac{1}{2}5!4! = 1440$, and that there are $\binom{5}{2}^2 \cdot 3! = 600$ decomposable matrices in $\mathcal{A}(5, 2)$.

Problem 16H. In case 1, there are $n - 1$ possible choices. In case 2, remove row 1 and column 1, substitute an element of $\mathcal{A}(n - 1, 2)$ and in two ways then produce an element of $\mathcal{A}(n, 2)$.

Problem 16I. Straightforward substitution.

Problem 17A. Index the first two rows by x and y , the first two columns by u and v , all under the assumption that we have the multiplication table of a group of order 5. Show that $(v^{-1}u)^2 = 1$.

Problem 17B. This is already difficult, despite the small size of the square! Take $a = 1$. Note that the 1 in the upper left-hand corner is in subsquares of type $\begin{pmatrix} 1 & i \\ i & 1 \end{pmatrix}$ for $i = 2, 3, 4, 5$. Consider any Latin square with this property. If the $(2,3)$ entry is not 4, then permuting rows 4 and 5, columns 4 and 5, and symbols 4 and 5, changes the square into an equivalent one with a 4 in position $(2,3)$. At this point, there is only one way to complete the square. So, if a Latin square has any cell with a property like the one we mentioned for the upper left hand 1, then it is equivalent to this one.

Using the same kind of argument one can show that there are only a few possibly inequivalent squares of order 5. For some, one then has to establish the equivalence, a tedious task.

Problem 17C. At this point, trial and error is prescribed. However, see Chapter 22.

Problem 17D. Sufficiency is shown by an example (you can, but do not have to, use Theorem 17.1). For necessity, observe that just

appending one more column to a Latin square of order m requires m new symbols.

Problem 17E. Apply the algorithm.

Problem 17F. For part (i), describe an algorithm that recovers the original Latin square of order n from the constructed Latin square of order $n + 1$ with constant back diagonal. For (ii), explain why the number of Latin squares of order n with n 's on the back diagonal is equal to $N(n)/n!$.

Problem 17G. (a) For $n = 6$, an example is 6, 1, 5, 2, 4, 3.

(b) Add the differences.

(c) Assume two pairs are equal and solve.

Problem 17H. Start by replacing the diagonal entries of the smaller square by $(n + 1)$'s.

Problem 17I. See Example 10.6.

Problem 17J. (i) Use inclusion exclusion. If k integers are in the wrong place, write $k = 2i + j$ where there are i pairs in the wrong place, etc.

(ii) Use $J - I$ of size n .

Problem 18A. To show this directly, argue as in Theorem 18.1 concerning the first three rows. Show that no further row can start with three $+1$'s. Hence, rows 5, 6, and 7 all start with $++-$ (why?). These can then be completed in a unique way, etc. For another solution, see Problem 19D.

Problem 18B. Use the method of Theorem 18.1. Note that a permutation of rows and columns, that preserves the 0-diagonal, does not help us to make a matrix symmetric or antisymmetric. So, only multiplications by -1 will do the job. Normalize the first row and make the first column (except for the 0th entry) all 1 or all -1 . It is now sufficient to show that the (2,3) entry and the (3,2) entry are the same, respectively opposites, whenever $n \equiv 2 \pmod{4}$, respectively $n \equiv 0 \pmod{4}$.

Problem 18C. A trivial exercise!

Problem 18D. We have $28 = 1 + 9 + 9 + 9$ and $28 = 1 + 1 + 1 + 25$. Use the first of these. Note that each W_i has 1 on the diagonal

and if it has $w_{ij} = 2$, then $w_{7-i,j}$ is also 2; similarly for -2 . The observation about occurrences of the U^i in the matrices W_j then completely forces the choice of the four matrices W_i . They prove to work.

Problem 18E. Show by induction that $M_n^{(i)} \dots M_n^{(m)} = \mathbf{H}_{2^{m-i+1}} \otimes I_{2^{i-1}}$. For the second part, count the number of non-zero elements of $M_n^{(i)}$. See the reference E. C. Posner (1968).

Problem 18F. For both questions use induction.

Problem 18G. For (2), show that the number of rows with first coordinate 0 (or 1) is at most n .

Problem 18H. Straightforward; see Theorem 18.4.

Problem 18I. Review the properties of Q .

Problem 19A. For the isomorphism in part (i): Label the vertices of K_6 with 0000, 1000, 0100, 0010, 0001, 1111 in \mathbb{F}_2^4 and label an edge with the sum in \mathbb{F}_2^4 of the labels on its ends. This gives a one-to-one correspondence between the edges of K_6 and the 15 nonzero vectors in \mathbb{F}_2^4 .

For part (ii), consider configurations consisting of three edges (there are four types). The construction is due to E. S. Kramer (1990), *Discrete Math.* **81**, 223–224.

Problem 19B. Calculate b_i , $i = 3, 2, 1, 0$; $b_1 \notin \mathbb{Z}$.

Problem 19C. This is Theorem 19.4.

Problem 19D. (i) Let N have column-sums c_i . Then $\sum c_i = 66$. The sum of all inner products of rows is $\sum \binom{c_i}{2}$. Use the Cauchy-Schwarz inequality. Conclude that all column-sums are 6 and all inner products are 3. (ii) To show uniqueness, consider the complement: a 2-(11,5,2) design. Without loss of generality, the first row is (1111100000); the remaining ten rows start with the $\binom{5}{2}$ pairs (110...), (1010...), etc. Then show that the rows 2 to 5 can be completed in one way. This leaves a 6 by 6 square to be completed. At first sight, there seem to be two ways to do this. Find a permutation that maps one into the other.

Problem 19E. Denote by a_i the number of blocks that meet B in i points. Calculate $\sum a_i$, $\sum ia_i$, and $\sum \binom{i}{2}a_i$. Derive an inequality for a_0 using the form $\sum (i - c)^2 a_i$. Compare with Theorem 19.9.

Problem 19F. The mapping $x \mapsto 2x$ has six orbits, two of which are too long to use (e.g. $(1,2,4,8,16,11)$). See Example 28.2.

Problem 19G. Use the corresponding orthogonal array. Use the common $\{0, 1\}$ to $\{1, -1\}$ mapping.

Problem 19H. For (1) use (19.2) or (19.4). For (3) count pairs $p, q \notin B$ that are contained in blocks that meet p . Thus find the parameters of \mathcal{D}^B . For (4), first suppose that \mathcal{D}^B is a single block. Consider Example 19.3. In the other case Fisher's inequality yields $k \geq (\lambda + 1)(\lambda + 2)$. Now, express b_0 as a fraction in k and λ and deduce that k must divide $2(\lambda + 1)(\lambda + 2)$.

Problem 19I. (i) Fix a point x on O . Count pairs (y, L) , $y \in O$, L a line through x and y . (ii) From (i) we see that if $|O| = n + 2$, then every line that meets O , meets it twice. Take a point $z \notin O$ and count the lines through z that meet O . (iii) Take any four points, no three on a line. These determine six lines, that together contain 19 points of the plane.

Problem 19J. For p_1 to p_5 take $(1,0,0)$, $(0,1,0)$, $(0,0,1)$, $(1,1,1)$ and $(1, t, t^2)$ and show that there are two ways to group these to produce $p_6 = (1, x, x^2)$, where $x = t/(1 + t)$.

Problem 19K. Let $B_1 \sim B_2$. How many blocks meet B_1 ? Take $x \in B_1$, $y \in B_2$; how many blocks meet both B_1 and B_2 ? There are $n + 1$ equivalence classes, each with n lines (blocks). To each class append a point that is to be added as an extra point to each line of that class, etc.

Problem 19L. Use Theorem 19.11. Consider the equation modulo 3.

Problem 19M. For v even, use quadratic forms, as in the proof of Theorem 19.11. See J. H. van Lint and J. J. Seidel (1966), Equilateral point sets in elliptic geometry, *Proc. Kon. Nederl. Akad. Wetensch.* **69**, 335–348.

Problem 19N. (a) The method of Example 19.14 also works if $|V| = 1$; ($85 = 7(13 - 1) + 1$). (b) $15 = 7(3 - 1) + 1$.

Problem 19O. Consider the $n \times b$ incidence matrix N , where $b = |\mathcal{A}|$. Check that in case (i), $N^\top N$ is nonsingular modulo 2. For part (ii), let N_1 be obtained by adding column of all 1's to N , and show that $N_1^\top N_1$ has rank at least b modulo 2.

Problem 19P. The last of the displayed sums should evaluate to zero. This implies each μ_i is 1 or 2.

Problem 19Q. Use induction; start the induction with $t = 2$. Count, in two ways, ordered triples (x, A, B) where A and B are distinct blocks, both of which contain the point x .

Problem 19R. Represent lines as in Example 19.6 and use the fact that this is a cyclic representation. Distinguish different cases by the number of 'first' elements used in the SDR.

Problem 19S. It is possible to give a construction using induction on k , but it is quicker to give a direct construction using \mathbb{F}_2^k as the point set. Review Example 19.1.

Problem 19T. Use the result of Problem 19H. The extensions will appear in Chapter 20.

Problem 19U. Apply Theorem 5.5.

Problem 20A. Use (20.5).

Problem 20B. Apply the pigeonhole principle to the last two bits of the words. A binary code with three words is easily handled!

Problem 20C. For each of the three ways in which the conditions for a codeword can be violated, change a suitable coordinate to remedy the situation.

Problem 20D. (i) The rows of the generator matrix correspond to $\pm \mathbf{a}_i$, $i = 1, \dots, n$, where the \mathbf{a}_i are the rows of a Hadamard matrix. Let $\mathbf{u} \in \mathbb{F}_2^n$, where $n = 2^{2k}$. By \mathbf{u}^* we denote the ± 1 representation. Calculate $\sum \langle \mathbf{u}^*, \mathbf{a}_i \rangle^2$ to find the upper bound.

(ii) For equality, first find the weight of \mathbf{z} . Then use the fact that the codewords correspond to linear functions and adding a linear function to \mathbf{x} yields an equivalent quadratic form.

Problem 20E. (i) See Problem 20A. (ii) Count words of weight 5 ‘covered’ by codewords of weight 7; the other words of weight 5 are covered by codewords of weight 8. Using this idea, set up a system of linear equations for the A_i .

Problem 20F. A codeword at distance $\leq e$ from a word of weight $e + 1$ must have weight $2e + 1$.

Problem 20G. The codewords in the dual of the binary Hamming code of length $2^r - 1$ may be identified with linear functionals on \mathbb{F}_2^r (cf. the geometric description of Reed-Muller codes in Chapter 18); each nonzero codeword has weight 2^{r-1} .

Problem 20H. Use (19.6) and the fact that G_{24} is linear and has minimum weight 8; note that there are $\binom{21}{2}$ pairs of lines. If $\alpha = 1$, consider the 7-point configuration B^* in the plane. Any line that meets B^* must meet it in 1 point or in 3 points. How many meet B^* in 3 points?

Problem 20I. (i) Find the standard generator matrix for C . (ii) The conditions (1) and (2) clearly define a linear code. In (1) we have two choices for parity; in (2) we have 4^3 choices for the codeword; in five of the columns of A we then have two possibilities (not in the last one!). For the choice ‘even’, it is clear that a nonzero codeword in C forces weight ≥ 8 ; $\mathbf{0}$ has to be treated separately. For the choice ‘odd’, it is clear that we obtain a weight of at least 6; condition (1) ensures that equality cannot hold. For more on this wonderful description of the Golay code and many consequences see: J. H. Conway, The Golay codes and the Mathieu groups, Chapter 11 in J. H. Conway and N. J. A. Sloane, *Sphere Packings, Lattices and Groups*, Springer-Verlag, 1988.

Problem 20J. Self-duality is done as in Example 20.6. All weights in Sym_{12} are divisible by 3. Consider linear combinations of two rows of the generator matrix and then conclude what happens if we combine with a third row. Use (20.5).

Problem 20K. Prove the generalization by induction on r . For each r , find such a matrix none of whose columns is a constant vector. For the induction step, concatenate three copies of the matrix with r rows, to which have been appended a row of all 0’s,

all 1's, and all 2's, respectively, and then add three appropriate columns.

Problem 20L. The hint in the chapter should be sufficient.

Problem 21A. The argument is the same as for (21.4), now with inequalities.

Problem 21B. Use the integrality condition. Also see the reference A. J. Hoffman and R. R. Singleton (1960) from Chapter 4.

Problem 21C. Use (19.2); see Problem 20F. If two blocks are disjoint, count the number of blocks that meet both of them, each in two points. How many meet only one of them? Similar counting arguments (distinguish a few cases!) are used to show that $\mu = 6$.

Problem 21D. Suppose such a graph exists. Pick a vertex x and consider the sets $\Gamma(x)$ and $\Delta(x)$. We consider these as the points and blocks of a design. Show that this is a 2-(9,4,3) design. Next, fix a block of this design and let a_i be the number of blocks that meet this block in i points. Show that $a_0 \leq 1$ (see Problem 19E) and show that the fact that $\Delta(x)$ has degree 5 implies that a_0 should be at least 5.

Problem 21E. The first two questions are straightforward. For the third we refer to textbooks on matrix theory (see 'interlacing') or to Chapter 31. The theorem we are alluding to states that the eigenvalues of a principal submatrix B of a symmetric matrix A are bounded by the largest and the smallest eigenvalue of the matrix A . To prove this, just consider any vector \mathbf{x} and calculate $\mathbf{x}^\top A \mathbf{x} / \mathbf{x}^\top \mathbf{x}$. Specialize by letting \mathbf{x} be an eigenvector of B with 0's appended.

Problem 21F. Review the proof of Theorem 21.5. Show that $\Gamma(x) = \overline{K_{n-1, n-1}}$. Define a *grand clique* to be a clique of size n and show that any edge is in exactly one grand clique. Show that there are exactly $2n$ grand cliques, which fall into two classes of n so that grand cliques in the same class are disjoint. See S. S. Shrikhande, The uniqueness of the L_2 association scheme, *Ann. Math. Stat.* **30** (1959), 781–798.

Problem 21G. Count flags and other configurations, e.g. two intersecting lines and a point on one of them.

Problem 21H. See Problem 21E for v ; k is obvious. Take two points on line L . Points joined to both of them are on L or on one of the other $R - 1$ lines through one of them. A similar argument yields μ . For r and s see (21.6).

Problem 21I. On $\Gamma(x)$ use the fact that $\mu = 1$. Then consider $\{x\} \cup \Gamma(x)$.

Problem 21J. Eq. (21.8) leads to an equation like (21.6) with t instead of k . Although A is not symmetric the eigenvectors for eigenvalue $\neq k$ are orthogonal to \mathbf{j} .

Problem 21K. Show that if $(\lambda - \mu)^2 + 4(t - \mu)$ is not a square, then the eigenvalues have multiplicities $1, f$, and g , where $f = g = \frac{1}{2}(v - 1)$. Then show that $A = A^\top = J - I$ and $AA^\top = lJ + (l + 1)I$, where $v = 4l + 3$. Define $Q := A - A^\top$.

Problem 21L. Let $d := \sqrt{(\lambda - \mu)^2 + 4(t - \mu)}$. Apply (21.8) to \mathbf{j} and then show that d divides $(k - 1)^2$. Using $4k - 7 = d^2$, prove that d must divide 9.

For $v = 18$, use the matrix

$$\begin{pmatrix} cI & (c - 1)I + J \\ (\bar{c} - 1)I + J & \bar{c}I \end{pmatrix}$$

and replace c by the matrix C of Example 21.11 and d by C^2 to obtain a matrix A of size 18×18 .

Problem 21M. (i) Consider $\Gamma(x) \cap \Gamma(y)$ where (xy) is an edge.
(ii) Prove that \bar{G} is also neighborhood regular.

Problem 21N. (i) $\Gamma(x_1) = C \cup B$ is regular with degree a , so $|CB| = a|C| - |CC|$, etc.

(ii) Eliminate $|BC|$ and $|BD|$ from the relations in (i).

(iii) Interchange x_1 and x_2 . Use $d_1 \neq d_2$.

(iv) Express d_i in k_i , a , \bar{a} , and the number of vertices n of G . Then prove that $k_1 + k_2 = 2n - 3\bar{a} - a - 5$.

Problem 21O. Part (i) is straightforward. For example, $\lambda = (n + 3)/2$. (ii) If four triples of a clique C contain a point x , then all triples of the clique must contain x . (iii) If $n > 15$, the cliques

of size $(n - 1)/2$ in the graph of a triple system are in one-to-one correspondence with the points of the triple system.

Problem 21P. Equality would imply the existence of a $srg(a^2 + a + 1, a + 1, 1, 1)$. Use Theorem 21.1. Only $a = 1$ is possible and a K_3 obviously has no circuit on four vertices.

Problem 21Q. The graph G representing the friendship relation is either a union of triangles with one vertex common to all of them or G is regular. Use Theorem 21.1.

Problem 22A. Show, by computation, that the complement of the graph of an (n, n) -net has the parameters of the graph of an $(n, 1)$ -net. Then show that it *is* the graph of an $(n, 1)$ -net, i.e. there is a partition of the points into n sets of size n , no two points of which are collinear.

(More generally, an (n, r) -net may be completed to an $(n, n + 1)$ -net if and only if the complement of the graph of the (n, r) -net is the graph of an $(n, n + 1 - r)$ -net.)

Problem 22B. Use the constructions from fields described before the problem. Take $S(x, y) := (x + y)/2$ for q odd, for example.

For even q , we can use A and S to schedule mixed-doubles tennis matches. Suppose we have q couples—Mrs. i and Mr. i for $i \in \mathbb{F}_q$. Let Mrs. i and Mrs. j play against each other with respective partners Mr. $A(i, j)$ and Mr. $A(j, i)$ during round $S(i, j)$. There will be $q - 1$ rounds, labeled by the off-diagonal symbols in S , during which everyone is playing in exactly one match. It will be found that no one meets her or his spouse as partner or opponent the entire tournament, but meets everyone else exactly once as an opponent, and has everyone of the opposite sex exactly once as a partner. For q odd, we can have q rounds in which one couple sits out each round.

Problem 22C. Show that $m, m + 1, t$ and u each have the property that for each prime $p < x$, they are either prime to p or divisible by p^x .

Problem 22D. Review the connection between sets of pairwise orthogonal Latin squares and transversal designs.

Problem 22E. Use Theorem 22.6.

Problem 22F. Columns of A consist of integers between 1 and k . For every column of A and of S replace an integer i in the column of A by the i -th element in the column of S . By adding suitable columns and one row, complete to an $OA(v, c + 1)$.

Problem 22G. The proof is similar to the proof of Theorem 22.6. One now also needs a $(\mathcal{V}, \mathcal{K}, \mathcal{D})$, a $TD(v, k)$.

Problem 22H. Use Problem 22F.

Problem 22I. Use Problem 22G.

Problem 22J. Use Problem 22G.

Problem 23A. Note that the closure of a set S of edges consists of all edges that have both ends in the same connected component of the spanning subgraph of G with edge set S .

Problem 23B. The lines of $AG_r(2)$ have size 2.

Problem 23C. Dispose first of the cases when the union of two lines is the whole point set. Then show how to set up a one-to-one correspondence between the points of any two lines.

Problem 23D. The hardest part is showing that $\mathcal{F} = \{F_1 \cup F_2 : F_1 \in \mathcal{F}_1, F_2 \in \mathcal{F}_2\}$. Prove that $\overline{F_1 \cup F_2} = F_1 \cup F_2$ using the fact that the rank of $\overline{F_1 \cup F_2}$ is the sum of the ranks of F_1 and F_2 .

See H. Crapo and G.-C. Rota (1970) for a complete discussion of connectedness of combinatorial geometries and irreducibility of geometric lattices.

Problem 23E. Suppose $A \cap F = \emptyset$ and $\text{rank}(A) + \text{rank}(F) = \text{rank}(\overline{A \cup F})$. Show that these equations remain valid if A is replaced by $A' := \overline{A \cup \{x\}}$ where x is any point not in $\overline{A \cup F}$.

Problem 23F. Use (23.4).

Problem 23G. We may work in $PG_2(\mathbb{F})$ and assume without loss of generality that $L_1 = [1, 0, 0]$ and $L_2 = [0, 1, 0]$. Then (explain why) $a_1 = \langle 0, \alpha_1, 1 \rangle$, $b_1 = \langle 0, \beta_1, 1 \rangle$, and $c_1 = \langle 0, \gamma_1, 1 \rangle$, while $a_2 = \langle \alpha_2, 0, 1 \rangle$, $b_2 = \langle \beta_2, 0, 1 \rangle$, and $c_2 = \langle \gamma_2, 0, 1 \rangle$.

Problem 23H. See Chapter 13.

Problem 23I. Just use the definition of λ .

Problem 24A. See Chapter 13.

Problem 24B. One answer is $e_i = i(m - k + i)$. Consider k by $n + m$ matrices of rank k that are in echelon form. How many of these have i leading 1's in the first n columns?

Problem 24C. Check that x and y are contained in a coset of a subspace U if and only if $x - y$ is contained in U .

Problem 24D. Count all $n \times n$ matrices.

Problem 24E. See Theorem 6.4.

Problem 25A. For a subspace U of the r -dimensional space W , let $f(U)$ be the number of k -subspaces which intersect W in U . Use (25.5).

Problem 25B. For a subspace U , let $f(U)$ denote the number of nonsingular mappings whose set of fixed vectors is (exactly) U , and $h(U)$ the number of nonsingular linear mappings that fix (at least) the vectors in U . It is easy to give a formula for $h(U)$ in terms of n, q and the dimension of U . We require a formula for $f(\{\mathbf{0}\})$.

Problem 25C. Use (25.2) to calculate $\mu(0, x)$ for x of rank 1 or 2.

Problem 25D. There are only $n - 1$ partitions $x \neq 0_L$ (each consisting of one block of size 2 and $n - 2$ singletons) that satisfy $x \wedge a = 0_L$.

Problem 25E. For $x < z < y$ a chain of length k from x to z extends to a chain of length $k + 1$ from x to y .

Problem 25F. See Theorem 25.1 (iii). Count injective mappings from V to S and then vary $|S|$.

Problem 26A. The number of lines on a point x not in A which meet A is a constant, i.e. independent of x .

Problem 26B. Any line disjoint from the arc can be used to obtain a partition of the blocks into parallel classes, one parallel class for each point of the line.

Problem 26C. The point of intersection of the line through $\langle 1, 0, 0 \rangle$ and $\langle 0, 1, 0 \rangle$ and the line through $\langle 0, 0, 1 \rangle$ and $\langle 1, 1, 1 \rangle$, for example, is $\langle 1, 1, 0 \rangle$.

Problem 26D. Let μ_i be the cardinality of the intersection of the i -th line with S . The inequality is easy if some $\mu_i \geq \sqrt{n} + 1$, so assume otherwise and consider $\sum_i (\mu_i - 1)(\mu_i - \sqrt{n} - 1)$.

Problem 26E. Whether the characteristic is even or odd, f is degenerate if and only if $\mathbf{x}(C + C^\top) = 0$ for some \mathbf{x} with $f(\mathbf{x}) = 0$. To find such an \mathbf{x} when f is degenerate, take the last row of a nonsingular matrix A such that ACA^\top has a last row and column of all zeros, which exists because x_n , say, does not occur in some projectively equivalent form. Also see J. W. P. Hirschfeld (1979).

Problem 26F. By Theorem 26.6 with $q = 2$ and $n = 2m - 1$, nondegenerate quadratic forms in $2m$ variables have either $2^{2m-1} - 2^{m-1}$ or $2^{2m-1} + 2^{m-1}$ zeros, where we are counting the zero vector here. So the codewords (vectors of length 2^m) corresponding to such forms have weight $2^{2m-1} + 2^{m-1}$ or $2^{2m-1} - 2^{m-1}$. Since, as functions over \mathbb{F}_2 , $x_i^2 = x_i$, we may think of the polynomials $f(\mathbf{x}) + a(\mathbf{x})$ as quadratic forms, or their complements when there is a constant term 1. Show that all these forms are nondegenerate.

Alternatively, show that there is an ‘invertible affine substitution’ (where e.g. x_i may be replaced by $x_i + 1$) that takes $f(\mathbf{x}) + a(\mathbf{x})$ as a function on \mathbb{F}_2^{2m} , to $f(\mathbf{x})$ or $f(\mathbf{x}) + 1$.

Problem 26G. It is relatively straightforward to show that Q' is a nondegenerate quadric in W . There is nothing more to do if n is odd. Theorem 26.5 can be used to complete the proof for n even. It is easy to see that if Q' is hyperbolic, then so is Q . Next use equation (26.4) to show that every point p on a hyperbolic quadric Q in $PG_{n-1}(q)$ is contained in a flat $F \subseteq Q$ of projective dimension $n/2 - 1$. Check that such a flat is contained in T_p so that the flat $F \cap W \subseteq Q'$ has dimension one less than that of F .

Problem 26H. If point x is not on line ℓ , consider the plane determined by x and ℓ .

Problem 26I. The points of a triangle are on a line. For (iii) see Chapter 21.

Problem 26J. See the argument for arcs in projective planes.

Problem 26K. Consider three points. Let x_i be the number of blocks of the complementary design that contain i of these points. Use the usual counting argument to show that $x_0 + x_3 = \lambda$.

Problem 27A. It is not difficult to see that the even numbered items are equivalent to each other, and similarly for the odd numbered items. To show (3) and (4) are equivalent, for example, introduce an incidence matrix N and show that one is equivalent to the matrix equation $NN^T = (k - \lambda)I + \lambda J$, and the other to $N^T N = (k - \lambda)I + \lambda J$.

Problem 27B. View $(\mathbb{Z}_2)^4$ as a vector space over the field \mathbb{F}_2 . We may assume the difference set contains the zero vector. It will span $(\mathbb{Z}_2)^4$ and so contains a basis.

Problem 27C. Count separately the number of times a nonzero element of $G \times H$ can be written as a difference of two elements of $A \times (H \setminus B)$, a difference of two elements of $(G \setminus A) \times B$, and as a difference of one element of each of these sets.

Problem 27D. Multiply the sum of the elements, that we want to show is 0, by any square.

Problem 27E. We already said that this problem is similar to the illustrated calculation of λ_2 .

Problem 27F. Use Theorem 27.5. (A table of cyclic difference sets may be found in L. D. Baumert, *Cyclic Difference Sets*, Lecture Notes in Math. **182**, Springer-Verlag, 1971.)

Problem 27G. A zero ω of the polynomial $y^3 + 3y + 2$ (coefficients in \mathbb{F}_7) is a primitive element of \mathbb{F}_{7^3} .

Problem 27H. The cardinality of the intersection of a translate $D + g$ of D with the set $-D$ is the number of times g arises as a *sum* from D .

Problem 27I. For distinct i and j , the differences $\mathbf{x} - \mathbf{y}$, $\mathbf{x} \in U_i, \mathbf{y} \in U_j$, comprise all vectors in V , each exactly once.

Problem 28A. The Frobenius automorphism of $\mathbb{F}_{p^{t(n+1)}}$ is an automorphism of the symmetric design of 1-dimensional and n -dimensional subspaces of $\mathbb{F}_{p^{s(n+1)}}$ over \mathbb{F}_{p^t} .

Problem 28B. We may take $S(x)$ as in Lemma 28.4 with $D = \{1, 2, 4\}$ but where α is not a multiplier.

Problem 28C. If $n \equiv 0 \pmod{10}$, say, then for any $x \in D$, $\{x, 2x, 4x, 5x\} \subseteq D$ and the difference x is seen to occur twice unless $3x = 0$. If $3x = 0$ for all $x \in D$, then $3x = 0$ for all x in the group, and then $n^2 + n + 1$ must be a power of 3. Show that $n^2 + n + 1$ is never divisible by 9.

Problem 28D. The numbers of normalized difference sets with these parameters are, respectively: 2, 2, 4, 2, 0, 4.

Problem 28E. There are two normalized $(15, 7, 3)$ difference sets; they are equivalent since one consists of the negatives of the elements of the other. There are no normalized difference sets for any of the other parameters. To prove this in each case, first find a multiplier by Theorem 28.7.

For e.g. $(v, k, \lambda) = (25, 9, 3)$, Example 28.3 shows 2 is a multiplier of a hypothetical normalized difference set D . If the group is cyclic, D is the union of cycles of $x \mapsto 2x$ on \mathbb{Z}_{25} which are

$$\{0\}, \{5, 10, 20, 15\} \text{ and } \mathbb{Z}_{25} \setminus \{0, 5, 10, 15, 20\};$$

but no such union has nine elements. If the group is elementary abelian (exponent 5), then D must consist of 0 and two cycles of the form $\{x, 2x, 4x, 8x = 3x\}$; but the difference x occurs five times already among 0 and the elements of such a cycle.

Problem 28F. Assume $D(x^{-1}) = D(x)$ and use Lemma 28.2 with $p = 2$.

Problem 28G. Recall the construction of a symmetric design with those parameters from a Latin square of order 6 in Problem 19G.

Problem 28H. Assume $D(x^q) = D(x)$. Note that $q^3 \equiv -1 \pmod{|H|}$. Show $D(x^\alpha) \equiv 0 \pmod{q, H}$ and conclude that one of the coefficients of $D(x^\alpha)$ is $q + 1$ and all others are 1.

Problem 28I. The first part is similar to Problem 28H. Then show that if, in $PG_3(q)$, a line meets a set S of size $q^2 + 1$ in $k \geq 3$ points, then one of the $q + 1$ planes on that line contains more than $q + 1$ points of S .

Problem 29A. Review the proof of Theorem 20.6.

Problem 29B. Review the latter part of the proof of Proposition 29.5.

Problem 29C. The answer is $(v, k, \lambda) = (4n - 1, 2n - 1, n - 1)$ or $(4n - 1, 2n, n)$, i.e. Hadamard or the complement of Hadamard. Review the proof of Theorem 29.7.

Problem 30A. $A_1A_2 = 8A_1 + 8A_2 + 9A_3$ and $A_1^3 = 90A_0 + 83A_1 + 56A_2 + 36A_3$.

Problem 30B. By (30.3), $A_iA_j = \sum_{\alpha=0}^k P_i(\alpha)P_j(\alpha)E_\alpha$. Then by (30.4),

$$N A_iA_j = \sum_{\alpha=0}^k P_i(\alpha)P_j(\alpha) \sum_{\beta=0}^k Q_\alpha(\beta)A_\beta,$$

so evidently $p_{ij}^\ell = \frac{1}{N} \sum_{\alpha=0}^k P_i(\alpha)P_j(\alpha)Q_\alpha(\ell)$. The second eigenmatrix Q can be calculated by inverting P (also see Theorem 30.2).

Problem 30C. For the Latin square graphs,

$$P = \begin{pmatrix} 1 & (n-1)r & (n-1)(n-r+1) \\ 1 & n-r & -n+r-1 \\ 1 & -r & r-1 \end{pmatrix}.$$

Problem 30D. To evaluate the entries $P_\ell(0)$ of the top row of P , take the inner product (as introduced in the proof of Theorem 30.2) of both sides of (30.3) with E_0 .

Problem 30E. This is the dual to Problem 30B.

Problem 30F. Try $|A| = |B| = 3$.

Problem 30G. Note that for any automorphism σ , $|A \cap \sigma(B)| \leq 1$. Count the number of automorphisms of G .

Problem 30H. Given a metric scheme arising from a distance regular graph G , first note that A_1^i is a linear combination of

A_0, A_1, \dots, A_i where the coefficient of A_i is positive. Given a P -polynomial scheme, define a graph G by saying that x and y are adjacent in G if and only if they are 1st associates in the scheme, and show that two points are i -th associates if and only if they are at distance i in G .

Problem 30I. Use the counting argument of Problem 20K for words of weight 8 first; then find the other words satisfying the condition. Use the subcodes with a fixed j and the subcode of Problem 20K.

Problem 30J. If such a code did exist, it would be equivalent to a code with a generator matrix with $(1111100\dots 0)$ as first row and below that $(A B)$, where B generates a code of length 8, dimension 5, and minimum distance at least 3. Now use the fact that the $[7,4,3]$ Hamming code is unique (up to equivalence).

Problem 30K. (i) Distance depends on the size of the intersection only; just count; (ii) The graph has degree 4 and two triples corresponding to the Fano plane meet in one point.

Problem 30L. For $J(k, v)$ show that a necessary condition is that $1 + k(v - k)$ divide $\binom{v}{k}$.

Problem 31A. Consider the intersection of the eigenspaces of A_1 and A_2 corresponding to the eigenvalue 1.

Problem 31B. Since the adjacency matrix of the complement of a graph G with adjacency matrix A is $J - I - A$, the eigenvalues of \overline{G} are easily determined from those of G . The first examples in Chapter 21 are instances in which equality can occur.

Problem 31C. (i) The Petersen graph has *3-claws*, i.e. induced subgraphs on four vertices consisting of three edges incident with a common vertex (and no other edges). Explain why a line graph cannot contain a 3-claw. (ii) The matrix $N^\top N$ is positive semidefinite and is equal to $2I + A$, where A is the adjacency matrix.

Problem 31D. From the equation following (31.1) with \mathbf{x} the vector of all 1's, it follows that the largest eigenvalue of a graph is bounded below by the minimum degree of the graph. By Lemma 31.5, the largest eigenvalue of a graph G is bounded below by the

minimum degree of any induced subgraph H of G . If $\chi(H) = \chi(G)$ and the deletion of any vertex x of H decreases the chromatic number, then $\deg(x) \geq \chi(H) - 1$.

Problem 31E. If there are no directed paths from x to y in a digraph G with adjacency matrix A , let S be the set of vertices z such that there does exist a directed path in G from x to z . Then $A(x, y) = 0$ whenever $a \in S$ and $b \in V(G) \setminus S$, so A is not irreducible. The converse is even easier.

Problem 31F. (i) Show by straightforward calculation that $\mathbf{u}_j A = \lambda_j \mathbf{u}_j$, where $\mathbf{u}_j = (1, \omega^j, \omega^{2j}, \dots, \omega^{(n-1)j})$. For (ii), define, for each character χ , a vector \mathbf{u}_χ whose coordinates are indexed by G and where $\mathbf{u}_\chi(g) = \chi(g)$, and show that $\mathbf{u}_\chi A = \lambda_\chi \mathbf{u}_\chi$.

Problem 31G. To prove the lemma, show that if \mathbf{x} is a row-vector so that $\mathbf{x}S = \mathbf{0}$, then $\mathbf{x}a = 0$. Apply the lemma to $S = A + I$, where A is the adjacency matrix of the graph. The lemma may be found in B. Bagchi and N. S. Narasimha Sastry, Even order inversive planes, generalized quadrangles and codes, *Geometriae Dedicata* **22** (1987), 137–147. The graph problem (phrased in terms of ‘acquaintances’) is Problem 10851, by D. Beckworth, from the *American Mathematical Monthly* **108**.

Problem 31H. Most of the work has been done in the proof of Theorem 31.10: If the distinct eigenvalues of G are its degree d and μ_i , $i = 1, 2$, then $(A - \mu_1 I)(A - \mu_2 I) = \frac{1}{v}(d - \mu_1)(d - \mu_2)J$ where A is the adjacency matrix of G . This means that A^2 is in the algebra generated by I , J , and A . So G is strongly regular.

Problem 31I. Let G be an $srg(v, k, \lambda, \mu)$. The eigenvalues of $\Delta(x)$ interlace the eigenvalues

$$k, r, r, \dots, r, s, s, \dots, s \quad (r > s, \text{ say})$$

of G . Any sequence that interlaces this can have at most one term which is greater than r .

Except in the half-case, r and s are integers with $rs = \mu - k$; in particular, $r \leq k - \mu$ (even in the half-case). The graph $\Delta(x)$ is

regular of degree $k - \mu$. Were it not connected, $k - \mu$ would be an eigenvalue of $\Delta(x)$ of multiplicity greater than one.

Problem 31J. The eigenspace of A corresponding to eigenvalue 1, and the eigenspace of B corresponding to -1 , both have dimension 5, but are contained in the 9-dimensional space of vectors orthogonal to the vector of all 1's, and so there is a nonzero vector \mathbf{u} in the intersection of the eigenspaces. Show that connectivity of K leads to a contradiction to Theorem 31.11.

Problem 31K. (i) This follows from Theorem 31.13 or part of its proof. (ii) Multiply (31.6) by J . (iii) The number of undirected edges is one-half the trace of A^2 . (iv) Show that the undirected edges do not have a common vertex and that they are not joined by an edge. Up to reversing directions, this leaves only one way to complete the graph.

Problem 32A. One of the graphs has two vertices, one has three vertices, and two have four vertices.

Problem 32B. Let X be the set of vertices reachable by a directed path from s with $f(e) > 0$ on all edges of the path, and let Y be the remaining vertices, if any. If $t \notin X$, we have a contradiction to Eq. (7.1) (why?). For part (ii), use induction on k .

Problem 32C. Assign capacity 1 to all edges of D . Use Theorem 7.1.

Problem 32D. If (H, K) is an ℓ -separation and the deletion of the ℓ vertices $S := V(H) \cap V(K)$ does not disconnect the graph, then at least one of H or K has vertex set contained in S .

Problem 33A. Briefly explain why spanning trees of G that contain the edge e are in one-to-one correspondence with the spanning trees of G''_e and why spanning trees of G that do not contain the edge e are in one-to-one correspondence with the spanning trees of G'_e .

Problem 33B. Find an answer of the form $f(\lambda) + (-1)^n g(\lambda)$. Use induction, Equation (32.1), and Example 32.1.

Problem 33C. More strongly, a subdivision of $K_{3,3}$ (where edges are replaced by paths) occurs as a subgraph of the Petersen graph.

Problem 33D. Suppose a vertex of G''_S is incident with three distinct edges e_1, e_2, e_3 . Such a vertex is a connected component C of $G : S$. So e_i has an end x_i in C , $i = 1, 2, 3$ (these ends are not necessarily distinct). Explain why the connectivity of C implies that there exists a vertex x and possibly degenerate but internally disjoint paths in C from x to each of x_1, x_2 , and x_3 . That is, we have a subgraph of C isomorphic to a subdivision of the letter Y with the x_i 's at the ends of the arms if the paths all have length ≥ 1 , but otherwise some of the arms may be degenerate. This observation immediately leads to a solution of the first part of the problem.

Given four vertices $x_i, i = 1, 2, 3, 4$, of a connected graph C , show that there is a subgraph isomorphic to a subdivision of either the letter X or the letter I , though with possibly degenerate arms, and with the x_i 's at the ends of the arms.

Check that if a vertex, say 1, of K_5 is replaced by two vertices 1_L and 1_R joined by an edge, and the edges joining 1 to the other vertices are split, say 1_L is joined to 2 and 3, and 1_R is joined to 4 and 5, then the resulting graph has $K_{3,3}$ as a subgraph. Combine this with the observation of the previous paragraph to finish the problem.

Problem 33E. Use Euler's formula. The only pairs (d_1, d_2) that arise other than those $(3, 3), (3, 4), (3, 5), (4, 3), (5, 3)$ that correspond to the five Platonic solids are those $(2, n)$ and $(n, 2), n \geq 2$, that correspond to the polygons and bond-graphs.

Problem 34A. We have a linear mapping from the vector space over \mathbb{F}_2 of all subsets X of the vertex set $V(G)$ onto the cutset space of G , namely $X \mapsto \times(X, V(G) \setminus X)$. (The matrix of this mapping is N , the incidence matrix.) What are the sets X in the kernel of this mapping? The dimension of the cutset space is the number of vertices minus the dimension of the kernel.

Problem 34B. Use induction on the cardinality of the support of codewords.

Problem 34C. The circuits of G'_e are exactly those circuits of G that do not contain e . What are the bonds of H''_e ?

Problem 34D. One way to do this would be to first prove two things about subsets S of the edge set of a connected graph K : (1) S is the edge set of a spanning tree in K if and only if no circuit of K is contained in S and S is maximal with respect to this property and (2) S is the edge set of a spanning tree in K if and only if every bond of K meets S nontrivially and S is minimal with respect to this property.

Problem 34E. Show first that the two components that result from deleting an isthmus from a connected trivalent graph each have an odd number of vertices.

Problem 34F. Here is an idea to construct bonds. Deleting any edge of a spanning tree of G leaves a subgraph with two components; the set of edges with one end in each component is a bond of G .

Problem 34G. Deleting the edges of a bond S from a connected graph G always gives a graph with two components, but recall that we have chosen to delete isolated vertices when we defined G'_G . In part (ii), an equivalence of codes gives a one-to-one correspondence between the edge sets of H and G that takes circuits to circuits and bonds to bonds. Use part (i) and the fact that a graph without isolated vertices is nonseparable if and only if any two edges are contained together in a circuit; cf. Theorem 32.2.

Problem 34H. Given a polygon P in G , one may consider the subgraphs H and K where $H = P$ and K is the spanning subgraph of G containing all edges of G other than those of P .

Consider a bond B in G that consists of all edges with one end in X and one end in Y , where X and Y partition $V(G)$ and each induces a connected subgraph. Suppose for contradiction that G is Tutte- k -connected but that $|B| = \ell < k$. Let ℓ_1 be the number of vertices in X incident with edges of B . If the subgraph induced by X has at least ℓ_1 edges, we easily find an ℓ_1 -separation of G . Deal with the remaining situation.

Problem 34I. We give independent hints, even though one can derive (i) from (ii), or, as we have mentioned, the first two parts from (iii).

(i) If A and B are edge sets of polygons P and Q , start traversing P in both directions starting with the edge y , and stop as soon as vertices in Q are reached.

(ii) If A and B are the supports of codewords \mathbf{a} and \mathbf{b} , the support S of some linear combination of \mathbf{a} and \mathbf{b} will contain coordinate y but not x . Show that any support S of a codeword is the union of minimal supports of codewords, by induction on $|S|$.

(iii) Show that, in general, if $z \in \overline{S}$, then there is a minimal dependent set D so that $z \in D \subseteq S \cup \{z\}$. (Review Lemma 23.2.) Then show that y is in the closure of $(A \cup B) \setminus \{x, y\}$.

Problem 35A. Take the vertices of K_n to be \mathbb{Z}_n . For $n = 5$, use all cyclic shifts (translates) of $[1, 2, 4, 3] \pmod{5}$.

Problem 35B. Let us drop the last coordinate in the description of Example 21.4 and describe the Clebsch graph as having vertex set \mathbb{F}_2^4 and where \mathbf{x} and \mathbf{y} are adjacent when $\mathbf{x} + \mathbf{y}$ has weight 3 or 4. Try to choose one walk w and obtain the others as translates of w by all elements of \mathbb{F}_2^4 .

Problem 35C. Part (i) is similar to Theorem 33.5. For the proof of uniqueness of the mesh, we may take $V(K_7) = \{0, 1, \dots, 6\}$ and, without loss of generality, the walks traversing 0 are

$$[6, 0, 1], [1, 0, 2], [2, 0, 3], [3, 0, 4], [4, 0, 5], [5, 0, 6].$$

The walk traversing the edge $(6, 1)$ has third vertex 3 or 4 (otherwise the vertex condition is violated at 1 or 6) and in either case the other walks are uniquely determined.

Problem 35D. The vertices of the graph \mathcal{M}_x are the edges incident with x . These edges form the edge set of a bond in G and hence are the edges of a circuit in H .

Problem 35E. Let us use the term *flag* for a triple (x, e, F) consisting of a vertex x , an edge e incident with x , and a face F incident with e . There is exactly one other vertex x' so that (x', e, F) is a flag, exactly one other edge e' so that (x, e', F) is a flag, and exactly one other face F' so that (x, e, F') is a flag; these objects must hence be fixed by any automorphism α that fixes the terms of (x, e, F) .

Problem 35F. Use Theorem 35.1. The least value of $n > 2$ for which $K_{n,n}$ embeds in an orientable surface so that all faces are quadrilaterals is $n = 6$; n must be even, but $K_{4,4}$ does not embed in \mathcal{T}_0 . Some ideas and/or analysis of cases is required.

Problem 35G. All faces will have the same size. Consider the walk traversing the edge $(0, 1)$. The next several edges will be $(1, 1 - \omega)$, $(1 - \omega, 1 - \omega + \omega^2)$, $(1 - \omega + \omega^2, 1 - \omega + \omega^2 - \omega^3)$, etc. If $m \equiv 2 \pmod{4}$, for example, then the walk has length $m/2$.

Problem 36A. The sum of the determinants of all principal $n - 1$ by $n - 1$ submatrices of M is an appropriate sign times the coefficient of x in the characteristic polynomial $\det(xI - M)$ of M .

Problem 36B. There is one such arborescence for every mapping $f : \{2, 3, \dots, n\} \rightarrow \{1, 2, \dots, n - 1\}$ so that $f(i) < i$ for each i .

Problem 36C. If a vector g with coordinates indexed by $E(H)$ has the property that for every closed walk w , the signed sum of the values of g on the edges of w is zero, then define a vector h indexed by $V(H)$ as follows. (We assume H is connected for convenience; otherwise work separately with each component.) Fix a vertex x , define $h(x) := 0$, and for any vertex y , let $h(y)$ be the signed sum of the values of g on the edges of any walk from x to y . Check that h is well defined and that g is the coboundary of h .

Problem 36D. Let \mathcal{Z} denote the cycle space and \mathcal{B} the coboundary space. These are orthogonal complements, so their (direct) sum is \mathbb{R}^m (the space of all vectors with coordinates indexed by $E(D)$). Show that the linear transformation R is one-to-one on \mathcal{Z} and that $\mathcal{Z}R \cap \mathcal{B} = \{0\}$, so that \mathbb{R}^m is the direct sum of these subspaces.

Problem 36E. The sizes of all squares in Fig. 36.4 may be expressed as integral linear combinations of the sizes x, y, z of the three indicated squares. For example, the smallest square has size $z - x$ and the next smallest has size $x + z - y$. It will be found that the sizes of some squares can be so expressed in more than one way, and we thus have linear relations between x, y, z . Eventually, we can express the size of any square as a rational scalar multiple of x , and the least common denominator of these rational numbers is the value we should take for x .

Problem 36F. It may be quickest to proceed as in Problem 36E; let x, y, z , for example, denote the values of the current on three edges, etc. But one can evaluate determinants as in equation (36.3) to find the solutions.

Problem 37A. The rotations include: the identity (1), rotations of 90, 180, and 270 degrees about an axis through the centers of two opposite faces ($3 + 3 + 3$), rotations of 180 degrees about an axis through the centers of two opposite edges (6), and rotations of 120 and 240 degrees about an axis through two opposite vertices ($2 + 2 + 2 + 2$). The latter eight rotations, for example, contribute $8X_3^2$ to the cycle index.

Problem 37B. Use Theorem 37.2 and Problem 37A.

Problem 37C. Explain why the number of injections f fixed by (σ, τ) depends only on the cycle structure of σ and τ (i.e. on the numbers z_i of cycles of length i for each i) and find an expression for the number of injections in terms of the $z_i(\sigma)$'s and the $z_i(\tau)$'s.

Problem 37D. In Theorem 37.3, take G to be dihedral and H to be the symmetric group S_2 .

Problem 37E. If a rotation ρ of the cube has a cycles on the faces and b cycles on the vertices, the number of colorings fixed by ρ is $t^a s^b$. Use Burnside's Lemma.

Problem 38A. Let $m := v/2$. For each of the $M := v - 1$ colors i , we obtain an m -partition of $V(K_v)$ by taking the edges of color i , all singletons $\{x\}$ for x not incident with an edge of color i , and enough copies of the empty set to make an m -partition. Check that the condition (38.1) holds. Review the proof of Theorem 38.1.

Appendix 2

Formal power series

Before introducing the subject of this appendix, we observe that many of the assertions that we shall make will not be proved. In these cases the proof will be an easy exercise for the reader.

Consider the set

$$\mathbb{C}^{\mathbb{N}_0} := \{(a_0, a_1, a_2, \dots) : \forall_{i \in \mathbb{N}_0} [a_i \in \mathbb{C}]\}.$$

On this set we introduce an addition operation and a multiplication as follows:

$$(a_0, a_1, \dots) + (b_0, b_1, \dots) := (a_0 + b_0, a_1 + b_1, \dots),$$

$$(a_0, a_1, \dots)(b_0, b_1, \dots) := (c_0, c_1, \dots),$$

where $c_n := \sum_{i=0}^n a_i b_{n-i}$.

This definition produces a *ring* that we denote as $\mathbb{C}[[z]]$ and call the ring of *formal power series*. This name is explained in the following way. Let $z := (0, 1, 0, 0, \dots)$. Then z^n is the sequence $(0, \dots, 0, 1, 0, \dots)$ with a 1 in the n -th position. So, formally we have

$$\mathbf{a} = (a_0, a_1, \dots) = \sum_{n=0}^{\infty} a_n z^n =: a(z).$$

We shall use both notations, i.e. \mathbf{a} and $a(z)$, for the sequence. We say that a_n is the *coefficient of z^n* in \mathbf{a} (or $a(z)$). Notice that $\mathbb{C}[z]$, the ring of polynomials with coefficients in \mathbb{C} , is a subring of $\mathbb{C}[[z]]$. Some of the power series will be convergent in the sense of analysis. For these, we can use results that we know from analysis. Quite often these results can be proved in the formal sense, i.e. not using convergence or other tools from analysis.

Example 1. Let $f := (1, 1, 1, \dots)$. Using the definition of multiplication and $1-z = (1, -1, 0, \dots)$, we find $(1-z)f = (1, 0, 0, \dots) = 1$. So, in $\mathbb{C}[[z]]$, we have $f = (1-z)^{-1}$, i.e.

$$\frac{1}{1-z} = \sum_{n=0}^{\infty} z^n,$$

a result that we knew from analysis.

The regular elements in $\mathbb{C}[[z]]$ are the power series with $a_0 \neq 0$. This can be seen immediately from the definition of multiplication. From the relation $a(z)b(z) = 1$ we can calculate the coefficients b_n , since $b_0 = a_0^{-1}$ and $b_n = -a_0^{-1} \sum_{i=1}^n a_i b_{n-i}$. From this we see that the quotient field of $\mathbb{C}[[z]]$ can be identified with the set of so-called *Laurent series* $\sum_{n=k}^{\infty} a_n z^n$, where $k \in \mathbb{Z}$. Since it plays a special role further on, we give the coefficient of z^{-1} a name familiar from analysis. If $a(z)$ is the series, we say that a_{-1} is the *residue* of $a(z)$. This will be written as $\text{Res } a(z)$.

Let $f_n(z) = \sum_{i=0}^{\infty} c_{ni} z^i$ ($n = 0, 1, 2, \dots$) be elements of $\mathbb{C}[[z]]$ with the property

$$\forall_i \exists_{n_i} [n > n_i \Rightarrow c_{ni} = 0].$$

Then we can formally define

$$(1) \quad \sum_{n=0}^{\infty} f_n(z) = \sum_{i=0}^{\infty} \left(\sum_{n=0}^{n_i} c_{ni} \right) z^i.$$

This definition allows us to introduce *substitution* of a power series $b(z)$ for the ‘variable’ z of a power series $a(z)$. If $b_0 = 0$, which we also write as $b(0) = 0$, then the powers $b^n(z) := (b(z))^n$ satisfy the condition for formal addition, i.e.

$$a(b(z)) := \sum_{n=0}^{\infty} a_n b^n(z)$$

makes sense.

Example 2. Let $f(z) := (1 - z)^{-1}$, $g(z) = 2z - z^2$. Then formally

$$\begin{aligned} h(z) := f(g(z)) &= 1 + (2z - z^2) + (2z - z^2)^2 + \dots \\ &= 1 + 2z + 3z^2 + 4z^3 + \dots \end{aligned}$$

From calculus we know that this is the power series expansion of $(1 - z)^{-2}$, so this must also be true in $\mathbb{C}[[z]]$. Indeed we have

$$(1 - z)h(z) = \sum_{n=0}^{\infty} z^n = (1 - z)^{-1}.$$

This also follows from (legitimate) algebraic manipulation:

$$f(g(z)) = (1 - (2z - z^2))^{-1} = (1 - z)^{-2}.$$

Many power series that we often use represent well known functions, and in many cases the inverse function is also represented by a power series. This can also be interpreted formally for series $f(z)$ with $f_0 = 0$ and $f_1 \neq 0$. We ‘solve’ the equation $f(g(z)) = z$ by substitution. This yields $f_1 g_1 = 1$, $f_1 g_2 + g_1^2 = 0$, and in general an expression for the coefficient of z^n starting with $f_1 g_n$ for which the other terms only involve coefficients f_i and coefficients g_k with $k < n$. Setting this 0 allows us to calculate g_n .

Example 3. The reader who likes a combinatorial challenge can give a proof by counting of the formula

$$\sum_{k=0}^n \binom{2k}{k} \binom{2n-2k}{n-k} = 4^n.$$

This would be equivalent to proving that the formal power series $f(z) := \sum_{n=0}^{\infty} \binom{2n}{n} (z/4)^n$ satisfies the relation $f^2(z) = (1 - z)^{-1}$. By similar arguments or by algebraic manipulation one can then find the formal power series that deserves the name $(1 + z)^{\frac{1}{2}}$.

Now consider the formal power series $f(z) := 2z + z^2$. The ‘inverse function’ procedure that we described above will yield a power series $g(z)$ that satisfies $2g(z) + g^2(z) = z$, i.e. $(1 + g(z))^2 = 1 + z$. So this should be the series that we just called $(1 + z)^{\frac{1}{2}}$. It should

no longer be surprising that algebraic relations that hold for convergent power series are also true within the theory of formal power series.

Remark. We point out that substitutions that make perfect sense in calculus could be forbidden within the present theory. The power series $\sum_{n=0}^{\infty} \frac{z^n}{n!}$ will of course be given the name $\exp(z)$. In calculus we could substitute $z = 1+x$ and find the power series for $\exp(1+x)$. We do not allow that under formal addition.

We now introduce *formal derivation* of power series.

Definition. If $f(z) \in \mathbb{C}[[z]]$, then we define the *derivative*

$$(Df)(z) = f'(z)$$

to be the power series $\sum_{n=1}^{\infty} n f_n z^{n-1}$.

The reader should have no difficulty proving the following rules by using the definitions in this appendix:

- (D1) $(f(z) + g(z))' = f'(z) + g'(z)$;
- (D2) $(f(z)g(z))' = f'(z)g(z) + f(z)g'(z)$;
- (D3) $(f^k(z))' = k f^{k-1}(z) f'(z)$;
- (D4) $(f(g(z)))' = f'(g(z))g'(z)$.

The chain rule (D4) is an example of a more general statement, namely that

$$D \left(\sum_{n=0}^{\infty} f_n(z) \right) = \sum_{n=0}^{\infty} D(f_n(z)).$$

If convergence plays a role, this is a difficult theorem with extra conditions, but for formal power series it is trivial!

The familiar rule for differentiation of a quotient is also easily proved. So we can carry the theory over to Laurent series. We shall need the following two facts. Again we leave the proof as an exercise.

If $w(z)$ is a Laurent series, then

- (R1) $\text{Res}(w'(z)) = 0$;
- (R2) the residue of $w'(z)/w(z)$ is the least integer ℓ such that the coefficient of z^ℓ in $w(z)$ is nonzero.

We have already mentioned the idea of an ‘inverse function’ and have shown how to calculate its coefficients recursively. The next theorem gives an expression for the coefficients.

Theorem 1. *Let $W(z) = w_1z + w_2z^2 + \cdots$ be a power series with $w_1 \neq 0$. Let $Z(w) = c_1w + c_2w^2 + \cdots$ be a power series in w , such that $Z(W(z)) = z$. Then*

$$c_n = \operatorname{Res} \left(\frac{1}{nW^n(z)} \right).$$

PROOF: Observe that $c_1 = w_1^{-1}$. We now use formal derivation and apply it to the relation $Z(W(z)) = z$. This yields

$$(2) \quad 1 = \sum_{k=1}^{\infty} k c_k W^{k-1}(z) W'(z).$$

Consider the series obtained by dividing the right-hand side of (2) by $nW^n(z)$. If $n \neq k$, then the term $W^{k-1-n}(z)W'(z)$ is a derivative by (D3) and hence has residue 0 by (R1). By applying (R2) to the term with $n = k$ we find the assertion of the theorem. \square

This theorem makes it possible for us to give a proof of the Lagrange inversion formula (see Theorem 14.3) within the theory of formal power series. Let $f(z)$ be a power series with $f_0 \neq 0$. Then $W(z) := z/f(z)$ is a power series with $w_1 \neq 0$. Now apply Theorem 1. We find that $z = \sum_{n=1}^{\infty} c_n w^n$ with

$$c_n = \operatorname{Res} \left(\frac{f^n(z)}{nz^n} \right) = \frac{1}{n!} (D^{n-1} f^n)(0),$$

which is (14.19). This approach is based on P. Henrici, An algebraic proof of the Lagrange–Bürmann formula, *J. Math. Anal. and Appl.* **8** (1964), 218–224. The elegant simplification is due to J. W. Nienhuys.

As was observed above, we define

$$(3) \quad \exp(z) := \sum_{n=0}^{\infty} \frac{z^n}{n!}.$$

From previous knowledge we expect that replacing z by $-z$ will yield the inverse element in the ring $\mathbb{C}[[z]]$. Formal multiplication and the fact that $\sum_{k=0}^n (-1)^k \binom{n}{k} = 0$ for $n > 0$ shows that this is true.

It is now completely natural for us to also define

$$(4) \quad \log(1+z) := \sum_{n=1}^{\infty} (-1)^{n-1} \frac{z^n}{n}.$$

Again, calculus makes us expect a relation between the ‘functions’ \log and \exp . By our substitution rule, it makes sense to consider the power series $\log(\exp(z))$. From (D4) we then find

$$D(\log(\exp(z))) = \frac{\exp(z)}{\exp(z)} = 1,$$

i.e. $\log(\exp(z)) = z$. (Here we have used the fact that the formal derivative of $\log(1+z)$ is $(1+z)^{-1}$.)

Of course, much more can be said about formal power series. One could explore how many familiar results from analysis can be carried over or given a formal proof. We hope that this sketchy treatment will suffice to make things clearer.

Name Index

- Aardenne–Ehrenfest, T. van 520
Alltop, W.O. 223, 241
André, D. 138, 151
André, J. 320, 324
Assmus, E.F. 249, 259, 260
Appel, K. 24, 34, 35, 466, 471
- Baer, R. 255
Bagchi, N. 571
Baker, R.D. 300
Balinski, M. 457, 458
Bannai, E. 413, 431
Baranyai, Zs. 536, 537, 540, 541
Batten, L.M. 324, 363, 368
Baumert, L.D. 204, 214, 294,
295, 567
Beauregard Robinson, G. de
165, 167
Beckworth, D. 571
Beineke, L.W. 281
Belevitch, V. 200, 214, 265
Bermond, J.-C. 537
Bertrand, J.L.F. 151
Best, M.R. 207, 214
Beth, T. 301
Bhattacharya, K.N. 240, 241
Biggs, N. 450, 466, 471
Binet, A. 508, 510
Birkhoff, G. 48, 51, 52, 111
- Block, R.E. 371, 382
Blokhuis, A. 367, 368
Bollobás, B. 38, 41, 57
Bondy, J.A. 9, 542
Bose, R.C. 240, 264, 271, 272,
279, 280, 284, 288, 300, 301,
365, 367, 368, 409
Bouwkamp, C.J. 520, 521
Brégman, L.M. 101, 108
Brooks, R.L. 24, 35
Brouwer, A.E. 85, 87, 88, 272,
279, 280, 355, 368, 407, 431,
537, 541
Brouwer, L. E. J. 458
Bruck, R.H. 230, 241, 280, 381,
382, 383, 398
Bruijn, N.G. de 55, 59, 71, 75,
76, 216, 241, 433, 513, 514,
520, 532, 535
Buekenhout, F. 281
Bürmann, H. 582
Burnside, W. 94, 370
- Cameron, P.J. 259, 260, 279,
280, 281
Catalan, E. 150, 151
Catherine the Great 284
Cauchy, A.L. 94, 108, 508, 510
Cayley, A. 12, 22, 504, 505, 508

- Chakravarti, I.M. 367, 368
 Chandrasekharan, K. 167, 230, 241
 Chang, L.C. 271, 280, 281
 Chartrand, G. 462, 471, 491, 505
 Chowla, S. 230, 241, 301, 383, 398
 Chvátal, V. 70
 Clebsch, A. 263, 279, 498, 505, 575
 Cohen, A.M. 407, 431
 Cohen, G.D. 241
 Connor, W.S. 228, 241, 280, 281
 Conway, J.H. 216, 560
 Crapo, H. 324, 490, 564
 Crawley, P. 304, 313, 319, 324
 Cruse, A. 541
 Cvetković, D.M. 440, 450

 Da Silva, D.A. 96
 De Clerck, F. 280, 281
 Dedekind, J.W.R. 167
 Dehn, M. 520, 521
 Delsarte, P. 279, 280, 281, 405, 412, 413, 419, 422, 424, 431
 Dembowski, P. 324, 368
 Dénes, J. 197
 Denniston, R.H.F. 223, 242, 252, 268
 Desargues, G. 317, 323
 Diaconis, P. 181
 Diestel, R. 462, 463, 471
 Dilworth, R.P. 53, 60, 304, 313, 319, 324
 Dinitz, J.H. 294, 301, 469
 Dirac, G.A. 40
 Doob, M. 450
 Dowling, T. 341, 342, 349
 Duijvestijn, A.J.W. 517, 520, 521
 Dulmage, A.L. 295, 302

 Duval, A.M. 276, 281

 Ebbenhorst Tengbergen, C. van 55, 59
 Edmonds, J. 69, 503, 505
 Egoritsjev, G.P. 110
 Egecioğlu, Ö. 16, 23
 Elspas, B. 446, 450
 Erdős, P. *Preface*, 5, 10, 33, 35, 51, 59, 216, 241, 301, 331, 418, 430, 433, 520, 544
 Euler, L. 6, 10, 136, 157, 166, 182, 284, 290, 300, 465, 466, 480, 491, 497, 513, 542, 573
 Evans, T. 189, 197

 Falikman, D.I. 110
 Fan, K. 491, 505
 Fano, G. 225, 240, 242, 492
 Fekete, M. 103, 109
 Ferrers, N.M. 166, 327
 Fibonacci 150
 Fisher, R.A. 222, 240, 558
 Flye Sainte-Marie, C. 75, 76
 Ford, L.R. 64, 66, 70
 Fourier, J.B. 212
 Frame, J.S. 165, 167, 553
 Frankl, P. 59, 60, 331, 332
 Franklin, F. 157, 167
 Fréchet, M. 491, 505
 Freeman, J.M. 553
 Frobenius, G. 94, 167, 442, 568
 Fulkerson, D.R. 64, 66, 69

 Gale, D. 181
 Galvin, F. 194, 197, 469
 Gantmacher, F.R. 442, 450
 Gardner, M. 521
 Garey, M. 9, 10
 Gauss, C.F. 97, 325, 332
 Gelling, E.N. 537, 541

- Gewirtz, A. 267, 281
 Gödel, K. 458
 Godlewski, P. 241
 Godsil, C.D. 227, 281
 Goethals, J.-M. 266, 279, 280,
 281
 Golay, M.J.E. 252, 259, 417, 429
 Golomb, S.W. 204, 214
 Gordon, B. 381, 382
 Goulden, I.P. 150, 151
 Graham, R.L. 32, 35, 78, 88,
 332, 432, 521
 Granell, M.J. 223, 242
 Greene, C. 59, 60, 312, 334, 547
 Griggs, T.S. 223, 242
 Grinstead, C.M. 35
 Grossman, J.W. 10
 Grünbaum, B. 349, 350, 456,
 457, 458
 Gustin, W. 504, 506
 Guthrie, Francis 465
 Guthrie, Frederick 465
- Hadamard, J. 213, 268, 375
 Haemers, W. 280, 435, 450
 Haken, W. 24, 34, 35, 466, 471
 Hall, M. 51, 60, 196, 204, 214,
 281, 298, 302, 319, 324, 383,
 394, 395
 Hall, P. 43, 51, 52
 Halmos, P.R. 51, 52
 Hamilton, W.R. 8, 10, 465
 Hamming, R.W. 259, 406, 417
 Harary, F. 535
 Hardy, G.H. 166, 167
 Hautus, M.L.J. 51
 Heawood, P.J. 433, 466, 493,
 494, 498, 505
 Henrici, P. 582
 Hickerson, D. 150
 Higman, D.G. 267, 279, 281
- Hilbert, D. 470
 Hirschfeld, J.W.P. 358, 359, 368,
 566
 Hoffman, A.J. 41, 280, 282, 434,
 440, 450, 561
 Hoffman, D. 197
 Hsieh, W.N. 331, 332
 Hu, T.C. 70
 Hubaut, X. 279, 282
 Hughes, D.R. 321, 324
- Ito, T. 413, 431
- Jackson, D.M. 150, 151, 181,
 280, 431
 Jacobi, C.G.J. 167
 Jeans, J.H. 519, 521
 Johnson, D. 295, 302
 Johnson, D.S. 9, 10
 Johnson, S. 35, 406
 Jones, B.W. 80, 88
 Joyal, A. 141, 151
 Jungnickel, D. 227, 242, 301, 404
- Karp, R.M. 69
 Katona, G.O.H. 59, 60
 Keedwell, A.D. 197
 Kempe, A.B. 466, 467, 470
 Kirchhoff, G.R. 500, 515
 Kirkman, T.P. 240, 242
 Klarner, D.A. 132, 151
 Klein, F. 285, 499
 Kleitman, D.J. 59, 60, 547
 Knuth, D. 87, 163, 167, 181
 Ko, Chao 51, 331, 418, 430
 Koch, J. 466, 470, 471
 König, D. 51, 52
 Körner, J. 258
 Koornwinder, T.H. 280, 282
 Kramer, E.S. 557
 Krause, M. 172, 181

- Kreher, D.L. 224, 242
Krein, M.G. 267, 279, 280
Kronecker, L. 201, 268
Kruyswijk, D. 55, 59
Kuratowski, K. 462, 470
- Lagrange, J.L. 145, 151, 230,
240, 582
Lam, C.W.H. 242
Lander, E.S. 394, 398, 404
La Poutré, J.A. 86, 88
Laurent, P.M.H. 579
Leavitt, D.W. 224, 242
Leeb, K. 332
Lenz, H. 301
Leonardo of Pisa 150
Lesniak, L. 462, 491, 505
Lewin, M. 35, 36
Lint, J.H. van 51, 52, 60, 86, 88,
108, 109, 110, 118, 166, 167,
259, 260, 279, 280, 281, 282,
431, 543, 546, 551, 552, 558
Lloyd, E.K. 466, 471
Lloyd, S.P. 425, 427, 431
Locke, S.C. 553
London, D. 114, 118
Lorentz, H.A. 118
Lovász, L. 41, 42, 436, 437, 438,
450, 546
Lubell, D. 54, 60
Lucas, F.E.A. 95, 97, 150
- MacLane, S. 480, 490
MacMahon, P.A. 166, 167
MacNeish, H.F. 288, 290, 300,
302
MacWilliams, F.J. 248, 258, 259,
260
Magliveras, S.S. 224, 242
Maldeghem, H. Van 280, 282
Mann, H.B. 298, 302, 394, 395
- Mantel, W. 37, 42
Marcus, M. 112, 114, 118
Mathieu, É. 260
Mathon, R. 280
Mattson, H.F. 249, 259, 260
McFarland, R.L. 381, 382
McKay, B.D. 176, 181, 277, 281
Medema, P. 520, 521
Mendelsohn, E. 537, 541
Mendelsohn, N.S. 295, 302
Menger, K. 454, 455, 458
Merkx, F. 241
Mesner, D.M. 264, 279, 280, 409
Mills, W.H. 223, 242, 381, 382
Minc, H. 101, 108, 109, 118
Mirsky, L. 54, 60
Möbius, A.F. 97, 333, 362
Moivre, A. de 108
Montmort, P.R. de 97
Moon, J.W. 108, 109
Moore, E.H. 300, 302
Morgan, A. de 465
Muir, T. 108
Muller, D.E. 199ff, 213, 214, 261
Muzychuk, M. 448
- Narasima Sasbry, N.S. 571
Nešetřil, J. 521
Neumaier, A. 270, 272, 282, 407,
431
Neumann, P.M. 97
Newman, M. 112, 114, 118
Nichols, W. 553
Niderhausen, H. 553
Nienhuys, J.W. 582
Niven, I. 150, 151
Nordstrom, A.W. 419
- Ohm, G.S. 515
Ostrand, P. 51, 52

- Paige, L.J. 298, 302
 Paley, R.E.A.C. 203, 213, 214,
 262, 375
 Paola, J. di 368
 Pappus of Alexandria 318, 323
 Parker, E.T. 284, 288, 301
 Pasch, M. 314, 323
 Payne, S.E. 280, 282
 Pedoe, D. 319, 324
 Peltesohn, R. 537, 541
 Perron, O. 442
 Petersen, J.P.C. 261, 433, 462,
 465,477, 483, 491ff, 508, 542
 Petrenjuk, A.Ya. 222, 242
 Pierce, J.R. 88
 Piper, F.C. 321, 324
 Pless, V. 252, 260, 404
 Plotkin, M. 212
 Plücker, J. 239
 Pollak, H.O. 78, 88, 432
 Pólya, G. 522, 535
 Posner, E.C. 213, 214, 557
 Prüfer, H. 13, 23
 Pulver, E.D. 535
 Pythagoras 166

 Rademacher, H. 166, 167
 Rado, R. 51, 331, 418, 430
 Radziszowski, S.P. 35, 36, 224,
 242
 Ramanujan, S. 166, 167
 Ramsey, F.P. 28, 35, 36
 Raney, G.N. 151
 Ray-Chaudhuri, D.K. 222, 242,
 367, 368, 425, 431
 Reed, I.S. 213, 214, 361
 Rees, G.M.J., van 294, 302
 Remmel, J.B. 16, 23
 Riemann, G.F.B. 97
 Ringel, G. 493, 494, 502, 506
 Roberts, S.M. 35
 Robertson, N. 463
 Robinson, J.P. 419
 Rogers, D.G.E.D. 181
 Rosa, A. 537, 541
 Rota, G.-C. 151, 324, 349, 350,
 378, 490, 564
 Rothschild, B.L. 32, 33, 35, 332
 Ryser, H.J. *Preface*, 99, 108,
 109, 181, 187, 197, 213, 229,
 230, 241, 292, 383, 394, 395,
 398

 Sachs, H. 450
 Schellenberg, P.J. 294, 302
 Schläfli, L. 275
 Schönheim, J. 59, 60
 Schrijver, A. 65, 101, 107, 108,
 109, 280, 282, 355, 368, 537,
 541
 Schur, I. 22, 34, 544
 Schutzenberger, M.P. 240, 242
 Schwenk, A.J. 450
 Scott, L.L. 279
 Seberry, J. 213
 Segner, J.A. von 136
 Seidel, J.J. 266, 279, 280, 281,
 282, 558
 Seymour, P. 463
 Shannon, C.E. 259, 260, 436
 Shimamoto, T. 279
 Shrikhande, S.S. 284, 288, 301,
 561
 Simonyi, G. 258
 Sims, C.C. 267, 279, 281
 Singer, J. 377, 378, 382
 Singleton, R.R. 41, 561
 Skolem, Th. 241, 242
 Sloane, N.J.A. 258, 259, 260, 560
 Smetaniuk, B. 189, 197
 Smith, C. A. B. 520
 Spencer, J.L. 33, 35, 59, 60, 332,
 544

- Sperner, E. 54, 59, 60, 326
Sprott, D.A. 376, 384
Stanley, R.P. 150, 151, 349, 350,
460, 471
Stanton, R.G. 376, 384
Staudt, K.G.C. von 240
Steiner, J. 217, 240, 242
Steinitz, E. 465, 470, 471, 486
Stinson, D.R. 284, 302
Stirling, J. 108, 128
Strauss, E.G. 301
Swiercz, S. 241
Sylvester, J.J. 96, 166, 432
Szegő, G. 535
Szekeres, G. 33, 35
- Tait, P.G. 481–486, 490
Tarry, G. 284
Tarsy, M. 35
Teirlinck, L. 224, 242
Thas, J.A. 280, 287
Thiel, L. 242
Thomas, S. 330, 332
Thomassen, C. 469, 471
Thompson, J.G. 259, 260
Thompson, T.M. 258, 263
Thrall, R.M. 165, 167
Tits, J. 221, 242
Todd, J.A. 375
Turán, P. 38, 41, 42
Turner, J. 446, 450
Tutte, W.T. 457, 458, 462, 471,
483, 489, 490, 512, 517, 520
Tverberg, H. 53, 60
- Valiant, W.G. 107, 109
Vallée-Poussin, C.J. De La 213
Vandermonde, A.-T. 163
- Vanstone, S.A. 181, 227, 242,
280, 294, 302, 431
Vaughan, H.E. 51
Veblen, O. 279, 290
Vedder, K. 362
Voigt, M. 470
Voorhoeve, M. 105, 109
- Waerden, B.L. van der 32, 36,
76, 110, 118, 197
Wald, A. 458
Wallis, J.S. 213, 214
Watkins, J.J. 10, 11
Watson, G.N. 151
Wedderburn, J.H.M. 319, 402
Weisner, L. 335, 339, 350
Welch, L.R. 381, 382
Welsh, D.J.A. 490
White, A.T. 506
Whitney, H. 454, 458, 472ff, 490
Whittaker, E.T. 151
Wilbrink, H.A. 396, 404
Wilf, H. 450
Williamson, J. 204, 214
Wilson, R.J. 10, 11, 281, 466,
471
Wilson, R.M. 222, 242, 279, 282,
301, 302, 331, 334, 341, 350,
412, 430
Winkler, P. 80, 88
Witt, E. 223, 242, 397
Woolhouse, W.S.B. 240, 243
Wright, E.M. 160, 166, 167, 168
- Yamamoto, K. 395
Young, A. 167, 168
Young, J.W. 313, 324
Youngs, J.W.T. 493, 494, 502,
506

Subject Index

- (0, 1)-matrices 48, 100ff, 169ff
- 1-skeleton of a polytope 456
- 1-factor in a graph 537
- 1-factorization of a graph 537
- 15 schoolgirls problem 240
- 2-cell embedding of a graph 463, 473, 494–495
- 2-designs 224ff, 311
- 3-claw 570
- 3-connected graph 483–484
- 36 officers problem 284
- 5-designs 223, 242, 249, 252–253, 255, 266
- 6-designs 224

- absolute bound for strongly regular graphs 270, 273
- acyclic edge 482
- acyclic orientations of a graph 461
- addressing problem 77ff
- adjacency matrix of a digraph 432
- adjacency matrix of a graph 263ff, 391–402, 449ff
- adjacency matrix of a multigraph 507
- adjacency matrix of a scheme 409

- adjacency matrix of a tournament 432
- adjacent vertices in a graph 4
- affine geometry 304
- affine hyperplane 211
- affine plane 227, 273, 287
- affine subspace 304
- affine translation plane 320
- algebraic methods 264, 267, 432ff
- alphabet of a code 244
- ancestor 20
- André’s reflection principle 118
- antichain 53ff, 327
- arborescence 15, 145
- arc 351–353, 367
- arithmetic progression 32
- Assmus–Mattson theorem 249
- associates in a scheme 406ff
- association matrices of a scheme 409ff
- association scheme 279, 405ff
- associative block design 83ff
- atomic lattice 305
- augmenting path; *see also special path* 63, 69
- automorphism of a code 260
- automorphism of a graph 3, 422, 542, 569

- automorphism of a map 499, 575
- automorphism of a symmetric design 316, 329ff, 379, 566
- automorphism of a tree 13
- axis of perspectivity 317

- Baer subplane 255, 355, 394
- balanced incomplete block design (BIBD) 217ff
- balanced orientation of a graph 68
- ballot problem 150
- Baranyai's theorem 536ff
- base blocks 236, 241
- base of a Ferrers diagram 158
- bases in a combinatorial geometry 310ff
- Bell numbers 125, 149
- binary code 244
- binary Golay code 243, 252–255, 259, 417, 560
- binary relation on a set 406
- binary tree 139
- bipartite graph 24, 43, 55, 69, 196, 324
- biplane 267
- Birkhoff's theorem 48, 65, 111
- block design 217ff
- block graph of a design 266
- Block's Lemma 371
- block of cheese 41
- blocking set in a projective plane 355
- blocks of an incidence structure 215
- block-size of a t -design 216
- bond-graph 451, 473
- bond of a graph 475ff
- Boolean algebra 303
- Bose–Mesner algebra of a scheme 409ff, 419, 430
- Bose–Mesner algebra of a strongly regular graph 264ff
- breadth-first search 19, 81
- bridge 20, 482
- bridges of Königsberg 6, 7, 10, 59
- Brooks' theorem 24, 34
- Bruck–Ryser–Chowla theorem 230, 241, 383, 398
- De Bruijn graphs 71ff
- De Bruijn sequences 71ff, 513
- De Bruijn–Erdős theorem 216, 433
- Burnside's lemma 94, 97, 370, 524

- capacity of a cut 62ff
- capacity of an edge 62ff
- Catalan numbers 136–141, 150, 16
- Cauchy–Binet theorem 508, 510
- Cauchy inequality 115
- Cayley graph 446, 504–505
- Cayley's theorem 12ff, 145, 508
- cell 162
- central collineation 367
- chain 53ff, 305, 348
- Chang graphs 271, 280
- character 202, 248, 394
- cheapest spanning tree 18, 543
- Chinese Remainder Theorem 293
- chromatic number 24, 327, 398, 466, 571
- chromatic polynomial 341, 349, 459
- circle geometries 365
- circuits of a graph 475ff
- circulant graph 446, 448
- circular sequences 94–95, 120
- circulation on a digraph 66ff

- claw 218, 500
- claw bound 272–273
- Clebsch graph 263, 276, 279, 440, 447, 498, 505, 575
- clique in a graph 271, 435
- clique in a scheme 421
- closed path 5
- closed walk 5, 515
- closure in a combinatorial geometry 308ff
- coboundary space of a digraph 514
- coclique in a graph 434–435, 440
- coclique in a scheme 421
- code 244ff, 396ff
- code in a scheme 422
- code of a design 256–258, 396ff
- code of a graph 475ff
- codewords 244
- coding theory 244ff
- coline 309
- collinear 272
- collineation of a projective plane 353, 366
- colorings of graphs 24, 306, 459ff
- column-complete 196
- column of a Latin square 182
- combinatorial design 351
- combinatorial geometry 306ff
- combinatorial proofs of identities 121–122, 125, 138, 147, 552
- cometric scheme 422
- complement of a design 220, 251, 569
- complement of a difference set 391
- complement of a graph 393, 563, 570
- complement of a symmetric design 401
- complement of an incidence structure 215
- complementing permutation 342
- complete bipartite graph 6, 39, 432
- complete cycle 72–75
- complete graph 3, 12, 24, 27–28, 30, 33, 37ff, 78, 217, 261, 432, 491, 492, 494, 500, 502, 508, 540
- complete mapping of a group 298
- complete matching in a bipartite graph 43ff, 56
- complete multipartite graph 38
- complete uniform hypergraph 540
- complexity of a graph 460, 519
- component 5
- composition methods 288
- composition of a number 154, 553
- conference matrix 200ff, 233, 265, 402
- configuration counting series 528
- confoundable words 436
- conjugate of a partition 156, 169
- conjugates of a Latin square 183
- connected combinatorial geometry 313, 564
- connected graph 5–6, 347, 451
- connected strongly regular graph 261
- connectivity of a graph 451ff
- conservation of flow 62
- contraction of edges 462ff
- convex n -gon 33, 139, 146
- convex combination of permutation matrices 49, 111
- convex polytope 336, 349, 456, 465, 486
- cost of an edge 17
- cotree 462, 473

- counting in two ways 4, 207,
 212, 219, 262
 covering radius 245, 247
 covering in a poset 303, 305, 335
 cut in a transportation network
 62
 cutset space of a graph 476ff
 cutsets of a graph 475ff
 cycle index 524
 cycle space of a digraph 514
 cycle space of a graph 453
 cycles of a graph 475ff
 cycles of a permutation 123, 127,
 524ff
 cyclic difference set 373ff, 386,
 567
 cyclotomic scheme 408
- d*-code in a metric scheme 422
 De Bruijn graphs 71ff
 De Bruijn sequences 71ff
 De Bruijn–Erdős theorem 216,
 433
 decode 209, 212
 Dedekind η -function 167
 degree of a face 465
 degree of a vertex 4
 degrees of a scheme 406
 deletion of edges 459
 Delsarte’s inequalities 405, 416,
 418
 dependency graph 31
 depth-first search 19, 81
 depth of an orthogonal array 183
 derangements 90, 97, 129, 142,
 149
 derivation 146
 derived design 228
 Desargues configuration 317
 Desargues’ theorem 318, 321,
 322
 Desarguesian planes 319, 352
 descendant 20
 design of experiments 240
 design theory 215
 designs in a scheme 422
 determinant of the distance
 matrix 80
 difference methods 234, 240,
 288, 294ff, 498
 difference set 369ff, 389ff
 digraph 2, 194, 454
 Dilworth’s theorem 53, 55
 dimension of a combinatorial
 geometry 304
 Dinitz conjecture 194, 469
 directed Eulerian circuit 16, 71,
 75
 directed graph 2
 directed path 16
 discrepancy function 82
 distance in a code 244
 distance between vertices 5
 distance matrix of a graph 79–80
 distance regular graph 407
 distribution vector in a scheme
 406, 416–417
 dodecahedron 8, 492
 dominant eigenvalue 444
 doubly stochastic matrix 49,
 104, 108, 110ff
 drawing of a graph 1, 461
 dual arc in projective planes
 352–353
 dual code 246
 dual graph 466ff, 472ff
 dual of a symmetric design 228
 dual partial geometry 272
 dual poset 307
- echelon form 246, 327–328
 edge colorings 27

- edges of a graph 1
- eigenmatrices of a scheme 413, 415
- eigenspaces 264, 410
- eigenvalues of a graph 264, 433ff
- electrical network 507, 514, 515
- elementary cycle 514
- elementary flow 64
- elliptic quadratic form 359ff
- elliptic quadric 359ff
- embedding of a graph 461ff
- endpoints of an edge 1
- ends of an edge 1
- equivalent codes 246
- equivalent designs 221
- equivalent difference sets 374
- equivalent Latin squares 183
- Erdős–Ko–Rado theorem 56, 59, 331, 418, 430
- Erdős–number 5, 10
- error-correcting code 208, 244–246, 258–259
- Euler characteristic 497
- Euler function 92
- Euler’s conjecture 281ff, 288, 300
- Euler’s formula 349, 464, 465, 466, 480, 491, 542, 573
- Euler’s identity 157
- Eulerian circuit 6–9, 71, 513
- Eulerian graph 6
- Eulerian poset 350
- Evans conjecture 189–193
- excess of a Hadamard matrix 207
- exchange axiom 309
- exponential generating function 129ff
- extended code 246
- extended design 239
- extremal graphs 38–40
- extremal set theory 56, 59
- face of a convex polytope 456
- face of a graph or an embedding 463
- falling factorial 119
- Fano configuration or plane 225, 237, 255, 258, 354, 394, 430, 434, 492
- fast Fourier transform 212
- feasible flow 61ff
- feasible parameters for strongly regular graphs 265
- Fekete’s lemma 103, 106, 108, 130, 150, 436
- Ferrers diagram 156ff, 170–171, 327–328
- Fibonacci numbers or sequence 97, 149, 150, 550
- Fibonacci recursion 150, 159, 551
- finite differences, calculus of 97
- finite graph 4
- first order Reed–Muller code 210–212, 361
- Fisher’s inequality 222, 226, 353, 364, 405, 430
- Five Color Theorem 34, 466, 469
- fixed points of an automorphism 353, 369
- flags of an incidence structure 215
- flats 303, 309, 315
- flow 61
- Ford sequence 75
- forest 17
- formal derivative 145, 581
- formal power series 130–151, 578ff
- formally dual schemes 420
- formally dual theorems 424
- four color problem 459ff

- Four Color Theorem 24, 34, 427, 466, 482
Friendship Theorem 279
Frobenius automorphism 568
fully indecomposable matrix 111
- g*-torus 491
Gaussian coefficients 325
Gaussian numbers 312, 325ff
Gaussian polynomials 326
generalized quadrangle 273–274, 280, 363, 367
generating function 126, 129ff
generator matrix of a code 246, 570
Generalized Steiner System 238–239, 304
genus of a surface 491
geometric graph 272
geometric lattice 305ff, 340, 342, 490, 564
Gewirtz graph 267
girth of a graph 9, 39–40
Golay codes 241–244, 252–255, 259, 279, 417, 429, 560
graceful labeling 22
Graeco-Latin square 284
grand clique in a strongly regular graph 271, 280, 561
graph of a polytope 456
graph 1
greedy algorithm 18
group ring 383ff
- Hadamard 2-design 218
Hadamard 3-design 218, 220, 252
Hadamard difference set 375–377, 380, 569
Hadamard matrix 199ff, 218, 279, 411–412, 424
Hadamard product of matrices 268–269, 409, 415, 419
half-case of strongly regular graphs 265, 277
Hall multiplier 386
Hall's theorem 43–47, 65
Hamiltonian circuit 8, 40–41, 449, 483, 545
Hamming bound 245
Hamming code 246–247, 376, 560
Hamming distance 77, 244
Hamming scheme 406, 411ff
handle of a representation 437
hash-coding 84
hash function 84
head of a directed edge 2, 460
Heawood conjecture 493, 498
Heawood graph 433, 434, 492
hermitian form 364ff
hermitian variety 364ff
higher incidence matrices of a *t*-design 222
Higman–Sims graph 267, 279
Hoffman–Singleton graph 41
homeomorphic graphs 453
homogeneous coordinates 317
homomorphisms of the group ring 385ff
hooks in Young tableaux 165
hooklengths 165–166
horizontally convex polyomino 132
hyperbolic quadratic form 359ff
hyperbolic quadric 359ff
hypercube 77
hyperoval 227, 248, 255, 258, 266–267, 274
hyperplanes in combinatorial geometries 309ff

- idempotent quasigroup 28ff
- idempotents in the Bose–Mesner algebra 236, 410
- idempotents in the group ring 402
- incidence algebra of a poset 333ff
- incidence in a graph 1
- incidence matrix 221
- incidence matrix of a design 221ff, 225
- incidence matrix of a directed graph 62, 509
- incidence matrix of a graph 475
- incidence matrix of a symmetric design 228ff
- incidence structure 215
- inclusion–exclusion 89–97, 98, 122, 177, 337, 535, 549, 556
- independence number of a graph 436
- independent edges in a graph 18
- independent set 37
- independent subset of a
 - combinatorial geometry 309ff
- independent vertices in a graph 37, 434–435
- index of a design 216
- index of an orthogonal array 216, 423
- induced drawing 463
- induced subgraph 4, 77
- information rate 209
- inner (or dot or scalar) product 115–116, 396ff, 415
- Instant Insanity 7
- integral flow 64–66, 171, 540
- integrality condition for strongly regular graphs 265, 561
- interlacing of eigenvalues 439–440, 561, 571
- interval of a poset 307
- invariant factors 399
- inversive plane 362
- involution 323
- irreducible matrix 442
- isolated vertex 1
- isomorphic designs 221
- isomorphic difference sets 380
- isomorphic graphs 2, 411, 466
- isomorphic Latin squares 183
- isomorphic orthogonal arrays 183
- isotropic vector 115
- isthmus of a graph 20, 482
- Jacobi triple product identity 160
- Johnson scheme 406, 413ff
- join (least upper bound) 305ff
- joins (in a graph) 1
- Jordan arcs 472ff
- Jordan curve theorem 464
- Joyal theory 141ff
- k -class association scheme 406
- k -connected graph 451
- k -subspace 325
- k -Tutte connected 457, 489
- k -vertex connected 451, 454
- Kempe chain 467
- Kirchhoff’s laws 500, 515
- Kirkman schoolgirl problem 240
- Klein bottle 499
- König’s theorem 48, 51
- Krein condition 267, 269, 273, 279, 280
- Krein parameters of a scheme 420
- Kronecker product 201, 208, 213, 268, 287, 309, 437
- Kuratowski’s theorem 462

- labeled graph 12, 149
- labeled tree or forest 12ff, 141, 145
- Lagrange inversion formula 145, 151, 582
- Latin rectangle 186
- Latin square 182ff, 226, 273, 358
- Latin square graph 274, 276, 414
- Latin squares, number of 186–187, 192
- lattice (poset) 305ff, 333ff
- lattice graph 262
- lattice of contractions 308, 340
- Laurent series 579, 581
- length of a walk 5
- length of an edge 17
- line graph 194, 435–436, 570
- line of a block design 323
- line of a linear space 215
- line of a matrix 48
- line of a projective plane 225
- line of perspectivity 317
- linear code 244ff, 398
- linear order 53
- linear programming 69, 457
- linear programming bound 406, 418, 419
- linear recursion 130–134
- linear space 215, 289ff, 303, 313
- line-sums of $(0, 1)$ -matrices 100–101, 173–181
- link-graph 451, 471, 453
- list assignment 194
- list-colored graph 194
- Lloyd's theorem 405, 427
- loop of a graph 1
- loop switching problem 88
- Lorentz space 115–118
- Lovász Sieve 31
- MacNeish's theorem and conjecture 288, 290
- MacWilliams' theorem 248, 418
- MacWilliams relations 249
- magic square 300
- majorize 169–170
- Mantel's theorem 37
- map on a surface 491
- marriage theorem 43, 65
- matching in a graph 43
- Mathieu groups 259, 560
- matrix-tree theorem 507
- matroid 324, 489, 490
- maxflow–mincut theorem 64, 171, 540
- maximal arc in a projective plane 367
- maximal chain in a poset 53–54, 306, 325
- maximum distance separable code 248, 259, 347–348
- maximum flow 62
- maximum matching 69
- meet (greatest lower bound) 305
- Menger's theorem 454, 455
- mesh in a graph 494
- method of differences; *see difference methods*
- metric scheme 407, 422
- Minc's conjecture 101–103, 108
- minimal counterexample 24–26
- minimizing matrix 110ff
- minimum cut 64ff
- minimum distance of a code 211, 244
- minimum weight 245
- minor of a graph 462
- Möbius function of a poset 333ff, 344
- Möbius function, number theoretic 92–94, 333
- Möbius inversion 93, 136, 298, 333, 336, 337, 339, 346, 347, 370

- Möbius plane 362
 modular combinatorial geometry 313ff
 modular law 313
 modular complement 314
 monochromatic triangles 27–28
 monotone subsequence 55
 monovalent vertex 13
 multigraph 2
 multinomial coefficients 16, 120
 multiple edges 2
 multiplicities of a scheme 411
 multiplier of a difference set 386ff
 Multiplier Theorem 386ff, 390ff
 mutually orthogonal Latin squares 300
- n -gon 6, 153, 460
 near pencil 216, 313, 354
 necklaces 94–95, 522, 525–530, 533
 negative Latin square graphs 414
 neighborhood regular graph 277
 neighbors of a vertex 4
 net (partial geometry) 273, 280, 286, 287, 563
 nonassociative product operation 136
 nondegenerate quadratic form 356
 nonembeddable design 228–229, 240
 nonnegative matrices 111ff, 442ff
 nonseparable graph 451ff, 483ff, 499
 nontrivial difference set 372
 Nordstrom–Robinson code 419
 normalized difference set 374, 388
 normalized Hadamard matrix 199
- NP-complete 9
 numerical multiplier of a difference set 386
- odd graph 430
 Ohm’s law 515
 optimal representation of a graph 437
 orbits of a group 95, 370, 407, 523, 528, 530, 532
 order of a Hadamard matrix 199
 order of an orthogonal array 183
 order of a projective plane 225
 ordinary generating function 129
 orientable mesh 497
 orientation of a graph 21, 460
 orthogonal array 182, 294, 423
 orthogonal idempotents of a scheme 410
 orthogonal Latin squares 283ff, 563
 orthogonality relations 415
 orthomorphism of an abelian group 297–298, 339
 orthonormal representation of a graph 437
 oval in a projective plane 227, 381
 oval in a symmetric design 367
 ovoid in projective 3-space 362, 394
- P -polynomial 422
 pairwise orthogonal Latin squares 285, 300
 Paley graph 262, 265
 Paley matrix 203, 252–253, 256, 374
 Paley–Todd difference sets 375–377
 Pappian planes 319

- Pappus' theorem 318
- parabolic quadratic form 359ff
- parabolic quadric 359ff
- parallel class in a Steiner system 353
- parallel class in an affine plane 227, 273
- parallel class of sets 537
- parallel edges 2
- parameters of a scheme 406
- parent 20
- parity check matrix of a code 246
- parity check symbol 246
- partial fractions 153, 553
- partial geometry 271ff, 363
- partial Latin square 185
- partial match query 84
- partially balanced design 430
- partially ordered set (poset) 53, 333ff
- partition function 155ff, 166
- partition lattice 307–308, 336, 344–346
- partitions of a number 152ff, 169, 327–329
- partitions of a set 49, 106–107, 126, 537ff
- partly decomposable matrix 111
- Pasch axiom 314ff
- path in a graph 5
- paths in the X, Y plane 122, 130, 138, 149, 552
- pentagonal numbers 157
- perfect arc 351–353, 367
- perfect code 245, 248, 250, 254, 259, 405, 425, 427, 430
- perfect matching 44, 546
- permanent of a matrix 98ff, 549
- permanents of $(0,1)$ -matrices 100–104
- permanents of nonnegative integral matrices 105ff
- permutation matrices 48, 83, 114, 148, 205, 221, 193, 329
- Perron–Frobenius theorem 442–443
- perspective from a line 317
- perspective from a point 317
- Petersen graph 9, 40, 261, 263, 276, 430, 433–434, 436, 449, 462, 465, 477, 483, 485, 486, 491, 492, 508, 542, 570, 572
- pigeonhole principle 55, 559
- planar difference set 372, 388–389, 396, 403
- planar graph 1, 461ff, 479, 480
- plane at infinity 367
- plane tree 139
- planted plane trees 139
- Platonic solids 465, 499, 573
- Plotkin's bound 212
- point graph of a partial geometry 272
- point of a combinatorial geometry 303, 309
- point of an incidence structure 215
- point of a lattice 305
- point of perspectivity 317
- Pólya theory 522ff
- polygon 5, 83, 475
- polynomial scheme 422
- polyomino 132, 150
- poset (partially ordered set) 53, 333ff
- positive and negative vectors 115
- positive semidefinite or definite 223, 435, 439
- probabilistic method 30–32, 35, 544
- problème des ménages 95, 549

- problème des rencontres 97
 projective design 224
 projective geometry 225, 303,
 304, 313, 351
 projective plane 225, 232, 256,
 280, 287, 290, 313, 351–355,
 396
 projectively equivalent hermitian
 forms 364
 projectively equivalent quadratic
 forms 356ff
 proper coloring of a graph 24,
 341, 459
 proper drawing of a graph 461ff
 proper partial geometry 273, 280
 Prüfer code 13
 pseudo-geometric graph 272, 280

q-analogues 326, 337, 408
q-ary code 244
Q-polynomial 422
 quadratic form 78–80, 231, 355,
 558, 559, 566
 quadric in projective space 356ff,
 566
 quasigroup 182, 288ff
 quasiresidual design 228, 275
 quasisymmetric design 266, 275
 quotient set 372–373

 rain in Holland 97
 Raleigh quotient 434
 Ramsey's theorem 27ff, 37, 332
 rank in a combinatorial
 geometry 309ff
 rank of a connected graph 453
 rank of a flat 309
 rank of a hermitian form 364
 rank of a quadratic form 356
 rational function 132
 real projective plane 226, 492,
 496

 recoloring 24, 467
 recurrence relation 124, 134ff,
 159, 329
 recursive method 201, 233
 Reed–Muller codes 210–213,
 361, 560
 refinement order on partitions
 307
 regions of an embedding 463,
 472
 regular bipartite graph 44
 regular graph 4, 40, 149, 422,
 445
 regular Hadamard matrix 208,
 218, 226, 375
 repeated blocks 215, 223
 repetition 177
 repetition code 209, 245
 replication number 219, 240, 430
 residual design 228, 275
 resolvable Steiner system 353
 resolvable transversal designs
 291
 Riemann zeta function 93
 Ringel–Youngs theorem 494
 rooted trees and forests 15, 19,
 145–146
 rotating drum problem 71
 rotations of the cube 526, 577
 row 182
 row-complete 196
 row-sum 169

 saturated edge 63ff
 scheme 405f
 Schlaefli graph 275
 Schröder–Bernstein Theorem 51
 SDR theorem; see Hall's
 theorem
 SDR's and permanents 100
 self-conjugate partitions 162

- self-dual code 246, 396ff
- self-orthogonal codes 246, 396ff
- semi-simple algebra 402
- semimodular lattice 306ff, 342
- semimodular law 311
- semiregularity 44
- Shannon capacity of a graph 436–437
- sieve methods 96
- signless Stirling numbers 123, 534
- simple answers 288
- simple closed path 5
- simple design 215ff, 223
- simple difference set 372
- simple digraph 2
- simple graph 2
- simple path 5, 25
- simplex code 247
- Singer difference sets 378–380
- Singer's theorem 377, 381
- Singleton bound 247
- sink in a transportation network 61
- Six Color Theorem 467
- Skolem sequences 241
- slope of a Ferrers diagram 158
- Smith normal form 399
- source in a transportation network 61
- spanning arborescence 16ff, 512, 543
- spanning subgraph 4
- spanning subset in combinatorial geometries 310
- spanning tree 12ff, 81, 479, 507ff, 519, 543, 548, 572, 574
- special network 517
- special path 63ff
- Sperner's theorem 54, 56, 59, 326, 484
- sphere packing bound 245, 419, 425
- spherical 2-distance set 269
- spread 320, 330
- square design 224
- squared rectangle 516ff
- squared square 507
- standard tableaux 162
- Stanton–Sprott difference sets 376
- Steiner system 216ff, 221, 223, 303, 351ff, 362, 364–365
- Steiner triple system 233–241, 276, 278
- Stirling numbers 123–127, 534
- Stirling's formula 32, 107, 108, 187, 208
- strength of a flow 62
- strength of an orthogonal array 423
- strong product of graphs 436
- strongly connected digraph 442
- strongly regular graph 261ff, 405, 407, 449
- sub-Latin square 185
- subdivision of a graph 452ff
- subgeometry 304
- subgraph 4
- subplane of a projective plane 353ff
- subsquare of a Latin square 185
- subsquares of orthogonal Latin squares 298
- substitution of power series 579
- substitution principle 114, 117
- substructure of an incidence structure 353
- support of a codeword 249, 475
- supporting hyperplane 446
- surjections, number of 90, 125, 337

- Sylvester's law 96, 432
 symbol 182
 symmetric chain 55, 57, 58
 symmetric designs 224, 299, 367,
 369, 396ff, 568
 symmetric functions 535
 symmetry code 252
 system of distinct representatives
 (SDR) 43ff, 100, 106–108, 186
 system of walks in a graph 487ff
- t*-designs 216ff, 223, 249–253,
 255, 266, 330, 405, 423
 tail of a directed edge 2, 460
 Tait coloring of a graph 481–483
 tangent 367
 tennis matches 563
 ternary code 244
 ternary Golay code 256, 417
 tight design 223, 425, 428
 torus 492
 total order 53
 totally isotropic 397
 totally unimodular matrices 510
 tournament 33, 432
 transitive tournament 33
 translation plane 320, 331
 transportation network 61ff,
 170, 538
 transversal design 273, 290, 563
 tree 6, 12–22, 77–80, 459
 triangles in a graph 27, 37–39,
 543, 544
 triangular embedding of a graph
 500, 505
 triangular graph 262, 270, 275
 triangular mesh 494
 trifferent code 258
 trivalent graph 481–482, 546,
 551, 574
 trivalent tree 139
- Turán's theorem 37ff
 Tutte connectivity 451, 457, 458
 type of a partition of a set 346,
 526
 type of a permutation 370,
 525–528
- unipotent Latin square 288
 unital 365
 unordered partition 152
- valency or valence of a vertex 4
 Van der Waerden conjecture
 104, 108, 186, 197
 Vandermonde determinant 163
 Vandermonde matrix 251
 varieties 240
 vertex condition 497
 vertex connectivity 451
 vertices of a graph 1
- van der Waerden conjecture 104,
 110–118, 186, 197
 walk in a graph 5
 walks in the X, Y plane 122,
 130, 138, 149, 552
 weight of a codeword 244
 weight enumerator of a code 248
 weighted graph 17, 434
 Weisner's theorem 335, 339, 344
 Whitney dual of a graph 472ff
 Whitney's theorem 479, 480
 Williamson's method 204, 206
 Wilson–Petrenjuk inequality 222
 Witt design 223, 255, 256, 266
 write-once memory 237
- Young diagram 156
 Young tableau 162–167
- zeta function of a poset 333
 zeta function, Riemann 93, 97